

LILY HOUSE 28 APN: 007-103-0 2821 CONGRESS RD., PEBBLE	TECTONIC BUILDERS — CORPORATION —		
VICINITY MAP PROJECT DIRECTORY			10118 Bandley Dr. #E, Cupertino, CA 95014
Paradise Park Rd Contry Club Gate Paradise Rd Paradise Rd Paradi	PROPERTY OWNER	LILLY CHIING 890 YAKIMA DR. FREMONT, CA 94539 1ECTONIC BUILDERS CORPORATION 10118 BANDLEY DR., #E CUPERTINO, CA 95014 408-216-0804 LARRY WANG larrywang@tectoniccorp.com	LARRYL WANG Catsor Revelvingenzer PTF OF CALLOR
rarestunder Ra asauen Ra a	SURVEY	CENTRAL COAST SURVEYORS 5 HARRIS COURT, STE N-11 MONTEREY, CA 93940 650-823-6466 DAVID EDSON <u>DAVE@CCSURVEYORS.COM</u>	PLAN CHECK SET These documents are property of TECTONIC BUILDERS, INC., and are not to be reproduced, changed or copied without the expressed written consent of TECTONIC BUILDERS INC. DATE: 09/26/2024 DRAWN: KC
Assisted Living X.s Assisted	CIVIL ENGINEER	C3 ENGINEERING INCORPORATED 126 BONIFACIO PLACE SUITE C MONTEREY, CA 93940 831-647-1192 JENNIFER P. RUDOLPH, P.E. QSD JRUDOLPH@C3ENGINEERING.NET	CHECKED: LW REVISIONS BY: A A A A A A A A A A A A A
SCOPE OF WORK I. BUILD A NEW GROUND UP TWO STORY SINGLE FAMILY RESIDENCE WITH (3) CAR GARAGE ON A EMPTY LOT 2. REMOVE (43) EXISTING TREES PER FUEL MANAGEMENT PLAN AND BUILDING OUTLINE, DETAILS SEE LANDSCAPE PLANS AND ARBORIST REPORT. DDO IECT DATA	LANDSCAPE ARCHITECT	JEFFREY HEID, LANDSCAPE ARCHITECT 1465 WINZER PLACE GILROY, CA 95020 408-691-5207 JEFFREY HEID WJHEIDASLA@GMAIL.COM	RELEASED BY: 2024_03_22_PRELIMINARY_ARB_PLANNING SUBMITTAL 2024_09_26_1ST_PLANNING_SUBMITTAL
PROJECT DATALOT LOCATION:2821 CONGRESS RD., PEBBLE BEACH, CA 93953APN:007-103-011PLANNING DEPARTMENT:COUNTY OF MONTEREYI441 SCHILLING PLACE, SALINAS, CA 93901OCCUPANCY GROUP:R-3/ UCONSTRUCTION TYPE:TYPE V-BZONING DISTRICT:MDR/ B-6-D-RESNUMBERS OF STORIES:2	CERTIFIED ARBORIST	SENIOR ENVIRONMENTAL SCIENTIST/ CERTIFIED ARBORIST DD&A, INC. 947 CASS ST, SUITE 5 MONTEREY, CA 93940 831-373-4341 X 29 PATRIC KRABACHER PKRABACHER@DDAPLANNING.COM	JOB NO:
arcoss site Area (Equal to Net site Area):.44 ACRES: 19,218 \$F $FAR 35%:$ $6,726 F LOT COVERAGE: 35%: $6,726 F EXISTING \$F:O \$F (EXISTING EMPTY) $PROPOSED FLOOR AREA $F:$ $5,335 F REQUIRED SETBACKSSETBACKSSETBACKSSETBACKSSETBACKSIDREQUIRED BUILDING HEIGHT: $20'$ SIDE IO'IO' REQUIRED BUILDING HEIGHT: $27'-O''$ PROPOSE: $25'-O''$ MAIN HOUSE(5 MASTERS BEDROOMS W/ 3 CAR GARAGE)LOT COVERAGE (35%): $6,7265F$ IST FLOOR: $3,420 F (ARCF: $3,420 F	BUILDING CODES AL PLANS TO COMPLY WITH THE FOLLOWING: 2019 CALFORNIA ADMINISTRATIVE CODE 2019 CALFORNIA BUILDING CODE 2019 CALFORNIA PLUMBING CODE 2019 CALFORNIA BUILDING CODE 2019 CALFORNIA BUILDING CODE 2019 CALFORNIA BESTORITAL CODES 2019 CALFORNIA RESTORITAL CODES 2019 CALFORNIA RESTORITAL CODE 2019 CALFORNIA RESTORICAL PLANIAGE DE ACUHTECTURAL AO.O COVER SHEET SURVEY- TOPO MAP C1 CIVIL TITLE SHEET C2 GRADING AND DRAINAGE PLANI C3 DETALS C4 EROSION CONTROL PLAN A.O SITE PLANI AO.O SITE PLAN		LILLY HOUSE 2821 2821 CONGRESS RD., PEBBLE BEACH, CA 93953
GARAGE: 682 SF GARAGE: 682 SF PATIO: 955 SF 2NP FLOOR: 2,025 SF PORCH: 628 SF PROPOSED TOTAL: 6,125 SF < 6,726 SF OK			JURISDICTION APPROVAL STAMP: SHEET INFO COVER SHEET SHEET NO. AOOO OF SHEETS

LILY HOUSE 28 APN: 007-103-0			
2821 CONGRESS RD., PEBBLE	BEACH,	CA 93953	TECTONIC BU — CORPORA
VICINITY MAP	PROJECT DIRE	CTORY	10118 Bandley Cupertino, CA
Paradise Park Rd Meland And Re Rd Country Club Gate Country Club G	PROPERTY OWNER ARCHITECT	LILLY CHIING 890 YAKIMA DR. FREMONT, CA 94539 TECTONIC BUILDERS CORPORATION	CARRYL WAN Gateor Carry Control Control Carry Control Carry Control Carr
A Pacific Grove Pacific Grove Forest Lodge Rd Forest	SURVEY	IOII8 BANDLEY DR., #E CUPERTINO, CA 95014 408-216-0804 LARRY WANG larrywang@tectoniccorp.com CENTRAL COAST SURVEYORS 5 HARRIS COURT, STE N-11	PLAN CHECK
asourer Rd saver Rd s	CIVIL ENGINEER	MONTEREY, CA 93940 650-823-6466 DAVID EDSON <u>DAVE@CCSURVEYORS.COM</u> C3 ENGINEERING INCORPORATED 126 BONIFACIO PLACE SUITE C	BUILDERS, INC., and are not the changed or copied without the consent of TECTONIC BUILDED DATE: 09/26/20 DRAWN: KC CHECKED: LW
All a hard a good a hard a har		MONTEREY, CA 93940 831-647-1192 JENNIFER P. RUDOLPH, P.E. QSD JRUDOLPH@C3ENGINEERING.NET	REVISIONS BY:
SCOPE OF WORK 1. BUILD A NEW GROUND UP TWO STORY SINGLE FAMILY RESIDENCE WITH (3) CAR GARAGE ON A EMPTY LOT 2. REMOVE (43) EXISTING TREES PER FUEL MANAGEMENT PLAN AND BUILDING OUTLINE, DETAILS SEE LANDSCAPE PLANS AND ARBORIST REPORT. PROJECT DATA	LANDSCAPE ARCHITECT	JEFFREY HEID, LANDSCAPE ARCHITECT 1465 WINZER PLACE GILROY, CA 95020 408-691-5207 JEFFREY HEID WJHEIDASLA@GMAIL.COM	RELEASED BY: 2024_03_22_PRELIMINARY_A SUBMITTAL 2024_09_26_1ST_PLANNING_
LOT LOCATION: APN: PLANNING DEPARTMENT: 2821 CONGRESS RD., PEBBLE BEACH, CA 93953 007-103-011 COUNTY OF MONTEREY 1441 SCHILLING PLACE, SALINAS, CA 93901	CERTIFIED ARBORIST	SENIOR ENVIRONMENTAL SCIENTIST/ CERTIFIED ARBORIST DD&A, INC. 947 CASS ST, SUITE 5 MONTEREY, CA 93940	
OCCUPANCY GROUP:R-3/UCONSTRUCTION TYPE:TYPE V-BZONING DISTRICT:MDR/B-6-D-RESNUMBERS OF STORIES:2GROSS SITE AREA (EQUAL TO NET SITE AREA):.44 ACRES: 19,218 SFFAR 35%:6,726 SF		831-373-4341 X 29 PATRIC KRABACHER PKRABACHER@DDAPLANNING.COM	JOB NC
LOT COVERAGE: 35%:6,726 SFEXISTING SF:O SF (EXISTING EMPTY)PROPOSED FLOOR AREA SF:5,335 SF <u>REQUIRED_SETBACKS</u>	BUILDING COL ALL PLANS TO COMPLY WIT	TH THE FOLLOWING:	
SETBACKSIST FLR.2ND FLR.FRONT20'20'SIDEIO'20'REARIO'IO'REQUIRED BUILDING HEIGHT:27'-O''PROPOSE: 25'-O''MAIN HOUSE(5 MASTERS BEDROOMS W/ 3 CAR GARAGE)LOT COVERAGE (35%):6,7265FIST FLOOR:3,420 SFGARAGE:682 SFGARAGE:682 SF	2019 CALIFORNIA ADMINIS 2019 CALIFORNIA BUILDING 2019 CALIFORNIA PLUMBIN 2019 CALIFORNIA MECHAN 2019 CALIFORNIA ELECTRIC 2019 CALIFORNIA RESIDEN 2019 CALIFORNIA ENERGY 2019 CALIFORNIA FIRE COL 2019 CALIFORNIA FIRE COL 2019 CALIFORNIA FIRE COL 2019 CALIFORNIA EXISTING 2019 CALIFORNIA REFEREN COUNTY OF MONTEREY PLA	G CODE NG CODE NCAL CODE C CODE NTAL CODE3 EFFICIENCY STANDARDS (11TLE 24) BUILDING STANDARDS CODE 2E G BUILDING CODE NCED STANDARDS CODE	LILLY HOUS 2821 CONGRE PEBBLE BEACH,
PATIO: 553 SF 2ND FLOOR: 2,023 SF PORCH: 628 SF PROPOSED TOTAL: 28% 5,283 SF < 6,726 SF OK	SHEET INDEX ARCHITECTURAL AO.O COVER SHEET		JURISDICTION APPR
IMPERVIOUS AREA MAX.: 9,0005F DRIVEWAY PAVER: 2,597 SF PATIO: 553 SF PORCH: 628 SF LANDING: 24 SF IST FLOOR: 3,420 SF GARAGE: 682 SF	SURVEY- TOPO MAP CI CIVIL 111LE SHEET C2 GRADING AND DRA C3 DETAILS C4 EROSION CONTRO		
TRASH ENCLOSURE PAD:37 SFTOTAL7,941 SF OK	AI.O SITE PLAN AI.OA SITE PLAN WITH CO A2.O IST FLOOR PLAN A2.I 2ND FLOOR PLAN A2.2 ROOF PLAN A3.O ELEVATIONS A3.I ELEVATIONS		SHEET IN COVER SHE
	LI PLANTING PLAN L2 DETAILS L3 WILDFIRE PROTECT L4 HYDROZONE PLAN L5 DETAILS		SHEET N AO OF S

WATER SHED CALCULATION	<u>,</u>
IMPERVIOUS AREA MAX .:	9,0005F
DRIVEWAY PAVER:	2,597 SF
PATIO:	553 SF
PORCH:	628 SF
LANDING:	24 SF
IST FLOOR:	3,420 SF
GARAGE:	682 SF
TRASH ENCLOSURE PAD:	37 SF
2021L	

TOTAL	7,941 SF OK

ASSESSOR PARCEL MAP

NOTES:


1. ALL DISTANCES SHOWN HEREON ARE EXPRESSED IN FEET AND DECIMALS THEREOF.


× 236.80

FOUND 3/4" IRON PIPE W/PLASTIC PLUG STAMPED, "RCE15310"/

LOT 10

- 2. BOUNDARY LOCATIONS SHOWN HEREON WERE DETERMINED WITH THE BENEFIT OF A FIELD SURVEY SUPPLEMENTED BY RECORD DATA. ALL BOUNDARY DATA SHOWN ARE
- FROM THE RECORDS. THIS IS NOT A BOUNDARY SURVEY. 3. ELEVATIONS SHOWN ARE BASED ON AN ASSUMED DATUM THAT APPROXIMATES THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88). PROJECT BENCHMARK IS A MAG. NAIL SET IN CONCRETE PAVERS, AS SHÒWN. ELEVATION = 237.00 FEET (APPROX. NAVD88)
- 4. CONTOUR INTERVAL = ONE FOOT.
- 5. TREE TYPES ARE INDICATED WHEN KNOWN. DIAMETERS OF TREES ARE SHOWN IN INCHES. TREES SMALLER THAN 5" ARE NOT SHOWN.






LEGEND:

B.S.L.	BUILDING SETBACK LINE PER (13-C&T-105)
P.U.E.	PUBLIC UTILITY EASEMENT PER (13-C&T-105)
O 10"P	DENOTES A 10" DIA. PINE TREE (TYP.)
O 10"Q	DENOTES A 10" DIA. OAK TREE (TYP.)
	DENOTES PROTRACTED BOUNDARY
	DENOTES A WOOD FENCE



TOPOGRAPHIC MAP
LOT 11 IN TRACT NO. 852 AS SHOWN ON THE MAP ENTITLED "TRACT NO. 852, MONTEREY PENINS COUNTRY CLUB NO. 6" FILED IN, VOL. 13 - CAT - PG. 1 OFFICIAL RECORDS OF MONTEREY CO
PEBBLE BEACH COUNTY OF MONTEREY STATE OF CA
prepared for Lily Ching
B Y CENTRAL COAST SURVEYORS 5 HARRIS COURT, SUITE N-11 MONTEREY, CALIFORNIA 939 Phone: (831) 394-4930 Fax: (831) 394-4931
SCALE: 1" = 8' JOB No. 23-94 OCTOE
PREPARER: LLJS
APN: 007-103-011



GENERAL NOTES

1. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THESE PLANS AND ACCOMPANYING SPECIFICATIONS, IN ADDITION ALL WORK SHALL ALSO CONFORM WITH THE FOLLOWING:

LATEST REVISION OF THE COUNTY OF MONTEREY DESIGN STANDARDS AND SPECIFICATIONS

THE LATEST REVISION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS (STATE SPECIFICATIONS) THE 2023 EDITIONS OF THE CALIFORNIA BUILDING CODE (CBC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA MECHANICAL CODE (CMC), CALIFORNIA ENERGY CODE (CEnC), CALIFORNIA ELECTRICAL CODE (CEC).

2. THE CONTRACTOR SHALL FAMILIARIZE THEMSELVES WITH THE PLANS, DETAILS, AND SPECIFICATIONS AND SITE CONDITIONS PRIOR TO THE START OF CONSTRUCTION. IN THE EVENT THAT THE CONTRACTOR FINDS ANY DISCREPANCIES, OMISSIONS, OR DEFICIENCIES IN THE PLANS, THE CONTRACTOR SHALL NOTIFY THE DESIGN ENGINEER AND THE OWNER'S REPRESENTATIVE IMMEDIATELY.

3. IT IS THE CONTRACTORS RESPONSIBILITY TO SECURE ALL REQUIRED PERMITS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE MONTEREY COUNTY BUILDING SERVICES DEPARTMENT (COUNTY) AT LEAST 24 HOURS PRIOR TO THE START OF CONSTRUCTION.

4. THE TOPOGRAPHY, LOCATIONS AND SIZE OF UNDERGROUND UTILITIES AND OR OTHER STRUCTURES SHOWN HEREON WERE OBTAINED FROM A FIELD SURVEY (BY OTHERS) AND OR FROM RECORD INFORMATION. NEITHER THE ENGINEER NOR THE OWNER MAKES ANY REPRESENTATION TO THE ACCURACY OF TOPOGRAPHY. SIZE AND OR LOCATION OF ANY OF THE UTILITIES OR STRUCTURES SHOWN ON THESE PLANS NOR FOR THE EXISTENCE OF ANY OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED THAT ARE NOT SHOWN ON THIS PLAN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE SIZE AND LOCATION OF EXISTING UNDERGROUND UTILITIES, SURFACE IMPROVEMENTS, AND OTHER STRUCTURES AND TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THEM FROM DAMAGE DURING CONSTRUCTION.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING APPROPRIATE UTILITY COMPANIES AND REQUESTING VERIFICATION OF SERVICE POINTS, FIELD VERIFICATION OF LOCATION, SIZE, DEPTH, ETC. FOR ALL THEIR FACILITIES AND TO COORDINATE WORK SCHEDULES.

6. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT AT (800) 227-2600 AT LEAST 48 HOURS PRIOR TO EXCAVATION TO VERIFY THE LOCATION OF EXISTING UNDERGROUND UTILITIES.

7. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH ANY CURRENTLY APPLICABLE SAFETY LAW OF ANY JURISDICTIONAL BODY. FOR INFORMATION REGARDING THIS PROVISION, THE CONTRACTOR IS DIRECTED TO CONTACT THE STATE OF CALIFORNIA, DIVISION OF OCCUPATIONAL SAFETY AND HEALTH. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL BARRICADES, SAFETY DEVICES, AND THE CONTROL OF TRAFFIC WITHIN THE CONSTRUCTION AREA. FOR ALL TRENCH EXCAVATION FIVE (5) FEET OR MORE IN DEPTH. THE CONTRACTOR SHALL OBTAIN A PERMIT FROM THE DIVISION OF OCCUPATIONAL SAFETY AND HEALTH PRIOR TO BEGINNING ANY EXCAVATION. A COPY OF THIS PERMIT SHALL BE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES.

8. EXISTING CURB, GUTTER, SIDEWALK, SURVEY MONUMENTS, AND OTHER IMPROVEMENTS WITHIN PROJECT SITE THAT ARE DAMAGED OR DISPLACED AS A RESULT OF THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED BY THE CONTRACTOR.

9. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS AND SAFETY OF ALL PERSONS AND PROPERTY DURING THE COURSE OF CONSTRUCTION OF THE PROJECT. THE CONTRACTOR AGREES TO HOLD HARMLESS, INDEMNIFY AND DEFEND THE OWNER, THE ENGINEER, AND ALL DESIGN CONSULTANTS FROM ANY AND ALL LIABILITY, CLAIMS, LOSSES OR DAMAGES ARISING FROM THE PERFORMANCE OF THE WORK DESCRIBED HEREIN EXCEPT THOSE ARISING FROM THE SOLE NEGLIGENCE OF ANY OF THE PREVIOUSLY MENTIONED PEOPLE OR ENTITIES. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL LEAVE A 24-HOUR EMERGENCY TELEPHONE NUMBER WITH THE POLICE, FIRE DEPARTMENTS AND PRIVATE SECURITY COMPANY (IF APPLICABLE), AND KEEP THEM INFORMED DAILY REGARDING ANY CONSTRUCTION RELATED ACTIVITY IN THE PUBLIC RIGHT OF WAY.

10. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL, OFF-HAUL, AND PROPER DISPOSAL OF ALL ITEMS TO BE REMOVED INCLUDING BUT NOT LIMITED TO: CONCRETE, ASPHALT CONCRETE, STRIPING, ANY AND ALL OTHER DEBRIS FROM THE SITE, EXCESS MATERIAL FROM TRENCHING AND PAVEMENT CONSTRUCTION, TREES AND ROOT BALLS, FENCING AND SPOILS FROM EXCAVATION AT THE CONTRACTOR'S EXPENSE AND SHALL BE DISPOSED OF IN A LAWFUL MANNER.

11. IF, DURING THE COURSE OF CONSTRUCTION, CULTURAL, ARCHAEOLOGICAL, HISTORICAL OR PALEONTOLOGICAL RESOURCES ARE UNCOVERED AT THE SITE (SURFACE OR SUBSURFACE RESOURCES) WORK SHALL BE HALTED IMMEDIATELY WITHIN 50 METERS (165 FEET) OF THE FIND UNTIL A QUALIFIED PROFESSIONAL ARCHAEOLOGIST CAN EVALUATE IT. MONTEREY COUNTY HCD - PLANNING AND A QUALIFIED ARCHAEOLOGIST (I.E., AN ARCHAEOLOGIST REGISTERED WITH THE REGISTER OF PROFESSIONAL ARCHAEOLOGISTS) SHALL BE IMMEDIATELY CONTACTED BY THE RESPONSIBLE INDIVIDUAL PRESENT ON-SITE. WHEN CONTACTED, THE PROJECT PLANNER AND THE ARCHAEOLOGIST SHALL IMMEDIATELY VISIT THE SITE TO DETERMINE THE EXTENT OF THE RESOURCES AND TO DEVELOP PROPER MITIGATION MEASURES REQUIRED FOR RECOVERY.

12. ALL REVISIONS TO THESE PLANS MUST BE APPROVED BY THE ENGINEER AS WELL AS THE OWNER PRIOR TO THEIR CONSTRUCTION AND SHALL BE ACCURATELY SHOWN ON RECORD DRAWINGS PRIOR TO THE ACCEPTANCE OF THE WORK AS COMPLETE. ANY CHANGES TO OR DEVIATIONS FROM THE PLANS MADE WITHOUT AUTHORIZATION SHALL BE AT THE CONTRACTOR'S SOLE RISK AND SHALL ABSOLVE THE ENGINEER OF ANY AND ALL RESPONSIBILITY ASSOCIATED WITH THE THE CHANGE OR DEVIATION.

13. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP THE SITE AND ADJACENT AREAS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY, THE CONTRACTOR SHALL REMOVE IT IMMEDIATELY.

14. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH

COVER STOCKPILES OF DEBRIS, SOIL, OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST. KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST.

LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE.

15. A COPY OF ALL FIELD REPORTS/COMPACTIONS TESTS AND FINAL GRADING REPORT SHALL BE SUBMITTED TO THE COUNTY AT SCHEDULED INSPECTIONS.

16. PAD ELEVATION/S SHALL BE CERTIFIED TO 0.1 FEET, PRIOR TO DIGGING ANY FOOTINGS OR SCHEDULING ANY INSPECTIONS.

GRADING AND DRAINAGE

1. CONTRACTOR SHALL NOTIFY THE COUNTY 48 HOURS BEFORE STARTING ANY GRADING OPERATIONS.

2. ALL GRADING SHALL CONFORM TO THE COUNTY GRADING ORDINANCE (CHAPTER 16.08) AND THE EROSION CONTROL ORDINANCE (CHAPTER 16.12) AS APPLICABLE.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE REQUIRED PERMITS PRIOR TO THE COMMENCEMENT OF GRADING. RIGHT-OF-ENTRY, PERMISSION TO GRADE, AND ENCROACHMENT PERMIT(S) MAY BE REQUIRED PRIOR TO GRADING.

4. IT IS THE CONTRACTORS RESPONSIBILITY TO PREPARE THE GROUND SURFACE TO RECEIVE THE FILLS AND TO PLACE, SPREAD, MIX, WATER, AND COMPACT THE FILL. THE CONTRACTOR SHALL ALSO REMOVE ALL MATERIAL CONSIDERED UNSATISFACTORY

5. WHERE UNSTABLE OR UNSUITABLE MATERIALS ARE ENCOUNTERED DURING SUBGRADE PREPARATION, THE AREA IN QUESTION SHALL BE OVER EXCAVATED AND BACKFILLED WITH SELECT MATERIAL.

6. MAXIMUM CUT AND FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL.

ALL CUT SLOPES SHALL BE ROUNDED TO MEET EXISTING GRADES AND BLEND WITH SURROUNDING TOPOGRAPHY. ALL GRADED SLOPES SHALL BE PLANTED WITH SUITABLE GROUND COVER.

8. TREE REMOVAL SHALL INCLUDE REMOVAL OF TRUNKS, STUMPS, AND ROOTBALLS. THE REMAINING CAVITY SHALL BE CLEARED OF ALL ROOTS LARGER THAN 1/2" TO A DEPTH OF NOT LESS THAN 18" AND BACKFILLED WITH SUITABLE MATERIAL THEN COMPACTED TO CONFORM WITH THE EXISTING GROUND.

9. CONTRACTOR SHALL USE CAUTION WHEN GRADING AROUND AND/OR OVER EXISTING UNDERGROUND UTILITIES.

10. ALL SURFACE DRAINAGE SHALL MAINTAIN 2% SLOPE MINIMUM UNLESS NOTED OTHERWISE.

11. PERVIOUS SURFACES IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT A SLOPE OF NOT LESS THAN 5% FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FEET OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED A MINIMUM OF 2% WHERE LOCATED WITHIN 10 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.


12. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15) THE FOLLOWING MEASURES MUST BE TAKEN:


A. DISTURBED SURFACES NOT INVOLVED IN IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.


B. ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON DOWNHILL PROPERTIES.

C. RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS, AND OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE.

D. DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY THROUGH THE LIFE OF THE PROJECT DURING WINTER OPERATIONS







				ΒY
				DESCRIPTION
				DATE
		INCORPORATED		
			UNIL ENGINEERING LUNU DEVELOPMENT STUTTIWATER 126 Bonifacio Place, Suite C, Monterey, CA 93940	Phone: (831) 647-1192 Fax (831) 647-1194 mail@C3Engineering.net
	PL	FC AN	DR NIN(G
	CONSTRUCTION DETAILS		2821 CONGRESS ROAD	PEBBLE BEACH, CA APN 007-103-011
	SCALE: DATE: DESIGN DRAWN CHECKE SHEET N	BY: D BY: JMBER:	11/1	NOTED 13/2024 JPR JPR
	OF 4 PROJEC	SHEETS		124107


	<u>GENERAL NOTES</u>
	1. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE TO NEIGHBORING PROPERTIES. THE CONTRACTOR SHALL CONFORM TO THE DUST-CONTROL AS ESTABLISHED BY THE AIR QUALITY MAINTENANCE DISTRICT. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:
	 A) PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH. SUFFICIENT WATERING TO CONTROL DUST IS REQUIRED AT ALL TIMES. B) COVER STOCKPILES OF DEBRIS, SOIL, OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST. C) KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST.
	 LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE. THE CONTRACTOR SHALL ASSUME LIABILITY FOR CLAIMS RELATED TO WIND BLOWN MATERIAL. IF THE DUST CONTROL IS INADEQUATE AS DETERMINED BY THE CITY, THE CONSTRUCTION WORK SHALL BE TER
	MEASURES ARE TAKEN. 2. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP STREETS AND ROADS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY, THE
	REMOVE IT IMMEDIATELY. 3. ALL CUT AND FILL SLOPES EXPOSED DURING CONSTRUCTION SHALL BE COVERED, SEEDED OR OTHERWISE TREATED TO CONTROL EROSION WITHIN 48 HOURS AFTER GRADING. CONTRACTOR SHAL DISTURBED AREAS THROUGH AN APPROVED PROCESS AS DETERMINED BY THE CITY. THIS MAY CONSIST OF EFFECTIVE PLANTING OF RYE GRASS, BARLEY OR SOME OTHER FAST GERMINATING SEED.
	 4. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15), THE FOLLOWING MEASURES MUST BE TAKEN: A) VEGETATION REMOVAL SHALL NOT PRECEDE SUBSEQUENT GRADING OR CONSTRUCTION ACTIVITIES BY MORE THAN 15 DAYS. DURING THIS PERIOD, EROSION AND SEDIMENT CONTROL MEASURES (STATE OF A STATE OF A STA
	SURFACES NOT INVOLVED IN THE IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND/OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION. B) ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR THE DOWNHILL PROPERTIES.
	C) RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE DISTURBED AREA OR SITE. TH MEASURES MUST BE MAINTAINED BY THE CONTRACTOR AS NECESSARY TO ACHIEVE THEIR PURPOSE THROUGHOUT THE LIFE OF THE PROJECT.
	 EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY CHECKED THROUGHOUT THE LIFE OF THE PROJECT DURING WI (GONZALES GRADING/EROSION ORD. 2806-16.12.090) E) THE GRADING INSPECTOR MAY STOP OPERATIONS DURING PERIODS OF INCLEMENT WEATHER IF EROSION PROBLEMS ARE NOT BEING CONTROLLED ADEQUATELY.
	 E) THE GRADING INSPECTOR MAY STOP OPERATIONS DURING PERIODS OF INCLEMENT WEATHER IF EROSION PROBLEMS ARE NOT BEING CONTROLLED ADEQUATELY. 5. IF VEGETATION REMOVAL TAKES PLACE PRIOR TO A GRADING OPERATION AND THE ACTUAL GRADING DOES NOT BEGIN WITHIN 30 DAYS FROM THE DATE OF REMOVAL, THEN THAT AREA SHALL BE PROVISION OF SECTION 16.08,340 TO CONTROL EROSION. NO VEGETATION REMOVAL OR GRADING WILL BE ALLOWED WHICH WILL RESULT IN SILTATION OF WATER COURSES OR UNCONTROLLABLE EROSION.
	 ALL POLLUTANTS AND THEIR SOURCES, INCLUDING SOURCES OF SEDIMENT ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION.
	 ALL NON-STORM WATER DISCHARGES ARE IDENTIFIED AND EITHER ELIMINATED, CONTROLLED, OR TREATED; SITE BMPS ARE TO BE EFFECTIVE AND RESULT IN THE REDUCTION OR ELIMINATION OF POLLUTANTS IN STORM WATER DISCHARGES AND AUTHORIZED NON-STORM WATER DISCHARGES FROM CONSTR
	 STABILIZATION BMPS INSTALLED TO REDUCE OR ELIMINATE POLLUTANTS AFTER CONSTRUCTION IS COMPLETED. BEST MANAGEMENT PRACTICES (BMPS) TO BE IMPLEMENTED BY THE PROJECT ARE LISTED BY CATEGORY. FACT SHEETS, AND DETAILS FOR THE BMPS SELECTED FOR THIS PROJECT, CAN BE FOUND IN T MANAGEMENT PRACTICE HANDBOOK.
	MONTEREY COUNTY INSPECTIONS
	1. PRIOR TO COMMENCEMENT OF ANY LAND DISTURBANCE, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT TO ENSURE ALL NECESSA PLACE AND THE PROJECT IS COMPLIANT WITH MONTEREY COUNTY REGULATIONS.
	2. DURING CONSTRUCTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT TO INSPECT DRAINAGE DEVICE INSTALLATION, REVIEW THE EFFECTIVENESS OF BMPS INSTALLED, AND TO VERIFY THAT POLLUTANTS OF CONCERN ARE NOT DISCHARGED FROM THE SITE. AT THE TIME OF THE INSPECTION, THE APPLICANT SHALL PROVIDE CERTIFICATION THAT ALL NECE INSPECTIONS HAVE BEEN COMPLETED TO THAT POINT.
	3. PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE DEPARTMENT OF HOUSING AND COMMUNITY DEVELOPMENT TO ENSURE THAT ALL DISTURBED AREAS HAVE BEEN STA TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THAT ARE NO LONGER NEEDED HAVE BEEN REMOVED.
	GOOD SITE MANAGEMENT "HOUSEKEEPING"
	1. POLLUTANTS IN STORM WATER DISCHARGES FROM THE PROJECT DURING CONSTRUCTION MAY ORIGINATE FROM THE DAILY OPERATION OF EQUIPMENT, GRADING OPERATIONS, AND STOCKPILING -DISCHARGERS SHALL IMPLEMENT GOOD HOUSEKEEPING MEASURES ON THE CONSTRUCTION SITE TO CONTROL THE AIR DEPOSITION OF SITE MATERIALS AND FROM SITE OPERATIONS. SUCH PARTICI
	not limited to, sediment, nutrients, trash, metals, bacteria, oil and grease and organics. WASTE MANAGEMENT POLLUTION CONTROL
	 THE DISCHARGER SHALL PREVENT DISPOSAL OF ANY RINSE OR WASH WATERS OR MATERIALS ON IMPERVIOUS OR PERVIOUS SITE SURFACES OR INTO THE STORM DRAIN SYSTEM. THE DISCHARGER SHALL ENSURE THE CONTAINMENT OF SANITATION FACILITIES (E.G., PORTABLE TOILETS) TO PREVENT DISCHARGES OF POLLUTANTS TO THE STORM WATER DRAINAGE SYSTEM OR REC
	 SANITATION FACILITIES SHALL BE CLEANED, REPLACED, AND INSPECTED REGULARLY FOR LEAKS AND SPILLS. WASTE DISPOSAL CONTAINERS SHALL BE COVERED AT THE END OF EVERY BUSINESS DAY AND DURING A RAIN EVENT. NO DISCHARGES FROM WASTE DISPOSAL CONTAINERS TO THE STORM WATER
	RECEIVING WATER SHALL BE ALLOWED. 4. STOCKPILED MATERIAL SHALL BE CONTAINED AND SECURELY PROTECTED FROM WIND AND RAIN AT ALL TIMES UNLESS ACTIVELY BEING USED.
	5. PROCEDURES SHALL BE DEVELOPED THAT EFFECTIVELY ADDRESS HAZARDOUS AND NONHAZARDOUS SPILLS. EQUIPMENT AND MATERIALS FOR CLEANUP OF SPILLS SHALL BE AVAILABLE ON SITE. SPILI CLEANED UP IMMEDIATELY AND DISPOSED OF PROPERLY.
	 CONCRETE WASHOUT AREAS SHALL BE CONTAINED SO THERE IS NO DISCHARGE INTO THE UNDERLYING SOIL AND ONTO THE SURROUNDING AREAS. DISCHARGER SHALL MAINTAIN VEHICLES TO PREVENT OIL, GREASE, OR FUEL TO LEAK IN TO THE GROUND, STORM DRAINS OR SURFACE WATERS. ALL EQUIPMENT OR VEHICLES SHALL BE FUELED, MAI DESIGNATED AREA FITTED WITH APPROPRIATE BMPS. LEAKS SHALL BE CLEANED IMMEDIATELY AND DISPOSED OF PROPERLY.
	 IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE WASTE MANAGEMENT POLLUTION CONTROL WHERE APPLICABLE: WM-1, MATERIAL DELIVERY AND STORAGE
	WM-2, MATERIAL USE WM-3, STOCKPILE MANAGEMENT
	WM-4, SPILL PREVENTION AND CONTROL WM-5, SOLID WASTE MANAGEMENT
ġ.s	WM-6, HAZARDOUS WASTE MANAGEMENT WM-7 CONTAMINATED SOIL MANAGEMENT WM-8, CONCRETE WASTE MANAGEMENT
BE EPARED. ART, IS 'RING.	WM-9, SANITARY/SEPTIC WASTE MANAGEMENT WM-10, LIQUID WASTE MANAGEMENT
HALL E PRI IN PZ GINEE	(SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) 9. THE CONTRACTOR SHALL REVIEW CONSTRUCTION ACTIVITIES TO IDENTIFY AND QUANTIFY LIKELY CONSTRUCTION MATERIALS AND WASTES. SPECIAL NOTICE SHALL BE MADE OF MATERIALS AND WA
NS S WER OR	OR DISPOSAL REQUIREMENTS; SUCH AS LEAD CONTAMINATED SOILS, CONCRETE SAW-CUTTING LIQUIDS, WASTE CHEMICALS AND EMPTY CHEMICAL CONTAINERS. THE CONTRACTOR SHALL FOLLOW ALL AND HANDLING RECOMMENDATIONS AND FOLLOW ALL FEDERAL, STATE, AND LOCAL REGULATIONS. WHERE POSSIBLE, CONTRACTOR SHALL USE SAFER AND LESS POLLUTING PRODUCTS.
SPECIFICATIONS SHALL BE WHICH THEY WERE PREPAREL DN, IN WHOLE OR IN PART, IS ONSENT OF C3 ENGINEERING.	EROSION CONTROL (SOIL STABILIZATION) 1. SUFFICIENT EROSION CONTROL MATERIALS WILL BE MAINTAINED ON-SITE TO ALLOW FOR IMMEDIATE DEPLOYMENT BEFORE THE ONSET OF RAIN.
SPECIF VHICH IN I	 DISCHARGERS SHALL PROVIDE EFFECTIVE SOIL COVERS FOR INACTIVE AREAS (MORE THAN 14 DAYS UN-DISTURBED) AND ALL FINISHED SLOPES, OPEN SPACE, UTILITY BACKFILL, AND COMPLETED LO DISCHARGERS SHALL LIMIT THE USE OF PLASTIC MATERIALS WHEN MORE SUSTAINABLE, ENVIRONMENTALLY FRIENDLY ALTERNATIVES EXIST. WHERE PLASTIC MATERIALS ARE DEEMED NECESSARY, THE D
AND S FOR V CATION N CON	THE USE OF PLASTIC MATERIALS RESISTANT TO SOLAR DEGRADATION. 4. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TEMPORARY AND FINAL EROSION CONTROL DURING CONSTRUCTION WHERE APPLICABLE: EC-1, SCHEDULING
S U S	EC-1, 3C REDUCING EC-2, PRESERVATION OF EXISTING VEGETATION EC-3, HYDRAULIC MULCH
THESE DRAWING HE ORIGINAL US ICTION, OR PUE HOUT THE WRIT	EC-4, HYDROSEEDING EC-5, SOIL BINDERS
ESE I ORIG TION, UT TI	EC-6, STRAW MULCH EC-7, GEOTEXTILES AND MATS
L L L L L	EC-8, WOOD MULCHING EC-9, EARTH DIKES AND DRAINAGE SWALES EC-10, VELOCITY DISSIPATION DEVICES
USE (ED TC REPR(NTED	EC-11, SLOPE DRAINS EC-12, STREAMBANK STABILIZATION
THE USE (RESTRICTED TO REUSE, REPRO PROHIBITED	ec-13, polyacrylamide (Source: stormwater best management handbook) 5. Special care shall be taken so that no fill materials shall be placed, spread, or rolled during unfavorable weather conditions.
RES RE	SEDIMENT CONTROL
	1. SUFFICIENT QUANTITIES OF TEMPORARY SEDIMENT CONTROL MATERIALS WILL BE MAINTAINED ON-SITE THROUGHOUT THE DURATION OF THE PROJECT, TO ALLOW IMPLEMENTATION OF TEMPORARY EVENT OF PREDICTED RAIN AND FOR RAPID RESPONSE TO FAILURES OR EMERGENCIES.
	 DISCHARGERS SHALL ESTABLISH AND MAINTAIN EFFECTIVE PERIMETER CONTROLS AND STABILIZE ALL CONSTRUCTION ENTRANCES AND EXITS TO SUFFICIENTLY CONTROL EROSION AND SEDIMENT DISCHARGERS SHALL EFFECTIVELY MANAGE ALL RUN-ON, ALL RUNOFF WITHIN THE SITE AND ALL RUNOFF THAT DISCHARGES OFF THE SITE. RUN-ON FROM OFF-SITE SHALL BE DIRECTED AWAY FROM A
	 COLLECTIVELY BE IN COMPLIANCE WITH THE EFFLUENT LIMITATION OF THIS PERMIT. 4. DISCHARGERS SHALL APPLY LINEAR SEDIMENT CONTROLS ALONG THE TOE OF THE SLOPE, FACE OF THE SLOPE, AND AT THE GRADE BREAKS OF EXPOSED SLOPES. 5. DISCHARGERS SHALL ENSURE THAT CONSTRUCTION ACTIVITY TRAFFIC TO AND FROM THE PROJECT IS LIMITED TO ENTRANCES AND EXITS THAT EMPLOY EFFECTIVE CONTROLS TO PREVENT OFFSITE TRAFT
	 DISCHARGERS SHALL ENSURE THAT ALL STORM DRAIN INLETS AND PERIMETER CONTROLS, RUNOFF CONTROL BMPS, AND POLLUTANT CONTROLS AT ENTRANCES AND EXITS (E.G. TIRE WASHOFF LOC, PROTECTED FROM ACTIVITIES THAT REDUCE THEIR EFFECTIVENESS.
	 DISCHARGERS SHALL INSPECT ON A DAILY BASIS ALL IMMEDIATE ACCESS ROADS DAILY. AT A MINIMUM DAILY (WHEN NECESSARY) AND PRIOR TO ANY RAIN EVENT, THE DISCHARGER SHALL REMOVE ANY SEDIMENT OR OTHER CONSTRUCTION ACTIVITY RELATED MATERIALS THAT ARE DEI
	VACUUMING OR SWEEPING). 9. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TEMPORARY AND FINAL SEDIMENT CONTROL DURING CONSTRUCTION WHERE APPLICABLE: SE-1, SILT FENCE
	SE-2, SEDIMENT BASIN SE-3, SEDIMENT TRAP
	SE-4, CHECK DAMS SE-5, FIBER ROLLS
	SE-6, GRAVEL BAG BERM SE-7, STREET SWEEPING AND VACUUMING SE-8, SANDBAG BARRIER
	SE-0, STRAW BALE BARRIER SE-10, STORM DRAIN INLET PROTECTION
	SE-11, CHEMICAL TREATMENT (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK)
бм,	TRACKING CONTROL 1. TRACKING CONTROLS SHALL BE IMPLEMENTED AND MAINTAINED YEAR-ROUND AND THROUGHOUT THE DURATION OF THE PROJECT, AT ALL ACCESS (INGRESS/EGRESS) POINTS TO THE PROJECT SITE
Plan.dwg	EQUIPMENT MAY TRACK SEDIMENT FROM THE CONSTRUCTION SITE ONTO PUBLIC OR PRIVATE ROADWAYS. 2. IN GENERAL, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TRACKING CONTROL DURING CONSTRUCTION WHERE APPLICABLE:
Grading	TC-1, STABILIZED CONSTRUCTION ENTRANCE/EXIT TC-2, STABILIZED CONSTRUCTION ROADWAY
	TC-3, ENTRANCE/OUTLET TIRE WASH (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK)
124107	WIND EROSION CONTROL WIND EROSION CONTROL BMPS SHALL BE IMPLEMENTED AND MAINTAINED YEAR-ROUND AND THROUGHOUT THE DURATION OF THE PROJECT ON ALL DISTURBED SOILS ON THE PROJECT SITE THAT A
/ <i>ø</i> /	EROSION, AND WHEN SIGNIFICANT WIND AND DRY CONDITIONS ARE ANTICIPATED DURING PROJECT CONSTRUCTION. THE OBJECTIVE OF WIND CONTROLS IS TO PREVENT THE TRANSPORT OF SOIL FROM PROJECT SITE BY WIND.
PB\d	2. IN GENERAL, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE WIND EROSION CONTROL DURING CONSTRUCTION WHERE APPLICABLE: WE-1, WIND EROSION CONTROL (SOURCE: STORAWATER BEST MANAGEMENT HANDROOK)
Congress	(source: stormwater best management handbook) NON-STORMWATER MANAGEMENT POLLUTION CONTROL
Conç	1. NON-STORM WATER DISCHARGES CONSIST OF ALL DISCHARGES TO/FROM A MUNICIPAL STORM WATER CONVEYANCE, WHICH DO NOT ORIGINATE FROM PRECIPITATION EVENTS (I.E., ALL DISCHARGES SYSTEM OTHER THAN STORM WATER).
-2821	 DISCHARGERS SHALL IMPLEMENT MEASURES TO CONTROL ALL NON-STORM WATER DISCHARGES DURING CONSTRUCTION. DISCHARGERS SHALL WASH VEHICLES IN SUCH A MANNER AS TO PREVENT NON-STORM WATER DISCHARGES.
Tectonic– 3am	 DISCHARGERS SHALL CLEAN STREETS IN SUCH A MANNER AS TO PREVENT UNAUTHORIZED NON-STORM WATER DISCHARGES. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE NON-STORMWATER MANAGEMENT POLLUTION CONTROL WHERE APPLICABLE: NS-1, WATER CONSERVATION PRACTICES
1	NS-1, WATER CONSERVATION PRACTICES NS-2, DEWATERING OPERATIONS NS-3, PAVING AND GRINDING OPERATIONS
124107 - 10:1	NS-4, TEMPORARY STREAM CROSSING NS-5, CLEAR WATER DIVERSION
rojects \ 12 2024	NS-6, ILLICIT CONNECTION/ILLEGAL DISCHARGE DETECTION AND REPORTING NS-7, POTABLE WATER / IRRIGATION NS-8, VEHICLE AND FOURMENT CLEANING
ojec 2(NS-8, VEHICLE AND EQUIPMENT CLEANING NS-9, VEHICLE AND EQUIPMENT FUELING

NS-10, VEHICLE AND EQUIPMENT MAINTENANCE NS-11, PILE DRIVING OPERATIONS NS-12, CONCRETE CURING

NS-13, MATERIALS AND EQUIPMENT USE OVER WATER NS-14, CONCRETE FINISHING

NS-15, STRUCTURE DEMOLITION/REMOVAL NS-16, TEMPORARY BATCH PLANTS

(SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK)






2 EXTERIOR PORCELAIN TILE OR LIMESTONE- LIGHT GRAY 24X48 SAMPLE



3 EXTERIOR PORCELAIN TILE - LIGHT GRAY 8X48- WOOD PLANK SAMPLE

2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA



SITE PLAN SCALE: 1/8" : 1'

<u>MATERIAL LIST</u>

- 1 CONCRETE PAVER SEE LANDSCAPE DWGS
- 2 EXTERIOR PORCELAIN TILE OR LIMESTONE- LIGHT GRAY 24X48
- 3 EXTERIOR PORCELAIN TILE LIGHT GRAY 8X48- WOODPLANK
- 4 METAL ROOF SNAP CLAD PANEL
- 5 SINGLE PLY ROOFING- CARLIE FLEECBACK TPO, WHITE
- 6 RETAILING WALL SEE LANDSCAPE DWGS
- 7 IRON FENCE PAINTED BLACK SEE LANDSCAPE DWGS

PROJECT INFORMATION

LOT: FAR: LOT COVERAGE:	35% 35%	19,218 SF 6,726 SF 6,726 SF
MAIN HOUSE	(5 MAS	TERS)
LOT COVERAGE	35%	6,726 SF
1ST FLOOR: GARAGE: PATIO: PORCH: TOTAL	28%	3,420 SF 682 SF 553 SF 628 SF 5,283 SF OK
<u>FAR AREA</u> 1ST FLOOR: GARAGE: 2ND FLOOR:		3,420 SF 682 SF 2,023 SF
TOTAL:	32%	6,125 SF OK

WATER SHED CALCULATION IMPERVIOUS AREA MAX.: 9,000SF

DRIVEWAY PAVER:	2,597 SF
PATIO:	553 SF
PORCH:	628 SF
LANDING:	24 SF
1ST FLOOR:	3,420 SF
GARAGE:	682 SF
TRASH ENCLOSURE PAD:	37 SF
TOTAL	7,941 SF OK


ADJACENT PROPERTY

∠ N



SITE PLAN

1ST PLANNING SUBMITTAL - COUNTY





2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA

SITE PLAN WITH (E) TOPO SCALE: 1/8" : 1'

NOTES:


- FOR GRADING, DRAINAGE, EROSION, CUT AND FILL INFORMATION SEE CIVIL PLAN
- FOR TREE DETAIL INFORMATION SEE LANDSCAPE PLAN AND ARBORIST
- REPORT AVERAGE GROUND ELEVATION (

AVERAGE (E) GROUND ELEVATION:

WEST	EL: 240.00'
NORTH	EL: 248.00'
EAST	EL: 248.00'
SOUTH	EL: 242.40'

AVERAGE: EL: 244.60'

LEGEND




(E) TREE TO BE REMOVED SEE LANDSCAPE PLAN AND ARBORIST REPORT FOR DETAIL



(E) TREE

ADJACENT PROPERTY


SITE PLAN W/ TOPOGRAPHIC TREE REMOVAL INFO.

















2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA




SECOND FLOOR PLAN

1ST PLANNING SUBMITTAL - COUNTY DATE 09-26-24 Tectonic Architects & Associates 10118 Bandley Dr. #E Cupertino, CA 95014 408-216-0804







2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA








10118 Bandley Dr. #E Cupertino, CA 95014 408-216-0804


A2



2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA








CHING RESIDENCE 2821 2821 CONGRESS RD., PEBBLE BEACH, CALIFORNIA











LUMENS

Andare Up and Down Outdoor Wall Light By Huxe


Andeuw Up and Down Ostdoor Wali Light By Hase

Product Options

MATERIAL LIST

1 STUCCO - PAINTED

ELEVATIONS





PLANT LEGEND AND NOTES

Symbol	Species	Size	Water	MICOLS
	Arctostaphylos Little Sur/Manzanita @60'' oc	l qallon	low	.2
	Achillea millefolium/ Yarrow @ 4811 oc	l qallon	low	.2
	Juncus patens/California Rush @ 36'' oc	l qallon	low	.2
A	Salvia Allen Chickering/Sage	5 qallo	n low	.2
в	Ribes sanquineum/Red Currant	5 qallo	n low	3
TI	Quercus agrifolia/Coast Live Oak	15 qall	on low	.2
12	Pinus radiata/Monterey Pine	15 qall	on med	,5


1) Preparation of soil to be on an individual plant basis to protect the roots of existing trees to remain.

2) Incorporate compost into soil backfill.

3) Provide all required tree protection measures per the project arborist report and as determined in the field. Protection measures shall be to the satisfaction of the project arborist and the planning department.

4) Verify placement of all plant material prior to planting. Adjust as needed based on proximity to existing trees and project construction.

5) All plant material to be sourced from local nurseries only. Resources Code (PRC) Section 4291, only trees grown from locally collected seeds from trees uninfected with pitch canker or Phytophthora ramorum should be used. Special care should be taken to avoid contamination of seedlings with diseased materials. Trees propagated from nonnative genetic stock should not be used in landscaping and forest restoration. 6) Spread 3" of wood chip (Prochip Brown Tone, or equal) mulch around the base of all new planting only not in open areas and not within the 5' fire defense zone around the foundation of the house.



 \mathbf{X}

From Denise Duffy & Associated, Inc./Planning and Environmental Consulting - 9/17/24 (36) 11 - Quercus agrifolia/Coast Live Oak require for mitigation - (9) proposed at 15 gallon (3) T 2 Pinus radiata/Monterey Pine required for mitigation - (3) proposed at 15 gallon See report for other mitigation measures.

Existing tree to remain (Q) for Quercus/Oak, (P) for Pinus/Pine

Existing tree to be removed

LIGHTING LIGEND

- Low voltage black down lit path/driveway light - FX or equal

1) Verify placement of all landscape lighting at front yard.

2) All lighting to be directed downwards. 3) Verify electrical and location of transformer.

4) All work to be done according to local and state electrical code.

LOT 10

'AVEMENT


236.71






QUERCUS


PINUS




MASTER LANDSCAPE PLAN |/8" = |'-0"



date: 3,	/ 16/ 24
scale:	NOTED
drawn by:	HLW
job no. 💈	202404
sheet 1	
of sht	• 6






W. Jeffrey Heid Landscape Architect C-2235

1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wjheidasla@qmail.com

OWNERSHIP AND USE OF DRAWINGS

ll drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Project and are not to be used on any other project. Submission or distribution to meet official regulatory equirements or for other purposes in connection with the Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect , common law, copyright or other reserved rights.





CHING RESIDENCE

for: LILLY CHING 2821 CONGRESS ROAD PEBBLE BEACH, CA. 93953

TREE PLAN

9/9/24 date: drawn job no. sheet

Recommendation

Zone O: Ember Resistant Zone This is the ember resistant zone, which extends 5 feet from buildings, structures, stairs, decks, etc. A properly managed Zone O reduces the likelihood of structure ignition by reducing the potential for flame contact. Flames can be generated from embers that accumulate at the base of a wall and ignite vegetation, vegetative debris, or other combustible materials located close to the structure. Zone O is a critical component of structure defense and, when coupled with Zone 1 and Zone 2, is essential to defensible space. Management of the ember-resistant zone is now required by law (Assembly Bill [AB] 3074) beginning January I, 2023,3 This zone includes the area under and around all attached decks and requires the most stringent wildfire fuel reduction. The ember-resistant zone is designed to keep fire or embers from igniting materials that can spread the fire to the home. Backyards are considered Zone O. The following provides maintenance quidance for this zone.

* Use hardscape like gravel, pavers, concrete, and other noncombustible mulch materials. No sunthetic lawns, combustible bark, woodchips, or mulch. No lumber or round logs, railroad ties, or creosote-treated or pressure-treated wood. * No combustible attached trellis, pergola, shade covering, planters, privacy wall, etc.; no combustible storage structures (e.g., woodsheds, potting bench, etc.); and replace combustible fencing, gates, and arbors attached to the home with noncombustible alternatives.

* Wooden fences should not be directly attached to the residence, and a 10-foot non-combustible section (e.g., metal gate) should be placed between the wooden section of the fence and the house.

* Potted plants should not exceed 2 feet in vegetation height and must be contained in non-combustible containers (no wooden planter boxes, wine barrels, etc.).

* Remove all dead and dying weeds, grass, plants, shrubs, trees, branches, and vegetative debris (i.e., leaves, needles, cones, bark, etc.). * Check roofs, autters, decks, porches, stairways, etc. for accumulated debris, leaf litter, and other flammable materials; clean regularly.

* Remove all branches within 10 feet of any chimney or stovepipe outlet. * Limit plants in this area to low-growing, nonwoody, properly maintained plants.

* Limit combustible items (e.g., autobor furniture, planters, etc.) on top of decks.

* Trim and prune woody vegetation that extends into Zone O. No trees should be planted if their canopy at maturity can be expected to extend closer than 5 feet to the structurells roof, balcony, decks, or exterior wall (10 feet from any chimney or stovepipe outlet).

* Consider relocating garbage and recycling containers, woodsheds, and BBQs (propane) autside this zone.

Zone I: Lean, Clean, and Green Zone

Zone I is the second layer of a defensible perimeter around a residential structure in wildfire prone areas. It is designed to provide an additional level of protection for the building or structure, extending from 5 feet to 30 feet away from the structure and any attached balconies, patios, or outbuildings. The goal of fuel management in Zone | is to remove excess vegetation and to maintain the landscaping in a way that reduces ignition of the structure via heat transfer from burning vegetation. It also provides firefighters with space and access to protect the structure in case of a wildfire.

Fuel management in Zone | involves mowing, removing dead or duing plants, ladder fuels, pruning vegetation, and hauling away all materials, Remove branches that overlap with the root or are closer than 10 feet from windows and chimneys. Dead vegetation removal includes fallen leaves, needles, twigs, bark, cones, and small branches. Cut and mow annual grass and herbaceous plants down to a height of 4 inches, Mow before 10:00 a.m. and never on a hot or windy day. String trimmers are a safer option (versus lawnmowers) for clearing vegetation. Avoid removing all vegetation to bare soil, as this may cause erosion.


Vertical Spacing. An important aspect of vegetation management in Zone 1 is vertical spacing of trees, shrubs, and grasses (see Figure 7). Large trees do not need to be cut and removed as long as they fulfill the horizontal spacing requirement (see below) and all of the plants beneath them are managed to remove vertical fuel ladders. Healthy trees should be pruned (1.e., limbed) at least 6 feet from the ground. Allow extra vertical space between shrubs and trees. Lack of vertical space can allow a fire to move from the ground to the brush to the treetops like a ladder. This leads to more intense fire closer to the home. To create vertical spacing and reduce fuel ladders created bu shrubs under trees, tree branches should be limbed to a height of at least three times the height of the shrub.

* Place any woodpiles in Zone 2; establish a 10-foot clearance down to bare mineral soil around woodpiles.


* Wood mulch is acceptable in Zone | if there is a transition from Zone | to Zone O and if the vegetation in Zone I is grouped/clumped with the required horizontal distance.


Zone 2: Fuel Reduction Zone

Fuel management in this zone aims at reducing the potential behavior of an oncoming fire to prevent rapid spread of wildfire from plant to plant and to reduce flame lengths. Zone 2 actions reduce the amount of fuels, especially dead vegetation (e.g., leaves, needles, twigs, bark, cones, and small branches), Grasses and herbaceous vegetation should be mowed to a height of 4 inches. Mowing should occur before 10:00 a.m. and never on a hot or windy day. String trimmers are preferred, because they pose a low risk of sparking. Spacing of trees and shrubs is similar to that of Zone I, with a greater focus on vertical spacing (1.e., no ladder fuels). Horizontal space between trees should maintain a gap of at least 10 feet from the next tree. Where canopies overlap, selective removal of smaller trees can maintain the desired horizontal and vertical spacing of trees. Overlapping tree canopies should be avoided. Shrubs may be appreciated in clumps or islands that are well isolated from the surrounding shrubs and tree canopies. Spacing of shrubs and trees along fences should be managed according to the requirements of Zone O (i.e., 5-foot clearance to all structures).



|/8" = |'-0"







Maintain a vertical clearance between shrubs and trees. Example: A five foot shrub is growing near a tree. 3x5 =and the lowest tree branch.

Reference Evapotranspiration (ET _a)		36	Pro	Efficient Landscape Project Type			
	Plant	Irrigation	Irrigation	ETAF	Landscape	ETAF x	Estimated Total
Description ^a	Factor (PF)	Method ^t	Efficiency	(PF/IE)	Area (Sq. Ft)	Area	Water Use
2			(IE) ^c				(ETWU) ^d
Regular Landscape	Areas						•
#1 low water	0.2	Drip	0.81	0.25	575	142	316
#2 low water	0.2	Drip	0.81	0.25	195	48	107
#3 low water		Drip	D.81	0.25	210	52	115
#4 low water		Drip	0.81	0.37	225	83	186
#5 oak tree low water	0.2	Drip	0.81	0.25	1305	322	719
#6 pine tree med wate	0.5	Drip	D.81	0.62	435	269	599
•			D.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			D.75			0	
			D.75			0	
			0.75	0.00		0	
			D.75	0.00		0	
			0.75	0.00		0	
			0.75	0.00		0	
			•	Totals	2945	916	2044
Special Landscape A	reas						•
				1		0	
				1		0	
				1		0	
				1		0	
				Totals	0	0	
					ETV	/U Total	2044
		Ma	iximum Allowe	ed Wate	r Allowance (I	MAWA) ^e	3615
ETAF Calculations			-				
Regular Landscape Ar			Average ETA				
Total ETAF x Area	916	4	Landscape A below for res				
Total Area	2945		0.45 or below				
Average ETAF	0.31	J	21026			J	
All Landages Ares							
All Landscape Areas Total ETAF x Area	040	1					
Total ETAF x Area	916 2945	-					
LORAL ALEA	Z945	1					

- * Hydrozone # / Planting Description e.g. 1.) Front lawn
- 2.) Low water use planting 3.) Medium water use planting
- ^b Irrigation Method 1.) Overhead Spray 2.) Drip
- ^c Irrigation Efficiency
- 1.) 0.75 for Overhead Spray 2.) 0.81 for Drip
- ^d ETWU (Annual Gallons Required) =
- Eto x 0.62 x ETAF x Area Where 0.62 is a conversion factor to change acre-inches per acre per year to gallons per square foot per year • MAWA (Annual Gallons Allowed) =
- (Eto) (0.62) [(ETAF x LA) + ((1-ETAF) x SLA)] Where 0.62 is a conversion factor to change acre-inches per acre per year to gallons per square foot per year, LA is the total regular landscape area in square feet, SLA is the total special landscape area in square feet, and ETAF is 0.55 for residential areas and 0.45 for non-residential areas

0.45	Non-Residential
0.55	Residential
0.81	
0.75	Overhead
	0.55 0.81







1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wjheidasla@qmail.com

W. Jeffrey Heid Landscape Architect C-2235

OWNERSHIP AND USE OF DRAWINGS

All drawings, specifications and copies thereof furnished by

W. Jeffrey Heid Landscape Architect are and shall remain its

property. They are to be used only with respect to this

Project and are not to be used on any other project.

Submission or distribution to meet official regulatory

the Project is not to be construed as publication in

derogation of W. Jeffrey Heid Landscape Architect ,

common law, copyright or other reserved rights.

requirements or for other purposes in connection with

REVISED 5/11/24

REVISED 9/20/24 REVISED 11/15/24

HYDROZONE PLAN

LILLY CHING 2**821 CONGRESS ROAD** PEBBLE BEACH, CA. 93953

TO LANDSCAPE

No. 2235

Signature


EXPIRATION DATE: 06/30/2025


CHING

RESIDENCE

for:

3/18/24 date: NOTED HLW drawn by: 202404 job no. sheet shts





W. Jeffrey Heid Landscape Architect ^{C-2235} 1465 Winzer Place Gilroy, Ca. 95020 tel 408 691-5207 email wjheidasla@qmail.com OWNERSHIP AND USE OF DRAWINGS Il drawings, specifications and copies thereof furnished by W. Jeffrey Heid Landscape Architect are and shall remain its property. They are to be used only with respect to this Project and are not to be used on any other project Submission or distribution to meet official regulatory equirements or for other purposes in connection with the Project is not to be construed as publication in derogation of W. Jeffrey Heid Landscape Architect , common law, copyright or other reserved rights. REVISED 5/11/24 REVISED 9/9/24 REVISED 9/20/24 REVISED 11/15/24 OFO LANDSCAPE TO PIRATION DA CHING RESIDENCE

for: LILLY CHING 2821 CONGRESS ROAD PEBBLE BEACH, CA. 93953

DETAILS

date: 3/18/24 NOTED scale: HLW drawn by: job no. 202404 sheet shts