Before the Zoning Administrator in and for the County of Monterey, State of California

In the matter of the application of:

DEL SANTO (PLN180551) RESOLUTION NO. 19-025

Resolution by the Monterey County Zoning Administrator:

- 1) Finding the project qualifies as a Class 3
 Categorical Exemption pursuant to Section
 15303(a) of the CEQA Guidelines, and there
 are no exceptions pursuant to Section
 15300.2 were found; and
- 2) Approve a Design Approval to allow the demolition of an existing 3,408 square foot single-family dwelling and construct a 2,789 square foot above ground two story single-family dwelling with a 1,200 square foot subterranean basement and 273 square foot attached garage.

1000 Rodeo Road, Pebble Beach, Greater Monterey Peninsula Area Plan (APN: 007-312-001-000)

The Del Santo application (PLN180551) came on for a public hearing before the Monterey County Zoning Administrator on August 8, 2019. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Zoning Administrator finds and decides as follows:

FINDINGS

1. FINDING: CONSISTENCY / HEALTH AND SAFETY / NO VIOLATIONS

/ SITE SUITABILITY - The proposed project and/or use, as conditioned, is consistent with the policies of the Monterey County 2010 General Plan, Greater Monterey Peninsula Area Plan, Monterey County Zoning Ordinance (Title 21), and other County health, safety, and welfare ordinances related to land use development. The site is physically suitable for the development proposed, and no violations exist on the property.

EVIDENCE: a) The proposed project involves the demolition of an existing 3,408 square foot single-family dwelling and construction a 2,789 square foot two story single-family dwelling with a 1,200 square foot basement and 273 square foot attached garage.

b) The property is located at 1000 Rodeo Road in Pebble Beach (Assessor's Parcel Number 007-312-001-000), Greater Monterey Peninsula Area Plan. The parcel is zoned Medium Density Residential, with a Building Site, Design Control, and Parking & Use of Major Recreational Equipment Storage in Seaward zoning

- overlays (MDR/B-6-D-RES). Development of single-family dwellings is an allowed uses pursuant to MCC Sections 21.12.030.A. The Design Control zoning overlay requires the granting of a Design Approval for the proposed development (see Finding No. 2 below).
- c) The project has been reviewed for consistency with the text, policies, and regulations in:
 - the 2010 Monterey County General Plan;
 - Greater Monterey Peninsula; and
 - Monterey County Zoning Ordinance (Title 21)
- d) No conflicts were found to exist. No communications were received during the course of review of the project indicating any inconsistencies with the text, policies, and regulations in the applicable documents.
- Review of Development Standards. The development standards for e) the MDR zoning district in the Del Monte Forest are identified in MCC Section 21.12.070. Special required setbacks in the MDR district for main dwelling units are 20 feet (front), and 10 feet first story and 20 feet second story (sides). The proposed dwelling has a 20 feet (front), and 10 feet first story and 20 feet second story (side) setbacks. Corresponding maximum structure height is 27 feet. The proposed height for the single-family dwelling is 27 feet. The allowed maximum floor area coverage in the MDR district is 35 percent. The property is 9,745.15 square feet, which would allow floor area coverage of approximately 3,360 square feet. The proposed single-family dwelling and garage would result in site coverage of approximately 3,062 square feet or 31.4 percent. The building site coverage allowance for the MDR zoning district is also 35 percent. The proposed dwelling and garage would result in building site coverage of approximately 2,994 square feet or 30.7 percent. The 1,200 square feet basement is not calculated in the floor area since it is constructed below ground. Therefore, as proposed, the project meets all required development standards.
- f) The project has been reviewed for site suitability by RMA-Planning. The project planner reviewed the application materials and plans along with the County's GIS database to verify that the proposed project on the subject site conforms to the applicable plans, and that the site is suitable for the proposed development. The project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
- g) The following technical reports has been prepared:
 - Historic Report (LIB190198) prepared by Anthony Kirk, Inc., Los Gatos, California, June 2019.
 - Preliminary Cultural Resources Reconnaissance of APN 007-312-001-000 (LIB190191) prepared by Susan Morley, Marina, California, February 2019.

County staff has independently reviewed these reports and concur with their conclusions.

- h) Necessary public facilities are available. The sewer for the site will be served by Pebble Beach Community Services District and water will be served by Cal-Am.
- i) Design. See Finding No. 2.

- Archaeology. The project is in an area mapped as being high in j) archaeological sensitivity. Because the site is within an area of high archeological sensitivity, a report (LIB190191) was prepared for this property. The report found no surface evidence or previously recorded information that the site contains potentially significant archaeological resources. Because the project includes a basement and because it cannot be determined with certainty what lies beneath the soil, a standard condition has been included in the project that requires work to stop and notification of the County and a qualified archaeologist if previously unidentified resources are discovered during construction. Currently there is an existing single family dwelling with a mechanical basement. Proposed construction of the new single family dwelling would be over the building footprint of the existing house with a full basement. Estimated quantities are 1,500 cubic yards of cut and five cubic yards of fill.
- k) Monterey County RMA-Planning and RMA-Building Services records were reviewed, and the County is not aware of any violations existing on subject property.
- The project planner conducted a site inspection on March 7, 2019 to verify that the proposed project on the subject parcel conforms to the applicable plans and MCC.
- m) The project was referred to the Del Monte Forest Land Use Advisory Committee (LUAC) for review. Based on the LUAC Procedure guidelines adopted by the Monterey County Board of Supervisors, this application warranted referral to the LUAC because the project is a Design Approval subject to review by the Zoning Administrator. The LUAC, at a duly-noticed public meeting on March 7, 2019 voted 4 0 to support the project as proposed with 2 absent.
- n) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in project file PLN180551.

2. **FINDING:**

DESIGN – The design of the proposed project assures protection of the public viewshed, is consistent with neighborhood character, and assures visual integrity without imposing undue restrictions on private property.

EVIDENCE: a)

- The applicant proposes a single-family dwelling and an attached garage on an existing residential lot. The proposed dwelling incorporates architectural aesthetics Colonial modern style.
- b) Pursuant to Chapter 21.44, Title 21 (Zoning Ordinance) of the Monterey County Code (MCC), the proposed project site and surrounding area are designated as a Design Control Combining District (D District), which regulates the location, size, configuration, materials, and colors of structures and fences to assure the protection of the public viewshed and neighborhood character.
- c) <u>Material and Color Finishes</u>. The applicant proposes exterior colors and materials that are consistent with the residential setting. The primary colors and materials include gray cedar shingle siding, white wood trims and molding, stone veneer and white metal clad wood doors and windows. The proposed exterior finishes would blend with the surrounding environment, are consistent with the surrounding

- residential neighborhood character, and are consistent with other dwellings in the neighborhood.
- d) The proposed development is not visible from a common public viewing area; therefore, the proposed dwelling would not have an impact on a public viewshed and would not create a substantially adverse visual impact when viewed from a common public viewing area. As proposed, the project assures protection of the public viewshed, is consistent with neighborhood character, and assures visual integrity.
- f) Based on the evidence described above, the proposed structures and uses are consistent with the surrounding residential neighborhood character (i.e., structural design features, colors, and material finishes). As proposed, the project is consistent with neighborhood character, and assures visual integrity.
- g) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in project file PLN180551.
- 3. **FINDING:**

CEQA (Exempt) – The project is categorically exempt from environmental review and no unusual circumstances were identified to exist for the proposed project.

EVIDENCE:

- a) California Environmental Quality Act (CEQA) Guidelines Section 15303(a) categorically exempts the construction of new, small facilities or structures, including habitable and non-habitable structures accessory to a single-family dwelling or residential use.
- b) The subject project consists of the construction of a single-family dwellings with an attached garage. Therefore, the proposed development is consistent with the exemption parameters of CEQA Guidelines Section 15303(a).
- c) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. There is no substantial evidence of an unusual circumstance because there is no feature or condition of the project that distinguishes the project from the exempt class. The project does not involve a designated historical resource, a hazardous waste site, development located near or within view of a scenic highway. There is no substantial evidence that would support a fair argument that the project has a reasonable possibility of having a significant effect on the environment or that it would result in a cumulative significant impact.
- d) No adverse environmental effects were identified during staff review of the development application.
- 4. **FINDING:**

APPEALABILITY - The decision on this project may be appealed to the Monterey County Planning Commission.

EVIDENCE:

Pursuant to Section 21.80.040.B of the Monterey County Zoning Ordinance (Title 21), the Planning Commission shall consider appeals from the discretionary decisions of the Zoning Administrator. The decision of the Planning Commission would be final and may not be appealed.

DECISION

NOW, THEREFORE, based on the above findings and evidence, the Zoning Administrator does hereby:

- A. Find that the project is a single-family dwelling which qualifies as a Class 3 Categorical Exemption pursuant to Section 15303(a) of the CEQA Guidelines, and there are no exceptions pursuant to Section 15300.2; and
- B. Approve a Design Approval to allow the demolition of an existing 3,408 square foot single-family dwelling and construct a 2,789 square foot above ground two story single-family dwelling with a 1,200 square foot subterranean basement and 273 square foot attached garage.

In general conformance with the attached plans and subject to the attached condition, which are incorporated herein by reference.

PASSED AND ADOPTED this 8th day of August, 2019.

Mike Novo, Zoning Administrator

COPY OF THIS DECISION MAILED TO APPLICANT ON AUG 08 2019

THIS APPLICATION IS APPEALABLE TO THE PLANNING COMMMISSION. IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE SECRETARY OF THE PLANNING COMMISSION ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE _AUG_19_2019_.

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

NOTES

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.

Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from Monterey County RMA-Planning and RMA-Building Services Department office in Salinas.

This page intentionally left blank

Monterey County RMA Planning

Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN180551

1. PD001 - SPECIFIC USES ONLY

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure: This Design Approval (PLN180551) allows the demolition of an existing 3,408 square foot single family dwelling and construction of a 2,789 square foot two story single family dwelling with a 1,200 square foot basement and 273 square foot attached garage and appurtenant structures and fence. Outdoor fireplace height shall be no taller than adjacent fence. The property is located at 1000 Rodeo Road in Pebble Beach (Assessor's Parcel Number 007-312-001-000), Greater Monterey Peninsula Area Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the RMA Any use or construction not in substantial conformance with the Chief of Planning. terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA Planning)

Compliance or Monitoring Action to be Performed: The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

Print Date: 8/8/2019 11:25:26AM Page 1 of 4

2. PD002 - NOTICE PERMIT APPROVAL

Responsible Department:

RMA-Planning

Condition/Mitigation Monitoring Measure:

The applicant shall record a Permit Approval Notice. This notice shall state:

"A Design Approval (Resolution Number 19-025) was approved by the Zoning Administrator for Assessor's Parcel Number 007-312-001-000 on August 8, 2019. The permit was granted subject to six (6) conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

Responsible Department:

RMA-Planning

Condition/Mitigation Monitoring Measure:

during course of construction, cultural, archaeological, historical paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a qualified archaeologist (i.e., an archaeologist registered with the be immediately contacted Professional Archaeologists) shall by the When contacted, the project planner and the archaeologist individual present on-site. shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

Print Date: 8/8/2019 11:25:26AM Page 2 of 4

4. PW0044 - CONSTRUCTION MANAGEMENT PLAN

Responsible Department:

RMA-Public Works

Condition/Mitigation Monitoring Measure:

The applicant shall submit a Construction Management Plan (CMP) to RMA-Planning and RMA - Public Works for review and approval. The CMP shall include measures to minimize traffic impacts during the construction/grading phase of the project.

CMP shall include, at a minimum, duration of the construction, hours of operation, truck routes, estimated number of truck trips that will be generated, number of construction workers, and on-site/off-site parking areas for equipment and workers and locations of truck staging areas. Approved measures included in the CMP shall be implemented by the applicant during the construction/grading phase of the project.

Compliance or Monitoring Action to be Performed: 1. Prior to issuance of the Grading Permit or Building Permit, Owner/Applicant/Contractor shall prepare a CMP and shall submit the CMP to the RMA-Planning Department and the

Department of Public Works for review and approval.

2. On-going through construction phases Owner/Applicant/Contractor shall implement the

approved measures during the construction/grading phase of the project.

5. PD041 - HEIGHT VERIFICATION

Responsible Department:

RMA-Planning

Condition/Mitigation Monitoring Measure: The applicant shall have a benchmark placed upon the property and identify the benchmark on the building plans. The benchmark shall remain visible on-site until final building inspection. The applicant shall provide evidence from a licensed civil engineer or surveyor to the Director of RMA - Building Services for review and approval, that the height of the structure(s) from the benchmark is consistent with what was approved on the building permit associated with this project, and shall be at a maximum of 27 feet. (RMA - Planning and RMA - Building Services)

Compliance or Monitoring Action to be Performed:

Prior to the issuance of grading or building permits, the Owner/Applicant shall have a benchmark placed upon the property and identify the benchmark on the building plans. The benchmark shall remain visible onsite until final building inspection.

Prior to the foundation pre-pour inspection, the Owner/Applicant shall provide evidence from a licensed civil engineer or surveyor, to the Director of RMA- Building Services for review and approval, that the height of first finished floor from the benchmark is consistent with what was approved on the building permit.

Prior to the final inspection, the Owner/Applicant/Engineer shall provide evidence from a licensed civil engineer or surveyor, to the Director of RMA- Building Services for review and approval, that the height of the structure(s) from the benchmark is consistent with what was approved on the building permit.

Print Date: 8/8/2019 11:25:26AM Page 3 of 4

6. PW031-BOUNDARY SURVEY

Responsible Department: RMA-Public Works

Condition/Mitigation Monitoring Measure: Owner/Applicant shall have a professional land surveyor perform a boundary survey of the boundary lines of the subject parcel and have said lines monumented. (Public Works).

Compliance or Monitoring Action to be Performed:


Prior to foundation inspection, Owner/Applicant shall have a professional land surveyor survey and monument the boundary lines of the subject parcel and provide evidence to the County Surveyor of conformance to the setbacks shown on the approved Site Plan. The surveyor shall be responsible for compliance with the requirements of Section 8762 of the California Business and Professions Code (PLS Act).


Print Date: 8/8/2019 11:25:26AM Page 4 of 4

Del SANTO RESIDENCE

1000 RODEO ROAD PEBBLE BEACH, CA 93953

REVISION







OPOSED SITE PLAN

ARCHITECT


SET OF SUMMER SET OF STEPLAN

JOB NAME: DelSanto Residence 1000 Rodeo Road Pebble Beach, CA A.P.N. 007-312-001

ARCHITECT

ERIC MILLER ARCHITECTS, INC.

211 HOFFMAN AVENUE MONTEREY, CA 93940 Pebble Beach, CA A.P.N. 007-312-001



MANAGEMENT

1. CONSTRUCTION VEHICLES SHALL NOT PARK ON OCEAN ROAD OR RODEO ROAD. OFF SITE PARKING SHALL BE PROVIDED FOR CONSTRUCTION WORKERS.

2. LIMITED PARKING SHALL BE AVAILABLE ON THE SITE FOR TEMPORARY ACCESSIBILITY TO THE SITE.

3. NO CONSTRUCTION SHALL OCCUR DURING MAJOR EVENTS SPECIFIED BY PEBBLE BEACH SUCH AS THE AT\$T AND CONCOURSE IN ADDITION TO THE STANDARD PEBBLE BEACH REQUIREMENTS FOR CONSTRUCTION DAYS AND HOURS.

4. GENERAL CONTRACTOR SHALL MORK MITH NEIGHBORS ON A DAILY BASIS, OR AS REQUIRED.

E CONSTRUCTION MANAGEMENT PLAN

ARCHITECT

ERIC MILLER ARCHITECTS, INC.

211 HOFFMAN AVENUE MONTEREY, CA 93940
PHONE (831) 372-0410 FAX (831) 372-7840 WEB: www.ericmillerarchitects.com


CONSULTANT: REVISION


|0/|8/|8

DelSanto Residence

A.P.N. 007-3|2-00|

1000 Rodeo Road Pebble Beach, CA





BASEMENT FLOOR PLAN


DelSanto Residence 1000 Rodeo Road Pebble Beach, CA A.P.N. 007-312-001


ARCHITECT

ERIC MILLER ARCHITECTS, INC.

211 HOFFMAN AVENUE MONTEREY, CA 93940
PHONE (831) 372-0410 • FAX (831) 372-7840 • WEB: www.ericmillerarchitects.com

CONSULTANT:






SECOND FLOOR PLAN


DelSanto Residence 1000 Rodeo Road Pebble Beach, CA A.P.N. 007-312-001


ERIC MILLER ARCHITECTS, INC. : 211 HOFFMAN AVENUE MONTEREY, CA 93940

PHONE (831) 372-0410 FAX (831) 372-7840 WEB: www.ericmillerarchitects.com

ARCHITECT







NORTH ELEVATION


SCALE: 1/4"= 1'-0"


REVISION

ERIC MILLER
211 HOFFMAN AVENUE
PHONE (831) 372-0410 - FAX (831) 3

10/18/18 DATE: 1/4"=1'-0" SCALE:

DRAWN: JOB NUMBER:





REVISION






CHIMNEY CAP WITH METAL SPARK



PATH LIGHT - 25W COPPER FINISH



SIDE WALL LIGHT - 25W COPPER FINISH



TRENCH GRATE

DRAIN COVER

DRAINAGE GRATES

(10) WOOD GATE

URBAN ACCESSORIES-OT



WOOD WINDOWS & DOORS



WOOD - BROWN STAIN **GARAGE DOOR**



LAMP - LED-25 WATT EQUIVALENT FINISH - BLACK MATT GLAZING - HEAVY SEEDY





SLATE TILE



REVISION

COPPER STANDING SEAM






WHITE POWDER COAT **GUTTER &**



SHINGLE SIDING



STONE VENEER


FOR REFERENCE ONLY



DOWNSPOUT



EXTERIOR COLORS



DRAWN: JOB NUMBER:

10/18/18




ARRESTOR




COLUMN STYLE




PATIO PAVING



FRONT WALK PAVING



(11) STEEL WINDOW WALL




GRADING, DRAINAGE & EROSION CONTROL PLAN

DEL SANTO RESIDENCE

APN: 007-312-001

PEBBLE BEACH, MONTEREY COUNTY, CALIFORNIA



VICINITY MAP

GENERAL NOTES:

- 1) PROJECT DESIGN BASED ON INFORMATION PROVIDED AND SHOWN ON THE SITE PLAN FOR TH DEL SANTO RESIDENCE, AND THE BASE TOPOGRAPHIC INFORMATION PREPARED BY LANDSET ENGINEERS
- SURFACE ARE SHOWN. SUB-SURFACE UTILITY LINES DRAWN MAY NOT BE COMPLETE AND SHOULD BE VERIFIED BY FIELD RECONNAISSANCE. UNDERGROUND UTILITY LOCATIONS CAN BE OBTAINED FROM THE APROPRIATE UTILITY COMPANIES, PUBLIC AGENCIES, OWNER'S AS-BUILT DRAWINGS, ETC., AND SHOULD BE THROUGHLY COMPILED AND DEEMED COMPLETE WITH THE PROJECT AREA, PRIOR TO ANY SITE DEVELOPMENT DESIGN AND/OR CONSTRUCTION
- 3) THIS MAP PORTRAYS THE SITE AT THE TIME OF THE SURVEY AND DOES NOT SHOW SOILS OR GEOLOGY INFORMATION, UNDERGROUND CONDITIONS, EASEMENTS, ZONING OR REGULATORY OR ANY OTHER ITEMS NOT SPECIFICALLY REQUESTED BY THE PROPERTY OWNER.
- 4) THIS MAP DOES NOT REPRESENT A BOUNDARY SURVEY.

GRADING & DRAINAGE NOTES:

- 1) ALL GRADING SHALL CONFORM TO THE MONTEREY COUNTY GRADING ORDINANCE AND EROSION CONTROL ORDINANCE. THE RECOMMENDATIONS FOUND IN THE PROJECT SOIL'S ENGINEERING INVESTIGATION PREPARED BY ? LANDSET ENGINEERS, INC. PROJECT No. XXX, DATED JAN. XX, 2017, THE LATEST VERSION OF THE CALTRANS SPECIFICATIONS, THE GOVERNING PUBLIC AGENCIES, THE 2016 CALIFORNIA BUILDING CODE (CBC) AND THESE PLANS.
- 2) SURFACE ORGANICS SHALL BE STRIPPED AND STOCKPILED FOR LATER USE AS TOPSOIL MATERIAL ACTUAL GRADING SHALL BEGIN WITHIN 30 DAYS OF VEGETATION REMOVAL OR THE AREA SHALL BE PLANTED TO CONTROL EROSION.
- 3) NO ORGANIC MATERIAL SHALL BE PERMITTED IN FILLS EXCEPT AS TOPSOIL USED FOR SURFACE PLANT GROWTH ONLY AND WHICH DOES NOT EXCEED 4" IN DEPTH.
- 4) THERE ARE APPROXIMATELY 1500 C.Y. OF CUT AND 5 C.Y. OF FILL WITH AN EXPORT OF 1495 C.Y. EXCAVATION SHALL BE USED FOR EMBANKMENT CONSTRUCTION, LANDSCAPE PURPOSES AND/OR HAULED OFF-SITE. ADDITIONAL ON-SITE SPOILS GENERATED FROM FOUNDATIONS, UTILITY TRENCHES, SEPTIC CONSTRUCTION, ETC. IS NOT INCLUDED IN THE ABOVE REFERENCED QUANTITIES. IMPORT MATERIAL SHALL MEET THE REQUIREMENTS OF SELECT STRUCTURAL FILL AS NOTED IN THE SOIL'S REPORT AND BE APPROVED BY THE SOILS ENGINEER PRIOR TO PLACEMENT.
- 5) EMBANKMENT MATERIAL SHALL BE PLACED IN 8" LOOSE LIFTS, MOISTURE CONDITIONED, AND COMPACTED TO 90% MIN. REL. COMPACTION. ALL BASEROCK AND THE UPPER 12" OF SUBGRADE SHALL BE COMPACTED TO 95% MIN. REL. COMPACTION.
- 6) ALL CUT AND FILL SLOPES SHALL BE 2:1 OR FLATTER. STEEPER SLOPES MAY BE ALLOWED ONLY WITH THE PERMISSION OF THE SOIL'S ENGINEER.
- 7) PAD ELEVATIONS SHALL BE CERTIFIED TO 0.10', PRIOR TO DIGGING ANY FOOTINGS OR SCHEDULING ANY INSPECTIONS.
- 8) DUST FROM GRADING OPERATIONS MUST BE CONTROLLED. CONTRACTOR SHALL PROVIDE ADEQUATE WATER TO CONTROL DUST DURING AND FOR GRADING OPERATIONS.
- 9) A COPY OF ALL COMPACTION TESTS AND FINAL GRADING REPORT SHALL BE SUBMITTED TO THE COUNTY OF MONTEREY PLANNING AND BUILDING INSPECTION DEPARTMENT AT SCHEDULED INSPECTIONS.
- 10) THE GROUND IMMEDIATELY ADJACENT TO FOUNDATIONS SHALL BE SLOPED AWAY FROM THE BUILDING AT 5% FOR A MINIMUM DISTANCE OF 10 FEET. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FOOT OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED AT A MINIMUM OF 1% WHERE LOCATED WITHIN 5 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED AT A MINIMUM OF 2% AWAY FROM THE BUILDING.
- 11) ROOF DRAINAGE SHALL BE CONTROLLED BY GUTTER AND DOWN SPOUTS WITH SPLASH BLOCKS WHICH OUTLET INTO LANDSCAPE AREAS AND/OR PERVIOUS PAVERS OR CONNECTED INTO THE SITE STORM DRAIN SYSTEM AS SHOWN. RAIN WATER LEADERS SHALL BE 4" PVC-SDR 35 PIPE, HAVE A MINIMUM SLOPE OF 1% AND A MINIMUM COVER OF 12". THE RAIN WATER LEADER TRENCHES SHOULD HAVE THEIR BEARING SURFACES FOUNDED BELOW AN IMAGINARY 1:1 (HORIZONTAL-VERTICAL) LANE PROJECTED UPWARD FROM THE BOTTOM EDGE OF THE BUILDING FOOTINGS.
- 12) STORM WATER (SURFACE RUNOFF) SHALL BE COLLECTED BY A COMBINATION OF AREA DRAINS AND DRAINAGE SWALES OUTLETTING ONTO DISSIPATORS AS SHOWN ON THE SITE DRAINAGE PLAN.
- 13) SUBSURFACE DRAINAGE FOR FOUNDATIONS & UNDERSLAB IS REQUIRED AND WILL BE COLLECTED AND PIPED TO A SUMP (CHRISTY BOX U32) LOCATED IN THE MECHANICAL ROOM AND PUMPED UP TO EXISTING STREET LEVEL (GOLF COURSE) AND SHALL REMAIN INDEPENDENT OF THE SURFACE RUNOFF.
- 14) THE STORM DRAIN FACILITIES SHALL BE AS SHOWN ON THE PLANS. CATCH BASIN SHALL BE CHRISTY PRODUCTS V5 & V12 WITH CAST IRON GRATE OR APPROVED EQUAL, AND TRENCH DRAIN SHALL BE Z-886 PERMA-TRENCH. THE STORM DRAIN PIPE SHALL BE P.V.C. MIN. SDR 35.



LOT OVERVIEW

- 15) ALL NEW UTILITY AND DISTRIBUTION LINES SHALL BE PLACED UNDERGROUND.
- 16) UTILITY TRENCHES WITHIN THE BUILDING PAD OR ANY NEW PAVED AREAS SHALL BE BACKFILLED WITH CLEAN, IMPORTED SAND AND THE TRENCH BACKFILL SHALL BE COMPACTED TO 95% MIN. REL. COMPACTION. THE TOP 8" OF TRENCH SHALL BE CAPPED WITH NATIVE SOIL. IN NON-PAVED AREAS NATIVE BACKFILL SHALL BE USED AND COMPACTED TO 90% MIN. REL. COMPACTION.
- 17) ALL WORK IS SUBJECT TO APPROVAL BY THE PUBLIC WORKS SUPERINTENDENT INSPECTION AND
- 18) NO LAND DISTURBING OR GRADING SHALL OCCUR ON THE SUBJECT PARCEL BETWEEN OCTOBER 15 AND APRIL 15 UNLESS AUTHORIZED BY THE DIRECTOR OF RMA — BUILDING SERVICES.
- 19) SPECIAL INSPECTIONS, BY A SPECIAL INSPECTOR, ARE REQUIRED DURING FILL PLACEMENT AND THAT PROPER MATERIALS AND PROCEDURES ARE USED IN ACCORDANCE WITH THE PROVISIONS OF THE APPROVED GEOTECHNICAL REPORT.
- 20) THE LOCATION, HEIGHT AND THE PLATE HEIGHTS OF THE NEW STRUCTURE MUST BE CERTIFIED BY A SURVEYOR TO BE IN CONFORMANCE WITH THE APPROVED PLANS.
- 21) IF DURING THE COURSE OF CONSTRUCTION, CULTURAL, ARCHAEOLOGICAL, HISTORICAL OR PALEONTOLOGICAL RESOURCES ARE UNCOVERED AT THE SITE (SURFACE OR SUBSURFACE RESOURCES) WORK SHALL BE HALTED IMMEDIATELY WITHIN 50 METERS (165 FEET) OF THE FIND UNTIL A QUALIFIED PROFESSIONAL ARCHAEOLOGIST CAN EVALUATE IT. MONTEREY COUNTY RMA - PLANNING AND A QUALIFIED ARCHAEOLOGIST SHALL BE IMMEDIATELY CONTACTED BY THE RESPONSIBLE INDIVIDUAL PRESENT ON-SITE. WHEN CONTACTED, THE PROJECT PLANNER AND THE ARCHAEOLOGIST SHALL IMMEDIATELY VISIT THE SITE TO DETERMINE THE EXTENT OF THE RESOURCES AND TO DEVELOP PROPER MITIGATION MEASURES REQUIRED FOR RECOVERY.

INDEX TO SHEETS

SHEET C1 COVER SHEET TOPOGRAPHIC MAP/EXISTING CONDITIONS GRADING, DRAINAGE & UTILITY PLAN SHEET C3

GRADING SECTIONS & CONSTRUCTION DETAILS

EROSION & SEDIMENT CONTROL PLAN

EROSION & SEDIMENT CONTROL NOTES:

- 1) ALL EROSION CONTROL MEASURES SHALL CONFORM WITH THE CITY OF CARMEL-BY-THE-SEA EROSION CONTROL ORDINANCE.
- 2) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN EFFECT FOR ANY CONSTRUCTION DURING THE RAINY SEASON, APPROX. OCTOBER 15 TO APRIL 15. EROSION CONTROL PLAN SHALL BE PREPARED AND SUBMITTED FOR APPROVAL BY SEPT. 15 OF ANY OR EACH CALENDAR YEAR THAT CONSTRUCTION MAY EXTEND BEYOND OCTOBER 15.
- 3) ALL SLOPES SHALL BE PROTECTED WITH STRAW MULCH OR SIMILAR MEASURES TO PROTECT AGAINST EROSION UNTIL SUCH SLOPES ARE PERMANENTLY STABILIZED.
- 4) RUNOFF SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS, AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE.
- 5) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE AT THE END OF EACH DAY'S WORK.
- 6) EROSION CONTROL PLANTINGS AND MULCH SHALL BE CLOSELY MONITORED THROUGHOUT THE WINTER AND ANY RUNOFF PROBLEMS CORRECTED PROMPTLY. SEE LANDSCAPE ARCHITECT'S PLAN FOR PERMANENT PLANTINGS AND
- 7) DISTURBED SURFACES NOT INVOLVED IN THE IMMEDIATE GRADING OPERATIONS MUST BE PROTECTED BY MULCHING AND/OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.
- 8) ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON THE DOWNHILL PROPERTIES.
- 9) DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY THROUGHOUT THE LIFE OF THE PROJECT DURING WINTER OPERATIONS.
- 10) REVEGETATION SHALL CONSIST OF A MECHANICALLY APPLIED HYDROMULCH SLURRY OR HAND SEEDED WITH A STRAW MULCH COVER. MULCH SHALL BE ANCHORED BY AN APPROVED METHOD SUCH AS PUNCHING, TACKING, OR THE USE OF JUTE NETTING, AS DEEMED NECESSARY FOR THE SITE CONDITIONS TO ALLOW FOR GERMINATION AND ENABLE ADEQUATE GROWTH TO BE ESTABLISHED.
- 11) CHECK DAMS. SILT FENCES, FIBER ROLLS OR OTHER DESIGNS SHALL BE INCORPORATED TO CATCH ANY SEDIMENT UNTIL AFTER THE NEWLY EXPOSED AREAS ARE REVEGETATED SUFFICIENTLY TO CONTROL EROSION. EROSION CONTROL PLANTINGS AND MULCH SHALL BE CLOSELY MONITORED THROUGHOUT THE WINTER AND ANY RUNOFF PROBLEMS SHALL BE CORRECTED PROMPTLY. ALL EROSION AND/OR SLIPPAGE OF THE NEWLY EXPOSED AREAS SHALL BE REPAIRED BY THE PERMITTEE AT THEIR EXPENSE.
- 12) THE GRASS SEED SHALL BE PROPERLY IRRIGATED UNTIL ADEQUATE GROWTH IS ESTABLISHED AND MAINTAINED TO PROTECT THE SITE FROM FUTURE EROSION DAMAGE. ALL NEWLY EXPOSED (DISTURBED) AREAS SHALL BE SEEDED WITH THE FOLLOWING EROSION CONTROL MIX: BROMUS CARINATUS (CALIFORNIA BROME), VULPIA MICROSTACHYS (NUTTALL'S FESCUE), ELYMUS GLAUCUS (BLUE WILD RYE), HORDEUM BRACHYANTHERUM (MEADOW BARLEY), FESTUCA RUNRA'MOLATE BLUE AND A MIXTURE OF LOCALLY NATIVE WILDFLOWERS.
- 13) THE DIRECTOR OF BUILDING INSPECTION (BUILDING OFFICIAL) SHALL STOP OPERATIONS DURING PERIODS OF INCLEMENT WEATHER IF HE OR SHE DETERMINES THAT EROSION PROBLEMS ARE NOT BEING CONTROLLED ADEQUATELY.
- 14) GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EROSION AND SEDIMENT CONTROL BMP INSTALLATION AND MAINTENANCE AND SHALL PROVIDE FULL PARTICULARS TO THE CITY OF CARMEL-BY-THE-SEA PRIOR TO BEG. WORK.

LEGEND:

EXISTING: SEE SHEET C2 - TOPO MAP

NEW:

RWL		MAJOR CONTOUR LINE (5' INTERVAL) MINOR CONTOUR LINE (1' INTERVAL) DRAINAGE SWALE FLOW LINE STORM DRAIN LINE RAIN-WATER LEADER
		SUBDRAIN PIPE
		UNDER-SLAB DRAIN
		FORCE MAIN LINE
	← ~	SURFACE DRAINAGE FLOW DIRECTION
	61.75	SPOT ELEVATION
	0 🖂	ROOF DOWNSPOUT/SPLASH BLOCK
		ASPHALT CONCRETE SURFACE
		PORTLAND CEMENT CONCRETE SURFACE
		CONCRETE TITLE PATIO
		CONVENTIONAL CONCRETE PAVER SURFACE

NOTE: PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL PROVIDE CERTIFICATION FROM THE PROJECT GEOTECHNICAL ENGINEER THAT ALL DEVELOPMENT HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE RECOMMENDATIONS IN THE PROJECT SOIL ENGINEERING INVESTIGATION

Inspection item:	Who will conduct the inspection:	When the Inspection is to be completed:	Inspection completed by:	Date completed
Site stripping and clearing	LandSet Engineers, inc.	Beginning of Project	7	
Subexcavation, fill placement, and compaction	LandSet Engineers, inc.	Throughout grading operations		
Foundation Excavations	LandSet Engineers, inc.	Prior to placement of forms and reinforcing steel		
Surface and subsurface drainage improvements	LandSet Engineers, inc.	Prior to trench backfill		
Utility trench compaction	LandSet Engineers, inc.	During backfill operations		-
Retaining wall backfill compaction	LandSet Engineers, inc.	During backfill operations		
Baserock subgrade compaction	LandSet Engineers, inc.	Prior to pavement installation		

TOTAL IMPERVIOUS AREA = 5,277 SQ.FT. TOTAL AREA OF DISTURBANCE = 9,745 SQ.FT.

CONTACT INFORMATION: PRIMARY: OWNER
MR. & MRS. JOHN & MAUREEN DEL SANTO
730 BREWER DRIVE HILLSBOROUGH, CA 93953

SECONDARY: ARCHITECT ERIC MILLER ARCHITECS, INC ATTN: MR. DADO MARQUEZ 211 HOFFMAN AVE. MONTEREY, CA 93940 PH (831)372-0410


SITE LOCATION: 1000 RODEO ROAD PEBBLE BEACH, CA 93953


SCALE: AS SHOWN DATE: OCTOBER 2018 IOB NO. 1746-02


10/15/18 AMS RELEASED TO CLIENT No. DATE BY





OF 5 SHEETS















UNDERSLAB SUBDRAIN DETAILS NOT TO SCALE



UNDERSLAB SUBDRAIN SUMP PUMP

MONTEREY COUNTY RESOURCE MANAGEMENT AGENCY

Carl P. Holm, AICP, Director John Guertin, Acting Deputy Director Daniel Dobrilovic, Acting Building Official Michael Novo, AICP, Director of Planning Benny J. Young, Interim Directorof Public Works & Facilities

168 W. Alisal Street, 2nd Floor Salinas, CA 93901 (831) 755-4800 http://www.co.monterey.ca.us/rma

Site Design and Runoff Reduction Checklist

Site Design and Runoff Reduction

Projects that create and/or replace > 2,500 square feet of impervious surface, collectively over the entire project site, including detached single-family home projects, shall implement <u>all</u> of the following design strategies in the design of the project:

Implemented Limited disturbance of creeks and natural drainage features

- Minimized compaction of highly permeable soils
- Limited clearing and grading of native vegetation at the site to the minimum area needed to build the project, allow access, and provide fire protection
- Minimized impervious surfaces by concentrating improvements on the least-sensitive portions of the site, while leaving the remaining land in a natural undisturbed state

Directed runoff from sidewalks, walkways, and/or patios onto vegetated areas safely away from

And must minimize stormwater runoff by implementing one or more of the following site design measures:

Directed roof runoff into cisterns or rain barrels for reuse


- Directed roof runoff onto vegetated areas safely away from building foundations and footings, consistent with California building code
- building foundations and footings, consistent with California building code Directed runoff from driveways and/or uncovered parking lots onto vegetated areas safely away from
- building foundations and footings, consistent with California building code Constructed bike lanes, driveways, uncovered parking lots, sidewalks, walkways, and patios with
- permeable surfaces

Property Owner/Agent Name JOHN & MAUREEN DEL SANTO

Date Prepared 10/15/2018

Property Owner/Agent Signature

Permit File Number




ዒ SWALE

NOTES:

- 1) MINIMUM LONGITUDINAL SLOPE SHALL BE NOT LESS THAN 1.0%
- 2) THE SWALE SHALL BE REVEGETATED WITH A HYDROMULCH SLURRY OR HAND SEEDED WITH A STRAW MULCH COVER UNTIL GROWTH IS ESTABLISHED.
- 3) IT SHALL BE THE RESPONSIBILITY OF THE OWNER TO REGULARY MAINTAIN THE SWALE AS NEEDED FROM EXCESSIVE GROWTH FROM EXCESSIVE GROWTH AND/OR SILTATION.

EARTH DRAINAGE SWALE



CONCRETE SWALE NOT TO SCALE

No. DATE BY

DATE: OCTOBER 2018 JOB NO. 1746-02 SHEET 10/15/18 AMS RELEASED TO CLIENT

SCALE: AS SHOWN

OF 5 SHEETS

EARTH MOVING/GRADING:

HANDBOOK.

DURING PERIODS OF RAIN.

PORTABLE SANITATION FACILITY:

1. REMOVE EXISTING VEGETATION ONLY WHEN NECESSARY.

SCHEDULE GRADING ACTIVITIES DURING DRY PERIODS.
CASQA BMP HANDBOOK — EROSION CONTROL


MANAGEMENT, SANITARY WASTE MANAGEMENT.


4. USE CHECK DAMS OR DITCHES TO DIVERT WATER AROUND EXCAVATIONS. 5. COVER STOCKPILES OF EXCAVATED SOIL WITH TARPS.

7. CASQA BMP HANDBOOK - SANITARY/SEPTIC WASTE MANAGEMENT WM-9


2. REFER TO THE CASOA BMP HANDBOOK FOR BMP FACT SHEETS.

SE-1 Silt Fence





Stabilized Construction Entrance/Exit TC-1







TABLE 1706.6 REQUIRED VERIFICATION AND INSPECTION OF SOILS

VERIFICATION AND INSPECTION TASK	CONTINUOUS DURING TASK LISTED	CONTINUOUS DURING TASK LISTED
Verify material below shallow foundations are adequate to achieve the design bearing capacity		X
Verify excavations are extended to proper depth and have reached proper material	1 ==	Х
3. Perform classification and testing of compacted fill materials	7.4 .4.	x
4. Verify use of proper materials, densities and lift sicknesses during placement and compaction of compacted fill.	Х	15.7
5. Prior to placement of compacted fill, observe subgrade and verify that site has been prepared properly.	1-1-1-1	X

Material Delivery and Storage



Categories EC Erosion Control SE Sediment Control TC Tracking Control WE Wind Erosion Control NS Non-Stormwater Management Control Waste Management and WM Materials Pollution Control Primary Category Secondary Category

Description and Purpose Prevent, reduce, or eliminate the discharge of pollutants from material delivery and storage to the stormwater system or watercourses by minimizing the storage of hazardous materials onsite, storing materials in watertight containers and/or a completely enclosed designated area, installing secondary containment, conducting regular inspections, and training employees and subcontractors. This best management practice covers only material delivery and storage. For other information on materials, see WM-2,

Oil and Grease **Potential Alternatives** Material Use, or WM-4, Spill Prevention and Control. For information on wastes, see the waste management BMPs in this

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

☑ Primary Objective

Secondary Objective

Management Control


Waste Management and

Materials Pollution Control

Targeted Constituents

Stockpile Management

Description and Purpose



Stockpile management procedures and practices are designed to reduce or eliminate air and stormwater pollution from stockpiles of soil, soil amendments, sand, paving materials such as portland cement concrete (PCC) rubble, asphalt concrete (AC), asphalt concrete rubble, aggregate base, aggregate sub base or pre-mixed aggregate, asphalt minder (so called "cold Oil and Grease mix" asphalt), and pressure treated wood.

Targeted Constituents

WM-3


Non-Stormwater Management Control

Waste Management and

Materials Pollution Control

Potential Alternatives

Solid Waste Management



Targeted Constituents Description and Purpose Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste Metals collection areas and containers, arranging for regular disposal, and training employees and subcontractors.

> Organics **Potential Alternatives**

Oil and Grease

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control NS Non-Stormwater

Management Control

☑ Primary Objective

Secondary Objective

Waste Management and WM Waste Management S. Materials Pollution Control

Categories

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

Non-Stormwater

Management Control

WM Waste Management and Materials Pollution Control

☑ Primary Objective

Secondary Objective

CONSTRUCTION MANAGEMENT NOTES:

1. MINIMIZE USE OF OIL-BASED PAINTS
2. STORE SOLVENTS AND PAINTS IN ORIGINAL CONTAINERS OR OTHER FIRE MARSHAL APPROVED CONTAINER.
3. SPENT SOLVENTS ARE HAZARDOUS WASTES. STORE SPENT SOLVENTS IN APPROVED CONTAINERS, REUSE SOLVENTS AS MUCH AS POSSIBLE AND USE PAINTS AS MUCH AS POSSIBLE RATHER THAN DISPOSING OF THEM. DISPOSE OF SPENT SOLVENTS AND UNUSABLE PAINT AS A HAZARDOUS WASTE.
4. NEVER CLEAN PAINT EQUIPMENT WHERE SOLVENTS, PAINT OR CONTAMINATED RINSE WATER CAN ENTER THE STOR DRAIN SYSTEM.

5. CASQA BMP HANDBOOK - HAZARDOUS WASTE MANAGEMENT WM-6

PLASTERING/STUCCO/TILING/SITE-MIXED CONCRETE:

. STORE PLASTER AND CEMENT IN COVERED AREAS AND KEEP THEM OUT OF THE WIND. . CONSERVE MATERIALS, DO NOT MIX MORE PRODUCT THAN CAN BE USED BEFOR IT HARDENS. 3. IF THERE IS LEFT OVER PRODUCT, PLACE THE EXCESS IN AN EARTHEN DEPRESSION. LET THE PRODUCT CURE AND DISPOSE OF AS REGULAR REFUSE.

4. ALL RINSE WATER IS TO BE PLACED IN AN EARTHEN DEPRESSION CAPABLE OF HOLDING THE RINSE WATER AS WELL AS ANY RAIN WATER THAT WOULD FALL/RUN INTO THE DEPRESSION.
5. CASQA BMP HANDBOOK — CONCRETE WASTE MANAGEMENT WM—8

READY-MIXED CONCRETE:

TREE PROTECTION

8 EMPLOYEE PARKING AREA

TEMPORARY STOCKPILE AREA

1. HAVE AN EARTHEN DEPRESSION DUG PRIOR TO THE ARRIVAL OF THE READY—MIX TRUCK.
2. IF A PUMP IS USED, PLACE THE ENTIRE PUMP PRIMING FLUID AND REJECT CONCRETE IN THE DEPRESSION.
3. PLACE ALL SPILLED CONCRETE AND CHUTE WASH WATER IN THE DEPRESSION.
4. ALL TRUCK AND PUMP RINSE WATER IS TO BE TAKEN BACK TO THE READY—MIX BACH PLANT FOR TREATMENT/RECYCLING

5. BEFORE CREATING AN EXPOSED AGGREGATE FINISH, CAREFULLY PLAN AND PREPARE TO PREVENT THE SLURRY THAT IS WASHED OFF FROM ENTERING THE STORM DRAIN SYSTEM AND GUTTERS. 6. CASQA BMP HANDBOOK - CONCRETE WASTE MANAGEMENT WM-8

A- PRIOR TO COMMENCEMENT OF ANY LAND DISTURBANCE, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO ENSURE ALL NECESSARY SEDIMENT CONTROLS ARE IN PLACE AND THE PROJECT IS COMPLIANT WITH MONTEREY COUNTY GRADING

PLANT TEMPORARY VEGETATION WHEN SLOPE HAVE BEEN DISTURBED BUT CONSTRUCTION IS STILL ONGOING

1. LOCATE AWAY FROM DRAINAGE FACILITIES, WATERCOURSES, AND FROM TRAFFIC CIRCULATION.
2. MUST BE EQUIPPED WITH CONTAINMENT TO PREVENT DISCHARGE OF POLLUTANTS TO THE STORM DRAINAGE SYSTEM.
3. WASTEWATER SHOULD NOT BE DISCHARGED OR BURIED WITHIN THE PROJECT SITE.
4. TEMPORARY SANITARY FACILITIES THAT DISCHARGE TO THE SANITARY SEWER SYSTEM SHOULD BE PROPERLY CONNECTED TO AVOID ILLICIT DISCHARGES.

5. SANITARY & SEPTIC FACILITIES SHOULD BE MAINTAINED IN GOOD WORKING ORDER BY A LICENSED SERVICE.
6. ONLY REPUTABLE, LICENSED SANITARY AND SEPTIC WASTE HAULERS SHOULD BE USED.

1. CONTRACTORS STAGING AREA DESIGNATED FOR FOLLOWING STORM WATER BEST MANAGEMENT PRACTICES: SCHEDULLING, WATER CONSERVATION PRACTICES, VEHICLE AND EQUIPMENT CLEANING, VEHICLE AND

AND CONTROL, SOLID WASTE MANAGEMENT, HAZARDOUS WASTE MANAGEMENT, CONCRETE WASTE

EQUIPMENT MAINTENANCE, MATERIAL DELIVERY & STORAGE, STOCKPILE MANAGEMENT, SPILL PREVENTION

3. PROTECT DOWN SLOPE DRAINAGE COURSES BY RECOGNIZED METHODS SUCH AS THOSE IN THE CASQA

B- DURING CONSTRUCTION THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO UPDATE COMPACTION TEST RECORDS, INSPECT DRAINAGE DEVICE INSTALLATION, REVIEW THE MAINTENANCE AND EFFECTIVENESS OF BMP's INSTALLED, AS WELL AS, TO VERIFY THAT POLLUTANTS OF CONCERN ARE NOT DISCHARGED FROM THE SITE. C- PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO CONDUCT A

FINAL GRADING INSPECTION, COLLECT FINAL GEOTECHNICAL LETTER OF CONFORMANCE, ENSURE THAT ALL DISTURBED AREAS HAVE BEEN STABILIZED AND THAT ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THAT ARE NO LONGER NEEDED HAVE BEEN REMOVED.

Hazardous Waste Management


Description and Purpose Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Metals Bacteria Oil and Grease Organics

Targeted Constituents

Potential Alternatives

Sanitary/Septic Waste Management WM-9



Description and Purpose Proper sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and arranging for regular service and disposal.

Potential Alternatives

Trash

Oil and Grease

Organics

EC Erosion Control

SE Sediment Control

TC Tracking Control

WE Wind Erosion Control

☑ Primary Category

■ Secondary Category

Targeted Constituents


Non-Stormwater

Management Control

WM Materials Pollution Control

Waste Management and

Preservation Of Existing Vegetation EC-2



Description and Purpose Carefully planned preservation of existing vegetation minimizes the potential of removing or injuring existing trees, vines, shrubs, and grasses that protect soil from erosion.

Nutrients Bacteria Oil and Grease

Targeted Constituents

SCALE: AS SHOWN DATE: OCTOBER 2018 IOB NO. 1746-02

10/15/18 AMS RELEASED TO CLIENT No. DATE BY REVISION

Organics

GE

OF 5 SHEETS