

**Exhibit "C" to Radio Communication Site Lease Agreement**

EQUIPMENT LIST

(See attached)

EXHIBIT C

**PROPOSED LEWIS ROAD EQUIPMENT**

19 May 2015

<u>Qty</u>	<u>Description</u>
1	Concrete shelter, 11.5 ft x 15 ft, on concrete foundation
1	Steel tower, 100 ft., on concrete foundation
1	Cable ice bridge with concrete footings
1	Generator, 35 kW, on concrete foundation
	Associated wiring
1	Liquid propane fuel tank, 500 gal, on concrete foundation
	Associated piping
1	Power board with concrete footings
1	Floor standing UPS
1	Equipment rack containing:
	Network sentry
	MME unit
	Frequency standard
	VHF multicoupler
	Ethernet switch
	Ethernet router
	KVM
	MASTR V base stations
	Associated power supplies
	Associated cables
1	Equipment rack containing:
	VHF combining equipment
1	Equipment rack containing:
	Service aggregation router
	DC power supply
	Associated power supplies
	Associated cables
1	VHF receive antenna
	Associated mounting hardware
	Associated transmission lines
1	VHF transmit antenna
	Associated mounting hardware
	Associated transmission lines