

PLANNING INFO.

- PROPERTY OWNER:
GEORGE & DANA HOLLAND
7851 N. SPYGLASS AVENUE
FRESNO, CA. 93711
- PROJECT ADDRESS:
3363 17 MILE DRIVE
PEBBLE BEACH, CA. 93953
- PROJECT SCOPE:
NEW 1,200 SF ACCESSORY DWELLING UNIT; NEW 373 SF STONE TERRACE
W/ FIREPIT; NEW D.G. PATH; REMOVAL OF 1 OAK TREE; RELOCATE EXISTING
DRIVEWAY GATE
- OCCUPANCY: R-3, U
- CONST. TYPE: V-B
- A.P.N. 008-361-007
- LEGAL DESC.: LOT: BLOCK:
- ZONE: LDR/1.5-D(CZ)
- STORIES: 1
- MAX BLDG. HT: 30 FT / ADU: 15 FT
- GRADING: N/A
- TREE REMOVAL: 1 OAK
- TOPOGRAPHY: GENTLY SLOPING
- PROJECT CODE COMPLIANCE:
2022 CBC, CMC, CPC, CFC, CEC, CALIFORNIA RESIDENTIAL CODE,
CALIFORNIA GREEN BUILDING CODE & 2022 CALIFORNIA ENERGY CODE
- LOT AREA: 45,823 S.F. (1.05 Ac.)
- E.A.R. CALCULATIONS

MAIN BUILDING		EXISTING	PROPOSED ADDITION	PROPOSED TOTAL
MAIN FLOOR		3,464	0	3,464
UPPER FLOOR		553	0	553
BASEMENT*		197	0	0
DETACHED GARAGE		452	0	452
GUESTHOUSE		311	0	311
SHED		69	0	69
A.D.U.		0	1,200	1,200
TOTAL		4,849	1,200	6,049

*BASEMENT— NOT COUNTED


■ F.A.R. ALLOWED:	8,019 SF	(17.50%)
■ F.A.R. PROPOSED:	6,049 SF	(13.20%)

■ COVERAGE CALCULATIONS (BUILDING & IMPERVIOUS):


IMPERVIOUS BUILDING COVERAGE	EXISTING	PROPOSED REMOVAL	PROPOSED ADDITION	PROPOSED TOTAL
MAIN RESIDENCE	3,471	0	0	3,471
GUEST HOUSE	311	0	0	311
DETACHED GARAGE	452	0	0	452
SHED	69	0	0	69
A.D.U.	0	0	1,200	1,200
STONE STAIRS	319	0	0	319
STONE PATIO	143	0	0	143
STONE WALLS	447	0	0	447
TILE PATIO	362	0	0	362
TILE WALKWAY	692	0	0	692
PLASTER WALL	64	0	0	64
WATER FEATURES	406	0	0	406
ROOF TERRACE ACCESS STAIRS	73	0	0	73
TERRACE	272	0	373	645
BALCONY	62	0	0	62
STONE GATE POSTS	18	0	0	18
BUILDING COVERAGE SUBTOTAL	4,303	0	1,200	5,503
IMPERVIOUS COVERAGE TOTAL	7,161	0	1,573	8,734

- BUILDING SITE COVERAGE PROPOSED: 5,503 SF (12.01%)
- BUILDING SITE COVERAGE ALLOWED: 6,873 SF (15.00%)
- IMPERVIOUS COVERAGE PROPOSED: 8,734 SF
- PESCADERO COVERAGE LIMITATIONS 9,000 SF IMPERVIOUS

BLUE-LINE STREAM LOCATION



VICINITY MAP



SITE PLAN


SHEET NO.

A1.C

PROJECT ADDRESS:
**3363 17 MILE DR
PEBBLE BEACH
CA 93953**

ABN: 008 361 007

DATE: MAY 8, 2025



MERRIMACK OUTDOOR WALL SCONCE

the great outdoors®

by MINKA-LAVERY®

JUN A. SILLANO, AIA



ARCHITECTURE ♦ PLANNING ♦ INTERIOR DESIGN

**721 LIGHTHOUSE AVE
PACIFIC GROVE CA.
93950**


■ (831) 646-1261
■ (831) 646-1290
■ idg@idg-inc.net
■ idg-inc.net

DISCLAIMER:
ALL IDEAS, DESIGNS, ARRANGEMENTS AND PLANS INDICATED BY THIS DRAWING ARE OWNED BY, AND THE PROPERTY OF THIS OFFICE AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON, AND IN CONNECTION WITH, THE SPECIFIED PROJECT. NONE OF SUCH IDEAS, DESIGNS, ARRANGEMENTS OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF INTERNATIONAL DESIGN GROUP. WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALE DIMENSIONS: CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR, ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS OF ADEQUATE SCALE MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION ON ITEMS SO NOTED.

STAMPS:

A.D.U. EXTERIOR LIGHTING PLAN

$$1/16'' = 1' - 0''$$



LIGHTING LEGEND

EXISTING WALL MOUNTED LIGHT FIXTURE

EXISTING WALL MOUNTED LIGHT FIXTURE

EXTERIOR LIGHTING PLAN

SHEET NO.

A1.1

721 LIGHTHOUSE AVE
PACIFIC GROVE CA.
93950

PH ■ (831) 646-1261
FAX ■ (831) 646-1290
EMAIL ■ idg@idg-inc.net
WEB ■ idg-inc.net

DISCLAIMER:
ALL IDEAS, DESIGNS, ARRANGEMENTS AND PLANS INDICATED BY THIS DRAWING ARE OWNED BY, AND THE PROPERTY OF THIS OFFICE, AND WERE CREATED, EVOLVED AND DEVELOPED FOR THIS PROJECT. NO COPIES OR DERIVATION OF THIS DRAWING MAY BE MADE, IN WHOLE OR IN PART, WITHOUT THE EXPRESSED WRITTEN CONSENT OF THIS OFFICE. THIS DRAWING IS THE PROPERTY OF THIS OFFICE, AND IS NOT TO BE USED BY ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER. THIS DRAWING IS THE PROPERTY OF THE INTERNATIONAL DESIGN GROUP. WRITTEN DIMENSIONS ON THIS DRAWING ARE IN FEET AND INCHES. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS. THE DRAWING IS TO BE USED AS A GUIDE ONLY. ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS MUST BE APPROVED BY THIS OFFICE AND MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION ON ITEMS SO NOTED.

STAMPS:

PROJECT/CLIENT:
HOLLAND RESIDENCE A.D.U.
PROJECT ADDRESS:
3363 17 MILE DR
PEBBLE BEACH
CA 93953
APN: 008-361-007

DATE: MAY 22, 2025
PLANNING SUBMITTAL


REVISIONS:

- △
- △
- △
- △
- △
- △
- △


PROPOSED A.D.U. PLAN
1,200 S.F.

SHEET NO.

A2.0



PROPOSED A.D.U. PLAN (1,200 S.F.)



1/4"=1'-0"

WALL LEGEND

- 2X EXISTING WALL TO REMAIN
- 2X6 EXTERIOR STUD FRAMED WALL
- 2X4 INTERIOR STUD FRAMED WALL, U.O.N.

GENERAL ROOF NOTES

ROOF MATERIAL = CAP AND PAN CLAY TILE ROOF, MATCH (E) RESIDENCE

FIELD VERIFY WITH OWNER AND ARCHITECT COLOR AND/OR BLEND OF ROOFING UNITS PRIOR TO INSTALLATION

ROOF SLOPE = 4/12 UNLESS OTHERWISE NOTED

OVERHANG = 12" UNLESS OTHERWISE NOTED

COPPER GUTTERS WITH ROUND DOWNSPOUTS

GANG ALL VENT STACKS TO MINIMIZE QUANTITY OF ROOF JACKS AND LOCATE ROOF JACKS IN LEAST VISIBLE LOCATION

KEY NOTES

- 1 CHIMNEY TOP, SEE DETAIL 6/A8.0.
- 2 PERIMETER COPPER GUTTERS WITH DOWNSPOUTS. SEE DETAIL 11/A8.2. VERIFY DOWNSPOUT LOCATIONS WITH OWNER/ARCHITECT PRIOR TO GUTTER FABRICATION.
- 3 COPPER VALLEY FLASHING, TYP. SEE DETAIL 5/A8.0
- 4 WALL LINE BELOW
- 5 CRICKET, SEE DETAIL 4/A8.0
- 6 SOLAR PANELS (5'-6" x 3'-6")

JUN A. SILLANO, AIA



ARCHITECTURE • PLANNING • INTERIOR DESIGN

721 LIGHTHOUSE AVE
PACIFIC GROVE CA.
93950

PH (831) 646-1261
FAX (831) 646-1290
EMAIL idg@idg-inc.net
WEB idg-inc.net

DISCLAIMER:
ALL DESIGNS, ARRANGEMENTS AND PLANS INDICATED BY THIS DRAWING ARE OWNED BY, AND THE PROPERTY OF THIS OFFICE, AND WERE CREATED, EVOLVED AND DEVELOPED FOR THE USE OF THE ARCHITECTURE FIRM OF IDG PROJECT. NONE OF SUCH DESIGNS, ARRANGEMENTS OR PLANS ARE TO BE COPIED, REPRODUCED, OR USED BY ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER. THIS DRAWING IS THE PROPERTY OF IDG INTERNATIONAL DESIGN GROUP. WRITTEN DIMENSIONS ON THIS DRAWING ARE IN INCHES. DRAWING IS NOT TO SCALE. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS. THE DRAWING IS NOT TO SCALE. ANY BULKY OR VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS SHALL BE APPROVED BY THE ARCHITECT AND SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION ON ITEMS SO NOTED.

STAMPS:

PROJECT/CLIENT:
HOLLAND RESIDENCE
A.D.U.

PROJECT ADDRESS:
3363 17 MILE DR
PEBBLE BEACH
CA 93953

APN: 008-361-007

DATE: MAY 22, 2025
PLANNING SUBMITTAL


REVISIONS:

- △
- △
- △
- △
- △
- △


PROPOSED
A.D.U. ROOF PLAN

SHEET NO.

A5.0



PROPOSED A.D.U. ROOF PLAN




1/4"=1'-0"

721 LIGHTHOUSE AVE
PACIFIC GROVE CA.
93950

PH ■ (831) 646-1261
FAX ■ (831) 646-1290
EMAIL ■ idg@idg-inc.net
WEB ■ idg-inc.net


DISCLAIMER:
ALL DESIGN ARRANGEMENTS AND PLANS INDICATED BY THIS DRAWING ARE OWNED BY, AND THE PROPERTY OF THIS OFFICE, AND WERE CREATED, EVOLVED AND DEVELOPED FOR THE USE OF THE CONTRACTOR ON THE SPECIFIED PROJECT. NONE OF SUCH DESIGNS, ARRANGEMENTS OR PLANS ARE TO BE COPIED, REPRODUCED, OR SHOWN TO ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER. THIS DRAWING IS THE PROPERTY OF THE INTERNATIONAL DESIGN GROUP. WRITTEN DIMENSIONS ON THIS DRAWING ARE IN INCHES. DRAWINGS ARE NOT TO SCALE. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS. THE CONTRACTOR IS TO BE RESPONSIBLE FOR ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. THIS DRAWING IS NOT TO BE COPIED OR SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION ON ITEMS SO NOTED.

STAMPS:



WEST ELEVATION

1/4"=1'-0"



NORTH ELEVATION

1/4"=1'-0"

EXTERIOR FINISH LEGEND

- 1 "S" CLAY TILE ROOF - MATCH EXISTING RESIDENCE
- 2 5" HALF-ROUND COPPER GUTTERS, DOWNSPOUTS - MATCH EXISTING RESIDENCE
- 3 EXTERIOR STUCCO - MATCH EXISTING RESIDENCE
- 4 RANDOM STONE VENEER
- 5 ALUMINUM EXTERIOR DOORS & WINDOWS
- 6 CEDAR SILL WOOD - MATCH EXISTING RESIDENCE
- 7 PAINTED 6X SHAPED CEDAR CORBEL & BEAMS
- 8 PAINTED SHAPED FASCIA - MATCH EXISTING RESIDENCE
- 9 SOLAR PANEL (5'-6" x 3'-6")

PROJECT/CLIENT:

**HOLLAND
RESIDENCE
A.D.U.**

PROJECT ADDRESS:

3363 17 MILE DR
PEBBLE BEACH
CA 93953

APN: 008-361-007

DATE: MAY 22, 2025

PLANNING SUBMITTAL

REVISIONS:

- △
- △
- △
- △
- △
- △
- △
- △

**PROPOSED
A.D.U. ELEVATIONS**

SHEET NO.


A6.0

721 LIGHTHOUSE AVE
PACIFIC GROVE CA.
93950

PH ■ (831) 646-1261
FAX ■ (831) 646-1290
EMAIL ■ idg@idg-inc.net
WEB ■ idg-inc.net


DISCLAIMER:
ALL DESIGN, ARRANGEMENTS AND PLANS INDICATED BY THIS DRAWING ARE OWNED BY, AND THE PROPERTY OF THIS OFFICE, AND WERE CREATED, EVOLVED AND DEVELOPED FOR THE USE OF THE CONTRACTOR ON THE SPECIFIED PROJECT. NONE OF SUCH DESIGNS, ARRANGEMENTS OR PLANS ARE TO BE COPIED, REPRODUCED, OR SHOWN TO ANY PERSON, FIRM OR CORPORATION FOR ANY PURPOSE WHATSOEVER. THIS DRAWING IS THE PROPERTY OF THE INTERNATIONAL DESIGN GROUP. WRITTEN DIMENSIONS ON THIS DRAWING ARE IN INCHES. DRAWINGS ARE NOT TO SCALE. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS. THE CONTRACTOR IS TO BE RESPONSIBLE FOR ANY VARIATION FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. NO PART OF THIS DRAWING MAY BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION ON ITEMS SO NOTED.

STAMPS:



EAST ELEVATION

1/4"=1'-0"



SOUTH ELEVATION

1/4"=1'-0"

EXTERIOR FINISH LEGEND

- 1 "S" CLAY TILE ROOF - MATCH EXISTING RESIDENCE
- 2 5" HALF-ROUND COPPER GUTTERS, DOWNSPOUTS - MATCH EXISTING RESIDENCE
- 3 EXTERIOR STUCCO - MATCH EXISTING RESIDENCE
- 4 RANDOM STONE VENEER
- 5 ALUMINUM EXTERIOR DOORS & WINDOWS
- 6 CEDAR SILL WOOD - MATCH EXISTING RESIDENCE
- 7 PAINTED 6X SHAPED CEDAR CORBEL & BEAMS
- 8 PAINTED SHAPED FASCIA - MATCH EXISTING RESIDENCE
- 9 SOLAR PANEL (5'-6" x 3'-6")

PROJECT/CLIENT:

**HOLLAND
RESIDENCE
A.D.U.**

PROJECT ADDRESS:

3363 17 MILE DR
PEBBLE BEACH
CA 93953

APN: 008-361-007

DATE: MAY 22, 2025

PLANNING SUBMITTAL

REVISIONS:

△	
△	
△	
△	
△	
△	
△	

**PROPOSED
A.D.U. ELEVATIONS**

SHEET NO.

A6.1

GRADING, DRAINAGE, AND EROSION CONTROL PLAN

OF

THE HOLLAND RESIDENCE ADU

APN: 008-361-007

PEBBLE BEACH, MONTEREY COUNTY, CALIFORNIA

GENERAL NOTES:

- 1) PROJECT DESIGN IS BASED ON INFORMATION OBTAINED FROM THE ARCHITECTURAL PLANS FOR THE HOLLAND RESIDENCE ADU PREPARED BY IDG, DATED 04/10/2025; AND THE TOPOGRAPHIC MAP FOR THE SITE PREPARED BY LANDSET ENGINEERS, DATED 03/17/2025.
- 2) NOT ALL UNDERGROUND UTILITIES WERE LOCATED. ONLY VISIBLE FACILITIES ABOVE AND FLUSH WITH THE SURFACE ARE SHOWN. SUBSURFACE UTILITIES LINES DRAWN MAY NOT BE COMPLETE AND SHOULD BE VERIFIED BY FIELD RECONNAISSANCE. APPROPRIATE UTILITIES LOCATIONS SHOULD BE OBTAINED FROM APPROPRIATE UTILTY COMPANIES, PUBLIC AGENCIES, OWNER'S AS-BUILT DRAWINGS, ETC., AND SHOULD BE THOROUGHLY COMPILED AND DEEMED COMPLETE WITH THE PROJECT AREA, PRIOR TO ANY SITE DEVELOPMENT DESIGN AND/OR CONSTRUCTION.
- 3) THIS MAP PORTREYS THE SITE AT THE TIME OF THE SURVEY AND DOES NOT SHOW SOILS OR GEOLOGY INFORMATION, UNDERGROUND CONDITIONS, EASEMENTS, ZONING OR REGULATORY OR ANY OTHER ITEMS NOT SPECIFICALLY REQUESTED BY THE PROPERTY OWNER.
- 4) THIS MAP DOES NOT REPRESENT A BOUNDARY SURVEY.

GRADING & DRAINAGE NOTES:


- 1) ALL GRADING SHALL CONFORM TO THE LATEST AUTHORITY HAVING JURISDICTION GRADING ORDINANCE AND EROSION CONTROL ORDINANCE; THE RECOMMENDATIONS FOUND IN THE PROJECT'S GEOTECHNICAL REPORT PREPARED BY LANDSET ENGINEERS, DATED 04/07/2022; THE LATEST VERSION OF THE CALTRANS SPECIFICATIONS; THE GOVERNING PUBLIC AGENCIES; THE LATEST REVISION OF THE CALIFORNIA BUILDING CODE (CBC); AND THESE PLANS.
- 2) SURFACE ORGANICS SHALL BE STRIPPED AND STOCKPILED FOR LATER USE AS TOPSOIL. MATERIAL ACTUAL GRADING SHALL BEGIN WITHIN 30 DAYS OF VEGETATION REMOVAL. THE AREA SHALL BE PLANTED TO CONTROL EROSION.
- 3) NO ORGANIC MATERIAL SHALL BE PERMITTED IN FILLS EXCEPT AS TOPSOIL USED FOR SURFACE PLANT GROWTH ONLY AND WHICH DOES NOT EXCEED 4" IN DEPTH.
- 4) THERE ARE APPROXIMATELY 65 CUBIC YARDS OF CUT AND 45 CUBIC YARDS OF FILL TOTAL WITH A NET EXCESS OF 20 CUBIC YARDS. EXCAVATION SHALL BE USED FOR EMBANKMENT CONSTRUCTION, LANDSCAPE PURPOSES AND/OR HAULED OFF-SITE. ADDITIONAL ON-SITE SPOILS GENERATED FROM FOUNDATIONS, UTILITY TRENCHES, SEPTIC CONSTRUCTION, ETC. ARE NOT INCLUDED IN THE ABOVE REFERENCED QUANTITIES. IMPORT MATERIAL SHALL MEET THE REQUIREMENTS OF SELECT STRUCTURAL FILL AS NOTED IN THE SOILS REPORT AND BE APPROVED BY THE SOIL ENGINEER PRIOR TO PLACEMENT.
- 5) EMBANKMENT MATERIAL SHALL BE PLACED IN 8" LOOSE LIFTS, MOISTURE CONDITIONED, AND COMPAKTED TO 90% MINIMUM RELATIVE COMPAKCTION. ALL BASEROCK AND THE UPPER 12" OF SUBGRADE SHALL BE COMPAKTED TO 95% MINIMUM RELATIVE COMPAKCTION.
- 6) ALL CUT AND FILL SLOPES SHALL BE 2:1 OR FLATTER. STEEPER SLOPES MAY BE ALLOWED ONLY WITH THE PERMISSION OF THE SOIL ENGINEER.
- 7) PAD ELEVATIONS SHALL BE CERTIFIED TO 0.10' PRIOR TO DIGGING ANY FOOTINGS OR SCHEDULING ANY INSPECTIONS.
- 8) DUST FROM GRADING OPERATIONS MUST BE CONTROLLED. CONTRACTOR SHALL PROVIDE ADEQUATE WATER TO DO SO AND FOR USE IN GRADING OPERATIONS.
- 9) A COPY OF ALL COMPAKCTION TESTS AND THE FINAL GRADING REPORT SHALL BE SUBMITTED TO THE AUTHORITY HAVING JURISDICTION PLANNING AND BUILDING INSPECTION DEPARTMENT AT SCHEDULED INSPECTIONS.
- 10) THE GROUND IMMEDIATELY ADJACENT TO FOUNDATIONS SHALL BE SLOPED AWAY FROM THE BUILDING AT 5% FOR A MINIMUM DISTANCE OF 10'. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10' OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED AT A MINIMUM OF 2% WHERE LOCATED WITHIN 5' OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10' OF THE BUILDING FOUNDATION SHALL BE SLOPED AT A MINIMUM OF 2% AWAY FROM THE BUILDING.
- 11) ROOF DRAINAGE SHALL BE ACCOMPLISHED BY THE USE OF GUTTERS AND DOWNSPOUTS. THE DOWNSPOUTS SHALL BE DRAINED INTO A APPROVED RAINWATER LEADERS AND DRAINED INTO THE STORM DRAIN SYSTEM AS SHOWN. THE DOWNSPOUTS SHALL BE DOWNSPOUTS THAT ARE NOT CONNECTED TO A RAINWATER LEADER SHALL OUTLET onto SPLASH BLOCKS OR AN APPROVED ALTERNATIVE. SPLASH BLOCKS MAY BE UNNECESSARY IF THE DOWNSPOUT OUTLETS DIRECTLY onto AN IMPERVIOUS SURFACE THAT IS PROPERLY GRADED AWAY FROM FOUNDATIONS. RAINWATER LEADERS SHALL BE CONSTRUCTED WITH 4" SDR35 PVC PIPE. UNDER NO CIRCUMSTANCES SHALL A RAINWATER LEADER BE CONNECTED TO A SUBDRAIN LINE.
- 12) SURFACE RUNOFF SHALL BE COLLECTED BY A SYSTEM OF SWALES AND DRAINS. CAPTURED STORMWATER SHALL BE PIPED TO A DISPERSION TRENCH AS SHOWN IN THE SITE UTILITY PLAN. STORM DRAIN LINES SHALL DRAIN BY GRAVITY AND BE SLOPED AT A MINIMUM OF 2% TO AN OUTLET WHERE A 2% SLOPE IS IMPRACTICAL. PIPES SHALL BE SLOPED AT NO LESS THAN 1%. STORM DRAIN LINES SHALL HAVE A MINIMUM COVER OF 12" AND SHALL BE CONSTRUCTED WITH SDR35 PVC PIPE, SIZED AS INDICATED.
- 13) TRENCH DRAINS SHALL BE 6" CHANNEL DRAINS, SIZED AS INDICATED ON THE SITE UTILITY PLAN. FLAT-BOTTOMED CHANNELS SHOULD BE SLOPED AT A MINIMUM OF 0.5% TO AN OUTLET IN ORDER TO ENSURE PROPER DRAINAGE AND PREVENT STANDING WATER IN THE TRENCH. ANY CHANNEL SLOPED AT LESS THAN 0.5% SHALL HAVE OUTLETS SPACED AT NO MORE THAN 15'. GRATES AND CHANNELS SHALL HAVE A LOAD RATING GREATER THAN OR EQUAL TO THE EXPECTED LOADING IN THE INSTALLATION AREA. ALL TRENCH DRAINS SHALL BE SURROUNDED BY A MINIMUM OF 4" OF CONCRETE. TRENCH DRAINS SHOULD BE SIZED TO HANDLE THE PEAK RUNOFF RATE PRODUCED BY A 10-YEAR DESIGN STORM.
- 14) SUBSURFACE WATER BEHIND ANY RETAINING WALLS SHALL BE CONTROLLED BY THE INSTALLATION OF SUBDRAINS. SUBDRAIN LINES SHALL BE CONSTRUCTED WITH PERFORATED 4" SDR35 PVC PIPE PLACED WITH THE HOLES FACING DOWNWARD. CONSTRUCTED SUBDRAINS SHOULD BE SHOWN ON THE SITE UTILITY PLAN. PIPES CARRYING SURFACE WATER OR ROOF WATER SHALL NOT UNDER ANY CIRCUMSTANCES OUTLET INTO A SUBDRAIN LINE. THE SYSTEM OF SUBDRAINS SHALL REMAIN INDEPENDENT OF THE SURFACE STORM DRAIN SYSTEM.
- 15) UTILITY TRENCHES WITHIN THE BUILDING PAD OR ANY NEW PAVED AREAS SHALL BE BACKFILLED WITH CLEAN IMPORTED SAND AND THE TRENCH BACKFILL SHALL BE COMPAKTED TO 95% MINIMUM RELATIVE COMPAKCTION. THE TOP 8" OF TRENCH SHALL BE CAPPED WITH NATIVE SOIL. IN NON-PAVED AREAS NATIVE BACKFILL SHALL BE USED AND COMPAKTED TO 90% MINIMUM RELATIVE COMPAKCTION.
- 16) ALL WORK IS SUBJECT TO APPROVAL BY THE AUTHORITY HAVING JURISDICTION PUBLIC WORKS SUPERINTENDENT INSPECTION AND ACCEPTANCE.
- 17) SPECIAL INSPECTIONS BY A SPECIAL INSPECTOR ARE REQUIRED DURING FILL PLACEMENT TO ENSURE PROPER MATERIALS AND PROCEDURES ARE USED IN ACCORDANCE WITH THE PROVISIONS OF THE APPROVED GEOTECHNICAL REPORT.
- 18) THE LOCATION, HEIGHT, AND PLATE HEIGHTS OF THE NEW STRUCTURE MUST BE CERTIFIED BY A SURVEYOR TO BE IN CONFORMANCE WITH THE APPROVED PLANS.
- 19) STOP WORK WITHIN 50 METERS (165') OF UNCOVERED RESOURCE AND CONTACT THE AUTHORITY HAVING JURISDICTION RMA - PLANNING DEPARTMENT AND A QUALIFIED ARCHAEOLOGIST IMMEDIATELY IF CULTURAL, ARCHAEOLOGICAL, HISTORICAL, OR PALEONTOLOGICAL RESOURCES ARE UNCOVERED.

ABBREVIATIONS:

±	PLUS OR MINUS; APPROXIMATE	INV	PIPE INVERT
Ø	DIAMETER	JB	JUNCTION BOX
ABAN	ABANDON	JT	JOINT TRENCH
AC	ASPHALT CONCRETE	LF	LINEAR FEET
AD	AREA DRAIN	LP	LOW POINT
ADD	ADDITION	MAX	MAXIMUM
ADU	ACCESSORY DWELLING UNIT	MIN	MINIMUM
BC	BEGINNING OF CURVE	OC	ON-CENTER
A.E.	BUILDING ENVELOPE	OUT	OUTLET
BLDG	BUILDING	PCC	PORTLAND CEMENT CONCRETE
BOT	BOTTOM	PERF	PERFORATED
BSMT	BASEMENT	PERM	PERMEABLE
BVC	BEGINNING OF VERTICAL CURVE	PL	PROPERTY LINE
CB	CATCH BASIN	POC	POINT OF CONNECTION
CF	CUBIC FEET	PVC	POLYVINYL CHLORIDE
CL	CENTERLINE	RC	RELATIVE COMPAKCTION
CO	CLEANOUT	RES	RESIDENCE
CONC	CONCRETE	RM	ROOM
CY	CUBIC YARDS	RND	ROUND
DG	DECOMPOSED GRANITE	RW	RETAINING WALL
DK	DECK	RWL	RAINWATER LEADER
DS	DOWNSPOUT	SD	STORM DRAIN
DWY	DRIVEWAY	SF	SQUARE FEET
EC	END OF CURVE	SG	SUBGRADE
ELEV	ELEVATION	SQ	SQUARE
ESMT	EASEMENT	SS	SANITARY SEWER
EVC	END OF VERTICAL CURVE	STA	STATION
EW	EACH WAY	STN	STONE
EX	EXISTING	STP	STEP
FC	FLUSH CURB	SUBD	SUBDRAIN
FD	FIRE DEPARTMENT	TBR	TO BE REMOVED
FF	FINISHED FLOOR	TD	TRENCH DRAIN
FG	FINISHED GRADE	TW	TOP OF WALL
FL	FLOWLINE	TYP	TYPICAL
FM	FORCE MAIN	U.N.O.	UNLESS NOTED OTHERWISE
FP	FINISHED PAD	VC	VERTICAL CURB
GAR	GARAGE	VIF	VERIFY IN FIELD
GB	GRADE BREAK	W/	WITH
GR	GRATE	W/O	WITHOUT
HDPE	HIGH-DENSITY POLYETHYLENE	WD	WOOD
HP	HIGH POINT		
HT	HEIGHT		

LOT OVERVIEW

SCALE: 1" = 50'



LEGEND:

PROPERTY BOUNDARY
SETBACK
MAJOR CONTOUR (5' INTERVAL)
MINOR CONTOUR (1' INTERVAL)
RETAINING WALL
SWALE FLOW LINE
STORM DRAIN PIPE
RAINWATER LEADER
SUBDRAIN LINE
CATCH BASIN
AREA DRAIN
JUNCTION BOX
DISPERSION TRENCH
CONCRETE
DECOMPOSED GRANITE
IMPERVIOUS PAVERS
PERMEABLE PAVERS
STONE
TREE
TREE TO BE REMOVED

PROJECT DATA:

SITE LOCATION:
3363 17 MILE DR
PACIFIC GROVE, CA 93950

GRADING VOLUMES:

CUT	65 CY
FILL	45 CY
NET	20 CY CUT

SITE AREA: 45,823 SF (1.05 AC)
DISTURBED AREA: ±6703 SF
IMPERVIOUS LOT COVERAGE:
EXISTING 7253 SF
REMOVED 0 SF
NEW/REPLACED +1685 SF
TOTAL 8938 SF

INDEX TO SHEETS:

SHEET C1	COVER SHEET
SHEET C2	GRADING & DRAINAGE PLAN
SHEET C3	GRADING SECTIONS & DETAILS
SHEET C4	UTILITY PLAN
SHEET C5	CONSTRUCTION DETAILS
SHEET C6	EROSION & SEDIMENT CONTROL PLAN
SHEET C7	CONSTRUCTION MANAGEMENT PLAN

CONTACT INFORMATION:

PROPERTY OWNER:
GEORGE AND DANA HOLLAND
7851 N. SPYGLASS AVE
FRESNO, CA 93711

ARCHITECT:

IDG
721 LIGHTHOUSE AVE
PACIFIC GROVE, CA 93950
CONTACT: JASON DIAZ


CIVIL:

LANDSET ENGINEERS
520-B CRAZY HORSE CANYON RD
SALINAS, CA 93907
CONTACT: GUY GIRAUDO

SCALE: AS SHOWN
DATE: MAY 2025
JOB No. 2393-06
SHEET C1
OF 7 SHEETS
05/12/25 JAN RELEASED TO CLIENT
No. DATE BY REVISION

APPROVED BY:
GUY R. GIRAUDO
LANDSET ENGINEERS, INC.
520-B CRAZY HORSE CANYON RD
SALINAS, CA 93907
Office 831-443-3801
www.landseteng.com

"COVER SHEET"
GRADING, DRAINAGE, AND EROSION CONTROL PLAN
THE HOLLAND RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR GEORGE AND DANA HOLLAND



PROFESSIONAL ENGINEER
GUY R. GIRANDO
No. 56569
06-30-25
CIVIL
STATE OF CALIFORNIA
EXPIRES 5/1995

APPROVED BY:

GUY R. GIRANDO





LANDSET
ENGINEERS, INC.
520-8 Caro Horo Canyon Road
Salinas, California 93907
Office (831) 443-3801
www.landseteng.com

"GRADING, DRAINAGE, AND EROSION CONTROL PLAN"


OF
THE HOLLAND RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR
GEORGE AND DANA HOLLAND


APPROVED BY:

GUY R. GIRANDO



SCALE: AS SHOWN
DATE: MAY 2025
JOB No. 2393-06
SHEET C3
OF 7 SHEETS
05/12/25 JAN RELEASED TO CLIENT
No. DATE BY REVISION






APPROVED BY:

GUY R. GIRANDO
S-1925




"CONSTRUCTION DETAILS"
GRADING, DRAINAGE, AND EROSION CONTROL PLAN
OF RESIDENCE ADU
THE HOLLAND RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR GEORGE AND DANA HOLLAND

SCALE: AS SHOWN
DATE: MAY 2025
JOB No. 2393-06
SHEET C5
OF 7 SHEETS




Oldcastle Precast®
Enclosure Solutions
MACON/TRAFO/POD/VAL/PL/2004
Phone: 800.334.4664
Copyright 2009 Oldcastle Precast Inc.
www.oldcasteprecast.com


1 CHRISTY V64 CATCH BASIN




2 G5 STORM DRAIN CLEANOUT



3 PERIMETER SUBDRAIN




4 SUBDRAIN BEHIND RETAINING WALL




1. 4" THICK CONCRETE VALLEY GUTTER. LONGITUDINAL SLOPE SHALL NOT BE LESS THAN 1%
2. SIDE SLOPES SHALL BE A MINIMUM OF 5%
3. IT SHALL BE THE RESPONSIBILITY OF THE OWNER TO REGULARLY MAINTAIN THE SWALE AS
NEEDED FROM SILTATION
4. THE SOIL BELOW THE CONCRETE SHALL BE SCARIFIED 8" AND THEN RECOMPACTED TO A
MINIMUM OF 95% RELATIVE COMPACTION.


5 CONCRETE SWALE




6 NDS SPEE-D CHANNEL DRAIN



7 TRENCH DRAIN INSTALLATION



8 TRENCH DRAIN OUTLETS




13 DISPERSION TRENCH

11

12




Material Delivery and Storage WM-1



Description and Purpose
Prevent, reduce, or eliminate the discharge of pollutants from material delivery and storage to the stormwater system or waterways by preventing leakage of hazardous materials, waste, storage materials, and materials used in a completely enclosed designated area, installing secondary containment, conducting regular inspections, and training employees and subcontractors.

This best management practice covers only material delivery and storage. For other information on materials, see WM-2, Material Use, or WM-4, Spill Prevention and Control. For information on wastes, see the waste management BMPs in this section.

Solid Waste Management WM-5




Description and Purpose
Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training of employees and subcontractors.

Potential Alternatives
None

DETAILS NOT TO SCALE


WM-1



Description and Purpose
Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training of employees and subcontractors.

Potential Alternatives
None

WM-5




Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None

WM-6


Hazardous Waste Management WM-6



Description and Purpose
Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Potential Alternatives
None


Sanitary/Septic Waste Management WM-9




Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None


WM-9




CONCRETE WASHOUT NOT TO SCALE




SILT FENCE NOT TO SCALE



SECTION B-B NTS



STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE



FIBER ROLL NOT TO SCALE

EROSION & SEDIMENT CONTROL NOTES:


- 1) ALL EROSION CONTROL MEASURES SHALL CONFORM WITH THE AUTHORITY HAVING JURISDICTION EROSION CONTROL ORDINANCE.
- 2) ALL SLOPES SHALL BE PROTECTED WITH STRAW MULCH OR SIMILAR MEASURES TO PROTECT AGAINST EROSION UNTIL SUCH SLOPES ARE PERMANENTLY STABILIZED.
- 3) RUNOFF SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS, AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE.
- 4) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE AT THE END OF EACH DAY'S WORK. ACCESS ROADS SHALL BE CLEANED DAILY (IF NECESSARY) AND PRIOR TO ANY RAIN EVENT.
- 5) ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON THE DOWNSHILL PROPERTIES.
- 6) CONTRACTOR SHALL PROVIDE WATERING FOR DUST CONTROL DURING ALL GROUND DISTURBANCE OPERATIONS.
- 7) REVEGETATION SHALL CONSIST OF A MECHANICALLY APPLIED HYDROMULCH SLURRY OR HAND SEEDED WITH A STRAW MULCH COVER. MULCH SHALL BE ANCHORED BY AN APPROVED METHOD SUCH AS PUNCHING, TACKING, OR THE USE OF JUTE NETTING, AS DEEMED NECESSARY FOR THE SITE CONDITIONS TO ALLOW FOR GERMINATION AND ENABLE ADEQUATE GROWTH TO BE ESTABLISHED.
- 8) CHECK DAMS, SILT FENCES, FIBER ROLLS OR OTHER DESIGNS SHALL BE INCORPORATED TO CATCH ANY SEDIMENT UNTIL AFTER THE NEWLY EXPOSED AREAS ARE REVEGETATED SUFFICIENTLY TO CONTROL EROSION. EROSION CONTROL PLANTINGS AND MULCH SHALL BE CLOSELY MONITORED THROUGHOUT THE WINTER AND ANY RUNOFF PROBLEMS SHALL BE CORRECTED PROMPTLY. ALL EROSION AND/OR SLIPPAGE OF THE NEWLY EXPOSED AREAS SHALL BE REPAIRED BY THE PERMITTEE IN THEIR EXPENSE.
- 9) THE GRASS SEED SHALL BE PROPERLY IRRIGATED UNTIL ADEQUATE GROWTH IS ESTABLISHED AND MAINTAINED TO PROTECT THE SITE FROM FUTURE EROSION DAMAGE. ALL NEWLY EXPOSED (DISTURBED) AREAS SHALL BE SEEDED WITH THE FOLLOWING EROSION CONTROL MIX: BROMUS CARINATUS (CALIFORNIA BROME), VULPIA MICROSTACHYS (NUTTALL'S FESCUE), ELYMUS GLACIUS (BLUE WILD RYE), HORDEUM BRACHYANTHUM (MEADOW BARLEY), FESTUCA RUNNAMOLATE BLUE AND A MIXTURE OF LOCALLY NATIVE WILDFLOWERS.
- 10) SEDED AREAS SHALL BE RETAINED ON-SITE AND SHALL BE PREVENTED FROM FLOWING INTO THE STORM DRAINAGE SYSTEM. SEDIMENT CATCHMENT BARRIERS SHALL BE INSPECTED BY THE APPLICANT IMMEDIATELY AFTER ANY SIGNIFICANT RAINFALL AND AT LEAST DAILY DURING ANY PERIOD OF PROLONGED RAINFALL.
- 11) PRIOR TO COMMENCEMENT OF ANY LAND DISTURBANCE, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE AUTHORITY HAVING JURISDICTION TO ENSURE ALL NECESSARY SEDIMENT CONTROLS ARE IN PLACE AND THE PROJECT IS COMPLIANT WITH AUTHORITY HAVING JURISDICTION GRADING AND EROSION CONTROL REGULATIONS.
- 12) DURING CONSTRUCTION THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE AUTHORITY HAVING JURISDICTION TO UPDATE COMPACTION TEST RECORDS, INSPECT DRAINAGE DEVICE INSTALLATION, REVIEW THE MAINTENANCE AND EFFECTIVENESS OF BMPs INSTALLED, AS WELL AS, TO VERIFY THAT POLLUTANTS OF CONCERN ARE NOT DISCHARGED FROM THE SITE.
- 13) PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH THE AUTHORITY HAVING JURISDICTION TO CONDUCT A FINAL GRADING INSPECTION, COLLECT FINAL GEOTECHNICAL LETTER OF CONFORMANCE, ENSURE THAT ALL DISTURBED AREAS HAVE BEEN STABILIZED AND THAT ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THAT ARE NO LONGER NEEDED HAVE BEEN REMOVED.
- 14) THE APPLICANT SHALL SCHEDULE WEEKLY INSPECTIONS WITH THE AUTHORITY HAVING JURISDICTION DURING THE RAINY SEASON, OCTOBER 15th TO APRIL 15th, TO ENSURE CONTAMINANTS ARE NOT DISCHARGED INTO THE AREAS OF SPECIAL BIOLOGICAL SIGNIFICANCE.

"EROSION & SEDIMENT CONTROL PLAN"

OF RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR
GEORGE AND DANA HOLLAND

GRADING, DRAINAGE, AND EROSION CONTROL PLAN


OF RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR
GEORGE AND DANA HOLLAND



LANDSET
ENGINEERS, INC.
520-8 Caro Horse Canyon Road
Salinas, California 93907
Office 831-443-3801
www.landseteng.com

SCALE: 1" = 20'
DATE: MAY 2025
JOB No. 2.393-06
SHEET C6
OF 7 SHEETS
No. DATE BY REVISION


Material Delivery and Storage WM-1



Description and Purpose
Prevent, reduce, or eliminate the discharge of pollutants from material delivery and storage to the stormwater system or waterways by preventing leakage of hazardous materials, waste, storage materials, and materials used in a completely enclosed designated area, installing secondary containment, conducting regular inspections, and training employees and subcontractors.

This best management practice covers only material delivery and storage. For other information on materials, see WM-2, Material Use, or WM-4, Spill Prevention and Control. For information on wastes, see the waste management BMPs in this section.


Solid Waste Management WM-5



Description and Purpose
Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training of employees and subcontractors.

Potential Alternatives
None


WM-1



Description and Purpose
Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Potential Alternatives
None

WM-5




Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None

WM-6


Hazardous Waste Management WM-6



Description and Purpose
Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Potential Alternatives
None

Sanitary/Septic Waste Management WM-9




Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None

WM-9


DETAILS NOT TO SCALE



Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None


WM-5



Description and Purpose
Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Potential Alternatives
None


WM-6



Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None


WM-9



Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.

Potential Alternatives
None


WM-9



Description and Purpose
Prevent or reduce the discharge of pollutants to stormwater from hazardous waste through proper material use, waste disposal, and training of employees and subcontractors.

Potential Alternatives
None

WM-9



Description and Purpose
Prevent sanitary and septic waste management prevent the discharge of pollutants to stormwater from sanitary and septic waste by providing convenient, well-maintained facilities, and training of employees and subcontractors.


Potential Alternatives
None

WM-9

Material Delivery and Storage WM-1



PROJECTS - LANDSET ENGINEERS\2393 - Holland Residence\2393-06 ADU CIVIL\DWG\Holland ADU_2393_CIVIL.dwg



SITE GRADING:
THE PROPOSED GRADING INCLUDES APPROXIMATELY 65 CY OF CUT & 45 CY OF FILL.

CONSTRUCTION STAGING:
A. MOBILIZE, CLEAR AND GRUB

B. SITE GRADING

C. UTILITY INSTALLATION

D. CONSTRUCT STRUCTURE

E. INSTALL PAVERS AND LANDSCAPING

F. SITE CLEANING, PUNCH LIST

MATERIAL DELIVERIES SHALL BE SCHEDULED SUCH THAT THEY ARE USED PROMPTLY, AND MATERIAL STORAGE IS MINIMIZED. ALL CONSTRUCTION EQUIPMENT AND MATERIALS SHALL BE STORED IN A DESIGNATED AREA ON THE SUBJECT PROPERTY. SEE ARCHITECTURAL AND CIVIL PLANS FOR EROSION CONTROL AND DEMOLITION NOTES.

HAUL ROUTES:
HAUL TRUCKS SHALL BACK ONTO THE SITE FROM 17 MILE DR. HAUL TRUCKS WILL EXIT THE SITE, HEADING SOUTHEAST ON 17 MILE DR. TRUCKS WILL FOLLOW THE ROUTE SHOWN IN DETAIL B, FROM 17 MILE DR TO CA HWY 68 TO CA HWY 1. TRUCKS SHALL STAY ON 17 MILE DR AS TRUCKS BACK FROM THE PUBLIC RIGHT-OF-WAY INTO THE SITE. CONTRACTOR TO ENSURE THAT HEIGHT RESTRICTIONS WITHIN THE EASEMENT/DRIVeway AREA SHALL BE ADDRESSED BEFORE CONSTRUCTION VEHICLES ENTER THE SITE. SEE DETAILS B AND C, TRUCK ROUTING PLANS.

TRUCK STAGING AREA:
VEHICLES OR TRUCKS SHALL NOT QUEUE ON 17 MILE DR. TRUCKS SHALL QUEUE OFFSITE AND BE DIRECTED TO APPROACH THE SITE BY ONSITE PERSONNEL VIA RADIO OR PHONE.

EMPLOYEE PARKING:
EMPLOYEES SHALL PARK ON SITE WHENEVER POSSIBLE. EMPLOYEES SHALL CARPOOL WHENEVER POSSIBLE. PARKING IS PROHIBITED IN ALL NATURAL AREAS WHICH ARE NOT CURRENTLY PAVED OR GRAVEL.

LIMITS OF CONSTRUCTION:
ALL CONSTRUCTION SHALL TAKE PLACE WITHIN THE BORDER AS SHOWN. EXISTING CYPRESS, PINE, AND OAK TREES LOCATED WITHIN THE LIMITS SHOWN SHALL BE SURROUNDED BY ORANGE PROTECTIVE FENCING (SEE DETAIL).

NUMBER OF EMPLOYEES ONSITE PER DAY: APPROXIMATELY 10-20

NUMBER OF TRUCK TRIPS/DAY: 4

AMOUNT OF GRADING/DAY: 80 CY.

HOURS OF OPERATION/DAY: 8

DAYS OF OPERATION: MONDAY THROUGH FRIDAY


TIME OF OPERATION: 8:00 AM - 4:30 PM

PROJECT SCHEDULING: PROJECTED START DATE IS JANUARY 1, 2026. TOTAL PROJECT DURATION IS APPROXIMATELY 12 MONTHS.

CATEGORY	NO. OF TRUCK TRIPS	TOTAL DAYS
DEMOLITION	4	5
GRADING & SOIL REMOVAL (EXPORT)	4	1
ENGINEERING MATERIALS (IMPORT)	-	-
TOTALS	8	6

TRUCK TRIP GENERATION NOTES:


1. TRUCK TRIPS FOR THE GRADING/SOIL IMPORT IS BASED UPON 20 CUBIC YARDS PER TRUCKLOAD WITH AN AVERAGE OF 4 TRUCK LOADS PER DAY.
2. THERE ARE APPROXIMATELY 20 CUBIC YARDS OF SOIL MATERIAL TO BE EXPORTED FROM THE SITE.
3. GRADING OPERATIONS SHALL TAKE APPROXIMATELY 1 WORKING DAYS TO COMPLETE.
4. THE AMOUNT OF GRADING PER DAY WILL VARY, THE AVERAGE BETWEEN 80 & 100 CUBIC YARDS.



ESA FENCING
NOT TO SCALE



B NEIGHBORHOOD TRUCK ROUTING PLAN
NOT TO SCALE



C OVERALL TRUCK ROUTING PLAN
NOT TO SCALE

GRADING, DRAINAGE, AND EROSION CONTROL PLAN
OF RESIDENCE ADU
THE HOLLAND RESIDENCE ADU
A.P.N.: 008-361-007
PEBBLE BEACH, CALIFORNIA
FOR
GEORGE AND DANA HOLLAND

PROFESSIONAL ENGINEER
Guy R. Girando
No. 56569
Exp. 06-20-25
CIVIL STATE OF CALIFORNIA
LANDSET ENGINEERS, INC.
520-B Caro Horo Canyon Road
Salinas, CA 93907
Office: (831) 443-3801
www.landseteng.com

SCALE: #####
DATE: MAY 2025
JOB No. 2393-06
SHEET C7
OF 7 SHEETS
05/12/25 JAN RELEASED TO CLIENT
No. DATE BY REVISION