

# **Attachment 1**



04/09/2025

To whom it may concern, Here is a invoice from Ferrasci Park little league. We are trying to upgrade our little league park with new concrete and walk path for the kids. This is part of a beautification project we hope to accomplish in the near future. A local construction company Golz construction has given a quote to hepl us fulfill our goal. The work will include..

- . Excavate and off haul soil for new concrete slab.
- . Import, place and compact 4" of class 2 recycle base rock
- . Form, pour, place and finish 4" thick gray concrete slab #3 rebar at 18" OCEW
- . Clean up and dispose of any debris left by Golz operations.

Final price for job. \$22,500.000.

any questions please call Abel Vasquez 831-594-1528 President of Ferrasci little league Park.

**Golz Construction, Inc.**  
**General Engineering Contractor**  
**Salinas, CA 93908 Lisc.946565**

Ferrasci Little League

April 1, 2025

Re: 40' x 30' concrete slab behind backboard

Golz Construction, Inc. is pleased to provide the pricing to furnish the supervision, labor, equipment, and materials to complete the following site work construction for the above referenced site. This project is bid as Prevailing wage.

**Work to Include:**

- Excavate and off haul soil for new concrete slab
- Import, place and compact 4" of class 2 recycled base rock
- Form, pour, place and finish 4" thick gray concrete slab with #3 rebar at 18" OCEW
- Clean up and dispose of any debris left by Golz operations

Price:.....\$22,500.00

The proposed sum above is valid for thirty (30) days and is based on prices of materials and equipment in effect as of the date of this letter. The proposed sum is subject to increase because of tariffs, epidemics, import duties, trade policies, or market conditions.

**General Exclusions:**

- Increases in costs of materials that result from tariffs, epidemics, import duties, trade policy, or related market conditions are not included. Such increases shall be added to the contract sum via change order immediately
- Engineering, surveying and/or staking
- Golz construction is not to be held liable for damage to any areas used for access during construction
- Not responsible for utilities not locatable which include irrigation lines or any utilities untraceable
- Contractor is supply location for stockpiling, equipment storage and access routes
- Contractor is responsible for setting up and being there for any and all inspections
- No topsoil or landscaping of any kind is included UON
- No electrical/gas work is included UON
- No temporary or permanent fencing of any kind
- Soils and materials testing
- Not responsible for damage or repair of un-marked utilities
- Permits, fees and/or inspections
- Not responsible contaminated soil removal, disposal or handling
- Unsuitable soils and or dry back of any kind
- Supplying or paying for construction water
- SWWPP monitoring or reporting
- Existing underground utility removal and relocation due to elevation or alignment conflicts with new design.
- Anything not specifically mentioned in above proposal

Should you have any questions or need additional information, please contact me at your earliest convenience.

Respectfully Submitted,  
Cody Boyster  
Golz Construction, Inc.  
(831) 229-7792  
DIR# 1000025049

Accepted: \_\_\_\_\_ Date: \_\_\_\_\_

Printed Name: \_\_\_\_\_

(The above signed acknowledges that he / she is authorized to accept such work on behalf of property owner.)