

# Exhibit A

This page intentionally left blank.

**EXHIBIT A  
DRAFT RESOLUTION**

**Before the Planning Commission in and for the  
County of Monterey, State of California**

In the matter of the application of:

**MACKENZIE PATTERSON AND CAROL JUNGWIRTH (PLN170911)**

**RESOLUTION NO. ----**

Resolution by the Monterey County Planning  
Commission:

- 1) Finding that the project is a single-family residence, which qualifies for a categorical exemption pursuant to section 15303 of the California Environmental Quality Act Guidelines and that none of the exceptions under section 15300.2 apply; and,
- 2) Approving a Combined Development Permit consisting of 1) an Administrative Permit and Design Approval to allow a new 2,000 square foot one-story single family dwelling with a 522 square foot deck, a 576 square foot detached garage; and (2) a Use Permit for the removal of 5 oak trees.

[PLN170911, Patterson and Jungwirth, 25345  
Tierra Grande, Dr., (APN: 169-363-009-000)]

**The Patterson and Jungwirth application (PLN170911) came on for public hearing before the Monterey County Planning Commission on March 28, 2018. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Planning Commission finds and decides as follows:**

**FINDINGS**

1. **FINDING:** **CONSISTENCY** – The Project, as conditioned, is consistent with the applicable plans and policies which designate this area as appropriate for development.  
**EVIDENCE:**
  - a) During the course of review of this application, the project has been reviewed for consistency with the text, policies, and regulations in:
    - the 2010 Monterey County General Plan;
    - Carmel Valley Master Plan;No conflicts were found to exist. No communications were received during the course of review of the project indicating any inconsistencies with the text, policies, and regulations in these documents.
  - b) The property is located at 25345 Tierra Grande, Dr (Assessor’s Parcel Number 169-363-009-000), Carmel Valley Master Plan. The parcel is zoned Low Density Residential with Design Control, Site Plan, Building Site Zoning, and Residential Allocation Zoning overlays (LDR/B-6-D-

S-RAZ) which allows the first single family dwelling per lot with a Site Plan and Design Approval. Therefore, the project is an allowed land use for this site.

- c) The property and surrounding areas are designated as a Design Control Zoning District (“D” zoning overlay), which regulates the location, size, configuration, materials, and colors to assure the protection of the public viewshed and neighborhood character. The proposed structure color and materials include terra cotta colored standing seam metal roofing, grey fiber cement panels, and aluminum windows with a yellow/orange trim. The terra cotta roof color is consistent with other homes in the neighborhood and the low profile home design will blend with the surrounding environment and minimize any visibility from the road. The grey fiber cement panel siding blends with the surrounding environment and is appropriate for the very high fire hazard area.
- d) The project is consistent with Carmel Valley Master Plan Policy CV1.1 with states that development shall follow a rural architectural theme with Design Review. The modest-sized house prioritizes the existing wooded site and the colors have been selected to blend with the existing environment.
- e) The project is consistent with Carmel Valley Master Plan Policy CV-1.20(c), for Design and Site Plan overlay districts, which states that materials and colors used in construction shall be selected for compatibility with the structural system of the building and with the appearance of the building’s natural and man-made surroundings. The terra cotta roof color has been chosen to blend with the surrounding homes, while the grey siding will blend with the on-site oak trees.
- f) The property and surrounding areas are designated as a Site Plan Zoning District (“S” zoning overlay) for review of development in areas where development has the potential to adversely affect or be adversely affected by natural resources or site constraints. The parcel is significantly constrained due to the shape of the lot, slopes over 25%, and the presence of oak trees. Structures have been carefully sited within the required setbacks to minimize oak tree removal and avoid development on slopes.
- g) The project is consistent with requirements for the B-6 district because it does not involve subdivision or a lot line adjustment.
- h) The project is consistent with the requirements for the RAZ district because proposed dwelling is the first dwelling unit on a legal lot.
- i) The project planner conducted a site inspection on December 15, 2017 to verify that the project on the subject parcel conforms to the plans listed above.
- j) The project meets setback requirements for LDR lots. The required front setback is 30 feet for main structures and 50 feet for non-habitable accessory structures. The house will be 100 feet from the front property line and the garage will be 75 feet from the front property line. The required side setbacks are 10 percent of the average lot width. The parcel is narrowest at the front where it borders Tierra Grande Dr. and widens toward the back, with the widest portion at the rear property line. Ten percent of the average lot width is 15ft, 9in. The house will be exactly 15ft 9in from the north property line and 22ft 6in from the south

property line. The detached garage will be 12ft 6in from the south property line, which exceeds the 6ft required side setback for non-habitable accessory structures.

- k) The project was referred to the Carmel Valley Land Use Advisory Committee (LUAC) for review. Based on the LUAC Procedure guidelines adopted by the Monterey County Board of Supervisors, this application did warrant referral to the LUAC because the project includes a Design Approval and is subject to review by the Planning Commission. The LUAC voted 6-0 to support the project, but recommended that a construction parking plan be submitted prior to issuance of the building permit. The applicant has submitted a construction management plan identifying four parking areas on site and two optional spaces Tierra Grande Dr. The parking plan also requires a sign to be posted stating that no parking shall be permitted to block the driveway right-of-way or the neighbor's driveway.
- l) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN170911.

2. **FINDING:** **SITE SUITABILITY** – The site is physically suitable for the use proposed.

- EVIDENCE:**
- a) The project has been reviewed for site suitability by the following departments and agencies: RMA- Planning, Monterey County Regional Fire Protection District, RMA-Public Works, RMA-Environmental Services, Environmental Health Bureau, and Water Resources Agency. There has been no indication from these departments/agencies that the site is not suitable for the proposed development. Conditions recommended have been incorporated.
  - b) The following reports have been prepared:
    - “Patterson/Jungwirth Residence 25345 Tierra Grande, Carmel Valley, CA Tree Resource Assessment” (LIB180043) prepared by Frank Ono, Urban Forester, Pacific Grove, CA, October 31, 2017.
    - “Geotechnical Engineering Report for Proposed Single Family Residence and Detached garage 25345 Tierra Grande Drive Monterey County, CA” prepared by Beacon Geotechnical, Inc., Paso Robles, CA, December 8, 2017

The above-mentioned technical reports by outside consultants indicated that there are no physical or environmental constraints that would indicate that the site is not suitable for the use proposed. County staff has independently reviewed these reports and concurs with their conclusions.

- c) Staff conducted a site inspection on December 15, 2017 to verify that the site is suitable for this use.
- d) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA - Planning for the proposed development found in Project File PLN170911.

3. **FINDING:** **HEALTH AND SAFETY** - The establishment, maintenance, or operation of the project applied for will not under the circumstances of

this particular case be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use, or be detrimental or injurious to property and improvements in the neighborhood or to the general welfare of the County.

- EVIDENCE:**
- a) The project was reviewed by the RMA - Planning, Monterey County Regional Fire Protection District, Public Works, Environmental Health Bureau, and Water Resources Agency. The respective agencies have recommended conditions, where appropriate, to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
  - b) Necessary public facilities are available. The house will be served by an onsite well and a new septic system. Environmental Health has reviewed water quality and pump tests completed in 2008 and has conditioned the project to require updated quality tests prior to final of the construction permit. Septic system plans have been approved; however, new septic design will be required if building permits are obtained after an expected change in regulations in May 2018.
  - c) Staff conducted a site inspection on December 15, 2017 to verify that the site is suitable for this use.
  - d) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA - Planning for the proposed development found in Project File PLN170911.

4. **FINDING:**

**TREE REMOVAL** - Tree removal is the minimum required under the circumstances and the removal will not involve a risk of adverse environmental impacts.

- a) The project includes the removal of 5 oak trees. In accordance with the applicable policies of the Carmel Valley master plan and the Monterey County Zoning Ordinance (Title 21), a Use Permit is required and the authority to grant said permit has been met.
- b) Monterey County Zoning Ordinance Section 21.64.260(D)(3) requires a the submittal of a Forest Management Plan (FMP) and approval of a Use Permit for tree removal of more than 3 protected trees. The applicant has applied for and complied with these requirements.
- c) Staff has reviewed the project plans and visited the site on December 15, 2018 to analyze possible environmental impacts from tree removal.
- d) A Tree Resource Assessment was prepared by Frank Ono, a Certified Arborist, on October 31, 2017 (LIB180043).
- e) The 1 acre parcel contains a total of 59 oak trees, of which 5 are requested for removal.
- f) The proposed single family dwelling and driveway have been carefully designed to limit tree removal. Most of the mature oak trees on the property will be preserved. The originally proposed back patio has been redesigned as a deck to minimize disruption of tree roots and to promote better gaseous interchange and moisture for the critical root zone for a stand of three oak trees of 14 inch, 14 inch, and 18 inch diameters.
- g) Measures for tree protection during construction have been incorporated as a Condition of Approval (Condition 4), and include fencing and barricades.

- h) The tree removal will not involve risk of adverse environmental impacts. Trees close to construction activities are expected to survive with the recommended protection measures, and the majority of the trees on site will not be impacted by construction activities. No long term significant effects to the forest ecosystem were identified in the Tree Resource Assessment.
- i) Removed trees are not required to be replaced in accordance with Title 21.64.260 because replacement will cause special hardship to the site and would be detrimental to the long-term health and maintenance of the remaining habitat. The arborist report found that the site is overstocked and overcrowded with trees and that an overabundance of shade would not allow new trees to be sustained in a healthy condition. Monterey County Regional Fire Protection District stated that they agree with the project arborist that replacing the removed trees would contribute to an over-abundance of ladder fuels and would constitute a fire hazard.
- j) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA - Planning for the proposed development found in Project File PLN170911.

5. **FINDING:** **NO VIOLATIONS** - The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision, and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.

- EVIDENCE:**
- a) Staff reviewed Monterey County RMA - Planning and Building Services Department records and is not aware of any violations existing on subject property.
  - b) Staff conducted a site inspection on December 15, 2018 and researched County records to assess if any violation exists on the subject property.
  - c) There are no known violations on the subject parcel.
  - d) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN170911.

6. **FINDING:** **CEQA (Exempt):** - The project is categorically exempt from environmental review and no unusual circumstances were identified to exist for the proposed project.

- EVIDENCE:**
- a) California Environmental Quality Act (CEQA) Guidelines Section 15303 categorically exempts a single-family residence and accessory structures including garages within residentially zoned areas.
  - b) The proposed project involves the construction of a single-family residence and attached garage, both located within a residential zone.
  - c) No adverse environmental effects were identified during staff review of the development application during a site visit on December 15, 2018.
  - d) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. The project does not involve a designated historical resource, a hazardous waste site, development located near or within view of a scenic highway, unusual circumstances that would result in a significant effect on the environment, or development that would result in a cumulative significant impact

- e) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN170911.

7. **FINDING:** **APPEALABILITY** - The decision on this project may be appealed to the Board of Supervisors and not to the California Coastal Commission.
- EVIDENCE:**
- a) Section 21.80.040.D of the Monterey County Zoning Ordinance states that the proposed project is appealable to the Board of Supervisors.
  - b) The project is not located in the Coastal Zone.

### DECISION

**NOW, THEREFORE**, based on the above findings and evidence, the Planning Commission does hereby:

1. Find the project is a single-family residence, which qualifies for a categorical exemption pursuant to section 15303 of the California Environmental Quality Act Guidelines and that none of the exceptions under section 15300.2 apply; and,
2. Approving a Combined Development Permit consisting of 1) an Administrative Permit and Design Approval to allow a new 2,000 square foot one-story single family dwelling with a 522 square foot deck, and a 576 square foot detached garage; and (2) a Use Permit for the removal of 5 oak trees in general conformance with the attached sketch and subject to the attached conditions, all being attached hereto and incorporated herein by reference; and

**PASSED AND ADOPTED** this 28<sup>th</sup> day of March, 2018 upon motion of \_\_\_\_\_, seconded by \_\_\_\_\_, by the following vote:

AYES:  
NOES:  
ABSENT:  
ABSTAIN:

\_\_\_\_\_  
Jacqueline Onciano, Planning Commission

COPY OF THIS DECISION MAILED TO APPLICANT ON DATE

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE [DATE]

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

### NOTES

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.



Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from Monterey County RMA-Planning and RMA-Building Services Department office in Salinas.

2. This permit expires 3 years after the above date of granting thereof unless construction or use is started within this period.

Form Rev. 5-14-2014

# Monterey County RMA Planning

## DRAFT Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN170911

### 1. PD001 - SPECIFIC USES ONLY

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** This Combined Development permit (PLN170911) allows a 2000 square foot single family dwelling with a 522 square foot deck, a 76 square foot detached garage, and the removal of 5 oak trees. The property is located at (Assessor's Parcel Number 169-363-009-000), Carmel Valley Master Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the Director of RMA - Planning. Any use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

### 2. PD002 - NOTICE PERMIT APPROVAL

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall record a Permit Approval Notice. This notice shall state:  
"A [Type of Permit] (Resolution Number \*\*\*) was approved by [Name of Hearing Body] for Assessor's Parcel Number \*\*\* on [Date the permit was approved]. The permit was granted subject to \*\*\* conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

### 3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** If, during the course of construction, cultural, archaeological, historical or paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a qualified archaeologist (i.e., an archaeologist registered with the Register of Professional Archaeologists) shall be immediately contacted by the responsible individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.  
(RMA - Planning)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

### 4. PD049 - TREE AND ROOT PROTECTION

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Prior to beginning any tree removal, trees which are located close to trees approved for removal shall be protected from inadvertent damage from equipment or tree removal activity by fencing off the canopy drip-lines and/or critical root zones (whichever is greater) with protective materials. Any tree protection measures recommended by a County-approved tree consultant, in addition to the standard condition, shall be implemented. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** Prior to construction or tree removal, the Owner/Applicant/Tree Removal Contractor submit evidence of tree protection to RMA-Planning for review and approval.

After construction or tree removal, the Owner/Applicant/Tree Removal Contractor shall submit photos of the trees on the property to RMA-Planning to document that the tree protection has been successful or if follow-up remediation measures or additional permits are required.

## 5. PDSP001-CONSTRUCTION MANAGEMENT PLAN

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall submit a Construction Management Plan (CMP) to the Resource Management Agency (RMA) for review and approval. The CMP shall include measures to minimize traffic impacts and noise during the construction/grading phase of the project and shall provide the following information:

Duration of the construction, hours of operation, an estimate of the number of truck trips that will be generated, truck routes, number of construction workers, parking areas for both equipment and workers, and locations of truck staging areas. Specifically, the plan should limit construction noise from Monday through Friday 8am to 5pm and Saturday from 10am to 5pm and shall be designed to avoid blocking access and line of sight from neighboring driveways. Approved measures included in the CMP shall be implemented by the applicant during the construction/grading phase of the project.

**Compliance or Monitoring Action to be Performed:** Prior to issuance of construction permits, the applicant shall submit a Construction Management Plan to RMA for review and approval.

The Construction Management Plan shall be adhered to throughout the duration of grading and construction for the project.

## 6. PD035 - UTILITIES UNDERGROUND

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** All new utility and distribution lines shall be placed underground. (RMA - Planning and RMA- Public Works)

**Compliance or Monitoring Action to be Performed:** On an on-going basis, the Owner/Applicant shall install and maintain utility and distribution lines underground.

## 7. EHSP01 - DOMESTIC WELL: WATER QUALITY (Non-Standard)

**Responsible Department:** Health Department

**Condition/Mitigation Monitoring Measure:** A residential building shall be provided with an adequate supply of potable water pursuant to Section 601.1 of the Uniform Plumbing Code. In order to demonstrate a potable supply for domestic use, the well shall first undergo water quality testing. Sample collection shall include analysis of coliform bacteria, and primary inorganics and secondary compounds as listed in Tables 64431-A and 64449-A&B in Title 22 of the California Code of Regulations. Waivers for asbestos, MTBE, and thiobencarb may be available upon request. Sample collection shall be done by a person approved by EHB and shall be analyzed by a laboratory certified by the Environmental Laboratory Accreditation Program (ELAP). If water quality results indicate that the well exceeds a primary drinking water standard(s), a treatment system shall be installed before a building is occupied and the applicant shall record a deed restriction indicating that treatment is necessary for the well water to meet Title 22, CCR primary drinking water standards. (Environmental Health)

**Compliance or Monitoring Action to be Performed:** Prior to final of the construction permit, the applicant shall submit water quality analysis results to the Environmental Health Bureau (EHB) for review. If EHB determines that the water quality is adequate, no further action is required.

If EHB determines that treatment is necessary:

- Prior to issuance of a construction permit, the applicant shall provide plans prepared by a qualified individual for treatment to EHB for review and approval.
- Prior to occupancy of a building, the applicant shall provide to EHB for review and approval as-built plans prepared by a qualified individual for treatment and water quality analysis for a treatment effluent sample that demonstrates the treatment system is able to reduce the contaminant(s) to Title 22, CCR primary standards.

The applicant shall submit a draft deed restriction for review and approval by EHB and County Counsel.

The applicant shall provide proof of recordation of the approved deed restriction to EHB and Planning Department.

If the applicant chooses not to pursue utilizing the well as a source for domestic use, this condition shall not be applicable.

## 8. EROSION CONTROL PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit an Erosion Control Plan in conformance with the requirements of Monterey County Code Chapter 16.12. The Erosion Control Plan shall include a construction entrance, concrete washout, stockpile area(s), material storage area(s), portable sanitation facilities and waste collection area(s), as applicable. (RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit an Erosion Control Plan to RMA-Environmental Services for review and approval.

## 9. GEOTECHNICAL CERTIFICATION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall provide certification from a licensed practitioner that all development has been constructed in accordance with the recommendations in the project Geotechnical Report. (RMA- Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall provide RMA-Environmental Services a letter from a licensed practitioner.

## 10. GRADING PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit a Grading Plan incorporating the recommendations from the project Geotechnical Engineering Report prepared by Beacon Geotechnical, Inc. The Grading Plan shall include contour intervals and cross-sections that identify the existing grade, proposed grade, and the extent of any proposed excavation and/or fill. The Grading Plan shall include the geotechnical inspection schedule that identifies when the inspections will be completed, who will conduct the inspection (i.e., PG, PE, and/or Special Inspector), a description of the required inspection, inspector name, and the completion date. The applicant shall also provide certification from the licensed practitioner that the Grading Plan incorporates their geotechnical recommendations. (RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit a Grading Plan to RMA-Environmental Services for review and approval.

Prior to issuance of any grading or building permits, the applicant shall submit certification from a licensed practitioner that they have reviewed the Grading Plan for conformance with the geotechnical recommendations.

## 11. INSPECTION-DURING ACTIVE CONSTRUCTION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to inspect drainage device installation, review the maintenance and effectiveness of BMPs installed, and to verify that pollutants of concern are not discharged from the site. At the time of the inspection, the applicant shall provide certification that all necessary geotechnical inspections have been completed to that point. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** During construction, the applicant shall schedule an inspection with RMA-Environmental Services.

## 12. INSPECTION-FOLLOWING ACTIVE CONSTRUCTION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to ensure all disturbed areas have been stabilized and all temporary erosion and sediment control measures that are no longer needed have been removed. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

## 13. INSPECTION-PRIOR TO LAND DISTURBANCE

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to ensure all necessary sediment controls are in place and the project is compliant with Monterey County regulations. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to commencement of any land disturbance, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

## 14. WR002 - STORMWATER CONTROL

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide a drainage plan, prepared by a registered civil engineer or licensed architect, to mitigate on-site and off-site impacts. Impervious surface stormwater runoff shall be dispersed at multiple points, on the least steep available slopes, away from and below any septic leach fields. Erosion control shall be provided at each outlet. Drainage improvements shall be constructed in accordance with plans approved by the Water Resources Agency. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a drainage plan with the construction permit application.

The Building Services Department will route a plan set to the Water Resources Agency for review and approval.

## 15. WR049 - WATER AVAILABILITY CERTIFICATION

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide the Monterey County Water Resources Agency proof of water availability in the form of a complete Monterey Peninsula Water Management District Water Release Form. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a Water Release Form to the Water Resources Agency for review and approval.

A copy of the Water Release Form can be obtained at the Monterey Peninsula Water Management District, the Water Resources Agency, or online at:  
[www.mcwra.co.monterey.ca.us](http://www.mcwra.co.monterey.ca.us).

## 16. PD050 - RAPTOR/MIGRATORY BIRD NESTING

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Any tree removal activity that occurs during the typical bird nesting season (February 22-August 1), the County of Monterey shall require that the project applicant retain a County qualified biologist to perform a nest survey in order to determine if any active raptor or migratory bird nests occur within the project site or within 300 feet of proposed tree removal activity. During the typical nesting season, the survey shall be conducted no more than 30 days prior to ground disturbance or tree removal. If nesting birds are found on the project site, an appropriate buffer plan shall be established by the project biologist. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** No more than 30 days prior to ground disturbance or tree removal, the Owner/Applicant/Tree Removal Contractor shall submit to RMA-Planning a nest survey prepared by a County qualified biologist to determine if any active raptor or migratory bird nests occur within the project site or immediate vicinity.



Project Data: MacKenzie C. Patterson & Carol S. Jungwirth  
 Project: New Single Family Dwelling & Detached Garage  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000

Zoning:	LDR/B-6-D-S-RAZ		
General Plan Designation:	Residential		
Proposed:	2,000.00 SQ.FT.	Conditioned Living Space*	
	576.00 SQ.FT.	Detached Garage	
	205.50 SQ.FT.	8' East Roof Overhang	
	101.33 SQ.FT.	3' Roof Overhang Typical	
	39.00 SQ.FT.	3' Roof Overhang @ Garage	
	45.00 SQ.FT.	4' Roof Overhang @ Garage	
	2,966.83 SQ.FT.	Total Coverage	

\*Conditioned Living Space includes walls & fireplaces, etc.

Parcel Area: 44,866.80 SQ.FT. 1.03 Acres

Allowable Site Coverage: 25 %  
 Allowable Area: 11,216.70 SQ.FT.

Coverage:	Existing	Proposed	Total
Building	- SQ.FT.	2,966.83 SQ.FT.	2,966.83
Imperviot	750.00 SQ.FT.	1,080.00 SQ.FT.	1,830.00
	1.67 %	9.02 %	10.69 %

Floor Area Ratio: N/A  
 Grading: Cut 35.10 CU.YDS. Fill 39.36 CU.YDS.

Allowable Height:	30.00 Feet	Main Structure	30.00 Feet	Accessory Structure	15.00 Feet
Highest Point Existing Grade	100.00 Feet		100.00 Feet		101.00 Feet
Lowest Point Existing Grade	96.85 Feet		96.85 Feet		99.55 Feet
Average Natural Grade	98.43 Feet		98.43 Feet		100.28 Feet
Maximum Allowable Height	128.43 Feet		128.43 Feet		115.28 Feet
First Floor Elevation	99.50 Feet		99.50 Feet		99.50 Feet
Proposed Maximum Height	115.25 Feet		115.25 Feet		113.03 Feet

Setbacks:	Allowable	Proposed Main	Allowable Accessory	Proposed Acc.
Front	30.00 Feet	165.00 Feet	50.00 Feet	56.00 Feet
N.Side	15.73 Feet	36.00 Feet	6.00 Feet	139.00 Feet
S.Side	15.73 Feet	57.00 Feet	50.00 Feet	50.00 Feet
Rear	20.00 Feet	62.75 Feet	1.00 Feet	249.00 Feet
Between	10.00 Feet	10.00 Feet		

Parking:	2 Covered	1 Covered
	2 Uncovered	1 Uncovered

Tree Removal: 5 Oak


Water Provided by: Private On Site Well

No Areas are subject to inundation or 100 year flood levels.


No Known Environmentally sensitive habitat, archaeological resources, historical sites, or hazzards.

No Wetlands, Streams, Creeks, or any other bodies of water on subject property.

Scope of Work:  
 New One Story Single Family Residence with Detached Garage.



### ASSESSOR'S PARCEL MAP



### VICINITY MAP

#### WUI NOTICE & REQUIREMENTS

This Project is located within a Wildland-Urban Interface Fire Area designated by the local jurisdiction and shall comply with the requirements of CRC section R327 for exterior wildfire exposure.

Where the roof profile allows a space between the roof covering and the roof decking, the spaces shall be constructed to prevent the intrusion of flames and embers, be firestopped, or have one layer of 72 pound mineral-surfaced nonperforated cap sheet complying with ASTM D3909 installed over the combustible decking.

When provided, valley flashings shall be not less than 0.019 inch (No.26 galvanized sheet gauge) corrosion resistant metal installed over a minimum 36 inch wide underlayment consisting of one layer of 72 pound mineral surfaced nonperforated cap sheet complying with ASTM D3909 running the full length of the valley.

Roof Gutters shall be provided with means to prevent the accumulation of leaves and debris in the gutter. Please note that no gutters are proposed, except collection boxes at the valley terminations, which shall have debris covers

Roof and Attic Vents shall resist the intrusion of flame and embers into the attic area of the structure, or shall be protected by corrosion resistant, noncombustible wire mesh with openings of 1/16 inch and shall not exceed 1/8 inch. Please note that no operable attic vents are proposed, and that those shown on the exterior elevations are decorative only and are to be completely blocked off.

Vents shall not be installed on the underside of eaves and cornices, unless the vents are approved to resist the intrusion of flame and embers, the attic space is sprinklered in accordance with CRC Section 903.3.1.1, or if the exterior wall and underside of the eave are of ignition resistant materials and the vents are located more than 12 feet from the ground or walking surface. Please note that no eave or cornice vents are proposed.

Exterior wall coverings shall extend from the top of the foundation to the roof, and terminate at 2 inch nominal solid wood blocking between rafters and eaves at all roof overhangs, or in case of enclosed eaves, terminate at the enclosure. Please note that there are no overhangs, except the south Verandah which is fire sprinklered.

Enclosed eaves and soffits shall be approved noncombustible material, ignition resistant material, one layer of 5/8 inch Type X gypsum board, the exterior portion of an approved one-hour wall assembly, or have the horizontal underside meet the performance criteria of SFM 12-7A-3. Please note that there are no eaves or soffits, except the south Verandah which is fire sprinklered.

Exterior porch ceilings shall be approved noncombustible material, ignition resistant material, one layer of 5/8 inch Type X gypsum board, the exterior portion of an approved one-hour wall assembly, or have the horizontal underside meet the performance criteria of SFM 12-7A-3. Please note that the south Verandah is fire sprinklered.

Exterior Windows and exterior glazed doors shall be multipane glazing with a minimum of one tempered pane, glass block units, have a fire resistive rating of 20 minutes when tested in accordance with NFPA 257, or meet the requirements of SFM 12-7A-2.


Exterior Doors shall be of approved noncombustible construction or ignition resistant material, solid core wood having stiles and rails not less than 1-3/8 inches thick with interior field panel thickness no less than 1-1/4 inches thick, shall have a fire resistance rating of not less than 20 minutes when tested in accordance with NFPA 252, or meet the requirements of SFM 7A-1.

If, during the course of construction, cultural, archaeological, historical or paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a qualified archaeologist (i.e., an archaeologist registered with the Register of Professional Archaeologists) shall be immediately contacted by the responsible individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery. (RMA - Planning)

CONSTRUCTION ACTIVITY	
Construction Duration	12 Months, beginning upon permit issuance
Construction Hours	Monday - Saturday / 7AM - 7PM
Construction Vehicles	5
Construction Workers	4 regular pickup trucks
Estimated # Truck Trips	200
Stacking Parking Area Trucks	See #4 & #5 on adjacent Plan

- CONSTRUCTION SITE PLAN
- Proposed Residence
  - Proposed Garage
  - Temporary Job Trailer (Optional)
  - On Site Job Parking (4)
  - Optional Job Parking on Street (2)
  - Workers shall be cautioned to avoid blocking neighbor's driveways.
  - Temporary Porta Potty
  - Proposed Driveway
  - Existing Driveway to Neighbor
- A Sign shall be posted to state that NO Parking shall be permitted on the Driveway Right of Way, or in Neighbor's Driveway.

CONSTRUCTION COORDINATION  
 Owner shall post a sign with Owner/Architect's contact phone number  
 Readily visible from the street, such that anyone may contact the Owner /Architect with questions and/or complaints.




### CONSTRUCTION MANAGEMENT PLAN

### CONSTRUCTION BEST MANAGEMENT PRACTICES (BMPs)

Construction Projects Are Required to Implement the Stormwater Best Management Practices (BMP) on this Page, as they Apply to Your Project, All Year Long

MATERIALS & WASTE MANAGEMENT	EQUIPMENT MANAGEMENT & SPILL CONTROL	EROSION CONTROL	PAVING/ASPHALT WORK	CONCRETE, GROUT & MORTAR APPLICATION	PAINTING & PAINT REMOVAL	DEWATERING
<p><b>Non-Hazardous Materials</b></p> <ul style="list-style-type: none"> <li>Store and cover stockpiles of soil, dirt or other construction material with tarp when rain is forecast or if not actively being used within 14 days.</li> <li>Use (but don't overuse) reclaimed water for dust control.</li> </ul> <p><b>Hazardous Materials</b></p> <ul style="list-style-type: none"> <li>Store hazardous materials and wastes in water tight containers, when in appropriate secondary containment, and cover them at the end of every work day or during wet weather or when rain is forecast.</li> <li>Follow manufacturer's application instructions for hazardous materials and be careful not to use more than necessary. Do not apply chemicals outdoors when rain is forecast within 24 hours.</li> <li>Arrange for appropriate disposal of all hazardous wastes.</li> </ul>	<p><b>Waste Management</b></p> <ul style="list-style-type: none"> <li>Cover waste disposal containers securely with tarps at the end of every work day and during wet weather.</li> <li>Check waste disposal containers frequently for leaks and to make sure they are not overfilled. Never hose down a dumpster on the construction site.</li> <li>Clean or replace portable toilets, and inspect them frequently for leaks, spills, and debris. Dispose of all wastes and debris properly. Recycle materials and wastes that can be recycled (such as asphalt, concrete, aggregate base materials), wood, exp. board, pipe, etc.)</li> <li>Dispose of liquid residues from paint, thinners, solvents, glue, and cleaning fluids as hazardous waste.</li> </ul> <p><b>Construction Entrances and Perimeter</b></p> <ul style="list-style-type: none"> <li>Establish and maintain effective perimeter controls and schedule of construction entrance and exit to sufficiently control erosion and sediment discharges from site and tracking of mud on roads.</li> <li>Sweep or vacuum any street tracking immediately and score sidewalk surface to prevent further tracking. Never hose down streets to clean up tracking.</li> </ul>	<p><b>Spill Prevention and Control</b></p> <ul style="list-style-type: none"> <li>Keep spill cleanup materials (sags, absorbents, etc.) available at the construction site at all times.</li> <li>Inspect vehicles and equipment frequently for oil and fuel leaks promptly. Use drip pans to catch leaks until repairs are made.</li> <li>Clean up spills or leaks immediately and dispose of cleanup materials properly.</li> <li>Do not hose down surfaces where fluids have spilled. Use dry cleaning methods (absorbent materials, oil liner, and/or sawdust).</li> <li>Remove up spilled dry materials immediately. Do not try to wash them away with water, or bury them.</li> <li>Clean up spills on dirt areas by digging up and properly disposing of contaminated soil.</li> <li>Report significant spills immediately. You are required by law to report all significant releases of hazardous materials, including oil. If you are a local emergency services number, 2) Call the Governor's Office of Emergency Services Warning Center. (800) 852-7550 (24 hours).</li> </ul>	<p><b>Erosion Control</b></p> <ul style="list-style-type: none"> <li>Stabilize all denuded areas, install and maintain temporary erosion controls (such as erosion control fabric or bonded fiber matrix) until vegetation is established.</li> <li>Seed or plant vegetation for erosion control on slopes or other areas where erosion is likely to occur.</li> <li>Do not use water to wash down fresh asphalt concrete pavement.</li> </ul> <p><b>Sediment Control</b></p> <ul style="list-style-type: none"> <li>Protect storm drain inlets, gutters, ditches, and drainage courses with appropriate BMPs, such as gravel bags, filter rolls, berms, etc.</li> <li>Prevent sediment from migrating offsite by installing and maintaining sediment controls, such as filter rolls, silt fences, or sediment basins.</li> <li>Keep excavated soil on the site when it will not collect into the street.</li> <li>Transfer excavated materials to dump trucks on the site, not in the street.</li> </ul> <p><b>Soil Stabilization</b></p> <ul style="list-style-type: none"> <li>If any of the following conditions are observed, test for contamination and contact the Regional Water Quality Control Board:           <ul style="list-style-type: none"> <li>Unusual soil conditions, discoloration, or odor.</li> <li>Abandoned underground tanks.</li> <li>Abandoned wells.</li> <li>Stuck barrels, debris, or trash.</li> </ul> </li> </ul>	<p><b>Concrete, Grout &amp; Mortar Application</b></p> <ul style="list-style-type: none"> <li>Avoid piling and soil coating in wet weather, or when rain is forecast before fresh pavement will have time to cure.</li> <li>Cover storm drain inlets and manholes when applying seal coat, tack coat, slurry seal, fog seal, etc.</li> <li>Collect and recycle or appropriately dispose of excess slurry or seal.</li> <li>Do not use water to wash down fresh asphalt concrete pavement.</li> </ul> <p><b>Sweeping &amp; Asphalt/Concrete Removal</b></p> <ul style="list-style-type: none"> <li>Completely cover or barricade storm drain inlets when saw cutting. Use filter fabric, catch basin inlet filter, or gravel bags to keep slurry out of the storm drain system.</li> <li>Shovel, absorb, or vacuum saw-cut slurry and dispose of all waste as soon as you are finished in one location or at the end of each work day (whichever is sooner).</li> <li>Transfer excavated materials to dump trucks on the site, not in the street.</li> <li>If excavated slurry enters a catch basin, clean it up immediately.</li> </ul>	<p><b>Painting &amp; Paint Removal</b></p> <ul style="list-style-type: none"> <li>Store concrete, grout and mortar under cover, on pallets and away from drainage areas. These materials must never reach a storm drain.</li> <li>Wash out concrete equipment/trucks offsite or in a contained area, to prevent discharge into the underlying or onto surrounding areas. Let concrete harden and dispose of as garbage.</li> <li>Collect the wash water from washing exposed aggregate concrete and remove it to the appropriate disposal facility.</li> </ul> <p><b>Painting &amp; Paint Removal</b></p> <ul style="list-style-type: none"> <li>Effectively manage all run-off, all runoff within the site, and all runoff that discharges from the site. Direct run-off water from offsite away from all disturbed areas or otherwise ensure compliance.</li> <li>For water-based paints, paint out brushes to the extent possible. Store in the sanitary sewer once you have gained permission from the local wastewater treatment authority. Never pour paint down a drain.</li> <li>For oil-based paints, paint out brushes to the extent possible and clean with thinner or solvent. Dispose of brushes and solvent in a proper container. Filter and reuse thinners or solvents. Dispose of brushes and unusable thinners/solvents as hazardous waste.</li> </ul>	<p><b>Dewatering</b></p> <ul style="list-style-type: none"> <li>Effectively manage all run-off, all runoff within the site, and all runoff that discharges from the site. Direct run-off water from offsite away from all disturbed areas or otherwise ensure compliance.</li> <li>When dewatering, notify and obtain approval from the local wastewater treatment authority before discharging water to a street gutter or storm drain. Filter water or dewater through a basin, tank, or sedimentation tank to remove debris. Contaminated groundwater must be treated and held off-site for proper disposal.</li> </ul>

STORM DRAIN POLLUTERS MAY BE LIABLE FOR FINES OF UP TO \$10,000 PER DAY!



#### Basic Defensible Space & Vegetation Management Guidelines For Property Owners

Scope: These guidelines provide property owners with information regarding basic vegetation management practices to create defensible space around structures in all unincorporated areas of Monterey County. Use of these practices will help property owners bring the property into a **basic** level of compliance with:

- LE-100 Defensible Space Inspection Program
- Local fire dept. wildland fire safety requirements
- California Public Resources Code Section 4291
- Planning Services Dept. zoning, easement & environmental requirements

#### Within 30 feet immediately surrounding the building (or to property line, whichever ever is closer):

- Cut flammable vegetation around buildings a minimum 30 feet or to the property line, whichever is closer, except for landscaping, as follows:
  - Cut dry and dead grass to a maximum height of 4 inches.
  - Maintain the roof and gutters of the structure free of leaves, needles or other dead vegetative growth.
  - Maintain any tree adjacent to or overhanging a building free of dead wood.
  - Trim tree limbs that extend within 10 feet of the outlet of a chimney or stove pipe.
  - Trim dead portions of tree limbs within 10 feet from the ground.
  - Remove all limbs within 6 feet of the ground.
  - Remove all dead fallen material unless it is embedded in the soil.
  - Remove all cut material from the area.
- Remove all cut material from the area or chip and spread on site.
- Provide and maintain at all times a screen over the outlet of every chimney or stovepipe that is attached to a fireplace, stove or other device that burns any solid or liquid fuel. The screen shall be constructed of nonflammable material and openings of not more than one-half inch in size.
- Post house numbers per Fire Department requirements.

#### Between 30 and 100 feet around the building (or to the property line, whichever ever is closer)


- The fuel reduction zone in the remaining 70 feet (or to the property line) will depend on the steepness of your property and the type of vegetation. For additional information, refer to the Cal Fire brochure "Why 100 Feet? Protect Your Home...and Property"
- Cut plants and grass beneath tree canopies to prevent fire from spreading to the trees. These plants should be "topped off" leaving the root structure intact to minimize erosion.
- Do not use herbicide or other chemical methods to remove vegetation.

Note: Any further vegetation management activities, including those required by insurance companies, may require prior approval from the Planning Services Department when activities involve the following:

- Exposing soil to erosion
- Accelerating sediment runoff into water courses
- Impact sensitive habitat
- Tree removal

Permit requirements for these additional vegetation management activities are available at the Monterey County Planning Department office located at 168 W. Alisal St., 2nd Floor, Salinas, CA 93901. If you wish to speak to a Planner regarding these permit requirements, you may call (831) 755-5025.

MacKenzie Patterson Architect  
 ©2017  
 C7065  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853




A Residence for:  
**MacKenzie Patterson & Carol Jungwirth**  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202

COVER SHEET


A Residence for:  
**MacKenzie Patterson & Carol Jungwirth** LOT 6  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202

TERRA GRANDE DRIVE



A.P.# 169-363-009  
 LOT 7-A  
 17 SUR 62  
 1.03 Ac.

**MacKenzie Patterson Architect**  
 ©2017  
 C7065  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853



NOTES:  
 1. NO LANDSCAPING PROPOSED - AREA TO BE MAINTAINED WEED & BRUSH FREE WITH NATURAL EXISTING LEAF & CYPRESS MULCH.

**REVISIONS:**  
 8/30/06: Add 150' set back lines to nearest septic drain pits and well sites.  
 SIDE YARD SETBACK: 05.00' FRONT + 249.67' REAR = 314.67' 314.67' ÷ 2 = 157.34' × 10% = 15.73' REQ'D SIDE YARD SETBACK = 15'-9"

**NOTES:**  
 1. Elevation datum is assumed.  
 2. Points found or set are so indicated, others are shown for reference only.  
 3. Record data is shown in parenthesis (.....) where pertinent to location of improvements.  
 4. Distances and elevations are expressed in feet and decimals thereof.  
 5. k = live oak; c = cypress; p = pine

**TOPOGRAPHIC MAP**  
 of a portion of Assessor's Parcel No. 169-363-009, shown as a portion of Lots 8 & 7, Block 1, Rancho Tierra Grande No. 3, and shown on that certain Map filed in Vol. 17 of Surveys at Page 62, Official Records of Monterey County, California.

~ Prepared for ~  
**MACKENZIE PATTERSON**  
 Jon D. Hagemeyer Licensed Land Surveyor  
 Carmel, California  
 Scale: 1" = 8' W.O. 5080 October 2017





This map correctly represents a survey made by me or under my direction in July, 2005.

**SITE PLAN**

Scale: 1/8" = 1'-0"

DETAIL (not to scale)







A Residence for:

**Mackenzie Patterson & Carol Jungwirth**

25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202




**Mackenzie Patterson Architect**  
 C7065  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853




West Elevation

West Elevation between Garage




South Elevation

East Elevation Garage




East Elevation




North Elevation

Scale: 1/4" = 1'-0"

MacKenzie Patterson Architect  
 ©2017  
 C7065  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853





A Residence for:  
**MacKenzie Patterson & Carol Jungwirth**  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202



REV. 2.7.18 DECK

A Residence for:  
**MacKenzie Patterson & Carol Jungwirth**  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202

A.P.# 169-363-009  
 LOT 7-A  
 17 SUR 62  
 1.03 Ac.




DOWNHILL EMBANKMENT DETAIL  
 SCALE: 1/16" = 1'-0"

- REVISIONS:**
- 8/30/06: Add 150' set back lines to nearest septic drain pits and well sites.
  - 12/01/17: Add contours in drainfield area.

- NOTES:**
1. Elevation datum is assumed.
  2. Points found or set are so indicated, others are shown for reference only.
  3. Record data is shown in parenthesis (.....)
  4. Check for direction of tree growth in field where pertinent to location of improvements.
  5. Distances and elevations are expressed in feet and decimals thereof.
  6. k= live oak; c= cypress; p= pine

**TOPOGRAPHIC MAP**  
 of a portion of Assessor's Parcel No. 169-363-009, shown as a portion of Lots 6 & 7, Block 1, Rancho Tierra Grande No. 3, and shown on that certain Map filed in Vol. 17 of Surveys at Page 62, Official Records of Monterey County, California.

~ Prepared for ~  
**MACKENZIE PATTERSON**  
 Jon D. Hagemeyer Licensed Land Surveyor  
 Carmel, California  
 Scale: 1" = 8' W.O. 5060 November 2017





This map correctly represents a survey made by me or under my direction in July, 2005.


**DRAINFIELD 'A'**  
 60' x 10'-5" = 1250#  
 (REQUIRES 9'-0" COVER)

**DRAINFIELD 'B'**  
 60' x 10'-5" = 1250#  
 (REQUIRES 9'-0" COVER)

Scale: 1/8" = 1'-0"

**Mackenzie Patterson Architect**  
 ©2017  
 C7065  
 57740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853






LOT 6


TIERRA GRANDE DRIVE

MacKenzie Patterson Architect  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4858



A.P.# 169-363-009  
 LOT 7-A  
 17 SUR  
 1.03 AC

A Residence for:  
**MacKenzie Patterson & Carol Jungwirth**  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202



- NOTES:**
- Existing Contour lines are shown as long dashed lines at one foot intervals.
  - Proposed Contour lines are shown as short dashed lines at one foot contours.
  - See Arrows for direction of flow. All rainwater is directed to a series of three drywells.
  - See Grading Plan G1 for drywell locations.
  - There are no wetlands, streams, creeks or any other bodies of water on or near this site.
  - No areas on this site are subject to a 100 year flood.
  - There are no known environmentally sensitive habitat, archaeological resources, biological sites or geological hazards on this site.
  - See Sheet No.4 for Septic Drainfield.
  - See Erosion Control Notes for seeding of disturbed areas within the construction zone.
  - Provide a minimum of 5% down slope for ten feet minimum away from foundations typical.

**REVISIONS:**

8/30/06: Add 150' set back lines to nearest septic drain pits and well sites.

- NOTES:**
- Elevation datum is assumed.
  - Points found or set are so indicated, others are shown for reference only.
  - Record data is shown in parenthesis (.....)
  - Check for direction of tree growth in field where pertinent to location of improvements.
  - Distances and elevations are expressed in feet and decimals thereof.
  - k= live oak; c= cypress; p= pine


**TOPOGRAPHIC MAP**  
 of a portion of Assessor's Parcel No. 169-363-009, shown as a portion of Lots 6 & 7, Block 1, Rancho Tierra Grande No. 3, and shown on that certain Map filed in Vol. 17 of Surveys at Page 62, Official Records of Monterey County, California.

~ Prepared for ~  
**MACKENZIE PATTERSON**  
 Jon D. Hagemeyer Licensed Land Surveyor  
 Carmel, California W.O. 5060 October 2017



This map correctly represents a survey made by me or under my direction in July, 2005.

Scale: 1/8" = 1'-0"



**GRADING NOTES & CONDITIONS**

- A copy of all compaction tests and final grading report shall be submitted to the County prior to scheduling any inspections. This shall be prepared by the Geotechnical Engineer.
- All erosion control measures shall be in place at the end of each working day, between October 15<sup>th</sup> and April 15<sup>th</sup>. See Erosion Control Plan Notes.
- All grading shall conform with the County of Monterey Grading Ordinance #2535, and Erosion Control Ordinance #2806.
- Pad elevations shall be certified to 0.1 feet, prior to digging any footings or scheduling any inspections. Certification shall be by a licensed land surveyor.
- Any retaining walls (not attached to the residence) require a separate Building Permit. None Anticipated.
- Statement of Intentions: The specific intention of the grading is to accommodate the placement of the residential structure, detached garage and the driveway. The objective is not to intrude on the natural terrain wherever possible.
- It is estimated that the construction will be about 10 months duration. Estimated start date is April 15, 2018. Estimated completion date is February 15, 2018.
- Driveway Specifications: Driveway to be 2 inch asphaltic concrete with 4" compacted class 2 base rock, over 6" compacted to 95% native subgrade. Where any fill is required under any part of the driveway it shall be compacted class 2 base rock. The subgrade shall be compacted to 95% of standard AASHTO maximum density.
- Recommendations of Geotechnical Soils-Foundation & Geoseismic Report with Geohazard Evaluation prepared by **DEACON GEOTECH**, dated **12-5-17** are hereby incorporated into these Grading Plans.
- FILL PLACEMENT AND COMPACTION**
  - All fill soil should be placed in uniform lifts not exceeding eight inches (8") in loose thickness, and six inches (6") in compacted thickness, moisture conditioned and compacted to a minimum relative compactive effort. The minimum relative compactive effort of the native soil should be 90%. All base rock and the upper eight inches (8") of subgrade under paved areas should be compacted to a minimum of 95% relative compactive effort. Where slab-on-grade floors are to be used, the upper six-inches of subgrade should be compacted to minimum relative compaction of 90%. It is important that all native soil be moisture conditioned such that the moisture content is within two percent of optimum moisture content at the time of compaction.
  - The relative compaction will be based on the maximum dry density obtained from a laboratory compaction curve run in accordance with ASTM Procedure #D1557-78. This test will also establish the optimum moisture content of the material.
- FILL MATERIAL**

The on-site soil may be used as compacted fill; however soil to be used as fill which must be imported should meet the following requirements:

  - Free of organics, debris, and other deleterious materials.
  - Granular in nature, well graded, and contain sufficient binder to allow utility trenches to stand open.
  - Free of rocks and cobbles in excess of two inches (2") in size.
  - Have a Plasticity Index between 4 and 12.
  - Have a minimum Sand Equivalent of 20.
  - Have a minimum resistance "R" value of 30.
  - Have an expansivity not greater than medium.
- CUT AND FILL SLOPES**
  - All new cut and fill slopes (if needed) should not exceed a maximum gradient of 2:1 (horizontal to vertical). Requirements for benching and keyways will be determined at the time of construction. Note that where possible maximum design gradient is 4:1 (horizontal to vertical).
- UTILITY TRENCHES**
  - Trenches that are parallel to the sides of buildings, on level ground, should be placed so that they do not extend below an imaginary line sloping down and away at 2:1 (horizontal to vertical) from the bottom outside edge of all spread footings.
  - Trench backfill materials should be selected based on the type and location of each trench. Trenches in sensitive locations should typically be back filled with materials that have low permeable. Trenches in other areas may be filled with granular materials. All backfill material should be uniformly compacted by mechanical means to the relative compaction as required by local building codes, but not less than 95% under paved areas and 90% elsewhere. The relative compaction will be based on the maximum dry density obtained from a laboratory compaction curve run in accordance with ASTM Procedure #D1557-78. This test will also establish the optimum moisture content of the material.
  - A three-foot (3') long concrete plug should be placed in each trench where it passes under the exterior foundations. Care should be taken not to damage utility lines.
  - Trenches should be capped with 1.5+/- feet of relatively impermeable soil.
  - Trenches deeper than five feet (5') must be shored as required by the local agency, the State of California Division of Industrial Safety Construction Safety Orders, and Federal OSHA requirements.
- Cut slopes shall be no steeper than two horizontal to one vertical.
- Actual grading shall begin within 30 days of vegetation removal or the area shall be planted to control erosion.
- Fill slopes shall not be constructed on natural slopes steeper than two to one, unless a civil engineer or geologist devises a method of placement that will assure the fill will remain in place.
- Fill slopes shall toe out no closer than 12 feet horizontally to the top of existing or planned cut slopes.
- The ground surface shall be prepared to receive fill by the removal of topsoil and other unsuitable materials as determined by the soil engineer and, where the slopes are five to one or steeper, by keying into sound bedrock or other competent material.
- The ground surface shall be prepared to receive fill by removing vegetation, noncomplying fill, topsoil and other unsuitable materials, scarifying to provide a bond with the new fill, and where slopes are steeper than five to one, and the height is greater than 5 feet, by benching into sound bedrock or other competent material as determined by the geotechnical engineer.
- The bench under the toe of a fill on a slope steeper than five to one shall be at least twelve feet wide.
- The area beyond the toe of a fill shall be sloped for sheet overflow or a paved drain shall be provided.
- Where fill is to be placed over a cut, the bench under the toe of fill shall be at least ten feet wide but the cut must be made before placing fill and approved by the geotechnical engineer and engineering geologist as suitable foundation for fill. None anticipated.
- Fill slopes shall not be constructed on natural slopes steeper than 2:1.
- No organic material shall be permitted in fills except as topsoil used for surface plant growth only and which does not exceed 4 inches in depth.
- Rock over twelve inches in its maximum dimension may not be used in a fill.
- No compacted fills shall be made which creates an exposed surface steeper in slope than 2 horizontal to 1 vertical.
- All fills shall be compacted to a minimum of 90% of maximum density as determined by the 2016 UBC, Section 6003.

- Grading Calculations (Note that it is the responsibility of the Grading Contractor to prepare his own grading calculations for bidding and contract proposals.)
 





Residence:	Cut	Fill
A) N-WING	0 40' x 28' x 0.79 = 885 CF = 32.77 CU YDS.	
B) CENTER	0 8' x 28' x 0.50 = 112 CF = 4.15 CU YDS.	
C) S-WING	17.04 28' x 40' x 0.50 = 400 CF =	
D) S-WING	5.40 x 0.33 = 66 CF = 2.44 CU YDS	
E) DECK	8.89 40' x 6' x 0.75 = 240 CF =	
F) DRIVEWAY	9.17 750 SQ. FT. x 0.33 = 243 CF =	
<b>TOTAL</b>	<b>35.10 CU YDS CUT</b>	<b>39.36 FILL</b>

G) EXCESS AVAILABLE FOR ON SITE FILL FROM SEPTIC DRAIN FIELD:  
 60' x 9' x 1.33' = 720 CU FT x 2 = 1440' = 53.33 CU YDS.
- All cut and/or fill slopes exposed during the course of construction shall be covered, seeded with native grasses or otherwise treated to control erosion subject to the approval of the Director of Planning & Building Inspection.
- Native trees which are located close to the construction site shall be protected from inadvertent damage from construction equipment by: (Close is any tree within 10 feet of an "extent of grading or site disturbance" area as shown on the Grading Plan.)
  - Wrapping trunks with protective materials;
  - Fencing around the area within drip lines;
  - Avoiding fill of any type against the base of the trunks, and
  - Avoiding an increase in soil depth at the feeding zone or drip line of the retained trees.
 Said protection shall be demonstrated through either photographic evidence or by a site visit with Planning and Building Inspection staff prior to issuance of building permits.
- Provide a minimum of a 5% Downslope for a minimum of 10 feet away from the foundations, Typical.
- See Grading Plan for 4" diameter perforated pipe to be located below top of footing in Class 1 Type A drain rock, 12 inches wide, extending up to within 8 inches of finished grade, and covered with filter fabric above rock, typical. All drain lines connect to dry wells, see plan., with 4" diameter solid abs pipe.
- Where roof downslope discharges rainwater Note 33. Shall be supplemented with a gravel Moe Strip. See Detail 1/G2 Moe Strip, or "Smith" Model 9818 Trench drain at paved areas. Locate at center line of Drip line, Approximately 36 inches on center away from face of finish stucco. See Plan. Where Roof Valleys creates a concentrated rainwater discharge, provide an 18" section of 4" ogee gutter with a 3 inch diameter downspout, which shall lead into the 4" perforated drain pipe in the moe strip. See Grading & Erosion Control Plan for locations.
- Drywells: Shall be sized to accommodate a 2 inch rainfall in a 24 hour period. Maximum roof area served is 1,500 sq.ft. per drywell, produces 250 cu ft of rain water. A conservative percolation rate of 60 minutes per inch is used for this sizing. In 4 hours a 5'-0" diameter drywell 5 feet deep could percolate 4hrs x 19.63 sf bottom + 4 hrs x 78.54 side = 392 cu ft of water > 250 cu ft. Provide a 2" diameter overflow pipe from the last drywell in any series. All drywells shall be located a minimum of ten feet from any uphill foundation and 25 feet from any downhill foundation.
- Building pads shall have a drainage gradient of 2% toward approved drainage facilities. Grades around perimeter shall slope downward 1 inch minimum to a point 4 feet from structure typical.
- Dust from grading shall be controlled.


36. DISTURBED AREA 3,700 SQ. FT. APPROX.  
 37. PROVIDE 3'-0" HIGH BARRIER MADE WITH "BRANGE" NETTING SUCH THAT IT DEFINES THE "EXTENT OF GRADING" AND "SITE DISTURBANCE" AND PROVIDES TREE PROTECTION FOR ALL TREES OUTSIDE THIS ENVELOPE.

**EROSION CONTROL PLAN:**


- All Erosion Control measures shall conform with Monterey County Erosion Control Ordinance #2806.
- The Owner shall cooperate with the Monterey County Grading Inspector in compliance with winter operations to prevent erosion and siltation.
- Roof Drainage shall be collected in gravel strips. These strips shall be located along all downslope roof eaves. See Detail 1/G2. All roof drainage shall be directed to the drywells.
- Erosion Control facilities & measures shall be installed, maintained, and operated prior to the start of work between October 15<sup>th</sup> and April 15<sup>th</sup>.
- All disturbed areas excluding the building foundation and driveway shall be seeded as soon as possible after grading.
- The site shall be maintained so as to prevent sediment laden runoff from entering the natural drainage courses or adjacent properties.
- The rainy season is October 15<sup>th</sup> thru April 15<sup>th</sup>. No grading shall occur during this period unless otherwise authorized by the Director of Building & Planning.
- Re-vegetate and protect exposed soils by October 15<sup>th</sup>. Use appropriate grass/ legume seed mixes and or straw mulch for temporary cover. Permanent vegetation shall be native drought tolerant plants.
- Bare ground areas shall be seeded with grass and clean straw mulch applied to all bare soils to a thickness of at least two inches during and after the construction at an application rate of 2 tons per acre or one 74 pound bale per 800 square feet. Areas in excess of 20% shall be anchored with plastic netting.
- Recommended seed mix as follows: (per 1,000 square feet)
  - 1/3 Pounds - Blue Wild Rye
  - 1/10 Pound Zorro Fescue
  - 1/8 Pound - Red Creeping Fescue
  - Water and fertilizer as required to establish.
- The sites existing vegetation of Oak Trees, wild flowers, and native grasses shall be maintained outside all areas of the "Extent of Grading".



**MacKenzie Patterson Architect**  
 ©2017  
 C7065  
 37740 Palo Colorado Rd, Carmel, CA 93923  
 Phone: 831-238-0202, Fax: 831-624-4853



**MacKenzie Patterson & Carol Jungwirth**  
 25345 Tierra Grande Drive, Carmel, California 93923  
 Monterey County A.P.No. 169-363-009-000, mcptwo@gmail.com, Phone: 831-238-0202



This page intentionally left blank