

# Exhibit A

This page intentionally left blank.

## DRAFT RESOLUTION

### Before the Planning Commission in and for the County of Monterey, State of California

In the matter of the application of:

**Carmel Inn Ventures LLC (PLN150378)**

**RESOLUTION NO. \_\_\_\_**

Resolution by the Monterey County Planning  
Commission:

- 1) Considering an Addendum to the adopted Mitigated Negative Declaration approved for the Carmel River Inn (Resolution No. 06013; PLN030646);
- 2) Approving an amendment to a Combined Development Permit and General Development Plan for Carmel River Inn to eliminate four multi-unit structures to be replaced with 22 removable cabins subject to 62 conditions of approval; and
- 3) Adopting a Mitigation Monitoring and Reporting Program.

[26600 Oliver Road, Carmel, Carmel Area Land Use Plan]

**The Carmel Inn Ventures LLC Amendment application (PLN150378) went to public hearing before the Monterey County Planning Commission on June 29, 2016. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Planning Commission finds and decides as follows:**

#### FINDINGS

1. **FINDING:** **AMENDMENT** – Consideration of the request for the amendment has been carried out pursuant to Monterey County Code Section 20.70.105.B (Title 20).  
**EVIDENCE:**
  - a) Pursuant to Section 20.70.105.A and B of the Monterey County Code, an amendment, not minor or trivial in nature, shall be taken to the decision-making body of the original permit and processed consistent with the original permit procedures. The original appropriate authority is the Planning Commission. The replacement of the multi-unit combo structures with cabin park-model cabin is not minor or trivial in nature because the use of cabin park-model cabins instead of conventionally built structures has never been proposed or considered in the Carmel area. However, the proposed cabin units better meet floodplain and design control regulations.
  - b) On December 23, 2015, the applicant, Carmel Inn Ventures LLC,

submitted an application to amend a previously-approved Combined Development Permit and General Development Plan (PLN140154) to allow: 1) reduction of units in the existing main lodge from 19 to 17 units with to accommodate a 624 square foot employee unit which was originally approved to replace an existing maintenance building; 2) maintaining all 24 historic cottages; and 3) replace four multi-unit combo structures with 22 cabin park-model cabins. The modification does not exceed the approved allotment of 63 units. The previously-approval (PLN140154) was a two year extension to a previously-approved two year extension (PLN110577) to an amendment (PLN070415) of the original permit (PLN030464).

- e) All conditions from the previously-approval (PLN140154, Resolution No. 14-043), have been either applied, updated or modified, except for three mitigation measures (see Finding 4, Evidence b) by this amendment, and attached to this resolution. The approval of this amendment effectively expires PLN030464, PLN070415, PLN1105774 and PLN140154 and becomes the primary reference file for the project.
- f) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the amendment can be found in Project File PLN150378.

2. **FINDING:**

**CONSISTENCY** - The subject amendment conforms to the plans, policies, requirements, and standards of the certified Monterey County Local Coastal Program (LCP), the LCP for the project consists of the Carmel Area Land Use Plan, the Regulations for Development in the Carmel Area Land Use Plan (Part 4), Part 6 of the Coastal Implementation Plan (Appendices), and the Monterey County Zoning Ordinance (Title 20) which designates this area as appropriate for development.

**EVIDENCE:**

- a) Pursuant to Section 20.82.050 of the Zoning Ordinance, Action by Appropriate Authority, the Planning Commission shall make findings as necessary to support its decision on this amendment. Such findings shall address, but not be limited to, consistency with the General Plan, area plans, site suitability, environmental issues and Variance hardships.
- b) **Zoning Consistency.** The property is located at 26600 Oliver Road Carmel (Assessor's Parcel Number 009-563-005-000), Carmel Area Land Use Plan. The parcel is zoned VSC-D (CZ) and RC-D (CZ) ("Visitor Serving Commercial and Resource Conservation, both within a Design Control District in the Coastal Zone"). The subject property complies with all the rules and regulations pertaining to zoning uses and applicable provisions of Title 20, and is therefore the amendment is a consistent use and development.
- c) **Allowable Units.** By proposing a total of 63 visitor serving units, the project does not exceed the maximum unit allowance of 86 visitor serving units and 12 employee units as described in the Policy 4.4.3.D.4 of the Carmel Area LUP.
- d) **Biological Resources.** The multi unit structures were analyzed to

encroach 15 feet into the 150 foot setback from a riparian corridor. Consistent with Section 20.146.040.C.2.c of the Coastal Implementation Plan – Part 4, in contrast the amendment using cabin units will meet the required 150 foot setback from riparian habitat and does not propose the removal of native trees which were approved for removal originally. One 10 inch in diameter Holly tree will be removed which isn't protected (Section 20.146.060.A, Coastal Implementation Plan). An updated biological assessment was provided by LSA associates, dated November 30, 2015 and February 3, 2016. The assessment reviewed the property for potential impacts to federal and state protected species. Although the property is located adjacent to the Carmel River which is a known habitat for California Tiger Salamander, California red-legged frog, Western pond turtle and other species, the project maintains a 150-foot setback from riparian vegetation habitat which the proposed development location does not have a suitable aquatic habitat or vegetation that would support said species. Additionally, approved impacts related to the construction of four multi-unit structures from development (grading, tree removal, excavation due to liquefaction) will be reduced by this amendment because the cabin-units require less grading for the driveway, parking areas and pads. As recommended by the assessment, a bird nesting survey (Condition No. 14) and construction management plan with recommendations from the assessment (Condition No. 15) have been included as conditions of project approval which is consistent with Section 20.146.040.B. of the Coastal Implementation Plan which requires development adjacent to locations of environmentally sensitive habitats to incorporate necessary site and design features to protect adjacent habitat.

- e) **Employee Housing.** The project meets the employee housing requirements described in the Carmel LUP Policies (4.4.3.H.2) and CIP Regulation (20.146.120.B.3.e) by providing an employee housing unit onsite to address the increase in visitor units. Affordable Units: As originally approved, the amendment meets the provisions of the Carmel LUP Policy 4.4.3.D.3 and CIP Regulations (20.146.120.B.3.a) related to the provision of low to moderate income visitor serving units as part of an expansion of an existing facility. The project will not exceed the average cost of similar units in the area (between \$200 and \$250 per night) by 10% or more which requires the provision for a percentage of low cost units (30% below average) to be available.
- f) **Aesthetics.** The Design Control regulations (Section 20.44.010, Zoning Ordinance) require structures to protect the viewshed, neighborhood character and visual integrity of the surrounding area. The cabin units will be designed with a natural cedar exterior with a corrugated metal roof which is similar to the materials approved for the combo structures. The sizing and location of each cabin unit is similar to the existing cottage. Each cabin unit is between 300-360 square feet. The spacing between each unit will provide landscaping similar to vegetation

existing on the property. The cabin units are not visible from Highway 1, a designated scenic highway. Therefore, the cabin units harmonize and are subordinate to the natural scenic character of the area using appropriate design and materials (Policy 2.2.2, Carmel Area LUP).

- g) **Historic Resources.** The amendment repairs and remodels all 24 historic cottages. Consistent with Section 21.54.040 and Section 18.25.080 of the Monterey County Code, the amendment was reviewed by the HRRB (Historic Resources Review Board) on March 3, 2016. The HRRB recommended approval of the project by a vote of 4-0. The HRRB recommended conditions which require: 1) an on-site meeting with hired contractor, Inn manager, hired historical consultant, a building inspector and project planner to insure repairs to cottages will not degrade the historic integrity of the cottages (Condition No. 62); and 2) amend the adopted Historic Resource District Overlay to include cottage #22 which was relocated outside the overlay boundary (Condition No. 10).
- h) **Floodplain Regulations.** The project is located within the FEMA Special Flood Hazard Area (SFHA) Zone AE, 100-year floodplain of the Carmel River, as shown on FEMA Flood Insurance Rate Map 06053C-0320G. MCC subsection 16.16.050.J.1 which requires “until a regulatory floodway is adopted, no new construction, substantial development, or other development, (including fill) shall be permitted within Zones AE, unless it is demonstrated that the cumulative effect of the proposed development, when combined with all other development, will not increase the water surface elevation of the base flood more than one foot at any point” (Regulations for Floodplains in Monterey County, MCC Chapter 16.16). The amendment included an acceptable hydraulic analysis prepared by TetraTech Inc., dated October 28, 2015, demonstrating compliance with MCC subsection 16.16.050.J.1. The hydraulic analysis concluded the proposed project resulted in no change to the 100-year water surface elevations at and upstream of the project site. The proposed cabin units are consistent with Section 16.16.010 MCC in that the design promotes public health, safety and general welfare and minimize public and private losses due to flood conditions. The cabin units are designed to allow 12 of the 22 cabin units to relocate outside of the floodway during a flood emergency. All relocated cabin units will be retained on the property in locations above the water surface elevation of 100 year flood. 10 of the 22 cabin units are located above the water surface elevation of 100 year flood, and therefore, do not require relocation. Relocation of the cabin-units during a flood emergency will remain on-site.
- i) Consistent with the Land Use Advisory Committee Guidelines, adopted by the Board of Supervisors, the amendment was reviewed by the Carmel Highlands LUAC (Land Use Advisory Committee) because the amendment is a discretionary review that requires a public hearing. On January 19, 2016, the LUAC recommended approval of the project by a

vote of 3-1. The main contentions raised by neighbors in attendance was that 1) temporary structures (cabin) are not taxed the same as permanent structures, so the project is a loss of money to the County, 2) the use of cabin units instead of conventionally built structures may decrease neighborhood property values, 3) proposed fire-pits may impact the air quality in the area, and 4) flood evacuation and cabin unit relocation will not work as designed.

3. **FINDING:**

**SITE SUITABILITY** – The site is physically suitable for the use proposed.

**EVIDENCE:**

- a) The project has been reviewed for site suitability by the following departments and agencies: RMA - Planning Department, Carmel Highlands Fire Protection District, Public Works, Environmental Health Division, and Water Resources Agency and the California Coastal Commission. There has been no indication from these departments/agencies that the site is not suitable for the proposed development. Conditions recommended have been incorporated.
- b) The following reports have been prepared and were evaluated:
  - *“Preliminary Archaeological Reconnaissance for the Proposed New Construction Area on Assessor’s Parcel 009-563-005-000 in Carmel, Monterey County, California” prepared by Mary Doane, B.A. and Trudy Haversat, M. A., RPA of Archaeological Consulting, Inc., Salinas, CA, March 5, 2004.*
  - *“Carmel River Inn/Biological Survey & Assessment” prepared by Jeffery B. Froke, Ph.D., of California Wildlife Ecology, Watsonville, CA, January 13, 2004 and January 21, 2004.*
  - *“Biological Site Assessment at the Carmel River Inn” prepared by LSA Associates, LLC, San Luis Obispo, CA, November 30, 2015 and February 3, 2016.*
  - *“Historical and Architectural Evaluation for the Carmel River Inn” prepared by Kent L. Seavey, Preservation Consultant, Salinas, CA, April 1, 2004; updated on February 15, 2016.*
  - *“Liquefaction Study, Proposed Carmel River Inn Expansion” prepared by D&M Consulting Engineers, Inc., November 24, 2004. “Liquefaction Update Letter” prepared by Haro, Kasunich and Associates, Inc., Watsonville, CA, November 21, 2015.*
  - *“Impact of Proposed Improvements for Carmel River Inn on the Carmel River Base Flood Elevations” prepared by TetraTech, Inc., San Luis Obispo, CA, October 28, 2015.*

The above-mentioned technical reports indicate there are no potential impacts beyond what was originally analyzed for the project in 2006 (PLN030464) and 2007 (PLN070415). The reports indicate that the site is suitable for the amendment.

4. **FINDING:**

**CEQA (Addendum):** - The project was previously analyzed by a Mitigated Negative Declaration (MND) that was adopted by the

Planning Commission on February 22, 2006. Revisions to the original design have been made and minor changes to the adopted MND are required an addendum has been prepared for the revised project.

- EVIDENCE:**
- a) California Environmental Quality Act (CEQA) Guidelines Section 15164 which requires an addendum to an adopted negative declaration is prepared if only minor technical changes or additions are necessary.
  - b) Minor technical changes regarding aesthetics, air quality, biological resources, cultural resources, geology, hydrology, noise and traffic were analyzed and presented no new adverse environmental effects. The following mitigation measures and conditions were altered or added as part of the technical change to the MND:
    - Hydrology: Mitigation Action and Measures 6, 7 and 8 in the Mitigated Negative Declaration regarding combo unit development in the floodway are no longer valid. The following conditions of approval have been applied related to the cabin units:
      - Foundation Plan – Enclosures/Grade Elevations (Condition No. 19): Provide foundation plan, prepared by a registered civil engineer or licensed architect, certifying the 10 cabin cabins (not to be relocated during a flood emergency) are compliant with foundation regulations.
      - FEMA Zone AE Recreational Vehicle Plan (Condition No. 20): The applicant shall provide a recreational vehicle evacuation plan certifying the 12 cabins which will remain recreational vehicles and non-elevated. The plans shall demonstrate all recreational vehicles on-site will be fully licensed ,maintained at all time to be ready for evacuation, attached to the site only by quick disconnect type utilities, clear of obstructions and has no permanently attached additions.
      - FEMA Zone AE Mobile Home Anchoring Plan (Condition No. 21): The applicant shall provide an anchoring plan and supporting calculations prepared by a registered civil engineer. In accordance with Monterey County Code Chapter 16.16.050, the 10 elevated cabins shall be designed to resist flotation, collapse, and lateral movement.
      - FEMA Zone AE Anchoring Certification (Condition No. 22): The applicant shall provide certification from a registered civil engineer that the 10 elevated cabins were constructed in accordance with the approved anchoring plan.
    - Biological Resources: Bird Nesting Survey (Condition No. 14) and Construction Management Plan (Condition No. 15) with recommended best management practices have been added per the recommendation by biological consultant, LSA Associates, Inc.

5. **FINDING:** **APPEALABILITY** - The decision on this project may be appealed to the Board of Supervisors.



**EVIDENCE:** Section 21.80.040 (D) Monterey County Zoning Ordinance (Title 21).

**DECISION**

**NOW, THEREFORE**, based on the above findings and evidence, the Planning Commission does hereby:

1. Consider an Addendum to the adopted Mitigated Negative Declaration approved for the Carmel River Inn (Resolution No. 06013; PLN030646);
2. Approve an amendment to a Combined Development Permit and General Development Plan for Carmel River Inn to eliminate four multi-unit structures to be replaced with 22 removable cabins. The project in general conformance with the attached plans and subject to the 62 conditions, all being attached hereto and incorporated herein by reference. The approval of this amendment supersedes related previously-approved permits.

**PASSED AND ADOPTED** this 29th day of June, 2016 upon motion of \_\_\_\_, seconded by \_\_\_\_, by the following vote:

AYES:

NOES:

ABSENT:

ABSTAIN:

\_\_\_\_\_  
Carl P. Holm, AICP, Secretary

COPY OF THIS DECISION MAILED TO APPLICANT ON \_\_\_\_.

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

**NOTES**

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.

Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from the Monterey County Planning Department and Building Services Department office in Salinas.

2. This permit expires 3 years after the above date of granting thereof unless construction or use is started within this period.

# Monterey County RMA Planning

## DRAFT Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN150378

### 1. PD001 - SPECIFIC USES ONLY

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** This amendment (PLN150378) to a Combined Development Permit and General Development Plan for Carmel River Inn to eliminate four multi-unit structures to be replaced with 22 removable cabins. The property is located at 26600 Oliver Road, Carmel (Assessor's Parcel Number 009-563-005-000), Carmel Area Land Use Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the Director of RMA - Planning. Any use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

### 2. PD002 - NOTICE PERMIT APPROVAL

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall record a Permit Approval Notice. This notice shall state:  
"An amendment (Resolution Number \*\*\*) was approved by the Planning Commission for Assessor's Parcel Number 009-563-005-000 on June 29, 2016. The permit was granted subject to 62 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

### 3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** If, during the course of construction, cultural, archaeological, historical or paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. The Monterey County RMA - Planning Department and a qualified archaeologist (i.e., an archaeologist registered with the Register of Professional Archaeologists) shall be immediately contacted by the responsible individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.  
(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to this condition on an on-going basis. Stop work within 50 meters (165 feet) of uncovered resource and contact the Monterey County RMA - Planning Department and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

#### 4. PD004 - INDEMNIFICATION AGREEMENT

**Responsible Department:** RMA-Planning

**Condition/Mitigation  
Monitoring Measure:**

The property owner agrees as a condition and in consideration of approval of this discretionary development permit that it will, pursuant to agreement and/or statutory provisions as applicable, including but not limited to Government Code Section 66474.9, defend, indemnify and hold harmless the County of Monterey or its agents, officers and employees from any claim, action or proceeding against the County or its agents, officers or employees to attack, set aside, void or annul this approval, which action is brought within the time period provided for under law, including but not limited to, Government Code Section 66499.37, as applicable. The property owner will reimburse the County for any court costs and attorney's fees which the County may be required by a court to pay as a result of such action. The County may, at its sole discretion, participate in the defense of such action; but such participation shall not relieve applicant of his/her/its obligations under this condition. An agreement to this effect shall be recorded upon demand of County Counsel or concurrent with the issuance of building permits, use of property, filing of the final map, recordation of the certificates of compliance whichever occurs first and as applicable. The County shall promptly notify the property owner of any such claim, action or proceeding and the County shall cooperate fully in the defense thereof. If the County fails to promptly notify the property owner of any such claim, action or proceeding or fails to cooperate fully in the defense thereof, the property owner shall not thereafter be responsible to defend, indemnify or hold the County harmless. (RMA - Planning)

**Compliance or  
Monitoring  
Action to be Performed:**

Upon demand of County Counsel or concurrent with the issuance of building permits, use of the property, recording of the final/parcel map, or recordation of Certificates of Compliance, whichever occurs first and as applicable, the Owner/Applicant shall submit a signed and notarized Indemnification Agreement to the Director of RMA-Planning for review and signature by the County.

Proof of recordation of the Indemnification Agreement, as outlined, shall be submitted to RMA-Planning .

## 5. PD005 - FISH & GAME FEE NEG DEC/EIR

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Pursuant to the State Public Resources Code Section 753.5, State Fish and Game Code, and California Code of Regulations, the applicant shall pay a fee, to be collected by the County, within five (5) working days of project approval. This fee shall be paid before the Notice of Determination is filed. If the fee is not paid within five (5) working days, the project shall not be operative, vested or final until the filing fees are paid.

(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Within five (5) working days of project approval, the Owner/Applicant shall submit a check, payable to the County of Monterey, to the Director of the RMA - Planning Department.

If the fee is not paid within five (5) working days, the applicant shall submit a check, payable to the County of Monterey, to the Director of the RMA - Planning Department prior to the recordation of the final/parcel map, the start of use, or the issuance of building permits or grading permits.

## 6. PD006 - MITIGATION MONITORING

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall enter into an agreement with the County to implement a Mitigation Monitoring and/or Reporting Plan in accordance with Section 21081.6 of the California Public Resources Code and Section 15097 of Title 14 Chapter 3 of the California Code of Regulations. Compliance with the fee schedule adopted by the Board of Supervisors for mitigation monitoring shall be required and payment made to the County of Monterey at the time the property owner submits the signed mitigation monitoring agreement.

(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Within sixty (60) days after project approval or prior to the issuance of building and grading permits, whichever occurs first, the Owner/Applicant shall:

1) Enter into agreement with the County to implement a Mitigation Monitoring Program.

2) Fees shall be submitted at the time the property owner submits the signed mitigation monitoring agreement.

## 7. PD011 - TREE AND ROOT PROTECTION

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Trees which are located close to construction site(s) shall be protected from inadvertent damage from construction equipment by fencing off the canopy driplines and/or critical root zones (whichever is greater) with protective materials, wrapping trunks with protective materials, avoiding fill of any type against the base of the trunks and avoiding an increase in soil depth at the feeding zone or drip-line of the retained trees. Said protection, approved by certified arborist, shall be demonstrated prior to issuance of building permits subject to the approval of RMA - Director of Planning. If there is any potential for damage, all work must stop in the area and a report, with mitigation measures, shall be submitted by certified arborist. Should any additional trees not included in this permit be harmed, during grading or construction activities, in such a way where removal is required, the owner/applicant shall obtain required permits.

(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permits, the Owner/Applicant shall submit evidence of tree protection to the RMA - Planning Department for review and approval.

During construction, the Owner/Applicant/Arborist shall submit on-going evidence that tree protection measures are in place through out grading and construction phases. If damage is possible, submit an interim report prepared by a certified arborist.

Prior to final inspection, the Owner/Applicant shall submit photos of the trees on the property to the RMA-Planning Department after construction to document that tree protection has been successful or if follow-up remediation or additional permits are required.

## 8. PD012(B) - LANDSCAPING: OTHER

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The site shall be landscaped. At least three (3) weeks prior to occupancy, three (3) copies of a landscaping plan shall be submitted to the Director of RMA - Planning Department. A landscape plan review fee is required for this project. Fees shall be paid at the time of landscape plan submittal. The landscaping plan shall be in sufficient detail to identify the location, species, and size of the proposed landscaping and shall include an irrigation plan. The landscaping shall be installed and inspected prior to occupancy. All landscaped areas and/or fences shall be continuously maintained by the applicant and all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition.  
(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** a) At least three (3) weeks prior to final inspection or occupancy, the Owner/Applicant/Licensed Landscape Contractor/Licensed Landscape Architect shall submit landscape plans and contractor's estimate to the RMA - Planning Department for review and approval.

b) On an on-going, the Owner/Applicant all landscaped areas and fences shall be continuously maintained by the applicant; all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition.

## 9. PD014(B) - LIGHTING-EXTERIOR LIGHTING PLAN (VS & RIDGELINE)

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** All exterior lighting shall be unobtrusive, down-lit, harmonious with the local area, and constructed or located so that only the intended area is illuminated and off-site glare is fully controlled. Exterior lighting shall have recessed lighting elements. Exterior light sources that would be directly visible from when viewed from a common public viewing area, as defined in Section 21.06.195, are prohibited. The applicant shall submit three (3) copies of exterior lighting plan which shall indicate the location, type, and wattage of all light fixtures and include catalog sheets for each fixture. The lighting shall comply with the requirements of the California Energy Code set forth in California Code of Regulations Title 24 Part 6. The exterior lighting plan shall be subject to approval by the Director of the RMA - Planning Department, prior to issuance of building permits.  
(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of building permits, the Owner/Applicant shall submit three copies of the lighting plans to the RMA - Planning Department for review and approval. Approved lighting plans shall be incorporated into final building plans.

Prior to occupancy and on an on-going basis, the Owner/Applicant shall ensure that the lighting is installed and maintained in accordance with the approved plan.



#### 10. PDSP001-HISTORIC DISTRICT (NON-STANDARD)

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall apply to have the appropriate area of the project site included in the California Register of Historic Places as a Historic District and apply for listing on the National Register consistent with recommendations contained in the "Historical and Architectural Evaluation" prepared by Kent Seavey. The applicant shall formally request the director to re-zone the historic district into "HR" zoning district. The district shall include the relocated "Sherman"Unite" #22

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to occupancy, provide evidence of applications to the California, and National Registers to the Prior to occupancy. RMA-Planning Department and request the RMA-Planning Department to amend the zoning map to include a "HR" over lay on the section of the property containing the historic cabins, including the relocated cabin #22.

#### 11. PDSP002 - CONSTRUCTION NOISE /ACTIVITY (NON-STANDARD)

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall limit construction activity to the hours of 7:00 am to 6:00 pm during weekdays and limit minimal interior construction on Saturday (8:00 am to 6:00 pm) and no construction activities on Sunday. The applicant shall post a sign at least 3 foot by 4 foot in size in a conspicuous location containing a phone number and message for neighbors to contact for noise complaints. The applicant shall log noise complaints and respond appropriately where reasonable and contact the County to report complaints on a monthly basis and how those complaints were resolved.  
(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of building permits, provide evidence of installation and maintenance of sign during construction.

Monthly/On going during construction, provide complaint logs to the County monthly during construction.

**12. PDSP003 - DEED RESTRICTION TRAIL, EMPLOYEE UNIT- OLIVER ROAD/GATE CLOSURE (NON-STANDARD)**

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall implement and record a deed restriction to include the following three items containing the following statements subject to approval by the RMA-Planning Director:

1. The applicant/owner and successors in interest agree to record a 15 foot wide public access easement over the length of the property in an east/west direction and obtain permits (where appropriate) and implement a trail management plan consistent with requirements of the public access requirements contained in the Carmel Area Land Use Plan and Coastal Implementation Plan within 1 year of the County approval of a formally adopted trail plan for the related trail segment shown in Figure 3 of the Carmel Area Land Use Plan.

2. The applicant/owner and successors in interest shall restrict the rent received from renters residing in the employee unit created as part of County permit approval PLN070415 to the amount of rent designated for low and moderate income renters as determined in the Monterey County Inclusionary Ordinance. The applicant/owner and successors in interest shall provide evidence of compliance every 5 years in the form of a report to be approved by the Director.

The applicant/owner and successors in interest shall restrict the use of the easterly gate onto Oliver Road as shown in permit plans PLN070415 to emergency access and not allow visitor/employee or construction access through the gate, and make the barrier on Oliver Road as shown in permit plans PLN070415 with boulders and landscaping and only allow access to the Inn from Highway 1 over the abandoned Oliver Road up to the barrier.

(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of building permit, provide draft Deed restriction for approval by the Director and show proof of approved recorded deed restriction.

6 months and 1 year after County approval of trail segment, submit trail easement and trail management plan to the RMA-Planning Director for approval within 6 months of County approval of trail segment. Provide evidence of recorded easement and trail management plan with one year of County approval of related Figure 3 trail segment.

Every 5 years after permit approval, provide evidence of rental income consistent with low an moderate income levels.

On an on-going basis, maintain restricted access and barriers at Oliver Road.

### 13. PDSP004 - TREE REPLACEMENT (NON-STANDARD)

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall implement tree replacement in accordance with the recommendations contained in the Forestry Evaluation prepared by Glenn C. Flamik of Forest City Consulting, dated May 7, 2004. The one oak tree proposed for removal shall be replaced by planting one oak tree at the site. Said replacement shall be demonstrated in the form of photos or a letter from a County- approved forester or arborist prior to final building inspection.  
(RMA - Planning Department)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to final building inspection, submit evidence of the tree replacement in the form of photos and a receipt or a letter from a County-approved forester or arborist to the RMA-Planning Department

### 14. PD050 - RAPTOR/MIGRATORY BIRD NESTING

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Any tree removal activity that occurs during the typical bird nesting season (February 22-August 1), the County of Monterey shall require that the project applicant retain a County qualified biologist to perform a nest survey in order to determine if any active raptor or migratory bird nests occur within the project site or within 300 feet of proposed tree removal activity. During the typical nesting season, the survey shall be conducted no more than 30 days prior to ground disturbance or tree removal. If nesting birds are found on the project site, an appropriate buffer plan shall be established by the project biologist. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** No more than 30 days prior to ground disturbance or tree removal, the Owner/Applicant/Tree Removal Contractor shall submit to RMA-Planning a nest survey prepared by a County qualified biologist to determine if any active raptor or migratory bird nests occur within the project site or immediate vicinity.

### 15. PDSP005 - CONSTRUCTION MANAGEMENT PLAN

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** A Construction Management Plan shall be submitted which identifies the contractor, estimated number of workers required during construction, parking location for equipment and construction workers and material storage. The construction management plan shall also include recommendations by the biological consultant in regards to fencing and best management practices during construction activities. Prior to review by RMA-Planning, the project biological consultant shall review and approve the plan. (RMA-Planning)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of a Construction Permit, the owner/applicant shall submit a Construction Management Plan for review and approval by RMA-Planning.

## 16. EH55 - EMPLOYEE HOUSING

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** Comply with Employee Housing Regulations found in the California Health and Safety Code Section 17000-17062.5 and the California Code of Regulations Title 25, Division 1, Chapter 1, Subchapter 3 Sections 600-940.  
(Environmental Health)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to occupancy, obtain a health permit for the Employee Housing from the Environmental Health Bureau. Continuously comply with Employee Housing Regulations.

## 17. EHSP001 - EXISTING SEPTIC SYSTEMS (NON-STANDARD)

**Responsible Department:** Health Department

**Condition/Mitigation Monitoring Measure:** All existing septic systems on the property shall be properly abandoned as per Monterey County Code, Chapter 15.20. A permit for the septic system abandonment shall be obtained from the Monterey County Health Department, Division of Environmental Health. (Environmental Health)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to Final or Occupancy, Division of Environmental Health must approve plans and perform inspection as part of the septic permit.

## 18. WRSP01 - ZONE AE ELEVATION REQUIREMENTS

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The lowest floor and attendant utilities shall be constructed at a minimum elevation of 25.0 feet (NAVD88). The applicant shall provide the Water Resources Agency certification from a registered civil engineer or licensed land surveyor that a reference marker has been established at the building site to provide for the floodproofing and certification of the lowest floor elevation requirements. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a letter, prepared by a registered civil engineer or licensed land surveyor, to the Water Resources Agency for review and approval.

## 19. WRSP02 - FOUNDATION PLAN - ENCLOSURES / GRADE ELEVATIONS

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide a foundation plan, prepared by a registered civil engineer or licensed architect, certifying the 10 permanent RV cabins are compliant with the following regulations:

1. All fully enclosed areas subject to flooding shall be designed to allow for the automatic entry and exit of floodwaters. Each enclosed area shall be defined and include a minimum of two openings on different sides.
2. The vents shall have a total net area not less than one square inch for every square foot of enclosed area subject to flooding.
3. The bottom of all openings shall be no higher than one foot above grade.
4. The foundation plan shall include a vent detail, the location and dimensions of all vents, as well as internal and external grade elevations.
5. All new construction materials below 25.0 feet (NAVD88) shall be resistant to flood damage. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a foundation plan to the Water Resources Agency for review and approval.

## 20. WRSP03 - FEMA ZONE AE RECREATIONAL VEHICLE PLAN

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide a recreational vehicle evacuation plan certifying the 12 cabins which will remain recreational vehicles and non-elevated. The plans shall demonstrate all recreational vehicles on-site will be fully licensed, maintained at all time to be ready for evacuation, attached to the site only by quick disconnect type utilities, clear of obstructions and with no permanently attached additions. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a recreational vehicle plan to the Water Resources Agency for review and approval.

## 21. WRSP04 - FEMA ZONE AE MOBILE HOME ANCHORING PLAN

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide an anchoring plan and supporting calculations prepared by a registered civil engineer. In accordance with Monterey County Code Chapter 16.16.050, the 10 elevated RV cabins shall be designed to resist flotation, collapse, and lateral movement. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a mobile home anchoring plan to the Water Resources Agency for review and approval.

## 22. WRSP05 - FEMA ZONE AE ANCHORING CERTIFICATION

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide certification from a registered civil engineer that the 10 elevated RV cabins were constructed in accordance with the approved anchoring plan. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall submit a letter, prepared by a registered civil engineer, to the Water Resources Agency for review and approval.

## 23. WRSP06 - ELEVATION CERTIFICATE

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide a FEMA Elevation Certificate, completed by a registered civil engineer or licensed land surveyor certifying each of the 10 RV cabins has been constructed in accordance with Chapter 16.16 of Monterey County Code. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall submit a FEMA Elevation Certificate, based on "finished construction", to the Water Resources Agency for review and approval.

A FEMA Elevation Certificate form can be obtained at the Water Resources Agency or online at: [www.mcwra.co.monterey.ca.us](http://www.mcwra.co.monterey.ca.us).

## 24. WR049 - WATER AVAILABILITY CERTIFICATION

**Responsible Department:** Water Resources Agency

**Condition/Mitigation Monitoring Measure:** The applicant shall provide the Monterey County Water Resources Agency proof of water availability in the form of a complete Monterey Peninsula Water Management District Water Release Form. (Water Resources Agency)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any construction permit, the owner/applicant shall submit a Water Release Form to the Water Resources Agency for review and approval.

A copy of the Water Release Form can be obtained at the Monterey Peninsula Water Management District, the Water Resources Agency, or online at: [www.mcwra.co.monterey.ca.us](http://www.mcwra.co.monterey.ca.us).

## 25. PW0007 - PARKING STD

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** The parking shall meet county standards and be approved by the Director of Public Works and the Director of Planning and Building Inspection.

**Compliance or Monitoring Action to be Performed:** Prior to Building/Grading Permits Issuance the Applicant's engineer or architect shall prepare a parking plan, Owner/Applicant/Engineer to submit plans for review and approval.

#### 26. PWSP001 - CIRCULATION PLAN (NON STANDARD)

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** The circulation plan shall be approved by the Department of Public Works.

**Compliance or Monitoring Action to be Performed:** Prior to Building/Grading permits issuance, applicant's engineer or architect shall prepare a circulation plan for review approval.

#### 27. PWSP002 - TRAFFIC IMPROVEMENT FEE (NON-STANDARD)

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** The applicant shall pay to the County a pro-rata share of the cost of short term improvements to Highway One.

**Compliance or Monitoring Action to be Performed:** Prior to Building/Grading permit issuance, applicant shall submit payment to the Building Department.

#### 28. PWSP003 - AREA 50 ACCESS (NON-STANDARD)

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** Provide for access to County Service Area 50 facilities. (Public Works)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to Building/Grading Permits Issuance, applicant shall provide evidence of access to the satisfaction of the Public Works Department

#### 29. PWSP004 - TAMC FEE (NON-STANDARD)

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** The applicant shall pay the Transportation Agency for Monterey County (TAMC) Regional Traffic Mitigation Fee identified in the TAMC nexus study.  
(Public Works)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to Building/Grading Permits Issuance  
Applicant shall submit payment to the Department of Public Works and TAMC where appropriate.

### 30. PWSP005 – NON-STANDARD CONDITION - COUNTY WIDE TRAFFIC IMPACT FEE

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** If the County Wide Traffic Impact Fee is in place prior to issuance of building permits, applicant shall pay the County Wide Traffic Impact Fee. The fee amount shall be determined based on the parameters adopted in the fee schedule.

(Condition transferred from PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of Building Permits Owner/Applicant shall pay Monterey County Building Services Department the traffic mitigation fee. Owner/Applicant shall submit proof of payment to the DPW.

### 31. PW0043 - REGIONAL DEVELOPMENT IMPACT FEE

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** Prior to issuance of building permits, applicant shall pay the Regional Development Impact Fee (RDIF) pursuant to Monterey Code Chapter 12.90. The fee amount shall be determined based on the parameters adopted in the current fee schedule.

**Compliance or Monitoring Action to be Performed:** Prior to issuance of Building Permits Owner/Applicant shall pay Monterey County Building Services Department the traffic mitigation fee. Owner/Applicant shall submit proof of payment to the DPW.

### 32. PW0045 – COUNTYWIDE TRAFFIC FEE

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** Prior to issuance of building permits, the Owner/Applicant shall pay the Countywide Traffic Fee or the ad hoc fee pursuant to General Plan policy C-1.8. The fee amount shall be determined based on the parameters in the current fee schedule.

**Compliance or Monitoring Action to be Performed:** Prior to issuance of Building Permits, the Owner/Applicant shall pay Monterey County Building Services Department the traffic mitigation fee. The Owner/Applicant shall submit proof of payment to the DPW.



### 33. FIRE008 - GATES

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** All gates providing access from a road to a driveway shall be located at least 30 feet from the roadway and shall open to allow a vehicle to stop without obstructing traffic on the road. Gate entrances shall be at least the width of the traffic lane but in no case less than 12 feet wide. Where a one-way road with a single traffic lane provides access to a gated entrance, a 40-foot turning radius shall be used. Where gates are to be locked, the installation of a key box or other acceptable means for immediate access by emergency equipment may be required. Responsible Land Use Department: \_\_\_\_\_ Fire District

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permits, the Applicant shall incorporate the specification of the entry gate into design and print the text of this condition as "Fire Department Notes" on plans.

Prior to requesting a final building inspection, the Applicant shall complete the installation of the entry gate and obtain fire department approval the final fire inspection.

### 34. FIRE011 - ADDRESSES FOR BUILDINGS

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** All buildings shall be issued an address in accordance with Monterey County Ordinance No. 1241. Each occupancy, except accessory buildings, shall have its own permanently posted address. When multiple occupancies exist within a single building, each individual occupancy shall be separately identified by its own address. Letters, numbers and symbols for addresses shall be a minimum of 4-inch height, 1/2-inch stroke, contrasting with the background color of the sign, and shall be Arabic. The sign and numbers shall be reflective and made of a noncombustible material. Address signs shall be placed at each driveway entrance and at each driveway split. Address signs shall be visible and legible from both directions of travel along the road. In all cases, the address shall be posted at the beginning of construction and shall be maintained thereafter. Address signs along one-way roads shall be visible from both directions of travel. Where multiple addresses are required at a single driveway, they shall be mounted on a single sign. Where a roadway provides access solely to a single commercial occupancy, the address sign shall be placed at the nearest road intersection providing access to that site. Permanent address numbers shall be posted prior to requesting final clearance. Responsible Land Use Department: Carmel Highlands Fire District

**Compliance or Monitoring Action to be Performed:** Prior to issuance of building permit, Applicant shall incorporate specification into design and print the text of this condition as "Fire Dept. Notes" on plans.

Prior to requesting a final building inspection, Applicant shall install the required address signage and shall obtain fire department approval of the fire department final inspection.

### 35. FIRE015 - FIRE HYDRANTS/FIRE VALVES

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** A fire hydrant or fire valve is required. The hydrant or fire valve shall be 18 inches above grade, 8 feet from flammable vegetation, no closer than 4 feet and no further than 12 feet from a roadway, and in a location where fire apparatus using it will not block the roadway. The hydrant serving any building shall be not less than 50 feet and not more than 1000 feet by road from the building it is to serve. Minimum hydrant standards shall include a brass head and valve with at least one 2 1/2 inch National Hose outlet supplied by a minimum 4 inch main and riser. More restrictive hydrant requirements may be applied by the Reviewing Authority. Each hydrant/valve shall be identified with a reflectorized blue marker, with minimum dimensions of 3 inches, located on the driveway address sign, non-combustible post or fire hydrant riser. If used, the post shall be within 3 feet of the hydrant/valve, with the blue marker not less than 3 feet or greater than 5 feet above the ground, visible from the driveway. On paved roads or driveways, reflectorized blue markers shall be permitted to be installed in accordance with the State Fire Marshal's Guidelines for Fire Hydrant Markings Along State Highways and Freeways, May 1988. Responsible Land Use Department: Carmel Highlands Fire District

(Condition transferred from PLN070415/PLN110577PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permit, Applicant shall incorporate specification into design and print the text of this condition as "Fire Dept. Notes" on construction plans.

Prior to requesting a final building inspection, the Applicant shall complete the installation of the water system improvements and shall obtain fire department approval of the final fire inspection.

### 36. FIRE021 - FIRE PROTECTION- SPRINKLER SYSTEM (STANDARD)

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** The building(s) and attached garage(s) shall be fully protected with automatic fire sprinkler system(s). Installation shall be in accordance with the applicable NFPA standard. A minimum of four (4) sets of plans for fire sprinkler systems must be submitted by a California licensed C-16 contractor and approved prior to installation. This requirement is not intended to delay issuance of a building permit. A rough sprinkler inspection must be scheduled by the installing contractor and completed prior to requesting a framing inspection. Responsible Land Use Department: Carmel Highlands Fire District

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permit, Applicant shall print the text of this condition as "Fire Dept. Notes" on construction plans.

Prior to requesting a framing inspection, the Applicant shall obtain fire department approval of the rough sprinkler inspection.

Prior to requesting a final building inspection, the Applicant shall complete the installation of the fire sprinkler system and obtain fire department approval of the final fire sprinkler inspection.

### 37. FIRE001 - ROAD ACCESS

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** Access roads shall be required for every building when any portion of the exterior wall of the first story is located more than 150 feet from fire department access. All roads shall be constructed to provide a minimum of two nine-foot traffic lanes with an unobstructed vertical clearance of not less than 15 feet. The roadway surface shall provide unobstructed access to conventional drive vehicles including sedans and fire apparatus and shall be an all-weather surface designed to support the imposed load of fire apparatus (22 tons). Each road shall have an approved name.

Responsible Land Use Department: \_\_\_\_\_ Fire District

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permits, the Applicant shall incorporate the specification of the roadway into design and print the text of this condition as Fire Department Notes on plans.

Prior to requesting a final building inspection, the Applicant shall complete the installation of roadway improvements and obtain fire department approval the final fire inspection.

### 38. FIRE002 - ROADWAY ENGINEERING

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** The grade for all roads shall not exceed 15 percent. Where road grades exceed 8 percent, a minimum structural roadway surface of 0.17 feet of asphaltic concrete on 0.34 feet of aggregate base shall be required. The length of vertical curves in roadways, exclusive of gutters, ditches and drainage structures designed to hold or divert water, shall not be less than 100 feet. No roadway turn shall have a horizontal inside radius of less than 50 feet. A roadway turn radius of 50 to 100 feet is required to have an additional 4 feet of roadway surface. A roadway turn radius of 100 to 200 feet is required to have an additional 2 feet of roadway surface. Roadway turnarounds shall be required on dead-end roads in excess of 150 feet of surface length. The minimum turning radius for a turnaround shall be 40 feet from the center line of the road. If a hammerhead/T is used, the top of the "T" shall be a minimum of 60 feet in length. Responsible Land Use Department: Carmel Highlands Fire District

**Compliance or Monitoring Action to be Performed:** Prior to issuance of grading and/or building permits, the Applicant shall incorporate the specification of the roadway into design and print the text of this condition as 'Fire Department Notes' on improvement plans.

Prior to issuance of building permit(s) for development on individual lots within the phase of the subdivision, the Applicant shall complete the installation of the roadway improvements and shall obtain fire dept. approval of the fire clearance inspection for each phase of development.

Prior to requesting a final building inspection, the Applicant shall complete the installation of roadway improvements and obtain fire department approval the final fire inspection.

### 39. FIRE023 - FIRE ALARM SYSTEM - (COMMERCIAL)

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** The building(s) shall be fully protected with an approved central station, proprietary station, or remote station automatic fire alarm system as defined by NFPA Standard 72. Plans and specifications for the fire alarm system shall be submitted by a California licensed C-10 contractor and approved prior to requesting a rough sprinkler or framing inspection. Responsible Land Use Department: Carmel Highlands Fire District.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of building permit, applicant shall enumerate as "Fire Dept. Notes" on plans.

Prior to rough sprinkler or framing inspection, applicant shall submit fire alarm plans and obtain approval.

Prior to final building inspection, applicant shall schedule fire alarm system acceptance test.

### 40. FIRES001 - OTHER (NON-STANDARD)

**Responsible Department:** Fire

**Condition/Mitigation Monitoring Measure:** The Applicant shall provide the following:

- 1) A minimum eight (8) inch water main to feed new buildings and hydrants (Looped system)
- 2) Hydrants are to be model #3775-JONES
- 3) A single FDC connection for the four combo buildings with a hydrant and the PIV in the area of the turn into the combo units
- 4) An additional hydrant in the area of cottage #16
- 5) Stand pipes on all combo units and Inn
- 6) A fire department turn around west of the new combo units
- 7) All water mains up-grades must be done prior to commencement of construction of the new Combo Units.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to Issuance of building or grading permits, applicant shall enumerate as "Fire Dept. Notes" and identify locations of hydrants and turn around on plans. The turnaround shall be located out of the 100 foot environmentally sensitive habitat buffer.

Prior to final inspection or as stated in the condition of approval, the applicant shall schedule a fire department inspection to verify compliance with these conditions

#### 41. MITIGATION MEASURE 1 - HISTORIC CABIN #22

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to avoid a substantial adverse change in the significance of a historical resource, cabin #22 ("Sherman"), which is one of the original cabins built ca. 1934, shall be relocated on the property within the Historic District adopted by the Board of Supervisors on July 24, 2007 (instead of demolished), consistent with the Secretary of the Interior's Standards for the Treatment of Historic Properties, with the Guidelines for Preserving, Rehabilitating, Restoring, and Reconstructing Historic Buildings, as deemed appropriate and approved by a qualified historian.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of grading or building permits

Monitoring Action 1: Prior to the issuance of grading or building permits, the applicant shall submit a revised site plan indicating the proposed new location of cabin #22, as well as a relocation and rehabilitation plan prepared by a qualified historian, which verifies that the plan is consistent with the Secretary of the Interior's Standards for the Treatment of Historic Properties, with the Guidelines for Preserving, Rehabilitating, Restoring, and Reconstructing Historic Buildings, as deemed appropriate. The revised site plan and relocation and rehabilitation plan for cabin #22 shall be subject to approval by the RMA - Planning Director.

#### 42. MITIGATION MEASURE 2 - LIQUEFACTION RISK

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce the risk of impacts from seismic-induced liquefaction to less-than-significant levels, the preparation of a final design-level geotechnical report will be required which includes geotechnical criteria for design and construction of the proposed improvements. These improvements shall include some combination of soil improvement and strengthened foundation design. Soil Improvement shall include some method of in-situ ground densification, such as vibro-replacement stone columns. Strengthened foundation design shall include such methods as shallow foundations reinforced with grade beams designed to resist minor differential settlements.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 2.A - Prior to issuance of grading or building permits, the applicant shall submit a final design-level geotechnical report to the RMA- Planning and Building Departments for review and approval.

#### 43. MITIGATION MEASURE 3 - FLOOD RISK

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce the risk of flooding of the project site, the hydraulic analysis and report prepared by Balance Hydrologics, dated July 23, 2004, shall be updated to reflect the new cross-sections resulting from the construction of stone columns and the placement of associated fill material. The proposed project shall not result in any increase in the base flood elevation. The updated hydraulic analysis shall be submitted to the Water Resources Agency for review and approval.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 3 - Prior to issuance of any grading or building permits, the applicant shall submit the updated hydraulic analysis and report to the Water Resources Agency for review and approval.

#### 44. MITIGATION MEASURE 4 - FLOODING RISKS

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce the risk of flooding of the project site, the applicant shall provide the Water Resources Agency "as-built" final grading plans for review and approval.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 4 - Prior to finalizing the grading permit, the applicant shall submit a copy of the "as-built" grading plans to the Water Resources Agency for review and approval.

#### 45. MITIGATION MEASURE 5 - DRAINAGE

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce onsite and offsite drainage impacts to less-than-significant levels, the applicant shall provide the Water Resources Agency a drainage plan prepared by a registered civil engineer or architect addressing on-site and off-site impacts. The plan shall include oil-grease/water separators for the paved parking areas. Drainage improvements shall be constructed in accordance with plans approved by the Water Resources Agency.

(Condition transferred from PLN070415/PLN110577)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 5 - Prior to issuance of any grading or building permits, the applicant shall submit 3 copies of the drainage plan to the Water Resources Agency for review and approval.

#### 46. MITIGATION MEASURE 9 - FEMA

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to avoid conflict with the Regulations for Floodplains in Monterey County, the applicant shall provide the Water Resources Agency a FEMA Elevation Certificate completed by a registered civil engineer or licensed land surveyor, certifying the forms have been set at a height that will ensure the minimum lowest floor elevation requirement.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 9 - Prior to the foundation pre-pour inspection, the applicant shall submit a completed FEMA Elevation Certificate, for each new unit, based on building under construction, to the Water Resources Agency for review and approval.

#### 47. MITIGATION MEASURE 10 - FEMA

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to avoid conflict with the Regulations for Floodplains in Monterey County, the applicant shall provide the Water Resources Agency a FEMA Elevation Certificate, based on finished construction, for each new unit and the main inn. The Elevation Certificates shall be completed by a registered civil engineer or licensed surveyor to certify each structure has been constructed in accordance with Chapter 16.16 of the Monterey County Code with the exception of the existing 23 cottages that have been granted a Variance from the requirements of this chapter due to their historic nature (PLN070420)

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 10 - Prior to final inspection, the applicant shall submit a completed FEMA Elevation Certificate, for each new unit, based on finished construction, to the Water Resources Agency for review and approval.

#### 48. MITIGATION MEASURE 11 - TRAFFIC IMPACTS

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce potential cumulative traffic impacts to less-than-significant levels at the Highway 1/Rio Road intersection, the applicant shall contribute toward the improvements necessary to provide a free right-turn lane from westbound Rio Road to northbound Highway 1 based on the estimated 0.55% of traffic generated by the proposed project under estimated cumulative conditions.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 11 - Prior to issuance of grading or building permits, the applicant shall pay a fee to be determined by the Public Works Department for improvements necessary to provide a free right-turn lane from westbound Rio Road to northbound Highway 1 based on the estimated 0.55% of traffic generated by the proposed project under estimated cumulative conditions.

#### 49. MITIGATION MEASURE 12 - OLIVER ROAD

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce potential safety hazards at the intersection of Highway 1 and Oliver Road to less-than-significant levels, the applicant shall improve corner-sight distances, the stop bar shall be moved to four (4) feet from the southbound Highway 1 travelway, the vegetation between Oliver Road and the Carmel River Bridge shall be cleared, and the Caltrans road condition sign shall be relocated either south of the Carmel River Bridge or north of Oliver Road.

(Condition transferred from PLN070415/PLN110577/PLN140154)

**Compliance or Monitoring Action to be Performed:** Monitoring Action 12.A - Prior to issuance of grading or building permits, the applicant shall solicit from either Caltrans or the Monterey County Public Works Department, as applicable, a memorandum of agreement that the agency with jurisdiction will carry out the work required by Mitigation Measure 12 prior to final inspection of the Combo Units.

Monitoring Action 12.B - Prior to issuance of grading or building permits, the applicant shall provide the RMA & Planning Department with a copy of a signed memorandum of agreement explicitly guaranteeing that the agency with jurisdiction will carry out the work required by Mitigation Measure 12 prior to final inspection of the Combo Units.

#### 50. MITIGATION MEASURE 13 - TRAFFIC GENERATION

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** In order to reduce peak hour construction/grading traffic generation to a less-than-significant level, the applicant shall arrange for construction/grading activities to begin by 7:00AM and end by 3:30PM. Deliveries to the construction site shall occur between 9:00AM and 4:00PM only.

(Condition transferred from PLN070415/PLN110577/PLN140514)

**Compliance or Monitoring Action to be Performed:** During construction and grading operations, the applicant shall submit monthly reports that include the daily truck trip log showing travel times to the RMA - Planning Director for review and approval. The contractor shall submit a signed certification to contain an "under penalty of perjury" clause. Failure to comply shall cause revocation of permit.

#### 51. CALIFORNIA CONSTRUCTION GENERAL PERMIT

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit a Waste Discharger Identification (WDID) number certifying the project is covered under the California Construction General Permit.  
(RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit a WDID number certifying the project is covered under the California Construction General Permit or a letter of exemption from the Central Coast Regional Water Quality Control Board.



## 52. EROSION CONTROL PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit an erosion control plan in conformance with the requirements of Monterey County Code Chapter 16.12. The erosion control plan shall include a construction entrance, concrete washout, stockpile area(s), material storage area(s), portable sanitation facilities and waste collection area(s), as applicable. (RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit an erosion control plan to RMA-Environmental Services for review and approval.

## 53. FIELD VERIFICATION OF POST-CONSTRUCTION STORMWATER CONTROL MEASURES

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall provide certification from a registered Professional Engineer that the stormwater control facilities have been constructed in accordance with the approved Stormwater Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall submit a letter to RMA-Environmental Services for review and approval.

## 54. GEOTECHNICAL CERTIFICATION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall provide certification from a licensed practitioner that all development has been constructed in accordance with the recommendations in the project Geotechnical Investigation. (RMA- Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall provide RMA-Environmental Services a letter from a licensed practitioner.

## 55. GRADING PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit an updated Geotechnical Investigation and a grading plan. The updated Geotechnical Investigation shall include project specific mitigation measures including measures necessary to address liquefaction. The grading plan shall incorporate the recommendations included in the Geotechnical Investigation, and the geotechnical inspection schedule shall be included on the plan. The geotechnical inspection schedule shall identify when the inspections will be completed, who will conduct the inspection, a description of the required inspection, inspector name and the completion date. The applicant shall provide certification from the licensed practitioner that the grading plan incorporates their geotechnical recommendations. (RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit a grading plan to RMA-Environmental Services for review and approval.

Prior to issuance of any grading or building permits, the applicant shall submit certification from a licensed practitioner that they have reviewed the grading plan for conformance with the geotechnical recommendations.

## 56. INSPECTION-DURING ACTIVE CONSTRUCTION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to inspect drainage device installation, review the maintenance and effectiveness of BMPs installed, and to verify that pollutants of concern are not discharged from the site. At the time of the inspection, the applicant shall provide certification that all necessary geotechnical inspections have been completed to that point. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** During construction, the applicant shall schedule an inspection with RMA-Environmental Services.

## 57. INSPECTION-FOLLOWING ACTIVE CONSTRUCTION

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to ensure all disturbed areas have been stabilized and all temporary erosion and sediment control measures that are no longer needed have been removed. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to final inspection, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

## 58. INSPECTION-PRIOR TO LAND DISTURBANCE

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall schedule an inspection with RMA-Environmental Services to ensure all necessary sediment controls are in place and the project is compliant with Monterey County regulations. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to commencement of any land disturbance, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

## 59. MAINTENANCE AGREEMENT

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall enter into a Maintenance Agreement (Agreement) that clearly identifies the responsible party for ongoing maintenance of structural Stormwater Control Measures. The Agreement shall contain provisions for an annual drainage system report, prepared by a registered Professional Engineer, that includes the status of all structural stormwater control measures and maintenance recommendations. The annual report shall be submitted to RMA-Environmental Services, for review and approval, no later than August 15th. All recommended maintenance shall be completed by October 15th of the same year. If maintenance is required, certification shall be provided that all recommended maintenance has been completed before the start of the rainy season. (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the owner/applicant shall submit the signed and notarized Agreement to RMA-Environmental Services for review and approval. The approved Agreement shall be recorded, and a copy of the recorded document shall be provided to RMA-Environmental Services.

A copy of the standard Agreement can be obtained at RMA – Environmental Services.

## 60. OPERATION AND MAINTENANCE PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit an Operation and Maintenance Plan prepared by a registered Professional Engineer that includes, at a minimum, the following:

- a) Site map identifying all structural Stormwater Control Measures requiring O&M practices to function as designed.
  - b) O&M procedures for each structural Stormwater Control Measure including, but not limited to, LID facilities, retention/detention basins, and proprietorship devices.
  - c) The O&M Plan shall include short- and long-term maintenance requirements, recommended frequency of maintenance, and estimated cost for maintenance.
- (RMA – Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any building or grading permits, the owner/applicant shall submit the O&M Plan to RMA-Environmental Services for review and approval.

## 61. STORMWATER CONTROL PLAN

**Responsible Department:** Environmental Services

**Condition/Mitigation Monitoring Measure:** The applicant shall submit a Stormwater Control Plan, prepared by a registered professional engineer, addressing the Post-Construction Stormwater Management Requirements (PCRs) for Development Projects in the Central Coast Region. The plan shall include the location of the drainage facilities and construction details. A report with supporting calculations shall also be provided. The Stormwater Control Plan shall be reviewed by a licensed practitioner to ensure conformance with the Geotechnical Investigation or Engineering Geology Report.  
(RMA-Environmental Services)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of any grading or building permits, the applicant shall submit a Stormwater Control Report and a Stormwater Control Plan to RMA-Environmental Services for review and approval.

Prior to issuance of any grading or building permits, the applicant shall submit certification from a licensed practitioner that they have reviewed and approved the Stormwater Control Plan for conformance with the geotechnical recommendations.

## 62. PDSP006 - REPAIR/REMODEL OF HISTORIC COTTAGES

**Responsible Department:** RMA-Public Works

**Condition/Mitigation Monitoring Measure:** As recommended by the Historic Resources Review Board on March 3, 2016, a pre-construction meeting shall occur on-site with the contractor, historian, architect, project planner and building official to discuss and determine protocol for repairing/replacing damaged work to the 24 historic cottages and how to proceed. If any deviation from the approved plan regarding the historic cottages are contemplated, the contractor must contact the architect of record. The architect will then contact the historian, project planner, and appropriate building official and propose a course of action in writing to address the problem consistent with the Secretary's Standards, and best preservation practices.

**Compliance or Monitoring Action to be Performed:** On an on-going basis, the owner/applicant shall request a pre-construction meeting shall occur on-site with the contractor, historian, architect, project planner and building official if repair or replacement to the historic cottages are proposed, or if any deviation from the approved plan regarding the historic cottages are contemplated.



- LEGEND**
- (A) EXISTING MAIN BUILDING  
SEE A-1
  - (B) EXISTING COTTAGES TO REMAIN AND BE  
REMODELED. SEE A-2
  - (C) NEWLY CONCRETE PAVES WITH  
UNITED PAVING. SEE A-3
- SHEET NOTES**
1. SWIMMING POOL WATER CONNECTION TO BE  
DISCONNECTED FROM POTABLE LINE AND CONNECTED  
TO DRAINAGE WELL
  2. NEW ENTRY MONUMENT
  3. EXISTING BRIDGE MONUMENT
  4. NEW LIGHT
  5. 50' WELL LET BACK
  6. EMPLOYEE UNIT TO BE EXPANDED. SEE FLOOR PLAN
  7. EXISTING LAUNDRY ROOM
  8. EXISTING MAINTENANCE ROOM
  9. NEW TRASH
  10. EXISTING COTTAGE BLOCK 20 TO REMAIN
  11. BUFFER LANDSCAPE
  12. EXISTING TREES TO REMAIN. TYP
  13. EXISTING SEWER LIFT STATION

- LEGEND**
- (A) EXISTING MAIN BUILDING  
SEE A-1
  - (B) EXISTING COTTAGES TO REMAIN AND BE  
REMODELED. SEE A-2
  - (C) NEWLY CONCRETE PAVES WITH  
UNITED PAVING. SEE A-3

UNICO GOLF ZONING


PROPOSED INDIVIDUAL  
DISTRICT PATCHES

100% OF NY

100% OF NY

**THE PAUL DAVIS PARTNERSHIP**  
**ARCHITECTS & PLANNERS**

The Paul Davis Partnership, LLP  
1000 Broadway, Suite 2000  
New York, NY 10018  
(212) 691-1000  
FAX: (212) 691-1001  
E-MAIL: paul.davis@pauldavispartnership.com



**SITE PLAN**  
SCALE: 1" = 400'  
PROJECT NORTH

0 10 20 40  
FEET

A 1.1

**MASTER SITE PLAN**

Sheet No. 130/15  
Drawing Date 10/26/15  
Project Number 1400

130/15

Project / Owner

**CARMEL  
RIVER INN**  
U.S. HIGHWAY 1  
CARMEL, CALIFORNIA  
P.O. BOX 211406  
CARMEL, CA 95022  
APN: 009-063-03

**THE  
PAUL DAVIS  
PARTNERSHIP**  
ARCHITECTS & PLANNERS

100 LAMAR STREET, SUITE 200, SAN FRANCISCO, CA 94102  
TELEPHONE (415) 398-2100 FAX (415) 398-2100

Drawn By: M.L.

Drawing Date: 05/26/10

Plot Date:

Date Issued for Construction:

Revisions:


1. ALL DIMENSIONS ARE TO FACE UNLESS NOTED OTHERWISE.  
2. ALL WALLS ARE 1/2" THICK UNLESS NOTED OTHERWISE.  
3. ALL FLOORS ARE 4" CONCRETE ON 2" GYPSUM BOARD UNLESS NOTED OTHERWISE.  
4. ALL CEILING ARE 8' HIGH UNLESS NOTED OTHERWISE.  
5. ALL ROOFS ARE 12/12 PITCH UNLESS NOTED OTHERWISE.  
6. ALL STAIRS ARE 36" WIDE UNLESS NOTED OTHERWISE.  
7. ALL DOORS ARE 36" WIDE UNLESS NOTED OTHERWISE.  
8. ALL WINDOWS ARE 36" WIDE UNLESS NOTED OTHERWISE.  
9. ALL EXTERIOR WALLS ARE 16" CMU UNLESS NOTED OTHERWISE.  
10. ALL INTERIOR WALLS ARE 1/2" GYPSUM BOARD ON 2" STUDS UNLESS NOTED OTHERWISE.

Sheet Title:


**EXISTING  
MAIN INN  
FLOOR PLANS**

Sheet Number:

**A 2.1**



**(E) UPPER LEVEL FLOOR PLAN**  
NO CHANGE  
PROJECT NORTH



**(E) MAIN LEVEL FLOOR PLAN**  
PROJECT NORTH

Project / Name:

CARMEL  
RIVER INN  
U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 221006  
CARMEL, CA 95022  
APN: 006-360-03

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

Paul Davis Partnership, LLP  
1000 California Street  
San Francisco, CA 94108  
415.774.2200 FAX 415.774.7150  
EMAIL: info@pauldavispartnership.com

Drawn By: M.J./VQ  
Drawing Date: 10/20/15  
Project Number: 1440


Revision: 12/27/15

NOT TO SCALE  
ALL DIMENSIONS ARE IN FEET AND INCHES  
UNLESS OTHERWISE NOTED  
SEE NOTES FOR MATERIALS AND FINISHES


See Also  
COTTAGES  
FLOOR PLANS

Sheet Number:


A2.2




UNIT 11  
EXISTING 225 SF  
ADDITION 30 SF  
TOTAL 255 SF




UNIT 12  
EXISTING 244 SF  
ADDITION 33 SF  
TOTAL 277 SF




UNIT 13  
EXISTING 230 SF  
ADDITION 30 SF  
TOTAL 260 SF




UNIT 14  
REBUILD 260 SF  
EXISTING 30 SF  
ADDITION 30 SF  
TOTAL 320 SF




UNIT 15  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF




UNIT 16  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF




UNIT 17  
EXISTING 225 SF  
ADDITION 30 SF  
TOTAL 255 SF




UNIT 18  
EXISTING 220 SF  
ADDITION 30 SF  
TOTAL 250 SF




UNIT 19  
EXISTING 230 SF  
ADDITION 30 SF  
TOTAL 260 SF




UNIT 20/21  
EXISTING 251 SF  
ADDITION 30 SF  
TOTAL 281 SF




UNIT 22  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF




UNIT 23  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF




UNIT 24  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF




UNIT 27  
EXISTING 225 SF  
ADDITION 30 SF  
TOTAL 255 SF




UNIT 28  
EXISTING 240 SF  
ADDITION 30 SF  
TOTAL 270 SF




UNIT 29  
EXISTING 240 SF  
ADDITION 30 SF  
TOTAL 270 SF



UNIT 30  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF



UNIT 31  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF



UNIT 32  
EXISTING 260 SF  
ADDITION 30 SF  
TOTAL 290 SF

## COTTAGES FLOOR PLANS

LEGEND  
EXISTING BUILDINGS  
ADDITIONS OR NEW BUILDINGS

SCALE: 1/8" = 1'-0"




Project / Owner

CARMEL  
RIVER INN  
U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 231608  
CARMEL, CA 93922  
APH: 686-58500


SHEET NOTES

1. GUARDRAIL
2. TABLE & CHAIRS
3. KING SIZE BED
4. QUEEN SIZE BED
5. NIGHTSTAND
6. LOUNGE CHAIR




SINGLE KING - CABIN FLOOR PLAN

SCALE 1/4" = 1'-0"



Drawn By: ML/VG  
Drawing Date: 10/20/15  
Project Number: 1440

Revisions: 12/27/15



DOUBLE QUEEN - CABIN FLOOR PLAN

SCALE 1/4" = 1'-0"



Sheet Number:

A2.3

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS


The Paul Davis Partnership, LLP  
1000 Montgomery Street  
Suite 200  
San Francisco, CA 94133  
415.397.7967, 415.397.7968  
DALLAS: 415.397.7967, 415.397.7968

These plans were prepared by the architect for the project described above. They are not to be used for any other project without the written consent of the architect.


These are  
FLOOR PLANS  
CABINS

Project / Owner:


CARMEL  
RIVER INN  
U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 221009  
CARMEL, CA 93922  
APH: 638-565-00




UNIT 14




UNIT 13




UNIT 11



UNIT 19



UNIT 18



UNIT 15




UNIT 22




UNIT 20




UNIT 21



UNIT 24 / 25



UNIT 30 / 31




UNIT 34 / 35

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

700 N. 1st Street, Suite 110  
San Jose, CA 95113  
(408) 277-7849  
FAX: (408) 277-7850  
E-MAIL: info@pauldavispartnership.com

## EXTERIOR FRONT ELEVATION - COTTAGES

SCALE: 1/8" = 1'-0"



## SAMPLE CABIN IMAGES (CAVCO MODELS)

Drawn By: M.J./VJ  
Drawing Date: 10/20/15  
Project Number: 1440

Revisions: 12/07/15

NOT TO SCALE  
FOR INFORMATION ONLY  
DO NOT CONSTRUCT  
BASED ON THIS DRAWING  
WITHOUT THE ARCHITECT'S  
WRITTEN PERMISSION

ELEVATIONS  
COTTAGES  
& CABINS

Sheet Number

## REFERENCE NOTES

- 1 Hand excavation may be required in this area to ensure root protection.
- 2 Existing Hedge: Preserve and Protect

**TREE PROTECTION NOTES**

- [illegible]

CARMEL  
RIVER INN

U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 221809  
CARMEL, CALIFORNIA 93922  
APN: 009-563-03

PHASE 1  
MASTER PLAN

**THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS**

2700 PACE HAVEN PARKWAY, LLC  
200 INTERNATIONAL SQUARE, MCLENNAN, CA 95048  
TEL: 925-372-2704 FAX: 925-372-2700



LANDSCAPE  
ARCHITECTS

---

425 Pacific Grove, Suite 20  
Monterey, California 93940  
831.640.1383 | www.bliz.com




Drawn By: JLL/SP  
Drawing Date: 10/20/00  
Revision:

## Tree Protection Plan

**Guest Member**

L-1.0



SCALE: 1" = 40'-0"

Project / Owner:

# CARMEL RIVER INN

U.S. HIGHWAY 1  
CARMEL, CALIFORNIA 95006  
P.O. BOX 271609  
CARMEL, CALIFORNIA 95022  
APR 009-554-53

## PHASE 1 MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

INTERNATIONAL PROJECTS, LLC  
1000 UNIVERSITY AVENUE, SUITE 200  
SAN FRANCISCO, CALIFORNIA 94103  
Tel: 415.774.2000  
Fax: 415.774.2001  
www.paul-davis.com



LANDSCAPE  
ARCHITECTS  
425 Pacific Street, Suite 201  
Menlo Park, California 94025  
Tel: 650.321.1000  
Fax: 650.321.1001  
www.infs.com




Drawn By: JLG/SP  
Checked By: JLG/SP  
Date: 10/20/16  
Project:

### REFERENCE NOTES

- Swimming pool water connection to be disconnected from potable line and connected to on-site well
- New entry signage
- Existing bridge monument
- Existing Cypress hedge to remain: Preserve and Protect
- 50' well setback
- New Trash Enclosure

### LEGEND

- Existing Cottage: 24 Total
- Proposed Cottage: 22 Total
- Concrete Pavers
- AC Paving
- Stabilized Decomposed Granite
- Geoblock with grass fill
- Carriageway of fire access
- Planting Area
- PA
- Existing Trees to Remain: No trees to be removed



SCALE: 1"=40'-0"

L-2.0

Project / Owner

# CARMEL RIVER INN

U.S. HIGHWAY 1  
CARMEL RIVER BRIDGE  
P.O. BOX 221609  
CARMEL, CALIFORNIA 95022  
APN: 005-565-001

## PHASE 1 MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

12 Paul Davis Partnership, LLP  
12000 Highway 1, Suite 200  
Carmel, CA 95006  
Tel: 831.923.1200 Fax: 831.923.1201  
www.pauldavis.com




Drawn By: JCS  
Checking Date: 10/04/13  
Revisions:



Sheet Title  
Flood Parking  
Site Plan

Sheet Number

FLOOD PARKING LEGEND		CABIN LEGEND	
<div>C15</div>	Cabin to Remain during flood: 10 total. Located permanently above the Water Surface Elevation (WSE) of 100 year flood	Cabin to be Relocated - 12 total	
		C1	C3
<div>C16</div>	Cabin to be relocated during flood: 12 total	C2	C4
		C3	C5
<div></div>	Cabin locations during times of flooding	C4	C6
		C5	C7
<div><div>*A</div></div>	Existing Cottages: 24 Total	C6	C8
		C7	C9
		C8	C10
		C9	C11
		C10	C12
		C11	C13
		C12	C14
		C13	C15
		C14	C16
		C15	C17
		C16	C18
		C17	C19
		C18	C20
		C19	C21
		C20	C22
		C21	C23
		C22	C24
		C23	C25
		C24	C26
		C25	C27
		C26	C28
		C27	C29
		C28	C30
		C29	C31
		C30	C32
		C31	C33
		C32	C34
		C33	C35
		C34	C36
		C35	C37
		C36	C38
		C37	C39
		C38	C40
		C39	C41
		C40	C42
		C41	C43
		C42	C44
		C43	C45
		C44	C46
		C45	C47
		C46	C48
		C47	C49
		C48	C50
		C49	C51
		C50	C52
		C51	C53
		C52	C54
		C53	C55
		C54	C56
		C55	C57
		C56	C58
		C57	C59
		C58	C60
		C59	C61
		C60	C62
		C61	C63
		C62	C64
		C63	C65
		C64	C66
		C65	C67
		C66	C68
		C67	C69
		C68	C70
		C69	C71
		C70	C72
		C71	C73
		C72	C74
		C73	C75
		C74	C76
		C75	C77
		C76	C78
		C77	C79
		C78	C80
		C79	C81
		C80	C82
		C81	C83
		C82	C84
		C83	C85
		C84	C86
		C85	C87
		C86	C88
		C87	C89
		C88	C90
		C89	C91
		C90	C92
		C91	C93
		C92	C94
		C93	C95
		C94	C96
		C95	C97
		C96	C98
		C97	C99
		C98	C100
		C99	C101
		C100	C102
		C101	C103
		C102	C104
		C103	C105
		C104	C106
		C105	C107
		C106	C108
		C107	C109
		C108	C110
		C109	C111
		C110	C112
		C111	C113
		C112	C114
		C113	C115
		C114	C116
		C115	C117
		C116	C118
		C117	C119
		C118	C120
		C119	C121
		C120	C122
		C121	C123
		C122	C124
		C123	C125
		C124	C126
		C125	C127
		C126	C128
		C127	C129
		C128	C130
		C129	C131
		C130	C132
		C131	C133
		C132	C134
		C133	C135
		C134	C136
		C135	C137
		C136	C138
		C137	C139
		C138	C140
		C139	C141
		C140	C142
		C141	C143
		C142	C144
		C143	C145
		C144	C146
		C145	C147
		C146	C148
		C147	C149
		C148	C150
		C149	C151
		C150	C152
		C151	C153
		C152	C154
		C153	C155
		C154	C156
		C155	C157
		C156	C158
		C157	C159
		C158	C160
		C159	C161
		C160	C162
		C161	C163
		C162	C164
		C163	C165
		C164	C166
		C165	C167
		C166	C168
		C167	C169
		C168	C170
		C169	C171
		C170	C172
		C171	C173
		C172	C174
		C173	C175
		C174	C176
		C175	C177
		C176	C178
		C177	C179
		C178	C180
		C179	C181
		C180	C182
		C181	C183
		C182	C184
		C183	C185
		C184	C186
		C185	C187
		C186	C188
		C187	C189
		C188	C190
		C189	C191
		C190	C192
		C191	C193
		C192	C194
		C193	C195
		C194	C196
		C195	C197
		C196	C198
		C197	C199
		C198	C200
		C199	C201
		C200	C202
		C201	C203
		C202	C204
		C203	C205
		C204	C206
		C205	C207
		C206	C208
		C207	C209
		C208	C210
		C209	C211
		C210	C212
		C211	C213
		C212	C214
		C213	C215
		C214	C216
		C215	C217
		C216	C218
		C217	C219
		C218	C220
		C219	C221
		C220	C222
		C221	C223
		C222	C224
		C223	C225
		C224	C226
		C225	C227
		C226	C228
		C227	C229
		C228	C230
		C229	C231
		C230	C232
		C231	C233
		C232	C234
		C233	C235
		C234	C236
		C235	C237
		C236	C238
		C237	C239
		C238	C240
		C239	C241
		C240	C242
		C241	C243
		C242	C244
		C243	C245
		C244	C246
		C245	C247
		C246	C248
		C247	C249
		C248	C250
		C249	C251
		C250	C252
		C251	C253
		C252	C254
		C253	C255
		C254	C256
		C255	C257
		C256	C258
		C257	C259
		C258	C260
		C259	C261
		C260	C262
		C261	C263
		C262	C264
		C263	C265
		C264	C266
		C265	C267
		C266	C268
		C267	C269
		C268	C270
		C269	C271
		C270	C272
		C271	C273
		C272	C274
		C273	C275
		C274	C276
		C275	C277
		C276	C278
		C277	C279
		C278	C280
		C279	C281
		C280	C282
		C281	C283
		C282	C284
		C283	C285
		C284	C286
		C285	C287
		C286	C288
		C287	C289
		C288	C290
		C289	C291
		C290	C292
		C291	C293
		C292	C294
		C293	C295
		C294	C296
		C295	C297
		C296	C298
		C297	C299
		C298	C300
		C299	C301
		C300	C302
		C301	C303
		C302	C304
		C303	C305
		C304	C306
		C305	C307
		C306	C308
		C307	C309
		C308	C310
		C309	C311
		C310	C312
		C311	C313
		C312	C314
		C313	C315
		C314	C316
		C315	C317
		C316	C318
		C317	C319
		C318	C320
		C319	C321
		C320	C322
		C321	C323
		C322	C324
		C323	C325
		C324	C326
		C325	C327
		C326	C328
		C327	C329
		C328	C330
		C329	C331
		C330	C332
		C331	C333
		C332	C334
		C333	C335
		C334	C336
		C335	C337
		C336	C338
		C337	C339
		C338	C340
		C339	C341
		C340	C342
		C341	C343
		C342	C344
		C343	C345
		C344	C346
		C345	C347
		C346	C348
		C347	C349
		C348	C350
		C349	C351
		C350	C352
		C351	C353
		C352	C354
		C353	C355
		C354	C356
		C355	C357
		C356	C358
		C357	C359
		C358	C360
		C359	C361
		C360	C362
		C361	C363
		C362	C364
		C363	C365
		C364	C366
		C365	C367
		C366	C368
		C367	C369
		C368	C370
		C369	C371
		C370	C372
		C371	C373
		C372	C374
		C373	C375
		C374	C376
		C375	C377
		C376	C378
		C377	C379
		C378	C380
		C379	C381
		C380	C382
		C381	C383
		C382	C384
		C383	C385
		C384	C386
		C385	C387
		C386	C388
		C387	C389
		C388	C390
		C389	C391
		C390	C392
		C391	C393
		C392	C394
		C393	C395
		C394	C396
		C395	C397
		C396	C398
		C397	C399
		C398	C400
		C399	C401
		C400	C402
		C401	C403
		C402	C404
		C403	C405
		C404	C406
		C405	C407
		C406	C408
		C407	C409
		C408	C410
		C409	C411
		C410	C412
		C411	C413
		C412	C414
		C413	C415
		C414	C416
		C415	C417
		C416	C418
		C417	C419
		C418	C420
		C419	C421
		C420	C422
		C421	C423
		C422	C424
		C423	C425
		C424	C426
		C425	C427
		C426	C428
		C427	C429
		C428	C430
		C429	C431
		C430	C432
		C431	C433
		C432	C434
		C433	C435
		C434	C436
		C435	C437
		C436	C438
		C437	C439
		C438	C440
		C439	C441
		C440	C442
		C441	C443
		C442	C444
		C443	C445
		C444	C446
		C445	C447
		C446	C448
		C447	C449
		C448	C450
		C449	C451
		C450	C452
		C451	C453
		C452	C454
		C453	C455
		C454	C456
		C455	C457
		C456	C458
		C457	C459
		C458	C460
		C459	C461
		C460</	

Project / Owner:

CARMEL  
RIVER INN

U.S. HIGHWAY 1  
& CARMEL RIVER BRIDGE  
P.O. BOX 211699  
CARMEL, CALIFORNIA 95022  
APN: 009-000-000

PHASE 1  
MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

THE PAUL DAVIS PARTNERSHIP LLP  
1000 CALIFORNIA STREET, SUITE 200  
SAN FRANCISCO, CALIFORNIA 94109  
TEL: 415.398.2200 FAX: 415.398.2201  
www.pauldavis.com



LANDSCAPE  
ARCHITECTS  
400 Pacific Street, Suite 201  
Menlo Park, California 94025  
TEL: (650) 321-1301 | www.hfs.com




Drawn By: JLD  
Drawing Date: 10/28/18  
Revised:

Scale: 1" = 20'-0"

Sheet Title:  
Enlarged  
Site Plan West

Sheet Number:

L-2.2



LEGEND

- Concrete Pavers
- AC Paving
- Stallied Decomposed Granite
- Grass



Project / Owner

# CARMEL RIVER INN

U.S. HIGHWAY 1  
CARMEL RIVER BRIDGE  
P.O. BOX 21169  
CARMEL, CALIFORNIA 95022  
APN: 038-080-021

## PHASE 1 MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

THE PAUL DAVIS PARTNERSHIP LLP  
1000 Highway 1, Suite 200  
Carmel, CA 95022  
Tel: 831.923.7800 Fax: 831.923.7801  
www.paul-davis.com



LANDSCAPE  
ARCHITECTS  
1000 Highway 1, Suite 200  
Carmel, CA 95022  
Tel: 831.923.7801 Fax: 831.923.7801  
www.hfs.com



Drawn By: JGP  
Checked By: JGP  
Date: 10/26/15




Sheet Title  
Enlarged  
Site Plan East

Sheet Number

SCALE: 1"=20'-0"  
20 0 20 40

L-2.3



Project / Owner

# CARMEL RIVER INN

U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 221600  
CARMEL, CALIFORNIA 93922  
PH: 831-938-5551

## PHASE 1 MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

1800 FIVE CANYON DRIVE, SUITE 200  
CARMEL, CALIFORNIA 93922  
TEL: 831-938-5551 FAX: 831-938-5552  
WWW.PAULDAVISPARTNERSHIP.COM



LANDSCAPE  
ARCHITECTS  
425 Pacific Street, Suite 201  
Menlo Park, California 94025  
(650) 321-1300 | www.hfs.com



Drawn By: JLP  
Drawing Date: 10/20/16  
Revised:

This plan was prepared by the Paul Davis Partnership Architects & Planners, Inc. for the Carmel River Inn. It is to be used only for the project and site described herein. No other use or reproduction is permitted without the written consent of the Paul Davis Partnership Architects & Planners, Inc.

Sheet Title  
Site Lighting  
Plan

Sheet Number

SCALE: 1"=20'-0"  
20 0 20 40



L-2.4

### LIGHTING LEGEND




Bollard Light (22) total, Shaper Exterior Bollard  
882-HW-LED-UN-ARBZ-3P-SMTGL available from Cooper  
Lighting at cooperlighting.com



Road Light (15) total, Shaper Light on custom post  
882-HW-LED-UN-ARBZ-3P-SMTGL available from Cooper  
Lighting at cooperlighting.com. Mount on 6" x 6" reduced post at 8' above  
finish surface.

Note: Existing lighting to be field adjusted to accommodate new  
road and cabin. Preserve and Protect all other site lighting

Bollard and Road Light





U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 221509  
CARMEL, CALIFORNIA 93922  
APN: 009-563-03

PHASE 1  
MASTER PLAN

**THE  
PAUL DAVIS  
PARTNERSHIP**  
ARCHITECTS & PLANNERS



LANDSCAPE  
ARCHITECTS

4225 Pacific Street, Suite 201  
Monterey, California 93940  
916.440.1383 | www.bjls.com



Person By:	JLSP
Printing Date:	10/20/
Page:	

...the ...

Planting Plan

David M. Weisberg

### PLANT LEGEND

WULF SYM.		BOTANICAL NAME		COMMON NAME
—	—	Machine		
<b>Tree</b>				
Q	Q	Quercus agrifolia 'Nuttall'		Coast Live Oak
S	S	<u>Grainoceros</u>		
A	A	Adiantum filix-mas		Common Yarrow
C	C	Ceanothus glauca horizontalis		Carmel Ceanoth
R	R	Rhamnus californica 'Eve Chase'		Eve Chase Chokeberry
S	S	Rhus sanguinalis		Red Flowering Currant
B	B	Bombyx concolor		Maillie Poppy
S	S	Salix daveauellii 'Man Chikling'		Clavated Sage
<b>Grasses</b>				
P	P	Panicum umicola		Barleywidge
F	F	Festuca californica		California Fescue
F	F	Festuca rubra		Creeping Red Fescue
S	S	Stemmatopogon		California Grey Rush
S	S	Stemmatopogon capitata		Pink Mucky Grass
G	G	Giant milk mill for Goodbodd Low water use plants		

Note: Limits of planting to follow limit of grading. All planting to be treated with dip brisnelson and controlled with ET controller

## • WATER USE CATEGORY (WUC) KEY

WUJOLS Region Applicable to this Project: REGION 1

H	High
M	Moderate
L	Low
VL	Very Low
NL	Species Not Listed

\* from: Water Use Classification of Landscape Species,  
A Guide to the Water Needs of Landscape Plants (WUCOLS)  
Revised 2014, University of California Cooperative Extension,  
J. B. Costello, K. S. Jones

## REFERENCE NOTES

- 1 Existing Cypress hedge to remain; Preserve and Protect
- 2 Planting extents to follow limits of grading



SCALE: 1"= 20'-0"



L-3.0

Project / Owner

WATER USE CATEGORY (WUC) KEY

WUCOLS Region Applicable to this Project: REGION 1

H High  
M Moderate  
NL Very Low  
NL Species Not Listed

\* from: Water Use Classification of Landscape Species,  
A Guide to the Water Needs of Landscape Plants (WUCOLS)  
Revised 2014, University of California Cooperative Extension,  
L.A. County, A.C. Jones

REFERENCE NOTES

- Existing Cypress hedge to remain; Preserve and Protect
- Planting areas to follow limits of grading

PLANT LEGEND

WUC SYM	BOTANICAL NAME	COMMON NAME
Tree	Quercus agrifolia 'Natalis'	Coast Live Oak
Shrub	Achillea millefolium	Common Yarrow
Shrub	Carduus griseus horizontalis	Cardinal Chrysanthemum
Shrub	Rhus microphylla 'Eve's Curse'	Eve's Curse Holly
Shrub	Ribes sanguineum	Red Flowering Currant
Shrub	Rosa californica	Maiden Rose
Shrub	Santolima coccinea	Cleveland Sage
Shrub	Ceanothus	Berkeley Sedge
Shrub	Ceanothus	California Fescue
Shrub	Festuca rubra	Creeping Red Fescue
Shrub	Juniperus procumbens	California Gray Rush
Shrub	Muhlenbergia capillaris	Pink Muhly Grass
Shrub	Grass mix bill for Geoblock-Low water use plants	

CARMEL  
RIVER INN  
U.S. HIGHWAY 1  
P.O. BOX 221609  
CARMEL, CALIFORNIA 93922  
APN: 008-000-003

PHASE 1  
MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS



hfs LANDSCAPE ARCHITECTS  
425 Pacific Street, Suite 200  
Menlo Park, California 94025  
TEL: (650) 321-1100 | www.hfsa.com





Drawn By: JGP  
Drawing Date: 12/20/11  
Revisions:



Sheet Title  
Planting Plan

Sheet Number

L-3.1



A map showing the project site area. Highway 1 runs diagonally from the top left to the bottom right. Rio Rd runs parallel to Highway 1, above it. Fisher Dr runs parallel to Highway 1, below it. Oliver Rd runs parallel to Highway 1, below Fisher Dr. Carmel River runs parallel to Highway 1, below Oliver Rd. The project site is a shaded area located between Fisher Dr and Oliver Rd, south of Highway 1. A line points from the text 'PROJECT SITE' to the shaded area.

SHEET INDEX		
DRAWING NO.	SHEET TITLE	
C-001	1	TITLE SHEET
C-002	2	NOTES, LEGEND, ABBREVIATIONS AND DETAILS
C-003	3	SITE PLAN
C-101	4	PRELIMINARY GRADING PLAN
C-201	5	UTILITIES
C-302	6	UTILITIES

# PHASE I MASTER PLAN

PROJECT DATA SUMMARY	
LAND USE DESIGNATION	MCR, VSD, NC
ZONING DESIGNATION	HOVPA(2C), VSD-C(2), RC-C(2)
INTERFURROW COVERAGE	60.957 SF
PARCEL AREA	453,000 SQFT (10.4 ACRES)
APN	0060800000
WATER SERVICE PROVIDER	MONTEREY PENINSULA WATER MANAGEMENT DISTRICT
SEWER SERVICE PROVIDER	CARMEL AREA WASTEWATER

**THE  
PAUL DAVIS  
PARTNERSHIP**  
ARCHITECTS & PLANNERS

**TETRA TECH**




8655 Arroyo Vista Ave., Suite 250  
San Luis Obispo, CA 93401  
P: (805) 542-0070 F: (805) 542-0254  
[www.tetratech.com](http://www.tetratech.com)

Drawn By:	EM	11-02-2015
Drawing Date:		
Print Date:		
Date Issued for Construction:		
Revisions:		



Shari Nunnberg  
G-001

SHEET 1 OF 8 SHEETS



**SITE MAP**  
1" = 50'

**DEVELOPER/OWNER**  
CARMEL RIVER INN  
P.O. BOX 221609  
CARMEL, CA 95022

**DATUM:**  
**ELEVATIONS ARE BASED ON THE FOUND N.G.S. VERTICAL CONTROL. BENCHMARK PID:AB730**

**BASIS OF BEARING**  
THE BEARING OF N45°27'30"W BETWEEN THE MONUMENTS SHOWN ON THIS MAP AND ON THE RECORD OF SURVEY VOLUME 18, PAGE 48, IS  
ELEVATION: 3370 (NAD83)

**SURVEY NOTES**

1. PROPERTY LINE BASED ON THE A.T.A SURVEY DATED SEPTEMBER 22, 2003 PREPARED BY BESTOR ENGINEERS, INC.
2. EXISTING TOPOGRAPHY AT THE PROJECT SITE BASED ON SITE SURVEYS PREPARED BY BESTOR ENGINEERS, INC. AND 20% CONTAINING SKETCHES BEYOND THE PROJECT PROPERTY TO PROVIDE AN OVERALL VIEW OF THE PROJECT SITE.
3. TETRA TECH DOES NOT GUARANTEE THE ACCURACY OF THE EXISTING TOPOGRAPHY SHOWN ON THIS MAP.

**CIVIL ENGINEER**  
**TETRA TECH**  
865 AEROVISTA AVE. SUITE 220  
SAN ILLIS CRINPO, CA 93001

**PROJECT ADDRESS**

28500 OLIVER ROAD  
CARMEL, CA 93923

L 23.10, N 10.10.0  
A 8 57 42

12 097  
311.85




**CARMEL  
RIVER INN**  
U.S. HIGHWAY 1  
@ CARMEL RIVER BRIDGE  
P.O. BOX 521606  
CARMEL, CA 93922  
APN: 006-563-03

**PHASE I  
MASTER PLAN**

**THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS**

JOE ELAMANDO STREET, MENCKERT, CA 94040  
TELEPHONE: (415) 317-3784 FAX: (415) 373-7448





 Drawn By: EM  
 Drawing Date: 11-02-2015  
 Print Date:  
 Date Issued for Construction:  
 Revisions:

Sheet Title


NOTES, LEGEND,  
ABBREVIATIONS AND  
DETAILS

Sheet Number: G-002


NUMBER OF SUBJECTS




4 TYPICAL RV PAD LAYOUT



1 TYPICAL 1-WAY ROAD SECTION  
- SCALE NTS



2 TYPICAL 2-WAY ROAD SECTION  
- SCALE: NTS



**NOTES:**

3 TYPICAL RV CONNECTION  
- SCALE: NTS

**LEGEND**

PROPOSED	EXISTING
PROPERTY LINE	DRAWN TO SCALE
SETBACK LINE	WATERLINE
SANITARY SEWER LINE	COUNTY
GATE VALVE	FIRE HYDRANT
MANHOLE	MANHOLE
CLEAN OUT	DAYLIGHT
BLOW OFF	FENCE
BACKFLOW PREVENTER	DAWG HOLE

ABBREVIATIONS	
AC	ASPHALT CONCRETE
BLD	BUILDING
BO	BLOW OFF
CD	COASTAL ZONE
CO	CLEAN OUT
ED	EXITING
EV	INVERT
MOR	MEDIUM DENSITY FIBERGLASS
HC	HEAVY CONCRETION
HT	SHIELDING
SB	SANITARY SEWER
SSAH	SANITARY SEWER MANHOLE
TYP	TYPICAL
PVC	POLYVINYL CHLORIDE
VSC	VISITOR SERVING COMMERCIAL
VSE	WATER SURFACE ELEVATION

## NOTES

1. CONSTRUCTION IS ALLOWED FROM 7AM TO 6 PM WEEKDAYS ONLY FOR EXTERIOR WORK AND LIMITED INTERIOR WORK ON SATURDAYS 8AM TO 6PM.
2. EXPORT MATERIAL TO BE DISPOSED OF AT THE MONTEREY REGIONAL WASTE MANAGEMENT DISTRICT LANDFILL.





Project / Owner

# CARMEL RIVER INN

U.S. HIGHWAY 101  
P.O. BOX 221809  
CARMEL, CA 93922  
APN: 008-553-03

## PHASE I MASTER PLAN

### NOTES

1. INSTALL NEW GATE VALVE IN EXISTING SEWER LINE. GATE VALVE TO BE CLOSED DURING ANTICIPATED FLOOD.
2. EXISTING SEWER INFRASTRUCTURE AND LIFT STATION PUMP AND ELECTRICAL TO BE REMOVED AND REPLACED.
3. EXISTING ON SITE WATER MAIN AND LATERALS TO BE REMOVED AND REPLACED.

### LEGEND

- PVC WATER LINE
- PVC SEWER LINE
- SEWER LATERAL
- ELECTRICIAN FIELD (RY UTILITIES)
- NEW LATERALS
- CLEAN OUT
- BLOW OFF
- MANHOLE
- FIRE HYDRANT
- GATE VALVE
- BACKFLOW PREVENTER

## THE PAUL DAVIS PARTNERSHIP ARCHITECTS & PLANNERS

100 CALIFORNIA STREET, SUITE 200  
SAN FRANCISCO, CA 94102  
TELEPHONE (415) 398-0940 FAX (415) 398-7449



Drawn By: EAT  
Drawing Date: 11-03-2015  
Print Date:  
Date Issued for Construction:



Revisions:

Sheet Title

### UTILITIES

Sheet Number:  
C-201

SHEET 3 OF 4 SHEETS



MATCHLINE: SEE SHEET C-202

Project / Owner:

CARMEL  
RIVER INN  
U.S. HIGHWAY 1  
900 CARMEL RIVER BRIDGE  
CARMEL, CA 93922  
APN: 009-563-03

PHASE I  
MASTER PLAN

THE  
PAUL DAVIS  
PARTNERSHIP  
ARCHITECTS & PLANNERS

1000 CARMEL AVENUE, SUITE 200  
CARMEL, CA 93922  
TELEPHONE (831) 372-2100 FAX (831) 372-7100

**TETRA TECH**  
www.tetratech.com  
835 Sacramento Ave., Suite 200  
Carmel, CA 93922  
P: (831) 342-2627 F: (831) 342-2624

Drawn By: CM  
Drawing Date: 11/03/2015  
Print Date:  
Date Issued for Construction:  
Revised:

UTILITY

Sheet Title


UTILITIES



Sheet Number

C-202

SHEET 8 OF 8 SHEETS



NOTES

1. INITIAL NEW GATE VALVE IN EXISTING SEWER LINE. GATE VALVE TO BE CLOSED DURING ANTICIPATED FLOOD.
2. EXISTING SEWER INFRASTRUCTURE AND LIFT STATION PER RECORD DRAWINGS.
3. EXISTING ON-SITE WATER MAIN AND LATERALS TO BE REMOVED AND REPLACED.

LEGEND

- PVC WATER LINE
- PVC SEWER LINE
- SEWER LATERAL
- ELECTRIC/GAS/TELECOM/SEWER UTILITIES
- NEW LATERALS

MATCHLINE: SEE SHEET C-201