#### Exhibit B

## Before the Monterey County Planning Commission in and for the County of Monterey, State of California

In the matter of the application of:

**SALIB (PLN170468)** 

### **RESOLUTION NO. ----**

Resolution by the Monterey County Planning Commission:

- 1) Finding that the project is a single-family residence which qualifies for a categorical exemption pursuant to Section 15303 of the California Environmental Quality Act Guidelines and that none of the exceptions under section 15300.2 apply; and,
- 2) Approving a Combined Development Permit consisting of:
  - Administrative Permit and Design
     Approval to allow the construction of a
     new 2,939-square foot two-level single
     family dwelling, a 508-square foot
     attached garage, a 587-square foot
     deck/covered patio and associated
     grading; and a
  - b. Use Permit for development on slopes exceeding 25%.

[PLN170468, Salib, 25575 Chiquito Place, Carmel, Carmel Valley Master Plan, Coastal Zone (APN: 015-052-026-000)]

The Salib application (PLN170468) came on for public hearing before the Monterey County Planning Commission on April 11, 2018. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Planning Commission finds and decides as follows:

#### **FINDINGS**

1. **FINDING: CONSISTENCY** – The project, as conditioned, is consistent with the

applicable plans and policies which designate this area as appropriate

for development.

**EVIDENCE:** a) The project has been reviewed for consistency with the text, policies, and regulations in:

- 2010 General Plan;
- Carmel Valley Master Plan
- Monterey County Zoning Ordinance (Title 21);

No conflicts were found to exist. Communications received during LUAC meetings were subsequently addressed in revised plans. Staff's

- review of the project did not indicate any inconsistencies with the text, policies, and regulations in these documents.
- b) The property is located at 25575 Chiquito Place, Carmel, to the east of Highway 1 (APN: 015-052-026-000), Carmel Valley Master Plan. The 1-acre property is zoned Low Density Residential, one unit per acre, with Site Plan Review, Resource Allocation Zone and Design Control overlays [LDR/1-D-S-RAZ] which allow the first single family dwelling per lot with an Administrative Permit, Site Plan and Design Approval. Because the project is proposed on a sloping hillside (25% or greater), a Use Permit was applied to the project.
- c) The 1.00192-acre lot (43,749 square feet) was created with the Record of Survey Map of a portion of Lot 4, Hatton Partition in Rancho Canada De La Segunda filed on May 16, 1946 in Volume 4 of Surveys, Page 31 in the office of the County Recorder of the County of Monterey.
- d) Visual Resources. The Carmel Valley Master Plan, Section 1.20 outlines the design review required for all new development throughout the Valley, including proposals for existing lots of record. Pursuant to this section, the development either shall be visually compatible with the character of the valley and immediate surrounding areas or shall enhance the quality of areas that have been degraded by existing development. The proposed location of the structure is not visible from a scenic highway or corridor and the profile of the house conforms to the topography of the site. The proposed two-level house is compatible with the character of the valley and colors and materials have been selected to blend with the existing environment. The lot has a 25-foot natural drainage easement on the westernmost portion of the lot (rear), contiguous to the Arroyo Trail which serves as an additional buffer between the edge of pavement and the nearest lot to the west (over 100 feet).
- e) <u>Site Plan Review.</u> The subject lot and surrounding areas are designated as a Site Plan Zoning District ("S" zoning overlay) for review of development in areas where development has the potential to adversely affect or be adversely affected by natural resources or site constraints. The parcel is significantly constrained due to the shape of the lot, topography (slopes over 25%), and the presence of trees clustered in the western portion of the lot (rear). Structures have been carefully sited within the required setbacks to minimize tree removal. Slopes range from 20 to 40 percent and the gentler part of the slope has been chosen for development. The Geotechnical Report (LIB170355) concludes that the site is geotechnically suitable for the proposed residence.
- f) Design. Pursuant to Chapter 21.44 of the Monterey County Zoning Ordinance, Title 21, a Design Control Zoning District ("D" zoning overlay), regulates the location, size, configuration, materials, and colors of structures and fences to assure the protection of the public viewshed and neighborhood character. The subject site is the last vacant lot in the Chiquito Place cul de sac. Existing single family dwellings are located on varying degrees of steepness (e.g. steeper on the southeast) and are generally recessed into the lots. The proposed single family dwelling would be situated on a sloping hillside. The plans show a terraced design where the main level and attached garage will sit

- at the top of the slope and a partial lower level will step down with the slope. The main level will utilize raised wood floors and the basement and garage will have concrete floor slabs on grade. Low retaining walls are planned along the driveway (approx. 8 inches tall). The selection of colors and materials include: "Tan Plan," exterior stucco, "Ladera Blend, Capistrano" one piece concrete tiles for roof, and dark brown 4-panel bead board garage door and painted metal guardrails for the proposed decks. The driveway design winds down into the garage and will be placed in the steepest part of the slope (greater than 25%).
- g) Resource Allocation Zone (RAZ). The project is consistent with requirements of RAZ because the first single family dwelling is a use permitted in the respective district with which RAZ is combined (e.g. LDR) and the because the lot meets the provisions of Chapter 21.62 (Height and Setback Exceptions).
- h) Setbacks. The project meets setback requirements for LDR lots. The required front setback is 30 feet for main structures and 50 feet for non-habitable accessory structures. The house and garage will be 82 feet from the front property line. The required side setbacks are 10 percent of the average lot width. The parcel is narrowest at the front where it fronts Chiquito Place and widens toward the back, with the widest portion at the rear property line. The plans show the narrowest part of the lot to be 49.99 ft. and the widest width to be 274.8 ft. Ten percent of the average lot width is shown to be16ft, 5in. The house will be 25ft, 2 in. from the north property line and 24ft 2in. from the south property line. Therefore, the project meets the setbacks required for the proposed development.
- i) Archaeological Resources. The proposed development is within a moderate archaeological sensitivity zone and required an Archaeological Report pursuant to Section 21.66.050 (Title 21). The report indicated that there was no evidence of historic or prehistoric cultural activity. Based on these negative findings, there are no archaeological concerns; however, a standard condition will be applied for the inadvertent discovery of any cultural resources (Condition No. 3).
- j) <u>LUAC</u>. The project was referred to the Carmel Valley Land Use Advisory Committee (Carmel Valley LUAC) for review. Based on the LUAC Procedure Guidelines adopted by the Monterey County Board of Supervisors, this application did warrant referral to the LUAC because it includes a Design Approval application subject to review by the Planning Commission. On October 16, 2017, the Carmel Valley LUAC voted 6 ayes, 0 noes, and 1 absent, to continue the project citing setback and siting issues. It would appear that the applicant was receptive to the feedback because they submitted plans with revisions on December 1, 2017 which addressed issues raised at the LUAC. The project was restaked accordingly. The project was placed on the December 18, 2017 LUAC agenda and was supported with changes (7 ayes, 0 noes, 0 absent). Changes included undergrounding utilities (see condition no. 9) and adding retaining walls as needed.

- k) Staff conducted site inspections on September 21, 2017 and December 5 to verify that the project on the subject parcel conforms to the plans listed above and to ensure staking and flagging had been installed.
- 1) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN170468.
- 2. **FINDING: SITE SUITABILITY** The site is physically suitable for the use proposed.
  - a) The project has been reviewed for site suitability by the following departments and agencies: RMA- Planning, Cypress Fire Protection District, RMA-Public Works, RMA-Environmental Services, Water Resources Agency, and the Carmel Valley LUAC. There has been no indication from these departments/agencies that the site is not suitable for the proposed development. Recommended conditions have been incorporated.
  - b) Staff identified potential impacts to Archaeological resources and soil stability. The following reports have been prepared:
    - "Preliminary Archaeological Assessment," (LIB 170354) prepared by Susan Morley, April 2017.
    - "Geotechnical Engineering Report (LIB170355), prepared by Earth Systems, August 23, 2017.

The above-mentioned technical reports by third-party consultants indicated that there are no physical or environmental constraints that would indicate that the site is not suitable for the use proposed. County staff has independently reviewed these reports.

- c) Tree Removal. The applicant proposes to remove 1 (one) 18-inch pine tree for the purposes of development. Pursuant to the language and requirements of the Monterey County Zoning Ordinance (Title 21) Section 21.64.260 (Preservation of Oaks & Other Protected Trees) and the Carmel Valley Master Plan, Oaks, Madrones and Redwoods are protected tree species. Pines, however, are not listed as a protected species. Therefore, the sections addressing the removal three or less protected trees (Section 21.64.260, 2) or the removal of more than three protected trees (Section 21.64.260, 3) do not apply.
- d) <u>Use Permit: Slopes</u>. According to the County's GIS data, the site has a low landslide and liquefaction risk and poses a moderate erosion hazard. The lot is on slopes which exceed 25% in some areas and will require the structure and retaining walls attached to the structure to be supported by a system of drilled, cast-in-place concrete piers interconnected by grade beams. Per the Geotechnical Report, the piers should penetrate through any fill and surface soil to be embedded into firm sandstone bedrock; fills should be placed and compacted in accordance with common hillside practices, including keying and benching of the slopes to receive help. To reduce the potential for subsurface water to affect the lower level floor slab, a sub-slab drainage system should be provided. Free subsurface water was not encountered within the 10-foot depth of exploration. Slope inclinations range from about 20 percent on the proposed building area, to over 40 percent toward the rear of the property. There are no feasible siting alternatives without imposing

**EVIDENCE:** 

undue restrictions on the applicant or the removal of more trees. The project has been conditioned to address erosion control (Condition No. 10), grading (Condition No. 12), storm water (Condition No. 16) and construction management (Condition No. 17). In addition, the project will require all new utilities and distribution lines to be placed underground (Condition No. 9). The Use Permit entitlement is appropriate for this project because proposed development impacting slopes in excess of 25 percent exceeds 10 percent of the total development footprint. It is the general policy of the County to require dedication of a scenic easement on a slope exceeding 25 percent, however, the (north) toe of the bank (as shown on the plans) follows the extension of the reserve leach field and beyond that point, the slope is less than 25 percent and abuts a utility and natural drainage easement. Therefore, staff did not impose a condition requiring a scenic easement.

- e) <u>Waste Management</u>. A private septic system (including septic tank, primary leech field and reserve leech field) is also part of this project and is proposed to the rear of the lot. The septic system meets the minimum setbacks from the structure.
- f) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA Planning for the proposed development can be found in Project File PLN170468.

### 3. **FINDING:**

**HEALTH AND SAFETY -** The establishment, maintenance, or operation of the use or structure applied for, will not, under the circumstances of the particular case, be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use; or be detrimental or injurious to property and improvements in the neighborhood; or to the general welfare of the County.

#### **EVIDENCE:**

- The project has been reviewed for site suitability by the following departments and agencies: RMA- Planning, Cypress Fire Protection District, RMA-Public Works, RMA-Environmental Services, and the Water Resources Agency. The respective agencies have recommended conditions, where appropriate, to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
- b) A private septic system (including septic tank, primary leech field and reserve leech field) is also part of this project and is proposed to the rear of the lot. The septic system meets the minimum setbacks from the structure. Minimum horizontal distance required from a structure to a septic tank is 5 feet; the proposed septic tank will be placed 22 feet downslope from the edge of the residence. The minimum distance required from a structure to a leach field is 10 feet; the primary leach field is 24 feet downslope from the proposed residence. The minimum distance required from the property line to a leach field is 10 feet; the reserve leach field is over 50 feet from the edge of pavement on the west side (rear).
- c) Water will be supplied by the Monterey Peninsula Water Management District. The applicant provided the purchase deed showing water credits from Malpaso for a 2.5 bath home.

- d) Staff conducted a site inspection on September 21 and December 5, 2017 to verify that the site is suitable for this use.
- by the project applicant to the Monterey County RMA Planning for the proposed development found in Project File PLN170468.
- 4. **FINDING:** NO VIOLATIONS The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.
  - **EVIDENCE:** a) Staff reviewed Monterey County RMA Planning and Building Services Department records and is not aware of any violations existing on subject property.
    - b) Staff conducted a site inspection on September 21 and December 5, 2017 and researched County records to assess if any violation exists on the subject property; none were found.
    - c) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN170468.
- 5. **FINDING: CEQA (Exempt): -** The project qualifies for a categorical exemption pursuant to Section 15303 of the California Environmental Quality Act Guidelines and that none of the exceptions under section 15300.2 apply
  - **EVIDENCE:** a) California Environmental Quality Act (CEQA) Guidelines Section 15303 is a Class 3 exemption which categorically exempts a single-family residence and accessory structures including garages within residentially zoned areas.
    - The proposed project involves the construction of a single-family residence and attached garage, both located within a residential zone.
    - b) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. The project does not involve a designated historical resource, a hazardous waste site, development located near or within view of a scenic highway, unusual circumstances that would result in a significant effect on the environment, or development that would result in a cumulative significant impact.
    - d) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN170468.
- 7. **FINDING: APPEALABILITY -** The decision on this project may be appealed to the Board of Supervisors but not the California Coastal Commission.
  - **EVIDENCE:** a) Section 21.80.040.D of the Monterey County Zoning Ordinance states that the proposed project is appealable to the Board of Supervisors.
    - b) The project is not located in the Coastal Zone.

#### **DECISION**

**NOW, THEREFORE**, based on the above findings and evidence, the Planning Commission does hereby:

- 1) Find that the project is a single-family residence which qualifies for a categorical exemption pursuant to Section 15303 of the California Environmental Quality Act Guidelines and that none of the exceptions under section 15300.2 apply; and,
- 2) Approve a Combined Development Permit consisting of:
  - c. Administrative Permit and Design Approval to allow the construction of a new 2,939-square foot two-level single family dwelling, a 508-square foot attached garage, a 587-square foot deck/covered patio and associated grading; and a
  - d. Use Permit for development on slopes exceeding 25%.

in general conformance with the attached plans and subject to eighteen (18) conditions of approval, all being attached hereto and incorporated herein by reference; and

| PASSED AND            | ADOPTED this 11th day of April, 2018 upon motion of      |
|-----------------------|--|
|                       | , by the following vote:                                 |
| AVEC.                 |  |
| AYES:                 |  |
| NOES:                 |  |
| ABSENT:               |  |
| ABSTAIN:              |  |
|                       |  |
|                       |  |
|                       | Jacqueline R. Onciano, Planning Commission Secretary     |
|                       |  |
| COPY OF THIS DECISION | ON MAILED TO APPLICANT ON                                |
| THIS APPLICATION IS   | APPEALABLE TO THE BOARD OF SUPERVISORS.                  |
| IF ANYONE WISHES TO   | O APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED |
| AND SUBMITTED TO T    | HE CLERK OF THE BOARD ALONG WITH THE APPROPRIATE FILING  |
| FEE ON OR BEFORE      |  |
| (Coastal Projects)    |  |
| THIS PROJECT IS LOCA  | ATED IN THE COASTAL ZONE AND IS TO THE COASTAL           |
| COMMISSION. UPON I    | RECEIPT OF NOTIFICATION OF THE FINAL LOCAL ACTION NOTICE |
|                       | DECISION BY THE FINAL DECISION MAKING BODY, THE          |
|                       | ISHES A 10 WORKING DAY APPEAL PERIOD. AN APPEAL FORM     |
| MUST BE FILED WITH    | THE COASTAL COMMISSION. FOR FURTHER INFORMATION.         |

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

CONTACT THE COASTAL COMMISSION AT (831) 427-4863 OR AT 725 FRONT STREET, SUITE

300, SANTA CRUZ, CA.

#### **NOTES**

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.

Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from Monterey County RMA-Planning and RMA-Building Services Department office in Salinas.

2. This permit expires 3 years after the above date of granting thereof unless construction or use is started within this period.

Form Rev. 5-14-2014

### **Monterey County RMA Planning**

# DRAFT Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN170468

#### 1. PD001 - SPECIFIC USES ONLY

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure: This Combined Development Permit (PLN170468) allows the construction of a new 2,939 square foot, two-level single family dwelling, a 508-square foot attached garage, a 587-square foot deck/covered patio, retaining walls and associated grading on slopes exceeding 25% in some areas. The project also includes the removal of a non-protected tree (18" Pine). The property is located at 25575 Chiquito Place, Carmel (Assessor's Parcel Number 015-052-026-000), Carmel Valley Master Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the Director of RMA -Any use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA -Planning)

Compliance or Monitoring Action to be Performed: The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

Print Date: 4/3/2018 12:13:12PM Page 1 of 7

#### 2. PD002 - NOTICE PERMIT APPROVAL

Responsible Department: F

RMA-Planning

Condition/Mitigation Monitoring Measure:

The applicant shall record a Permit Approval Notice. This notice shall state:

"A Combined Development Permit (Resolution Number \*\*\* ) was approved by the Planning Commission for Assessor's Parcel Number on April 11, 2018. The permit was granted subject to 18 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

#### 3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

Responsible Department:

RMA-Planning

Condition/Mitigation Monitoring Measure:

during course of construction, cultural, archaeological, historical paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified Monterey County RMA - Planning and a professional archaeologist can evaluate it. qualified archaeologist (i.e., an archaeologist registered with the be immediately contacted Professional Archaeologists) shall by the When contacted, the project planner and the archaeologist individual present on-site. shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.

(RMA - Planning)

Compliance or Monitoring Action to be Performed: The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

Print Date: 4/3/2018 12:13:12PM Page 2 of 7

#### 4. PD006(A) - CONDITION COMPLIANCE FEE

Responsible Department: RMA-Planning

Condition/Mitigation
Monitoring Measure:

The Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors, for the staff time required to satisfy

conditions of approval. The fee in effect at the time of payment shall be paid prior to

clearing any conditions of approval.

Compliance or Monitoring Action to be Performed:

Prior to clearance of conditions, the Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors.

#### 5. PD007- GRADING WINTER RESTRICTION

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

No land clearing or grading shall occur on the subject parcel between October 15 and April 15 unless authorized by the Director of RMA - Building Services. (RMA -

Planning and RMA - Building Services)

Compliance or Monitoring Action to be Performed: The Owner/Applicant, on an on-going basis, shall obtain authorization from the Director of RMA - Building Services Department to conduct land clearing or grading between October 15 and April 15.

#### 6. PD011 - TREE AND ROOT PROTECTION

Responsible Department: RMA-Planning

Condition/Mitigation
Monitoring Measure:

Trees which are located close to construction site(s) shall be protected from inadvertent damage from construction equipment by fencing off the canopy driplines and/or critical root zones (whichever is greater) with protective materials, wrapping trunks with protective materials, avoiding fill of any type against the base of the trunks and avoiding an increase in soil depth at the feeding zone or drip-line of the retained trees. Said protection, approved by certified arborist, shall be demonstrated prior to issuance of building permits subject to the approval of RMA - Director of Planning. If there is any potential for damage, all work must stop in the area and a report, with mitigation measures, shall be submitted by certified arborist. Should any additional trees not included in this permit be harmed, during grading or construction activities, in such a way where removal is required, the owner/applicant shall obtain required permits. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to issuance of grading and/or building permits, the Owner/Applicant shall submit evidence of tree protection to RMA - Planning for review and approval.

During construction, the Owner/Applicant/Arborist shall submit on-going evidence that tree protection measures are in place through out grading and construction phases. If damage is possible, submit an interim report prepared by a certified arborist.

Prior to final inspection, the Owner/Applicant shall submit photos of the trees on the property to RMA-Planning after construction to document that tree protection has been successful or if follow-up remediation or additional permits are required.

Print Date: 4/3/2018 12:13:12PM Page 3 of 7

#### 7. PD014(A) - LIGHTING - EXTERIOR LIGHTING PLAN

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

All exterior lighting shall be unobtrusive, down-lit, harmonious with the local area, and constructed or located so that only the intended area is illuminated and off-site glare is fully controlled. The lighting source shall be shielded and recessed into the fixture. The applicant shall submit three (3) copies of an exterior lighting plan which shall indicate the location, type, and wattage of all light fixtures and include catalog sheets for each fixture. The lighting shall comply with the requirements of the California Energy Code set forth in California Code of Regulations Title 24 Part 6. The exterior lighting plan shall be subject to approval by the Director of RMA - Planning, prior to the issuance of building permits.

(RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of building permits, the Owner/Applicant shall submit three copies of the lighting plans to RMA - Planning for review and approval. Approved lighting plans shall be incorporated into final building plans.

Prior to final/occupancy, the Owner/Applicant/Contractor shall submit written and photographic evidence demonstrating that the lighting has been installed according to the approved plan.

On an on-going basis, the Owner/Applicant shall ensure that the lighting is installed and maintained in accordance with the approved plan.

#### 8. PD050 - RAPTOR/MIGRATORY BIRD NESTING

Responsible Department: RMA-Planning

Condition/Mitigation
Monitoring Measure:

Any tree removal activity that occurs during the typical bird nesting season (February 22-August 1), the County of Monterey shall require that the project applicant retain a County qualified biologist to perform a nest survey in order to determine if any active raptor or migratory bird nests occur within the project site or within 300 feet of proposed tree removal activity. During the typical nesting season, the survey shall be conducted no more than 30 days prior to ground disturbance or tree removal. If nesting birds are found on the project site, an appropriate buffer plan shall be established by the project biologist. (RMA - Planning)

Compliance or Monitoring Action to be Performed: No more than 30 days prior to ground disturbance or tree removal, the Owner/Applicant/Tree Removal Contractor shall submit to RMA-Planning a nest survey prepare by a County qualified biologist to determine if any active raptor or migratory bird nests occur within the project site or immediate vicinity.

### 9. PD035 - UTILITIES UNDERGROUND

Responsible Department: RMA-Planning

Condition/Mitigation All new utility and distribution lines shall be placed underground. (RMA - Planning and Monitoring Measure: RMA- Public Works)

RIMA- Public Works

Compliance or On an on-going basis, the Owner/Applicant shall install and maintain utility an Monitoring distribution lines underground.

Action to be Performed:

Print Date: 4/3/2018 12:13:12PM Page 4 of 7

#### 10. EROSION CONTROL PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit an Erosion Control Plan in conformance with the requirements of Monterey County Code Chapter 16.12. The Erosion Control Plan shall include a construction entrance, concrete washout, stockpile area(s), material storage area(s), portable sanitation facilities and waste collection area(s), as applicable. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or building permits, the applicant shall submit an Erosion Control Plan to RMA-Environmental Services for review and approval.

#### 11. GEOTECHNICAL CERTIFICATION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall provide certification from a licensed practitioner that all development has been constructed in accordance with the recommendations in the project Geotechnical Engineering Report. (RMA- Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to final inspection, the owner/applicant shall provide RMA-Environmental Services a letter from a licensed practitioner.

#### 12. GRADING PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit a Grading Plan incorporating the recommendations from the project Geotechnical Engineering Report prepared by Earth Systems Pacific. The Grading Plan shall include contour intervals and cross-sections that identify the existing grade, proposed grade, and the extent of any proposed excavation and/or fill. The Grading Plan shall include the geotechnical inspection schedule that identifies when the inspections will be completed, who will conduct the inspection (i.e., PG, PE, and/or Special Inspector), a description of the required inspection, inspector name, and the completion date. The applicant shall also provide certification from the practitioner Grading Plan incorporates licensed that the their geotechnical recommendations. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to issuance of any grading or building permits, the applicant shall submit a Grading Plan to RMA-Environmental Services for review and approval.

Prior to issuance of any grading or building permits, the applicant shall submit certification from a licensed practitioner that they have reviewed the Grading Plan for conformance with the geotechnical recommendations.

Print Date: 4/3/2018 12:13:12PM Page 5 of 7

#### 13. INSPECTION-DURING ACTIVE CONSTRUCTION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall schedule an inspection with RMA-Environmental Services to inspect drainage device installation, review the maintenance and effectiveness of BMPs installed, and to verify that pollutants of concern are not discharged from the site. At the time of the inspection, the applicant shall provide certification that all necessary geotechnical inspections have been completed to that point. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed:

During construction, the applicant shall schedule an inspection with RMA-Environmental Services.

#### 14. INSPECTION-FOLLOWING ACTIVE CONSTRUCTION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall schedule an inspection with RMA-Environmental Services to ensure all disturbed areas have been stabilized and all temporary erosion and sediment control measures that are no longer needed have been removed. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to final inspection, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

#### 15. INSPECTION-PRIOR TO LAND DISTURBANCE

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall schedule an inspection with RMA-Environmental Services to ensure all necessary sediment controls are in place and the project is compliant with Monterey County regulations. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to commencement of any land disturbance, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

#### 16. STORMWATER CONTROL PLAN (PR1)

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit а Stormwater Control Plan addressing (PCRs) for Development Projects in the Central Post-Construction Requirements Coast Region. The Stormwater Control Plan shall incorporate the measures identified the completed the Site Design and Runoff Reduction Checklist. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or building permits, the applicant shall submit a Stormwater Control Plan to RMA-Environmental Services for review and approval.

Print Date: 4/3/2018 12:13:12PM Page 6 of 7

#### 17. PW0044 - CONSTRUCTION MANAGEMENT PLAN

#### Responsible Department:

RMA-Public Works

#### Condition/Mitigation **Monitoring Measure:**

The applicant shall submit a Construction Management Plan (CMP) to the Resource Management

Agency (RMA) for review and approval. The CMP shall include measures to minimize traffic

impacts during the construction/grading phase of the project and shall provide the following

information:

Duration of the construction, hours of operation, an estimate of the number of truck trips that will

be generated, truck routes, number of construction workers, parking areas for both equipment and

workers, and locations of truck staging areas. Approved measures included in the CMP shall be

implemented by the applicant during the construction/grading phase of the project.

#### Compliance or Monitoring Action to be Performed:

- 1. Prior to issuance of the Grading Permit or Building Permit Owner/Applicant/ Contractor shall prepare a CMP and shall submit the CMP to the RMA for review and approval.
- 2. On-going through construction phases Owner/Applicant/Contractor shall implement the approved measures during the construction/grading phase of the project.

#### 18. FIRE011 - ADDRESSES FOR BUILDINGS

#### Responsible Department: Fire

#### Condition/Mitigation Monitoring Measure:

All buildings shall be issued an address in accordance with Monterey County Ordinance No. 1241. Each occupancy, except accessory buildings, shall have its own permanently posted address. When multiple occupancies exist within a single building, each individual occupancy shall be separately identified by its own address. Letters, numbers and symbols for addresses shall be a minimum of 4-inch height, 1/2-inch stroke, contrasting with the background color of the sign, and shall be Arabic. The sign and numbers shall be reflective and made of a noncombustible material. Address signs shall be placed at each driveway entrance and at each driveway split. Address signs shall be visible and legible from both directions of travel along the road. In all cases, the address shall be posted at the beginning of construction and shall be maintained thereafter. Address signs along one-way roads shall be visible from both directions of travel. Where multiple addresses are required at a single driveway, they shall be mounted on a single sign. Where a roadway provides access solely to a single commercial occupancy, the address sign shall be placed at the nearest road intersection providing access to that site. Permanent address numbers shall be posted prior to requesting final clearance. Responsible Land Use Department: Fire District

#### Compliance or Monitoring Action to be Performed:

Prior to issuance of building permit, Applicant shall incorporate specification into design and print the text of this condition as "Fire Dept. Notes" on plans.

Prior to requesting a final building inspection, Applicant shall install the required address signage and shall obtain fire department approval of the fire department final inspection.

Print Date: 4/3/2018 12:13:12PM Page 7 of 7 - LATEST REVISION OF THE MONTEREY COUNTY DESIGN STANDARDS AND SPECIFICATIONS - THE LATEST REVISION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS (STATE SPECIFICATIONS)

- THE 2013 EDITIONS OF THE CALIFORNIA BUILDING CODE (CBC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA MECHANICAL CODE (CMC), CALIFORNIA ENERGY CODE (CEnC), CALIFORNIA ELECTRICAL CODE (CEC), CALIFORNIA FIRES

2. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE PLANS, DETAILS, AND SPECIFICATIONS AND SITE CONDITIONS PRIOR TO THE START OF CONSTRUCTION. IN THE EVENT THAT THE CONTRACTOR FINDS ANY DISCREPANCIES, OMISSIONS, OR DEFICIENCIES IN THE PLANS, THE CONTRACTOR SHALL NOTIFY THE DESIGN

3. IT IS THE CONTRACTORS RESPONSIBILITY TO SECURE ALL REQUIRED PERMITS PRIOR TO THE START OF CONSTRUCTION. GRADING PERMITS EXPIRE 180 DAYS FROM ISSUANCE DATE.

4. THE LOCATIONS AND SIZE OF UNDERGROUND UTILITIES AND OR OTHER STRUCTURES SHOWN HEREON WERE OBTAINED FROM A FIELD SURVEY (BY OTHERS) AND OR FROM RECORD INFORMATION. NEITHER THE ENGINEER NOR THE OWNER MAKES ANY REPRESENTATION TO THE ACCURACY OF SIZE AND OR LOCATION OF ANY OF THE UTILITIES OR STRUCTURES SHOWN ON THESE PLANS NOR FOR THE EXISTENCE OF ANY OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED THAT ARE NOT SHOWN ON THIS PLAN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE SIZE AND LOCATION OF EXISTING UNDERGROUND UTILITIES, SURFACE IMPROVEMENTS, AND OTHER STRUCTURES AND TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THEM FROM DAMAGE DURING CONSTRUCTION.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING APPROPRIATE UTILITY COMPANIES AND REQUESTING VERIFICATION OF SERVICE POINTS, FIELD VERIFICATION OF LOCATION, SIZE, DEPTH, ETC. FOR ALL THEIR FACILITIES AND TO COORDINATE WORK SCHEDULES.

6. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT AT (800) 227-2600 AT LEAST 48 HOURS PRIOR TO EXCAVATION TO VERIFY THE LOCATION OF EXISTING UNDERGROUND UTILITIES.

7. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH ANY CURRENTLY APPLICABLE SAFETY LAW OF ANY JURISDICTIONAL BODY. FOR INFORMATION REGARDING THIS PROVISION, THE CONTRACTOR IS DIRECTED TO CONTACT THE STATE OF CALIFORNIA, DIVISION OF OCCUPATIONAL SAFETY AND HEALTH. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL BARRICADES, SAFETY DEVICES, AND THE CONTROL OF TRAFFIC WITHIN THE CONSTRUCTION AREA. FOR ALL TRENCH EXCAVATION FIVE (5) FEET OR MORE IN DEPTH, THE CONTRACTOR SHALL OBTAIN A PERMIT FROM THE DIVISION OF OCCUPATIONAL SAFETY AND HEALTH PRIOR TO BEGINNING ANY EXCAVATION. A COPY OF THIS PERMIT SHALL BE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES.

8. EXISTING CURB, GUTTER, SIDEWALK, SURVEY MONUMENTS, AND OTHER IMPROVEMENTS WITHIN PROJECT SITE THAT ARE DAMAGED OR DISPLACED AS A RESULT OF THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED BY THE

9. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS AND SAFETY OF ALL PERSONS AND PROPERTY DURING THE COURSE OF CONSTRUCTION OF THE PROJECT. THE CONTRACTOR AGREES TO HOLD HARMLESS, INDEMNIFY AND DEFEND THE OWNER, THE ENGINEER, AND ALL DESIGN CONSULTANTS FROM ANY AND ALL LIABILITY, CLAIMS, LOSSES OR DAMAGES ARISING FROM THE PERFORMANCE OF THE WORK DESCRIBED HEREIN EXCEPT THOSE ARISING FROM THE SOLE NEGLIGENCE OF ANY OF THE PREVIOUSLY MENTIONED PEOPLE OR ENTITIES. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.

10. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL, OFF-HAUL AND DISPOSE OF ALL ITEMS TO BE REMOVED INCLUDING BUT NOT LIMITED TO: ASPHALT, CONCRETE STRIPING, ANY AND ALL OTHER DEBRIS FROM THE SITE, EXCESS FROM TRENCHING AND PAVEMENT CONSTRUCTION. TREES AND ROOT-BALLS FENCING AND SPOILS FROM EXCAVATION AT THE CONTRACTOR'S EXPENSE.

11. IF ARCHAEOLOGICAL RESOURCES OR HUMAN REMAINS ARE DISCOVERED DURING CONSTRUCTION, WORK SHALL BE HALTED WITHIN 150 FEET OF THE FIND UNTIL IT CAN BE EVALUATED BY A QUALIFIED PROFESSIONAL ARCHAEOLOGIST. IF THE FIND IS DETERMINED TO BE SIGNIFICANT, APPROPRIATE MITIGATION MEASURES SHALL BE FORMULATED AND IMPLEMENTED.

12. ALL REVISIONS TO THESE PLANS MUST BE APPROVED BY THE ENGINEER AS WELL AS THE OWNER PRIOR TO THEIR CONSTRUCTION AND SHALL BE ACCURATELY SHOWN ON RECORD DRAWINGS PRIOR TO THE ACCEPTANCE OF THE WORK AS COMPLETE. ANY CHANGES TO OR DEVIATIONS FROM THE PLANS MADE WITHOUT AUTHORIZATION SHALL BE AT THE CONTRACTOR'S SOLE RISK AND SHALL ABSOLVE THE ENGINEER OF ANY AND ALL RESPONSIBILITY ASSOCIATED WITH THE CHANGE OR DEVIATION.

13. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP THE SITE AND ADJACENT AREAS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY. THE CONTRACTOR SHALL REMOVE IT IMMEDIATELY.

14. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: A) PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH B) COVER STOCKPILES OF DEBRIS, SOIL, OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST. C) KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST.

D) LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE.

15. A COPY OF ALL FIELD REPORTS/COMPACTIONS TESTS AND FINAL GRADING REPORT SHALL BE SUBMITTED TO THE COUNTY AT SCHEDULED INSPECTIONS.

16. PAD ELEVATION/S SHALL BE CERTIFIED TO 0.1 FEET. PRIOR TO DIGGING ANY FOOTINGS OR SCHEDULING ANY

### STORM DRAIN

1. ALL STORM DRAIN PIPING 6"-24" SHALL BE HIGH DENSITY POLYETHYLENE TYPE-S WITH INTEGRAL BELL & SPIGOT JOINTS (ADS-N12 OR EQUAL) OR PVC (SDR 35). INSTALLATION SHALL BE PER MANUFACTURERS SPECIFICATIONS OR AS SHOWN ON PLANS.

3. ALL STORM DRAIN PIPE SHALL BE RIGID. NO FLEX PIPE.

### **SURVEY NOTES**

1. THE BEARING OF N 49°23' W ALONG THE NORTHERLY RIGHT OF WAY LINE OF CHIQUITO PLACE AS SHOWN ON THE MAP RECORDED IN VOLUME 4 OF CITIES & TOWNS AT PAGE 31 AS FOUND MONUMENTED, WAS TAKEN AS BASIS OF BEARINGS SHOWN UPON THIS MAP.

2. THE UTILITY EASEMENTS SHOWN HEREON MAY HAVE EXPIRED IN 1996 PER THE CONDITIONS SET FORTH IN THE DOCUMENT TITLED "DECLARATION OF RESTRICTIONS FOR RANCHO RIO VISTA" AND FILED IN BOOK 929 OFFICIAL RECORDS AT PAGE 5. CONSULT A TITLE COMPANY FOR FURTHER INFORMATION ON THE VALIDITY OF THESE EASEMENTS.

### GRADING & DRAINAGE

1. CONTRACTOR SHALL NOTIFY COUNTY 48 HOURS BEFORE STARTING ANY GRADING OPERATIONS.

2. ALL GRADING SHALL CONFORM TO THE COUNTY GRADING ORDINANCE.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE REQUIRED PERMITS PRIOR TO THE COMMENCEMENT OF GRADING. RIGHT-OF-ENTRY, PERMISSION TO GRADE, AND ENCROACHMENT PERMIT(S) MAY BE REQUIRED PRIOR TO

4. IT IS THE CONTRACTORS RESPONSIBILITY TO PREPARE THE GROUND SURFACE TO RECEIVE THE FILLS AND TO PLACE, SPREAD, MIX, WATER, AND COMPACT THE FILL. THE CONTRACTOR SHALL ALSO REMOVE ALL MATERIAL

5. WHERE UNSTABLE OR UNSUITABLE MATERIALS ARE ENCOUNTERED DURING SUB-GRADE PREPARATION. THE AREA IN QUESTION SHALL BE OVER EXCAVATED AND BACKFILLED WITH SELECT MATERIAL.

6. MAXIMUM CUT AND FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL UNLESS OTHERWISE DIRECTED.

7. ALL CUT SLOPES SHALL BE ROUNDED TO MEET EXISTING GRADES AND BLEND WITH SURROUNDING TOPOGRAPHY. ALL GRADED SLOPES SHALL BE PLANTED WITH SUITABLE GROUND COVER.

8. TREE REMOVAL SHALL INCLUDE REMOVAL OF TRUNKS, STUMPS, AND ROOT-BALLS. THE REMAINING CAVITY SHALL BE CLEARED OF ALL ROOTS LARGER THAN 1/2" TO A DEPTH OF NOT LESS THAN 18" AND BACKFILLED WITH SUITABLE MATERIAL THEN COMPACTED TO CONFORM WITH THE EXISTING GROUND.

9. CONTRACTOR SHALL USE CAUTION WHEN GRADING AROUND AND/OR OVER EXISTING UNDERGROUND UTILITIES.

10. EARTHWORK QUANTITIES:

CUT = 93 CYFILL = 75 CY

NET = 18 CY CUT

MAXIMUM HEIGHT OF EXCAVATION 4 MAXIMUM HEIGHT OF EMBANKMENT 6

EARTHWORK QUANTITIES ARE ESTIMATES ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACTUAL EARTHWORK QUANTITIES. NO ALLOWANCE HAS BEEN MADE TO ACCOUNT FOR QUANTITIES FROM TRENCHING FOR FOUNDATION, FOOTINGS, PIERS AND/OR UTILITIES TRENCHES.

11. ALL SURFACE DRAINAGE SHALL MAINTAIN 2% SLOPE MINIMUM.

12. PERVIOUS SURFACES IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT A SLOPE OF NOT LESS THAN 5% FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FEET OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED A MINIMUM OF 2% WHERE LOCATED WITHIN 10 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.

13. INVERTS OF ALL STORM DRAIN LINES CONNECTING RETAINING WALL SUB-DRAINS AND FOUNDATION SUB-DRAINS SHALL BE FIELD VERIFIED AFTER FOOTINGS ARE PLACED.

14. BUILDINGS CONSTRUCTED ACROSS CUT/FILL LINE SHALL HAVE COMPACTION TESTS TAKEN CUT AREA AS WELL AS THE FILL AREA. TESTS SHALL MEET 90% OF THE RELATIVE COMPACTION PER ASTM D1557.

15. ALL STORM DRAIN MAINS SHALL HAVE A MINIMUM OF 12" COVER.

(MONTEREY COUNTY GRADING/EROSION ORD.2806-16.12.090)

16. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15) THE FOLLOWING MEASURES MUST BE

A. DISTURBED SURFACES NOT INVOLVED IN IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.

B. ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON DOWNHILL PROPERTIES.

C. RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS. VEGETATED FILTER STRIPS, AND OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE.

D. DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY THROUGH THE LIFE OF THE PROJECT DURING WINTER OPERATIONS

17. ALL ROOF DRAINS SHALL DISCHARGE ONTO PAVED SURFACES, SPLASH BLOCKS OR BE HARD PIPED TO THE STORM DRAIN SYSTEM.

18. VEGETATION REMOVAL. ACTUAL GRADING SHALL BEGIN WITHIN 30 DAYS OF VEGETATION REMOVAL OR THAT AREA SHALL BE PLANTED UNDER THE PROVISIONS OF SECTION 16.08.340 TO CONTROL EROSIONS. (16.08.300)

19. NO VEGETATION REMOVAL OR GRADING WILL BE ALLOWED WHICH WILL RESULT IN SILTATION OF WATER COURSES OR UNCONTROLLABLE EROSION. (16.08.300)

20. PREPARATION OF GROUND FOR FILL. THE GROUND SURFACE SHALL BE PREPARED TO RECEIVE FILL BY THE REMOVAL OF TOPSOIL AND OTHER UNSUITABLE MATERIALS.

21. PREPARATION OF THE GROUND. THE GROUND SURFACE SHALL BE PREPARED TO RECEIVE FILL BY REMOVING VEGETATION, NON-COMPLYING FILL, TOPSOIL AND OTHER UNSUITABLE MATERIALS SCARIFYING TO PROVIDE A BOND WITH THE NEW FILL.

22. FILL MATERIAL PERMITTED. NO ORGANIC MATERIAL SHALL BE PERMITTED IN FILL EXCEPT AS TOPSOIL USED FOR SURFACE PLANT GROWTH ONLY AND WHICH DOES NOT EXCEED 4 INCHES IN DEPTH. (16.08.310)

### UNDERGROUND UTILITIES

1. CONTRACTOR SHALL EXPOSE AND VERIFY LOCATION AND ELEVATION OF EXISTING UTILITIES, INCLUDING STORM DRAINS, SANITARY SEWERS AND WATER LINES, BEFORE ORDERING MATERIALS AND/OR CONSTRUCTING NEW FACILITIES.

2. ALL EXISTING MANHOLES AND UTILITY BOXES WITHIN THE PROJECT AREA ARE TO BE SET FLUSH WITH FINISHED GRADE, UNLESS OTHERWISE NOTED.

3. ALL TRENCHES AND EXCAVATIONS SHALL BE CONSTRUCTED IN STRICT COMPLIANCE WITH THE APPLICABLE SECTIONS OF CALIFORNIA AND FEDERAL O.S.H.A. REQUIREMENTS AND OTHER APPLICABLE SAFETY ORDINANCES, CONTRACTOR SHALL BEAR FULL RESPONSIBILITY FOR TRENCH SHORING DESIGN AND INSTALLATION.

4. PIPE MATERIALS AND INSTALLATION PROCEDURE SHALL BE IN ACCORDANCE WITH APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS AND THE MANUFACTURER'S RECOMMENDATIONS.

5. SHOULD ANY WATER SYSTEM MAINS OR SERVICES BE DAMAGED BY THE CONTRACTOR, THE WATER SYSTEM SHALL BE REPAIRED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS OF THE COUNTY.

### TREE PROTECTION NOTES

THE FOLLOWING ACTIVITIES ARE PROHIBITED WITHIN THE LIMITS OF THE CRITICAL ROOT ZONE OF ANY PROTECTED

1. MATERIAL STORAGE: NO STORAGE OR PLACEMENT OF MATERIALS INTENDED FOR USE IN CONSTRUCTION OR WASTE MATERIALS ACCUMULATED DUE TO EXCAVATION OR DEMOLITION SHALL BE PLACED WITHIN THE LIMITS OF THE CRITICAL ROOT ZONE OF ANY PROTECTED TREE.

2. EQUIPMENT CLEANING/LIQUID DISPOSAL: NO EQUIPMENT SHALL BE CLEANED OR OTHER LIQUIDS, INCLUDING, WITHOUT LIMITATION, PAINT, OIL, SOLVENTS, ASPHALT, CONCRETE, MORTAR OR SIMILAR MATERIALS DEPOSITED OR ALLOWED TO FLOW INTO THE CRITICAL ROOT ZONE OF A PROTECTED TREE.

3. TREE ATTACHMENTS: NO SIGNS, WIRES OR OTHER ATTACHMENTS, OTHER THAN THOSE OF A PROTECTIVE NATURE, SHALL BE ATTACHED TO ANY PROTECTED TREE.

4. VEHICULAR TRAFFIC: NO VEHICULAR AND/OR CONSTRUCTION EQUIPMENT TRAFFIC OR PARKING SHALL TAKE PLACE WITHIN THE CRITICAL ROOT ZONE OF ANY PROTECTED TREE OTHER THAN ON EXISTING STREET PAVEMENT. THIS RESTRICTION DOES NOT APPLY TO SINGLE INCIDENT ACCESS WITHIN THE CRITICAL ROOT ZONE FOR PURPOSES OF ESTABLISHING THE BUILDING PAD AND ASSOCIATED LOT GRADING, VEHICULAR TRAFFIC NECESSARY FOR ROUTINE UTILITY MAINTENANCE, EMERGENCY RESTORATION OF UTILITY SERVICE, OR ROUTINE MOWING OPERATIONS.

5. NO HEAVY EQUIPMENT, INCLUDING BUT NOT LIMITED TO TRUCKS, TRACTORS, TRAILERS, BULLDOZERS, BOBCAT TRACTORS, TRENCHERS, COMPRESSORS, AND HOISTS, SHALL BE ALLOWED INSIDE THE DRIP-LINE OF ANY PROTECTED TREE ON ANY CONSTRUCTION SITE WITHOUT PRIOR WRITTEN APPROVAL OF THE ADMINISTRATIVE OFFICIAL.

6. ROOT PRUNING: ALL ROOTS TWO INCHES OR LARGER IN DIAMETER WHICH ARE EXPOSED AS A RESULT OF TRENCHING OR OTHER EXCAVATION SHALL BE CUT OFF SQUARE WITH A SHARP MEDIUM TOOTH SAW AND COVERED WITH PRUNING COMPOUND WITHIN TWO HOURS OF INITIAL EXPOSURE.

THE FOLLOWING PROCEDURES SHALL BE FOLLOWED ON ALL TYPES OF CONSTRUCTION PROJECTS (INCLUDING RESIDENTIAL, COMMERCIAL, AND MUNICIPAL / PUBLIC DOMAIN PROJECTS).

1. PROTECTIVE FENCING: PRIOR TO THE ISSUANCE OF ANY BUILDING OR EARTH DISTURBANCE PERMIT, OR COMMENCING CONSTRUCTION, THE OWNER, CONTRACTOR OR SUBCONTRACTOR SHALL CONSTRUCT AND MAINTAIN, FOR EACH PROTECTED TREE ON A CONSTRUCTION SITE. A PROTECTIVE FENCING WHICH ENCIRCLE THE OUTER LIMITS OF THE CRITICAL ROOT ZONE OF THE TREE TO PROTECT IT FROM CONSTRUCTION ACTIVITY.

2. ALL PROTECTIVE FENCING SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF ANY SITE WORK AND REMAIN IN PLACE UNTIL ALL EXTERIOR CONSTRUCTION ACTIVITY AT THE SITE HAS BEEN COMPLETED.

3. PROTECTIVE FENCING SHALL BE AT LEAST FOUR (4) FEET HIGH, CLEARLY VISIBLE, AND BE CLEARLY VISIBLE TO WORKERS ON THE SITE.

4. THE USE OF ORANGE VINYL CONSTRUCTION FENCING OR OTHER SIMILAR FENCING IS GENERALLY PERMITTED ONLY IF THERE IS NO CONSTRUCTION OR VEHICULAR ACTIVITY WITHIN TEN (10) FEET OF THE FENCE. IF CONSTRUCTION ACTIVITY OR VEHICULAR TRAFFIC IS EXPECTED WITHIN TEN (10) FEET OF THE FENCE, THE CONTRACTOR SHALL ALSO EMPLOY BARK PROTECTION.

### TREE PROTECTION NOTES

ACCESS ROADS SHALL BE REQUIRED FOR EVERY BUILDING WHEN ANY PORTION OF THE EXTERIOR WALL OF THE FIRST STORY IS LOCATED MORE THAN 150 FEET FROM FIRE DEPARTMENT ACCESS. ALL ROADS SHALL BE CONSTRUCTED TO PROVIDE A MINIMUM OF TWO NINE-FOOT TRAFFIC LANES WITH AN UNOBSTRUCTED VERTICAL CLEARANCE OF NOT LESS THAN 15 FEET. THE ROADWAY SURFACE SHALL PROVIDE UNOBSTRUCTED ACCESS TO CONVENTIONAL DRIVE VEHICLES INCLUDING SEDANS AND FIRE APPARATUS AND SHALL BE AN ALL-WEATHER SURFACE DESIGNED TO SUPPORT THE IMPOSED LOAD OF FIRE APPARATUS (22 TONS). EACH ROAD SHALL HAVE AN APPROVED

FIRE002 - ROADWAY ENGINEERING

THE GRADE FOR ALL ROADS SHALL NOT EXCEED 15 PERCENT. WHERE ROAD GRADES EXCEED 8 PERCENT, A MINIMUM STRUCTURAL ROADWAY SURFACE OF 0.17 FEET OF ASPHALTIC CONCRETE ON 0.34 FEET OF AGGREGATE BASE SHALL BE REQUIRED. THE LENGTH OF VERTICAL CURVES IN ROADWAYS, EXCLUSIVE OF GUTTERS, DITCHES AND DRAINAGE STRUCTURES DESIGNED TO HOLD OR DIVERT WATER, SHALL NOT BE LESS THAN 100 FEET. NO ROADWAY TURN SHALL HAVE A HORIZONTAL INSIDE RADIUS OF LESS THAN 50 FEET. A ROADWAY TURN RADIUS OF 50 TO 100 FEET IS REQUIRED TO HAVE AN ADDITIONAL 4 FEET OF ROADWAY SURFACE. A ROADWAY TURN RADIUS OF 100 TO 200 FEET IS REQUIRED TO HAVE AN ADDITIONAL 2 FEET OF ROADWAY SURFACE, ROADWAY TURNAROUNDS SHALL BE REQUIRED ON DEAD-END ROADS IN EXCESS OF 150 FEET OF SURFACE LENGTH. THE MINIMUM TURNING RADIUS FOR A TURNAROUND SHALL BE 40 FEET FROM THE CENTER LINE OF THE ROAD. IF A HAMMERHEAD/T IS USED, THE TOP OF THE "T" SHALL BE A MINIMUM OF 60 FEET IN LENGTH.

DRIVEWAYS SHALL NOT BE LESS THAN 12 FEET WIDE UNOBSTRUCTED, WITH AN UNOBSTRUCTED VERTICAL CLEARANCE OF NOT LESS THAN 15 FEET. THE GRADE FOR ALL DRIVEWAYS SHALL NOT EXCEED 15 PERCENT. WHERE THE GRADE EXCEEDS 8 PERCENT. A MINIMUM STRUCTURAL ROADWAY SURFACE OF 0.17 FEET OF ASPHALTIC CONCRETE ON 0.34 FEET OF AGGREGATE BASE SHALL BE REQUIRED. THE DRIVEWAY SURFACE SHALL BE CAPABLE OF SUPPORTING THE IMPOSED LOAD OF FIRE APPARATUS (22 TONS), AND BE ACCESSIBLE BY CONVENTIONAL-DRIVE

VEHICLES, INCLUDING SEDANS. FOR DRIVEWAYS WITH TURNS 90 DEGREES AND LESS, THE MINIMUM HORIZONTAL INSIDE RADIUS OF CURVATURE SHALL BE 25 FEET. FOR DRIVEWAYS WITH TURNS GREATER THAN 90 DEGREES, THE MINIMUM HORIZONTAL INSIDE RADIUS CURVATURE SHALL BE 28 FEET. FOR ALL DRIVEWAY TURNS, AN ADDITIONAL SURFACE OF 4 FEET SHALL BE

ALL DRIVEWAYS EXCEEDING 150 FEET IN LENGTH, BUT LESS THAN 800 FEET IN LENGTH, SHALL PROVIDE A TURNOUT NEAR THE MIDPOINT OF THE DRIVEWAY. WHERE THE DRIVEWAY EXCEEDS 800 FEET, TURNOUTS SHALL BE PROVIDED AT NO GREATER THAN 400-FOOT INTERVALS. TURNOUTS SHALL BE A MINIMUM OF 12 FEET WIDE AND 30 FEET LONG WITH A MINIMUM OF 25-FOOT TAPER AT BOTH ENDS. TURNAROUNDS SHALL BE REQUIRED ON DRIVEWAYS IN EXCESS OF 150 FEET OF SURFACE LENGTH AND SHALL BE LOCATED WITHIN 50 FEET OF THE PRIMARY BUILDING. THE MINIMUM TURNING RADIUS FOR A TURNAROUND SHALL BE 40 FEET FROM THE CENTER LINE OF THE DRIVEWAY. IF A HAMMERHEAD/T IS USED, THE TOP OF THE "T" SHALL BE A MINIMUM OF 60 FEET IN

### LEGEND

| EXISTING       |                               | PROPOSED  |
|----------------|-------------------------------|---|
|                | BOUNDARY LINE                 |   |
|                | EASEMENT (ESMT)               |   |
|                | CENTERLINE (CL)               |   |
|                | STORM DRAIN MAIN              | 35LF ~ SD<br>S=1%   |
|                | ROOF DRAIN LATERAL            | 4"SD  |
|                | SANITARY SEWER MAIN           | 35LE ~ SS<br>SS 1%  |
|                | WATER MAIN                    | ——— W ———   |
| <b></b>        | DRAINAGE FLOW LINE            | $\longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow \longrightarrow$ |
|                | SAWCUT                        |   |
| GB GB GB GB-   | GRADE BREAK                   | GB GB GB GB-  |
|                | ACCESSIBLE PATH OF TRAVEL     |   |
| — — —170— —    | MAJOR CONTOUR                 | 170   |
| — — — 167— — — | MINOR CONTOUR                 | 167   |
| X X            | FENCE                         | x x   |
| × 405.46       | SPOT ELEVATION                | TC<br>99.99   |
|                | DRAINAGE FLOW                 | ~~~   |
|                | DROP INLET (DI)               |   |
|                | CURB INLET (CI)               |   |
|                | AREA DRAIN (AD)               | ■ <sup>AD</sup>   |
| 0              | STORM DRAIN MANHOLE (SDMH)    |   |
| 0              | SANITARY SEWER MANHOLE (SSMH) |   |
| ₩              | FIRE HYDRANT (FH)             | ₩   |
| H              | WATER VALVE (WV)              | H   |
|                | CLEANOUT                      |   |

### SHEET INDEX

COVER & GENERAL NOTES

SLOPE MAP

DETAILS & SECTIONS EROSION CONTROL PLAN

GRADING & DRAINAGE PLAN & PROFILE

IS SI 05

AS NOTED SCALE: 11/27/2017 DATE: DESIGN BY: FJC ECH DRAWN BY: CHECKED BY: SHEET NUMBER:

SHEETS


117-133


PROJECT#


TO MARINA PACIFIC GROVE MONTEREY TO SALINAS SITE BEACH LAURELES GRADE ROAD CARMÈL - CARME, PACIFIC CARMEL VALLEY OCEAN CARMEL RIVER

VICINITY MAP

TO BIG SUR







## EROSION CONTROL NOTES

1. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE TO NEIGHBORING PROPERTIES. THE CONTRACTOR SHALL CONFORM TO THE STANDARDS FOR DUST—CONTROL AS ESTABLISHED BY THE AIR QUALITY MAINTENANCE DISTRICT. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: A) PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH. SUFFICIENT WATERING TO CONTROL DUST IS REQUIRED AT ALL TIMES.

B) COVER STOCKPILES OF DEBRIS, SOIL. OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST. C) KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST. D) LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE. THE CONTRACTOR SHALL ASSUME LIABILITY FOR CLAIMS RELATED TO WIND BLOWN MATERIAL. IF THE DUST CONTROL IS INADEQUATE AS DETERMINED BY THE CITY, THE CONSTRUCTION WORK SHALL BE TERMINATED UNTIL CORRECTIVE MEASURES ARE TAKEN.

2. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP STREETS AND ROADS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY, THE CONTRACTOR SHALL REMOVE IT IMMEDIATELY.

3. ALL CUT AND FILL SLOPES EXPOSED DURING CONSTRUCTION SHALL BE COVERED, SEEDED OR OTHERWISE TREATED TO CONTROL EROSION WITHIN 48 HOURS AFTER GRADING. CONTRACTOR SHALL RE-VEGETATE SLOPES AND ALL DISTURBED AREAS THROUGH AN APPROVED PROCESS AS DETERMINED BY THE CITY. THIS MAY CONSIST OF EFFECTIVE PLANTING OF RYE GRASS, BARLEY OR SOME OTHER FAST GERMINATING SEED.

4. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15), THE FOLLOWING MEASURES MUST

BE TAKEN: A) VEGETATION REMOVAL SHALL NOT PRECEDE SUBSEQUENT GRADING OR CONSTRUCTION ACTIVITIES BY MORE THAN 15 DAYS. DURING THIS PERIOD, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE. DISTURBED SURFACES NOT INVOLVED IN THE IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND/OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.

B) ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR THE DOWNHILL PROPERTIES. C) RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE DISTURBED AREA OR SITE.

THESE DRAINAGE CONTROL MEASURES MUST BE MAINTAINED BY THE CONTRACTOR AS NECESSARY TO ACHIEVE THEIR PURPOSE THROUGHOUT THE LIFE OF THE PROJECT. D) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF

EACH DAY AND CONTINUOUSLY CHECKED THROUGHOUT THE LIFE OF THE PROJECT DURING WINTER OPERATIONS. (GRADING/EROSION ORD. 2806-16.12.090)

E) THE GRADING INSPECTOR MAY STOP OPERATIONS DURING PERIODS OF INCLEMENT WEATHER IF EROSION PROBLEMS ARE NOT BEING CONTROLLED ADEQUATELY.

5. IF VEGETATION REMOVAL TAKES PLACE PRIOR TO A GRADING OPERATION AND THE ACTUAL GRADING DOES NOT BEGIN WITHIN 30 DAYS FROM THE DATE OF REMOVAL, THEN THAT AREA SHALL BE PLANTED UNDER THE PROVISION OF SECTION 16.08.340 TO CONTROL EROSION. NO VEGETATION REMOVAL OR GRADING WILL BE ALLOWED WHICH WILL RESULT IN SILTATION OF WATER COURSES OR UNCONTROLLABLE EROSION.

6. ALL POLLUTANTS AND THEIR SOURCES, INCLUDING SOURCES OF SEDIMENT ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION ACTIVITY ARE CONTROLLED;

7. ALL NON-STORM WATER DISCHARGES ARE IDENTIFIED AND EITHER ELIMINATED, CONTROLLED, OR TREATED;

8. SITE BMPS ARE TO BE EFFECTIVE AND RESULT IN THE REDUCTION OR ELIMINATION OF POLLUTANTS IN STORM WATER DISCHARGES AND AUTHORIZED NON-STORM WATER DISCHARGES FROM CONSTRUCTION

9. STABILIZATION BMPS INSTALLED TO REDUCE OR ELIMINATE POLLUTANTS AFTER CONSTRUCTION IS

10. BEST MANAGEMENT PRACTICES (BMPS) TO BE IMPLEMENTED BY THE PROJECT ARE LISTED BY CATEGORY. FACT SHEETS, AND DETAILS FOR THE BMPS SELECTED FOR THIS PROJECT, CAN BE FOUND IN THE CASQA STORMWATER BEST MANAGEMENT PRACTICE HANDBOOK.

### STORMWATER MANAGEMENT

THE FOLLOWING STANDARD BMPS SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE MONTEREY REGIONAL STORMWATER MANAGEMENT PROGRAM:

1. MINIMIZE USE OF OIL-BASED PAINTS

2. STORE SOLVENTS AND PAINTS IN ORIGINAL CONTAINERS OR OTHER FIRE MARSHAL APPROVED CONTAINER. 3. SPENT SOLVENTS ARE HAZARDOUS WASTES. STORE SPENT SOLVENTS IN APPROVED CONTAINERS. REUSE SOLVENTS AS MUCH AS POSSIBLE AND USE PAINTS AS MUCH AS POSSIBLE RATHER THAN DISPOSING OF THEM. DISPOSE OF SPENT SOLVENTS AND UNUSABLE PAINT AS A HAZARDOUS WASTE. 4. NEVER CLEAN PAINT EQUIPMENT WHERE SOLVENTS, PAINT OR CONTAMINATED RINSE WATER CAN ENTER THE STORM DRAIN SYSTEM.

PLASTERING/STUCCO/TILING/SITE-MIXED CONCRETE:

1. STORE PLASTER AND CEMENT IN COVERED AREAS AND KEEP THEM OUT OF THE WIND. 2. CONSERVE MATERIALS. DON'T MIX MORE PRODUCT THAN CAN BE USED BEFORE IT HARDENS. 3. IF THERE IS LEFT OVER PRODUCT, PLACE THE EXCESS IN AN EARTHEN DEPRESSION. LET THE PRODUCT CURE AND DISPOSE OF AS REGULAR REFUSE. 4. ALL RINSE WATER IS TO BE PLACED IN AN EARTHEN DEPRESSION CAPABLE OF HOLDING THE RINSE

WATER AS WELL AS ANY RAIN WATER THAT WOULD FALL/RUN INTO THE DEPRESSION. READY-MIXED CONCRETE:

1. HAVE AN EARTHEN DEPRESSION DUG PRIOR TO THE ARRIVAL OF THE READY—MIX TRUCK. 2. IF A PUMP IS USED, PLACE THE ENTIRE PUMP PRIMING FLUID AND REJECT CONCRETE IN THE 3. PLACE ALL SPILLED CONCRETE AND CHUTE WASH WATER IN THE DEPRESSION.

4. ALL TRUCK AND PUMP RINSE WATER IS TO BE TAKEN BACK TO THE READY—MIX BATCH PLANT FOR 5. BEFORE CREATING AN EXPOSED AGGREGATE FINISH, CAREFULLY PLAN AND PREPARE TO PREVENT THE

SLURRY THAT IS WASHED OFF FROM ENTERING THE STORM DRAIN SYSTEM AND GUTTERS.

EARTH MOVING/GRADING: 1. REMOVE EXISTING VEGETATION ONLY WHEN NECESSARY. 2. PLANT TEMPORARY VEGETATION WHEN SLOPE HAVE BEEN DISTURBED BUT CONSTRUCTION IS STILL ONGOING DURING PERIODS OF RAIN

3. PROTECT DOWN SLOPE DRAINAGE COURSES BY RECOGNIZED METHODS SUCH AS THOSE IN THE CASQA 4. USE CHECK DAMS OR DITCHES TO DIVERT WATER AROUND EXCAVATIONS.

5. COVER STOCKPILES OF EXCAVATED SOIL WITH TARPS. 6. SCHEDULE GRADING ACTIVITIES DURING DRY PERIODS.

REFER TO THE CASQA BMP HANDBOOK FOR BMP FACT SHEETS.

CONTRACTORS STAGING AREA DESIGNATED FOR FOLLOWING STORM WATER BEST MANAGEMENT PRACTICES: SCHEDULING, WATER CONSERVATION PRACTICES, VEHICLE & EQUIPMENT CLEANING, VEHICLE & EQUIPMENT MAINTENANCE, MATERIAL DELIVERY & STORAGE, STOCKPILE MANAGEMENT, SPILL PREVENTION & CONTROL, SOLID WASTE MANAGEMENT, HAZARDOUS WASTE MANAGEMENT, CONCRETE WASTE MANAGEMENT, SANITARY WASTE MANAGEMENT.

### LEGEND

**INLET PROTECTION** (SEE DETAIL A/C5)

PROPOSED DRAINAGE FLOW

FIBER ROLL

### BMP'S

**EROSION CONTROL:** EC-1 SCHEDULING

EC-2 PRESERVATION OF EXISTING VEGETATION

EC-3 HYDRAULIC MULCH EC-4 HYDROSEEDING

EC-8 WOOD MULCHING EC-16 NON-VEGETATIVE STABILIZATION

SE-1 SILT FENCE

SE-2 SEDIMENT BASINS

SE-3 SEDIMENT TRAP SE-5 FIBER ROLL

SE-6 GRAVEL BAG BERM SE-7 STREET SWEEPING AND VACUUMING

SE-8 SANDBAG BARRIER

SE-9 STRAW BALE BARRIER SE-10 STORM DRAIN INLET PROTECTION

SE-13 COMPOST SOCKS AND BERMS

SE-14 BIOFILTER BAGS

TRACKING CONTROL: TC-1 STABILIZED CONSTRUCTION ENTRANCE/EXIT

## WIND EROSION CONTROL: WE-1 WIND EROSION CONTROL

TC-3 ENTRANCE/OUTLET TIRE WASH

NON-STORM WATER MANAGEMENT:

NS-1 WATER CONSERVATION PRACTICES

NS-2 DEWATERING OPERATIONS NS-3 PAVING AND GRINDING OPERATIONS

NS-6 ILLICIT CONNECTION/DISCHARGE

NS-7 POTABLE WATER/IRRIGATION NS-8 VEHICLE AND EQUIPMENT CLEANING

NS-9 VEHICLE AND EQUIPMENT FUELING NS-10 VEHICLE AND EQUIPMENT MAINTENANCE

NS-12 CONCRETE CURING

NS-13 CONCRETE FINISHING NS-14 MATERIAL AND EQUIPMENT USE

### WASTE MANAGEMENT AND MATERIAL

POLLUTION CONTROL: WM-1 MATERIAL DELIVERY AND STORAGE

WM-10 LIQUID WASTE MANAGEMENT


WM-2 MATERIAL USED


WM-3 STOCKPILE MANAGEMENT WM-4 SPILL PREVENTION AND CONTROL

WM-5 SOLID WASTE MANAGEMENT WM-6 HAZARDOUS WASTE MANAGEMENT WM-7 CONTAMINATED SOIL MANAGEMENT

WM-8 CONCRETE WASTE MANAGEMENT WM-9 SANITARY/SEPTIC WASTE MANAGEMENT

REFER TO THE CASQA BMP HANDBOOK FOR BMP FACT SHEETS.





3"-6" COARSE

**AGGREGATE** 

STABILIZE ENTRANCE

Scale 1" = 20'

\_FILTER FABRIC OR SILT SACK DROP INLET PROTECTION (FLUSH)

STRAW BALES (OR EQUAL)

2" X 2" STAKES OR #4 J-BARS, 2 PER BALE

BALE CONFIGURATION

THIS SECTION REMOVED FOR GRAPHICAL REPRESENTATION ONLY. STRAW BALE PERIMETER SHALL BE CONTINUOUS.


CONCRETE WASHOUT

1.- FACE SIGN TOWARD NEAREST


2.— CONCRETE WASHOUT SHALL BE LOCATED BEHIND CURB AND 50 FT. MINIMUM FROM DRAINAGE


STREET OR ACCESS POINT

INLETS OR WATERCOURSES



FIBER ROLL






S. S. S.

r+1

| SCALE:          | AS NOTED   |  |
|-----------------|------------|--|
| DATE:           | 11/27/2017 |  |
| DESIGN BY:      | FJC        |  |
| DRAWN BY:       | ECH        |  |
| CHECKED BY: FJC |            |  |
| SHEET NUMB      | ER:        |  |

PROJECT# 117-133



PRELIMINARY NOT FOR CONSTRUCTION

Fratantoni Design

9


A CUSTOM RESIDENCE FOR HO RIO VISTA LOT

> RCHITECTURAL SITE PLAN

RINT DATE 11.29.17

REVISIONS

A1




**PRELIMINARY** NOT FOR CONSTRUCTION


Fratantoni Design

11.29.17

REVISIONS

HEET NO.






BASEMENT FLOOR PLAN - DIMENSIONED SCALE: 1/4"= 1'-0"

REVISIONS

A5





9

 $\sim$ 

<u>^1</u> \_\_\_\_\_

SHEET NO. **A6.1** 





9


EL

A6.2




# REAR ELEVATION


SCALE: 1/4"=1'-0"



<u>^</u>


A7





SCALE: 1/4"=1'-0"

# COLOR SAMPLES FOR PROJECT FILE NO. PW 170468



Materials: EXTERIOR STUCCO

Colors: <u>DUNN EDWARDS "TAN PLAN" DE6137</u>


Description: ONE COAT SYNTHETIC - SAND FINISH



Materials: ONE PIECE CONC. 'S' TILE

Materials: ONE PIECE CONC. 'S' TILE Colors: "LADERA BLEND" LHC 8710

Description: "CAPISTRANO" ONE PIECE CONCRETE TILE BY EAGLE ROOFING



Materials: PAINTED STEEL GARAGE DOOR Colors: DARK BROWN
Description: ENTREMATIC "OAK SUMMIT" - STYLE "BEAD BOARD", 4-PANEL, NO WINDOW

It is unlawful to alter the substance of any official form or document of Monterey County.

DA Request Form Instructions with Photo Guidelines Rev. 06/24/2015