## Before the Planning Commission in and for the County of Monterey, State of California

In the matter of the application of:

**THOMAS (PLN180039)** 

#### **RESOLUTION NO. 18-044**

Resolution by the Monterey County Planning Commission:

- Considering an addendum to the to the Santa Lucia Environmental Impact Report (EIR #94-005/Resolution #96-059) pursuant to CEOA Guidelines Section 15164; and
- 2) Approving a Combined Development Permit consisting of:
  - a) Administrative Permit and Design Approval to allow the construction of an approximately 3,995 square foot single family dwelling with 2,610 square foot basement, and an approximately 875 square foot 2-car detached garage with office: and
  - b) Use Permit to allow the removal of five protected trees (4 Oaks and 1 Madrone)
- 3) Adopting the Mitigation Monitoring and Reporting Program.

[PLN180039, Thomas, 28 Potrero Trail, Carmel, Greater Monterey Peninsula Area Plan (APN: 239-111-009-000)

The Thomas application (PLN180039) came on for public hearing before the Monterey County Planning Commission on November 14, 2018. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Planning Commission finds and decides as follows:

#### **FINDINGS**

1. **FINDING: CONSISTENCY** – The Project, as conditioned, is consistent with the

applicable plans and policies which designate this area as appropriate

for development.

**EVIDENCE:** a) During the course of review of this application, the project has been reviewed for consistency with the text, policies, and regulations in:

- The 2010 Monterey County General Plan;
- Greater Monterey Peninsula Area Plan
- Monterey County Zoning Ordinance (Title 21);
- The Santa Lucia Preserve Subdivision Environmental Impact Report

- No conflicts were found to exist. No communications were received during the course of review of the project indicating any inconsistencies with the text, policies, and regulations in these documents.
- b) The proposed project is a Combined Development Permit consisting of:
  a) Administrative Permit and Design Approval to allow the construction
  of an approximately 3,995 square foot single family dwelling with 2,610
  square foot basement, and an approximately 875 square foot 2-car
  detached garage with office; and b) A Use Permit to allow the removal
  of five trees (4 Oaks and 1 Madrone).
- c) The property, a 29.56 acre parcel, is located at 28 Potrero Trail, Carmel (Assessor's Parcel Number APN 239-111-009-000), Greater Monterey Peninsula Area Plan. The parcel is zoned Resource Conservation, 40 acres per unit with Design Control, Site Plan Review district overlays (RC/40-D-S). A single-family dwelling is allowed in the RC land use category, and the S overlay requires an Administrative Permit per section 21.45.040 of the Monterey County Zoning Ordinance. Therefore, the project is an allowed land use for this site.
- d) The project site is within a Design Control (D) District overlay which requires additional design review of proposed structures to assure protection of the public viewshed, neighborhood character, and to assure the visual integrity of certain developments without imposing undue restrictions on private property. The project has been designed to blend with the natural environment consistent with other homes in the Santa Lucia Preserve, and the proposed structures are not visible from any public viewing area. Colors and materials, comprised dark brown shiplap and earthy tone stone siding, non-reflective charcoal metal seam roofing, and metal clad windows and doors are consistent with the surrounding character of the neighborhood and blend with the natural landscape of the property. Additionally, the design was reviewed and approved by the Santa Lucia Preserve Design Review Board.
- e) The project site is within a Site Plan Review (S) district overlay, which is intended to provide district regulations where development, by reason of its location has the potential to adversely affect or be adversely affected by natural resources or site constraints, without imposing undue restrictions on private property. A site plan was included with the application. The project is proposed within a designated homeland boundary and has been appropriately sited to avoid development on slopes in excess of 30% slope while also minimizing removal of protected trees; therefore, the project is consistent with requirements of the S district overlay.
- f) The project planner conducted a site inspection on May 4, 2018 to verify that the project on the subject parcel conforms to the plans listed above.
- g) The project is consistent with required tree removal findings for the Santa Lucia Preserve Subdivision Environmental Impact Report. (An addendum has been prepared to address minor technical changes to the EIR). See Finding 6 and Finding 7.
- h) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN180039.

2. **FINDING: SITE SUITABILITY** – The site is physically suitable for the use proposed.

recommended have been incorporated.

EVIDENCE: a) The project has been reviewed for site suitability by the following departments and agencies: RMA- Planning, Monterey County Regional Fire Protection District, RMA-Public Works, RMA-Environmental Services, Environmental Health Bureau, and Water Resources Agency. There has been no indication from these departments/agencies that the site is not suitable for the proposed development. Conditions

- b) Staff identified potential impacts to Soil/Slope Stability, and Trees. The following reports have been prepared:
  - "Geotechnical Investigation for the Proposed Thomas Residence," (LIB180192) prepared by Haro, Kasunich and Associates, Inc., Carmel, CA, October, 2017.
  - "Project Impact Analysis Tree Protection Plan Santa Lucia Preserve Lot 195" (LIB180190) prepared by Maureen Hamb-WCISA Certified Arborist, Santa Cruz, CA, March 2018.

The above-mentioned technical reports by outside consultants indicated that there are no physical or environmental constraints that would indicate that the site is not suitable for the use proposed. County staff has independently reviewed these reports and concurs with their conclusions.

- c) Staff conducted a site inspection on May 4, 2018 to verify that the site is suitable for this use.
- d) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA Planning for the proposed development found in Project File PLN180039.
- 3. **FINDING:**

**HEALTH AND SAFETY -** The establishment, maintenance, or operation of the use or structure applied for, will not, under the circumstances of the particular case, be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use; or be detrimental or injurious to property and improvements in the neighborhood; or to the general welfare of the County.

**EVIDENCE:** 

- a) The project was reviewed by RMA Planning, Monterey County Regional Fire Protection District, RMA Public Works, Environmental Health Bureau, RMA Environmental Services, and Water Resources Agency. The respective agencies have recommended conditions, where appropriate, to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
- b) Necessary public facilities are available. The project is served by the Santa Lucia Mutual Water system for potable water and an on-site septic system will provide sewage disposal
- c) Staff conducted a site inspection on May 4, 2018 to verify that the site is suitable for this use.

d) The application, project plans, and related support materials submitted by the project applicant to the Monterey County RMA - Planning for the proposed development found in Project File PLN180039.

#### 4. **FINDING:**

**NO VIOLATIONS** - The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision, and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.

#### **EVIDENCE:**

- a) Staff reviewed Monterey County RMA Planning and Building Services Department records and is not aware of any violations existing on subject property.
- b) Staff conducted a site inspection on May 4, 2018 and researched County records to assess if any violation exists on the subject property.
- c) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN180039.

#### 5. **FINDING:**

**CEQA (Addendum): -** An Addendum to a previously certified EIR was prepared pursuant to Code of Regulations, Title 14, Section 15164 to reflect changes or additions in the project that do not cause substantial changes or new information that would require major revisions to the adopted EIR.

#### **EVIDENCE:**

- An Environmental Impact Report for the Santa Lucia Preserve Subdivision of the Santa Lucia Preserve was prepared and certified by the Board of Supervisors February 6, 1996 (EIR #94-005/Resolution #96-059).
- b) An Addendum to the Environmental Impact Report for the Santa Lucia Preserve Subdivision of the Santa Lucia Preserve was prepared for this project pursuant to Code of Regulations, Title 11, Section 15162 (CEQA Guidelines).
- c) Pursuant to the California Environmental Quality Act (CEQA) Guidelines Section 15162, when an EIR has been certified, no subsequent EIR shall be prepared for the project unless the agency determines that substantial changes are proposed which require major revisions or substantial changes occur with respect to the circumstances under which the project is undertaken due to new significant environmental effects. In this case, no new information has been presented to warrant further environmental review. The proposed structures are within a designated building envelope, and the proposed tree removal is within the overall tree removal analyzed for the subdivision.
- d) The Forest Management Plan prepared by Ralph Osterling for the Environmental Impact Report (EIR) in 1994 for Phase C provided specific tree removal estimates for each lot created by the subdivision. The Thomas parcel, Lot 195 had an estimated removal of 0 protected trees. The addendum was prepared to address impacts related to the removal of 5 protected trees for the Thomas project.
- e) The project includes the construction of a 3,995 square foot single family dwelling with 2,610 square foot basement, and an approximately

- 875 square foot 2-car detached garage with office; and removal of five trees (4 oaks and 1 madrone).
- The subject application requests the removal of five protected trees (4 oaks and 1 madrone) to accommodate the construction of the singlefamily dwelling. The project is consistent with all tree removal conditions pursuant to Use Permit PC94067 (Resolution No. 96-060) for the Santa Lucia Preserve Subdivision. As part of the EIR, removal of 1480 trees was approved for the subdivision (Phase A-C) and determined to be less than significant. To date, 621 trees have been approved for removal. If approved, the estimated 5 trees proposed for removal on Lot 195 would constitute less than 0.3% percent of the total trees approved for removal within the homeland boundary. The approval of the 5 trees proposed for this lot would account for an updated total of 626 trees, which would represent approximately 42% of the overall approved count for the subdivision. As a whole, even though 133 of 254 lots have been built out, the Santa Lucia Preserve Subdivision (Phase A-C/Rancho San Carlos) is well under the tree removal approved and analyzed by the EIR and will remain under the approved tree removal limits if remaining lots stay within the allowed tree removal. Though the tree removal amount proposed (5) exceeds what was approved for this lot (0), it is consistent with what was analyzed in the Santa Lucia Preserve EIR. The applicable conditions of approval from the original EIR have been incorporated into the proposed Thomas project. An Addendum to the EIR is also included as part of this project.
- g) Pursuant to Condition #24 of the Use Permit (PC94067), tree replacement for non-landmark trees are to be replaced at a 3:1 ratio, and landmark trees are to be replaced at a 5:1 ratio. The project, as conditioned, will result in the replanting of 15 oak trees and 3 madrones.
- h) No adverse environmental effects were identified during staff review of the development application during a site visit on May 4, 2018.
- i) Staff conducted a site inspection to verify that the site and proposed project meet the criteria for an exemption.
- j) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN180039.

#### 6. **FINDING:**

SANTA LUCIA PRESERVE SUBDIVISION (PHASE A, B & C) TREE REMOVAL – The project is consistent with all tree removal conditions pursuant to Use Permit PC94067 (Resolution 96-060) for the Santa Lucia Preserve Subdivision.

**EVIDENCE:** 

- The project proposes the removal of 5 trees. The tree amount indicated for the property was not assessed for tree removal in the Santa Lucia Forest Management Plan (FMP) by Ralph Osterling. According to the FMP, zero trees were assessed for removal. The Maximum Tree Removal List approves 0 trees for removal on the lot, therefore the application is before Planning Commission to consider approval.
- b) The tree permit for the Santa Lucia Preserve (Phases A-C) allowed removal of 1,480 trees. The removal of these 5 trees will bring the total number of trees removed to 626.

- The project requires an addendum to the Santa Lucia Preserve EIR. Though the tree removal amount proposed exceeds what was approved for the lot, it is consistent with what was analyzed in the Sant Lucia Preserve EIR (Resolution No. 94-005).
- d) Pursuant to Condition No. 24 in Use Permit PC94067, tree replacement for non-landmark trees are to be replaced at a 3:1 ratio, and landmark trees are to be replaced at a 5:1 ratio. The project, as conditioned, will result in the replanting of 15 oak trees. totaling eight (8) fifteen gallons and seven (7) 5 gallons. No madrones have been recommended for replacement. Per the arborist, Maureen Hamb, native madrone are difficult to propagate and usually have a 90% loss rate. There are cultivars (Arbutus Marina) but, it is a landscape type species that does not have the quality of the natives. Coast live oak is the dominant species on the site and would have a greater success rate and are easier to propagate. The replacement of the coast live oaks is more suitable given the condition of this site. However, 3 additional madrones will be planted without the requirement of monitoring and reporting.
- e) The reforestation program shall also include a monitoring element that guarantees a success period of not less than 5 years after planting and a success ratio threshold of no less than 90%. A condition of project approval, (Condition No. 6) requiring the replacement/replanting of all removed trees has been applied to the project.
- f) A condition of project approval (Condition No. 4) for surrounding trees located close to the construction site shall be protected from construction equipment by fencing off the canopy driplines and/or critical root zones with protective materials.
- Gounty Zoning Ordinance, Title 21, (Preservation of Oak and Other Protected Trees) of the Monterey County Zoning Ordinance, no oak, madrone or redwood tree six inches or more in diameter two feet above ground level shall be removed without approval of the permit(s) required in Subsection 21.64.260D. Based on substantial evidence, the tree removal is the minimum required under the circumstance of the case and the removal will not involve a risk of adverse environmental impacts.
- 7. **FINDING: APPEALABILITY -** The decision on this project may be appealed to the Board of Supervisors.
  - **EVIDENCE:** a) Section 21.80.040 of the Monterey County Zoning Ordinance states that the proposed project is appealable to the Board of Supervisors.

#### **DECISION**

**NOW, THEREFORE**, based on the above findings and evidence, the Planning Commission does hereby:

- 1. Consider an Addendum to the Santa Lucia Environmental Impact Report (EIR #94-005/Resolution #96-059) pursuant to CEQA Guidelines Section 15164; and
- 2. Adopt a resolution to approve a Combined Development Permit consisting of:

- a) Administrative Permit and Design Approval to allow the construction of an approximately 3,995 square foot single family dwelling with 2,610 square foot basement, and an approximately 875 square foot 2-car detached garage with office; and
- b) Use Permit to allow the removal of 5 protected trees (4 oaks, 1 madrone), all of which are in general conformance with the attached sketch and subject to the attached conditions, all being attached hereto and incorporated herein by reference.
- 3. Adopting the Mitigation Monitoring and Reporting Program.

**PASSED AND ADOPTED** this 14th day of November, 2018 upon motion of Commission Diehl, seconded by Commissioner Wizard, by the following vote:

AYES: Coffelt, Duflock, Diehl, Getzelman, Gonzalez, Mendoza, Roberts, Vandevere,

Wizard

NOES: None ABSENT: Ambriz ABSTAIN: None

Jacqueline R. Onciano, Planning Commission Secretary

COPY OF THIS DECISION MAILED TO APPLICANT ON NOV 2 0 2018

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE NOV 3 0 2018

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

#### **NOTES**

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.

Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from Monterey County RMA-Planning and RMA-Building Services Department office in Salinas.

2. This permit expires 3 years after the above date of granting thereof unless construction or use is started within this period.

Form Rev. 5-14-2014

### **Monterey County RMA Planning**

## Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN180039

#### 1. PD001 - SPECIFIC USES ONLY

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Development permit (PLN180039) consisting of: Combined Administrative Permit and Design Approval to allow the construction of a 3,995 square foot single 2,610 square 875 square dwelling with foot basement, garage/office; and 2) Use Permit for removal of five trees (4 Oaks and 1 Madrone) . located at 28 Potrero Trail (Assessor's Parcel property is Number 239-111-009-000), Greater Monterey Peninsula Area Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the Director of RMA - Planning. construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

#### 2. PD002 - NOTICE PERMIT APPROVAL

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

The applicant shall record a Permit Approval Notice. This notice shall state:

"A Combined Development Permit (Resolution Number 18-044) was approved by the Planning Commission for Assessor's Parcel Number 239-111-009-000 on November 14, 2018. The permit was granted subject to 20 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

PI N180039

Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

Print Date: 11/15/2018 11:01:02AM Page 1 of 8

#### 3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

#### **Responsible Department:**

RMA-Planning

#### Condition/Mitigation Monitoring Measure:

during course of construction, cultural, archaeological, historical paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a archaeologist an archaeologist registered with the (i.e., Professional Archaeologists) shall be immediately contacted by the individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.

(RMA - Planning)

#### Compliance or Monitoring Action to be Performed:

The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

#### 4. PD011 - TREE AND ROOT PROTECTION

#### Responsible Department:

RMA-Planning

#### Condition/Mitigation Monitoring Measure:

Trees which are located close to construction site(s) shall be protected from inadvertent damage from construction equipment by fencing off the canopy driplines and/or critical root zones (whichever is greater) with protective materials, wrapping trunks with protective materials, avoiding fill of any type against the base of the trunks and avoiding an increase in soil depth at the feeding zone or drip-line of the retained trees. Said protection, approved by certified arborist, shall be demonstrated prior to issuance of building permits subject to the approval of RMA - Director of Planning. If there is any potential for damage, all work must stop in the area and a report, with mitigation measures, shall be submitted by certified arborist. Should any additional trees not included in this permit be harmed, during grading or construction activities, in such a way where removal is required, the owner/applicant shall obtain required permits. (RMA - Planning)

#### Compliance or Monitoring Action to be Performed:

Prior to issuance of grading and/or building permits, the Owner/Applicant shall submit evidence of tree protection to RMA - Planning for review and approval.

During construction, the Owner/Applicant/Arborist shall submit on-going evidence that tree protection measures are in place through out grading and construction phases. If damage is possible, submit an interim report prepared by a certified arborist.

Prior to final inspection, the Owner/Applicant shall submit photos of the trees on the property to RMA-Planning after construction to document that tree protection has been successful or if follow-up remediation or additional permits are required.

Print Date: 11/15/2018 11:01:02AM Page 2 of 8

#### 5. PD011(A) - TREE REMOVAL

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Tree removal shall not occur until a construction permit has been issued in conformance with the appropriate stage or phase of development in this permit. Only those trees approved for removal shall be removed. (RMA-Planning)

Compliance or Monitoring Action to be Performed:

Prior to tree removal, the Owner/ Applicant/ Tree Removal Contractor shall demonstrate that a construction permit has been issued prior to commencement of tree removal.

#### 6. PD048 - TREE REPLACEMENT/RELOCATION

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Condition carried forward from Resolution No. 96-060, Condition No. 24 in Use Permit PC94067.

Prior to final inspection, the applicant shall replace and or relocate each tree approved for removal as follows:

- Replacement ratio recommended by arborist: 3:1 (replacement of 3 trees for every 1 removed), for a total of 15 oaks, with (7) -5 gallons & (8) -15 gallons.
- 3 madrones (no monitor or reporting is required for the madrones)

Replacement tree(s) shall be located within the homeland boundaries, refer to Tree Replacement Plan prepared by Bliss Landscape Architecture.

(RMA - Planning)

Compliance or Monitoring Action to be Performed:

The Owner/Applicant shall submit evidence of tree replacement to RMA-Planning for review and approval. Evidence shall be a receipt for the purchase of the replacement tree(s) and photos of the replacement tree(s) being planted.

Six months after the planting of the replacement tree(s), the Owner/Applicant shall submit evidence demonstrating that the replacement tree(s) are in a healthy, growing condition.

One year after the planting of the replacement of the oak tree(s), the Owner/Applicant shall submit a letter prepared by a County-approved tree consultant reporting on the health of the replacement tree(s) and whether or not the tree replacement was successful or if follow-up remediation measures or additional permits are required. This reporting shall be done yearly for five years.

Print Date: 11/15/2018 11:01:02AM Page 3 of 8

#### 7. CC01 INDEMNIFICATION AGREEMENT

Responsible Department:

County Counsel

Condition/Mitigation Monitoring Measure:

The property owner agrees as a condition and in consideration of approval of this discretionary development permit that it will, pursuant to agreement and/or statutory provisions as applicable, including but not limited to Government Code Section 66474.9, defend, indemnify and hold harmless the County of Monterey or its agents, officers and employees from any claim, action or proceeding against the County or its agents, officers or employees to attack, set aside, void or annul this approval, which action is brought within the time period provided for under law, including but not limited to, Government Code Section 66499.37, as applicable. The property owner will reimburse the County for any court costs and attorney's fees which the County may be required by a court to pay as a result of such action. The County may, at its sole discretion, participate in the defense of such action; but such participation shall not relieve applicant of his/her/its obligations under this condition. An agreement to this effect shall be recorded upon demand of County Counsel or concurrent with the issuance of building permits, use of property, filing of the final map, recordation of the certificates of compliance whichever occurs first and as applicable. The County shall promptly notify the property owner of any such claim, action or proceeding and the County shall cooperate fully in the defense thereof. If the County fails to promptly notify the property owner of any such claim, action or proceeding or fails to cooperate fully in the defense thereof, the property owner shall not thereafter be responsible to defend, indemnify or hold the County harmless. (County Counsel)

Compliance or Monitoring Action to be Performed: Upon demand of County Counsel or concurrent with the issuance of building permits, use of the property, recording of the final/parcel map, or recordation of Certificates of Compliance, whichever occurs first and as applicable, the Owner/Applicant shall submit a signed and notarized Indemnification Agreement to the County Counsel for review and signature by the County.

Proof of recordation of the Indemnification Agreement, as outlined, shall be submitted to the Office of County Counsel.

#### 8. AS-BUILT CERTIFICATION

Responsible Department:

**Environmental Services** 

Condition/Mitigation
Monitoring Measure:

Prior to final inspection, the applicant shall provide a letter from a licensed engineer certifying that all development has been constructed in accordance with the recommendations in the Geotechnical Investigation and the approved Grading and Stormwater Control Plans. (RMA- Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to final inspection, the owner/applicant shall provide RMA-Environmental Services a letter from a licensed professional engineer.

Print Date: 11/15/2018 11:01:02AM Page 4 of 8

#### 9. EROSION CONTROL PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit an Erosion Control Plan in conformance with the requirements of Monterey County Code Chapter 16.12. The Erosion Control Plan shall include a construction entrance, concrete washout, stockpile area(s), material storage area(s), portable sanitation facilities and waste collection area(s), as applicable. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or building permits, the applicant shall submit an Erosion Control Plan to RMA-Environmental Services for review and approval.

#### 10. GEOTECHNICAL REVIEW CERTIFICATION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall provide certification from the licensed practitioner that the geotechnical recommendations have been incorporated into the Grading Plan and Stormwater Control Plan. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of the construction permit, the applicant shall provide certification from the licensed practitioner(s).

#### 11. GRADING PLAN (<5,000 CY)

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit a grading plan incorporating the recommendations in the project Geotechnical Investigation prepared by Haro, Kasunich and Associates, Inc., dated October 2017. The grading plan shall include contour intervals and cross-sections that identify the existing grade, proposed grade, and the extent of any proposed excavation and/or fill. The grading plan shall include the geotechnical inspection schedule that identifies when the inspections will be completed, who will conduct the inspection (i.e., PG, PE, and/or Special Inspector), a description of the required inspection, inspector name, and the completion date. The applicant shall also provide certification from the licensed practitioner that the grading plan incorporates their geotechnical recommendations. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or building permits, the applicant shall submit a Grading Plan to RMA-Environmental Services for review and approval.

Prior to issuance of any grading or building permits, the applicant shall submit certification from a licensed practitioner that they have reviewed the Grading Plan for conformance with the geotechnical recommendations.

Print Date: 11/15/2018 11:01:02AM Page 5 of 8

#### 12. INSPECTION-DURING ACTIVE CONSTRUCTION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall schedule an inspection with RMA-Environmental Services to inspect drainage device installation, review the maintenance and effectiveness of BMPs installed, and to verify that pollutants of concern are not discharged from the site. At the time of the inspection, the applicant shall provide certification that all necessary geotechnical inspections have been completed to that point. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed:

During construction, the applicant shall schedule an inspection with RMA-Environmental Services.

#### 13. INSPECTION-FOLLOWING ACTIVE CONSTRUCTION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall schedule an inspection with RMA-Environmental Services to ensure all disturbed areas have been stabilized and all temporary erosion and sediment control measures that are no longer needed have been removed. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to final inspection, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

#### 14. INSPECTION-PRIOR TO LAND DISTURBANCE

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall schedule an inspection with RMA-Environmental Services to ensure all necessary sediment controls are in place and the project is compliant with Monterey County regulations. This inspection requirement shall be noted on the Erosion Control Plan. (RMA – Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to commencement of any land disturbance, the owner/applicant shall schedule an inspection with RMA-Environmental Services.

#### 15. STORMWATER CONTROL PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall provide a stormwater control plan to mitigate on-site and off-site impacts from impervious surface stormwater runoff. Drainage improvements shall be constructed in accordance with plans approved by RMA-Environmental Services. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to issuance of any grading or building permits, the applicant shall submit a Stormwater Control Plan to RMA-Environmental Services for review and approval.

Print Date: 11/15/2018 11:01:02AM Page 6 of 8

#### 16. PW0044 - CONSTRUCTION MANAGEMENT PLAN

Responsible Department: RMA-Public Works

Condition/Mitigation Monitoring Measure:

The applicant shall submit a Construction Management Plan (CMP) to RMA-Planning and RMA - Public Works for review and approval. The CMP shall include measures to minimize traffic impacts during the construction/grading phase of the project.

CMP shall include, at a minimum, duration of the construction, hours of operation, truck routes, estimated number of truck trips that will be generated, number of construction workers, and on-site/off-site parking areas for equipment and workers and locations of truck staging areas. Approved measures included in the CMP shall be implemented by the applicant during the construction/grading phase of the project.

Compliance or Monitoring Action to be Performed: 1. Prior to issuance of the Grading Permit or Building Permit, Owner/Applicant/Contractor shall prepare a CMP and shall submit the CMP to the RMA-Planning Department and the

Department of Public Works for review and approval.

2. On-going through construction phases Owner/Applicant/Contractor shall implement the

approved measures during the construction/grading phase of the project.

#### 17. WRSP01 - STORMWATER RUNOFF CONTROL PLAN - SANTA LUCIA PRESERVE

Responsible Department: Water Resources Agency

Condition/Mitigation Monitoring Measure:

The applicant shall provide a stormwater runoff control plan, prepared by a registered civil engineer or licensed architect, to mitigate on-site and off-site impacts from owner/applicant impervious surface stormwater runoff. The shall measures to control stormwater runoff in a manner consistent with the Santa Lucia The SLP Subdivision project requires that new Preserve (SLP) Subdivision project. development including impervious surfaces include measures to ensure stormwater runoff is dispersed over vegetated slopes and conveyed by impervious conduits to existing detention/retention basins, as appropriate. The Water Resources Agency is in receipt of a preliminary grading and drainage plan prepared by C3 Engineering, dated 03/29/18, which diverts storm water around the building, appropriately collects and disperses to dispersion structures. Through these improvements all impervious surface stormwater runoff shall be collected and conveyed to dispersion measures throughout the site and away from any septic leachfields. A registered civil engineer shall design a final stormwater runoff control plan to the satisfaction of the Water Resources Agency. (Water Resources Agency)

Compliance or Monitoring Action to be Performed:

Prior to issuance of any construction permit, the owner/applicant shall submit a stormwater runoff control plan with the construction permit application.

The RMA-Building Services Department will route a plan set to the Water Resources Agency for review and approval.

Print Date: 11/15/2018 11:01:02AM Page 7 of 8

#### 18. WRSP02 - WRA INSPECTION - PRIOR TO FINAL

Responsible Department: Water Resources Agency

Condition/Mitigation Monitoring Measure:

The applicant shall schedule an inspection with the Water Resources Agency to ensure all necessary stormwater runoff control. Prior to final inspection, the owner/applicant shall submit a certification letter to the Water Resources Agency certifying the stormwater runoff measures have been installed in accordance with the plans approved by the Water Resources Agency. (Water Resources Agency)

Compliance or Monitoring Action to be Performed: Prior to final inspection, the owner/applicant shall submit a certification letter to, and schedule an inspection with, the Water Resources Agency.

#### 19. PD006(A) - CONDITION COMPLIANCE FEE

Responsible Department: RMA-Planning

Condition/Mitigation
Monitoring Measure:

The Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors, for the staff time required to satisfy conditions of approval. The fee in effect at the time of payment shall be paid prior to clearing any conditions of approval.

Compliance or Monitoring Action to be Performed: Prior to clearance of conditions, the Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors.

#### 20. PD006 - CONDITION OF APPROVAL / MITIGATION MONITORING PLAN

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure: The applicant shall enter into an agreement with the County to implement a Condition of Approval/Mitigation Monitoring and/or Reporting Plan (Agreement) in accordance with Section 21081.6 of the California Public Resources Code and Section 15097 of Title 14, Chapter 3 of the California Code of Regulations. Compliance with the fee schedule adopted by the Board of Supervisors for mitigation monitoring shall be required and payment made to the County of Monterey at the time the property owner submits the signed Agreement. The agreement shall be recorded. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

Within sixty (60) days after project approval or prior to the issuance of building and grading permits, whichever occurs first, the Owner/Applicant shall:

- 1) Enter into an agreement with the County to implement a Condition of Approval/Mitigation Monitoring Plan.
- 2) Fees shall be submitted at the time the property owner submits the signed Agreement.
- 3) Proof of recordation of the Agreement shall be submitted to RMA-Planning.

Print Date: 11/15/2018 11:01:02AM Page 8 of 8

THOMAS RESIDENCE SANTA LUCIA PRESERV CARMEL VALLEY, CA

TITLE SHEET



2018-05-07 1/4" = 1'-0" AW Project Number

A0.0

**ARCHITECT** 

Tom Meaney

(805) 966-7668

LIC. #C14606

629 State Street, Suite 240

LANDSCAPE ARCHITECT

1312 PATCH COURT

MARINA, CA 93933 (831) 251-8551

BLISS LANDSCAPE ARCHITECTURE

Santa Barbara, CA 93101

SURVEYOR

(831) 394-4930

CIVIL ENGINEER

(831) 647-1192

CENTRAL COAST SURVEYORS


5 HARRIS COURT, SUITE N-11

126 BONAFACIO PLACE, SUITE C

MONTEREY, CA 93940

C3 ENGINEERING INC.

MONTEREY, CA 93940



M MEANEY ARCHITE

IMAS RESIDENCE TA LUCIA PRESERVE IMEL VALLEY, CA

SITE PLAN




Date 2018-04-02

Scale 1" = 20'-0"

Drawn AW

Job # Project


A1.1



Date Scale Drawn Job#

orawn
ob #


A2.0



BASEMENT FLOOR PLAN

**THOMAS RESIDENCE** SANTA LUCIA PRESERVE CARMEL VALLEY, CA

> BASEMENT FLOOR PLAN




Date
Scale
Drawn
Job #


A2.0B

1/8" = 1'-0"

FLOOR PLANS



As indicated



TOMMEANEY ARCHITECT

TOSUITE 240 SANTA BARBARA © CA © 93101 © TEL (CA

THOMAS RESIDENCE SANTA LUCIA PRESERV CARMEL VALLEY, CA

LOWER FLOOR PLAN






LOWER FLOOR PLAN



2018-02-27 1/4" = 1'-0"



I.C.F. EXTERIOR WALL ABOVE GRADE NUDURA 6" ICF BLOCK WITH STONE OR WOOD SIDING I.C.F. BASEMENT WALL NUDURA 8" ICF BLOCK WITH WATERPROOF MEMBRANE

WALL LEGEND

2x6 WOOD STUD WITH STONE OR WOOD SIDING


INTERIOR WALLS


2X4 WOOD STUD WALL W/ 5/8" GYPBOARD BOTH SIDES

2X6 WOOD STUD WALL W/ 5/8" GYPBOARD BOTH SIDES


**LOWER FLOOR PLAN** 

2018-02-27 1/4" = 1'-0"





# **GARAGE OFFICE PLAN** 1/4" = 1'-0"



### WALL LEGEND

I.C.F. EXTERIOR WALL ABOVE GRADE

NUDURA 6" ICF BLOCK WITH STONE OR WOOD SIDING

I.C.F. BASEMENT WALL

NUDURA 8" ICF BLOCK WITH WATERPROOF MEMBRANE


2x6 WOOD STUD WITH STONE OR WOOD SIDING

INTERIOR WALLS

2X4 WOOD STUD WALL W/ 5/8" GYPBOARD BOTH SIDES


2X6 WOOD STUD WALL W/ 5/8" GYPBOARD BOTH SIDES


**GARAGE FLOOR PLAN** 



Date
Scale
Drawn
Job #

A3.1






**ROOF PLAN** 

1/8" = 1'-0"








**GARAGE ROOF PLAN** 

1/4" = 1'-0"



TOMMEANEY ARCHITECT

629 STATE STREET 
SUITE 240 
SANTA BARBARA 
CA 
93101 
TEL (CA


THOMAS RESIDENCE SANTA LUCIA PRESER\ CARMEL VALLEY, CA


ROOF PLAN



Date 20
Scale 1/4
Drawn
Job #

A3.1B







MAIN FLOOR REFLECTED CEILING PLAN





Date Scale Drawn

A4.1E









TOM MEANEY ARCHIT

SANTA LUCIA PRESERVE

BUILDING SECTIONS



Date 2018-02

Scale 1/4" = 1

Drawn


Job # Proj

A5.1

2018-02-27 1/4" = 1'-0"


Date Scale Drawn Job #

A5.2



**EAST - WEST @ UPPER WING** 

1/4" = 1'-0"



1/8" = 1'-0"


2018-02-27

As indicated

Project Number

EXTERIOR ELEVATIONS

STATE STREET • SUITE 240 (SANTABARBARA)805.96



NORTH ELEVATION, HOUSE AND GARAGE

1/4" = 1'-0"

TOMMEANEY ARCHITEC


ARCHITEC

ARCHITEC

(SANTABARBARA) 805.966.7668 © FAX 805.966.7698 © WWW

THOMAS RESIDENCE SANTA LUCIA PRESERVE

EXTERIOR ELEVATIONS



Date 2018-02-27

Scale 1/4" = 1'-0"

Drawn AW

Job # Project
Number

A6.2

TOMMEANEY ARCHITECT


ARCHITECT

ARCHITECT

(SANTABARBARA • CA • 93101 • TEL (CARM (SANTABARBARA • CA • 93101 • TEL (CARM (SANTABARBARA)805.966.7668 • FAX 805.966.7698 • WWW.TOMMEAN

SANTA LUCIA PRESERVE

EXTERIOR ELEVATIONS



Date 2018-02-27


Scale 1/4" = 1'-0"

Drawn AW

Job # Project

Number

A6.3



TOM MEANEY ARCHITECT

THOMAS RESIDENCE SANTA LUCIA PRESERVE

EXTERIOR ELEVATIONS



2018-02-27
ale 1/4" = 1'-0"
AW

Project

A6.4

WINDO	OW SCH	EDULE				DOOR		DULE					
MARK	TYPE MARK	WIDTH	HEIGHT		DESCRIPTION	MARK	TYPE MARK	WIDTH		T PANEL FRAME	Ξ	DESCRIPTION	
0A 0B			3' - 6" 3' - 6"	7' - 0" TEMP. OUTSWING EGRESS 7' - 0" TEMP. OUTSWING EGRESS		001 002		2' - 6" 2' - 6"	7' - 0" 7' - 0"				
1A 1B			6' - 0" 6' - 0"	8' - 0" 8' - 0"		101	A B	8' - 6" 6' - 0"	8' - 0" 8' - 0"		ENTRY, FIXED SIDE	LITES	
1C		2' - 0" 2' - 0"	3' - 3" 3' - 3"	8' - 0" 8' - 0"		103 104	С	3' - 0" 6' - 0"	9' - 0" 9' - 0"				
1E	В	6' - 0"	6' - 0"	8' - 0"		105	В	6' - 0"	9' - 0"		FIXED		
1F 1G		2' - 0"	3' - 6" 3' - 6"	8' - 0" 8' - 0"		106 107	C D	3' - 0" 8' - 0"	9' - 0" 9' - 6"		FIXED		
1H		6' - 0" 2' - 0"	6' - 0" 3' - 6"	8' - 0" 8' - 0"		108 109	E E	6' - 0" 6' - 0"	8' - 0" 8' - 0"		FIXED		
1J	В	6' - 0"	6' - 0"	8' - 0"		110	В	3' - 0"	7' - 0"		111111111111111111111111111111111111111		
1L	В	9' - 0" 6' - 0"	6' - 0" 6' - 0"	9' - 6" 9' - 6"		111 112	B D	3' - 0" 8' - 0"	7' - 0" 9' - 6"				
1M 2A		6' - 0" 6' - 0"	6' - 0" 6' - 0"	9' - 6" 8' - 10"		113 114		3' - 6" 3' - 0"	8' - 0" 7' - 0"				
2B		6' - 0" 2' - 0"	4' - 4" 3' - 3"	7' - 0" 7' - 0"		115 116		5' - 0" 2' - 6"	7' - 0" 7' - 0"				
2D	D	6' - 0"	4' - 4"	7' - 0"		117		2' - 6"	7' - 0"				
2E 2F		2' - 0" 2' - 0"	3' - 3"	7' - 0" 7' - 0"		118 118		3' - 0" 2' - 6"	7' - 0" 7' - 0"				
2G 2H			3' - 6" 3' - 6"	7' - 0" 7' - 0"		119 120		2' - 6" 2' - 0"	7' - 0" 6' - 8"				
21	D	6' - 0"	4' - 4"	7' - 0"		121		2' - 2"	6' - 8"				
2K	С	2' - 0"	3' - 6" 3' - 6"	7' - 0" 7' - 0"		122 123		2' - 6" 3' - 0"	7' - 0" 6' - 8"				
2L 2M			4' - 4" 4' - 4"	7' - 0" 7' - 0"		201		2' - 6" 5' - 0"	6' - 8" 7' - 0"				
4D	С		2' - 6" 2' - 6"	6' - 6" 6' - 6"		203 204		2' - 6" 5' - 0"	6' - 8" 7' - 0"				
4F	D		4' - 4"	7' - 0"		205	В	5' - 0"	7' - 0"				
						206 207		3' - 0" 2' - 6"	7' - 0" 7' - 0"				
						208 209		3' - 0" 3' - 6"	7' - 0" 7' - 0"				
						210 211		2' - 6" 2' - 0"	7' - 0" 6' - 8"				
						212		5' - 0"	7' - 0"				
						213 501	G	3' - 0" 7' - 0"	7' - 0" 6' - 3"				
						502 503	F	8' - 6" 8' - 6"	8' - 3" 8' - 3"				
						504	F	8' - 6"	8' - 3"				
						505	В	6' - 0"	7' - 0"		SOLID WOOD GATE, PLA	ANK	
DOO	R NOTES	S			WINDOW/DOOR GLAZING NOTES								WINDOW LEGEND
1 Δ11	EYTERIOR DOO!	RS - METAL CL	AD EIR SINGI	E COLOR, LOW E U.N.O. PER SCHEDULE. MARVIN INFINITY SERIES DOORS AND	1. GLASS AND GLAZING SHALL CONFORM TO CODE AND WITH U.S. CONS	SLIMED DRODUCT	I SAEETY CO	MMISSION DE	OLUDEMENTS				1/4" = 1'-0"
WIN 2. ALL	DOWS, U.N.O. GLASS DOORS S	SHALL BE CON	ISTRUCTED O	MULTI-PANE (DUAL) TEMPERED GLAZING FOR ALL FIXED & OPERABLE PANELS IS PER CRC R308.4.	2. GLAZING SUBJECT TO HUMAN IMPACT SHALL CONFORM TO CODE AN OPENINGS IN DOORS, FIXED OR OPERABLE PANELS ADJACENT TO A	D WITH U.S. CON	SUMER PRO	DUCT SAFETY	COMMISSION	REQUIREMENTS. GLAZED			
3. ALL HAV	EXTERIOR DOOF	R ASSEMBLIES RAILS NOT LE	S SHALL BE OF ESS THAN 1 3	APPROVED NONCOMBUSTIBLE CONSTRUCTION, OR SOLID CORE WOOD 8" THICK WITH INTERIOR FIELD PANEL THICKNESS NO LESS THAN 1 1/4" THICK,	EITHER VERTICAL EDGE OF THE DOOR IN A CLOSED POSITION AND W WALKING SURFACE AND WITHIN 5 FT. OF THE TOP OR BOTTOM OF ST	HERE THE BOTT AIRS OR LANDING	OM EXPOSEI GS SHALL BE	DEDGE OF THE TEMPERED G	E GLAZING IS GLASS APPRO\	LESS THAN 60 INCHES ABOVE 1	THE D		
4. ALL	SHALL HAVE A FI INTERIOR DOOR DOORS, VERIFY	RS CLEAR VER	TICAL GRAIN I	NOT LESS THAN 20 MINUTES PER CRC R327.8. IR.	PANELS [> 9 SQ FT] WITHIN 18" OF THE ADJACENT FLOOR SHALL BE T  3. GLAZING IN SHOWER AND TUBS ENCLOSURES SHALL BE TEMPERED,				HAZARD.				
					4. EGRESS WINDOWS IN SLEEPING ROOMS SHALL CONFORM TO UBC F AT BOTTOM OF OPENING TO BE 44".	REQUIREMENTS::	MIN 20" WII	DE BY 24" HT (	CLEAR WHEN	IN THE OPEN POSITION. MAX I	HT		
					5. GLAZING IN EXTERIOR DOORS AND WINDOWS SHALL CONFORM TO H	IGH FIRE REQUIF	REMENTS WI	TH AT LEAST C	NE TEMPERE	D PANE.			
					<ul><li>6. VERIFY OPENINGS FOR REPLACEMENT WINDOWS</li><li>7. ALL GLAZING TO MEET MIN. REQUIREMENTS*:</li></ul>								
					WINDOWS: .17 SHGC, .32 U-FACTOR DOORS: .07 SHGC, .37 U-FACTOR								
					8. THE NFCR THERMAL PERFORMANCE LABELS SHALL REMAIN ON THE V	WINDOWS AND D	OORS UNTIL	FINAL INSPEC	CTION		С	С В	Α
WIND	OW INS	TALLAT	ION NO	OTES									DOOR LEGEND
1. ALL GLAZING TO BE 2. ALL GLAZING REQU	DUAL LOW E. IRED TO BE INSULATING GLAS	SS UNITS WITH A MINIMUN	M OF ONE TEMPERED PAN	PER WINDOW, REQUIRED TO BE 3/16*									1/4" = 1'-0"
TEMPERED GLASS, DI OF NOT LESS THAN 20 3. ALL OPERABLE WIN	JAL OR MULTILAYERED GLAZE MINUTES PER 2007 CBC CHA DOWS TO BE SCREENED.	ED PANELS, 1/4" LAMINATE APTER 7A & SBCO HIGH FIR	ED GLASS, GLASS BLOCK	OR HAVE A FIRE PROTECTION RATING									
	IDOWS, U.N.O. PER WINDOW S E INTERIOR PAINTED, U.N.O. I												
5" MIN A ROUGH CHOING	ADJOH OPENNO.	1 1	- ROUGH SPENNS -	+ BUILDING PAPER -					Γ				
	DHAD	05493	COMPANY	WINDOW SYSTEM WINDOW SYSTEM									
	-		5 Harros	EXTERIOR FINISH AND TRIN PER ARCHITECT									
4	9° un		3° MIN. 5	5 May 1 5							$\begin{array}{ c c c c c c c c c c c c c c c c c c c$		
1. APPLY PLIABI MEMBRANE T OVER SHEATI AT CORNERS	APE FLASHING METAL SI	G AND APPLY F	INSTALL JAMB FLASHING AND APPLY FLASHING OVER CORNERS.	4. INSTALL HEAD 5. INSTALL WINDOW SHIMS 6. APPLY BUILDING FLASHING AND APPLY AS NECESSARY INSTALL FLASHING OVER WINDOW IN CORNERS. OPENING PER MFR. EXTERIOR OVERLAP,									
AT CORNERS ROUGH OPEN APPLY PEEL STICK MEMBF AT FRAME.	ING. DETAIL A AND FLASHING	ND APPLY G OVER	STATE NO.	CORNERS.  OPENING PER MFR.  REQUIREMENTS,  MECHANICALLY FASTEN  FLANGE TO SUBSTRATE  AND APPLY TAPE OVER  REMAINING SIDES OF									
				REMAINING SIDES OF FLANGE.									
2.	SURFACES SHALL BE CLEAN AN FLASHING SHALL BE A MINIMUM FHAN THE DEPTH OF THE WIND SEQUENCE FLASHING INSTALLS	M OF 9" WIDE, FLASHING SHOOW AND OUT ONTO THE W	HALL WRAP INTO WINDOW VALL 3" MIN,		G F		Е			С	)	СВ	А
4. \$	SEQUENCE FLASHING INSTALLS SILL PAN TO BE COPPER U.N.O. NSTALLATION IF OTHER THAN	., CONTRACTOR TO SUBMIT											

Date 2018-02-27
Scale As indicated
Drawn AW
Job # Project
Number

DOOR AND WINDOW SCHEDULE

 629 STATE STREET ● SUITE 240 ● SANTA BARBARA ● CA ● 93101 ● TEL (CARMEL) 831.624.4278

 (SANTABARBARA)805.966.7668 ● FAX 805.966.7698 ● WWW.TOMMEANEY.COM ●

**≤** 

A8.1

GARAGE STONE SIDING: (MATCH SITE WALLS)





HOUSE AND GARGE METAL SEAM ROOFING (RIDGE CAP SAME)



DOOR AND WINDOW PANELS, JAMB, HEAD, SILLS AND TRIM COLOR:



## SITE FINISHES

MAIN AREA STONE RETAINING WALLS: (Santa Maria' random ashlar)



PATIO FLAGSTONE PAVERS, LARGE, GROUTED:





DRIVEWAY SURFACE, ASPHALT:



REAR RETAINING WALLS. BOARD FORM CONCRETE:

**EXTERIOR FINISH SCHEDULE** 

14 CONC. OR STONE STAIRS PER LANDSCAPE PLAN

19 STEEL DECK PER DETAIL

18 GALVANIZED METAL CHIMNEY FLUE. PAINT TO MATCH ROOF

MFR. SPECIFICATIONS. VERIFY WITH ARCHITECT

CLASS 'A', NON-REFLECTIVE METAL STANDING SEAM ROOF W/ 12" O.C. SEAMS, SUPPLY: CUSTOM-BILT METALS / CB-150 (CUSTOMBILTMETALS.COM), COLOR: MUSKET GREY. VERIFY W/ ARCHITECT

3 4X6 DOUGLAS FIR RAFTER TAILS PER DETAIL, 24" O.C. MAX., SMOOTH TEXTURE, PAINT TO MATCH SIDING - COLOR: VERIFY W/ ARCHITECT

6 | METAL CLAD EXTERIOR DOOR, DUAL GLAZED / LOW E - PER DOOR SCHEDULE, MFR: MARVIN INFINITY (WWW.MARVIN.COM), COLOR: BLACK

9 CEDAR PLANK GARAGE DOOR, WIRE BRUSHED W/ EASED EDGES, REFER TO DOOR SCHEDULE, COLOR/TEXTURE: PAINT TO MATCH SIDING

11 TAPERED DOUGLAS FIR POST 8X8:12X12, PER PLAN & DETAIL, COLOR/TEXTURE: PAINT TO MATCH SIDING - VERIFY W/ ARCHITECT

8X8 DOUGLAS FIR BEAM PER PLAN & DETAIL, SMOOTH TEXTURE, PAINT TO MATCH SIDING - COLOR: VERIFY W/ ARCHITECT

4 2X6 T&G KILN DRIED DOUGLAS FIR EAVES PER DETAIL, SMOOTH TEXTURE, PAINT TO MATCH SIDING - COLOR: VERIFY W/ ARCHITECT

5 | 1"x10" 'MICHIGAN PRESTAIN' HORIZONTAL SIDING, WIRE BRUSH, OVER 3/8" X 1-1/2" STURDI STRIPS. COLOR: WEATHERED SLATE

8 2X4 DOOR & WINDOW CASING PER DETAIL, CEDAR. COLOR: STAIN TO MATCH SIDING

10 CUSTOM WOOD GATE, REFER TO DOOR SCHEDULE, SUPPLY/COLOR: BLACK - VERIFY W/ ARCHITECT

5" SQUARE DOWNSPOUT TO MATCH ROOF, HINGED GUTTER GUARD, LOCK ON STYLE, COMPATIBLE W/ 5" GUTTERS TO PREVENT THE ACCUMULATION OF LEAVES AND DEBRIS, CONNECT DRAINAGE TO STORM DRAIN SYSTEM

7 METAL CLAD WOOD EXTERIOR WINDOW, DUAL GLAZED / LOW E - PER WINDOW SCHEDULE, MFR: MARVIN INFINITY (WWW.MARVIN.COM), COLOR: BLACK

CHIMNEY PER PLAN & DETAIL W/ SANTA BARBARA STONE VENEER, W/ CLASS 'A' INSULATED DOUBLE WALL STAINLESS STEEL FLUE FOR ALL CHIMNEY LENGTHS & ASSOCIATED COMPONENTS PER MFR SPECS, REPORTS & LISTINGS (UL103), MFR: DURAVENT - DURATECH 12" (WWW.DURAVENT.COM), PROVIDE SHROUD AND SPARK ARRESTOR TO COMPLY PER (CRC SECTION R1003.9.1), CHIMNEY TO EXTEND 2' ABOVE ANY PORTION OF THE BUILDING AND ROOF WITHIN 10' OF THE CHIMNEY OUTLET AND 3' ABOVE THE HIGHEST POINT WHERE CHIMNEY PASSES THROUGH ROOF, NET FREE AREA UNDER CHIMNEY CAP TO BE 4 TIMES GREATER THAN THE AREA OF THE CHIMNEY FLUE OUTLET

EXTERIOR WALL MOUNTED INDIRECT LIGHT FIXTURE PER PLAN, HIGH EFFICIENCY LED LAMP W/ SHIELDED GLASS, 25 WATT OR EQUIVALENT MAX., SUPPLY: VERIFY W/ ARCHITECT, COLOR: BLACK

STONE TERRACE & LANDINGS PAVERS, SLOPE 1/8" PER FT. TO DRAIN AWAY FROM STRUCTURES, STAIR LANDINGS 2% SLOPE MAX., PROVIDE 36" MIN. LANDING AT EACH GRADE LEVEL EXIT IN THE DIRECTION OF EGRESS, SUPPLY/COLOR: VERIFY W/ ARCHITECT

WEEP SCREED, PROFILE TO ALLOW SIDING BELOW SCREED PER DETAIL, PROVIDE 26 GAUGE MIN. GALVANIZED WEEP SCREED AT FOUNDATION, 4" MIN. ABOVE GRADE OR 2" MIN. ABOVE CONCRETE/PAVING WHERE OCCURS

ADHERED STONE VENEER WALL BASE TO MATCH LANDSCAPE WALLS. SANTA MARIA RANDOM ASHLAR BY COOPER STONE, U.N.O. FULL CUT CORNERS. 2" - 3" THICK SLOPED STONE CAP WITH 1" - 2" OVERLAP, 2" BELOW FLOOR LEVEL. EXTEND STONE 6" BELOW GRADE. OVER TWO LAYERS BUILDING PER




SITE STAIRS MATERIAL, CONC, WARM: MATCH FOR EGRESS WELL WALLS

MONOLITHIC STONE TREADS



EXTERIOR WOOD GATE COLOR:






2018-02-27 As indicated

Revision Schedule Date Description . (CARMEL) 831.624 FOMMEANEY.COM •

THOMAS RESIDENCE

ARCHITECTURAL **DETAILS** 



2018-02-27 3" = 1'-0"

NO

THOMAS RESIDENCE SANTA LUCIA PRESERVE CARMEL VALLEY, CA CONSTRUCTION ARCHITECTURAL DETAILS

**Revision Schedule** Date Description

2018-02-27 As indicated

- ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THESE PLANS AND ACCOMPANYING SPECIFICATIONS, IN ADDITION ALL WORK SHALL ALSO CONFORM WITH THE FOLLOWING: LATEST REVISION OF THE COUNTY OF MONTEREY DESIGN STANDARDS AND SPECIFICATIONS
- THE LATEST REVISION OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS (STATE SPECIFICATIONS)
  THE 2016 EDITIONS OF THE CALIFORNIA BUILDING CODE (CBC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA MECHANICAL CODE (CMC), CALIFORNIA ENERGY CODE (CENC),
- THE 2016 EDITIONS OF THE CALIFORNIA BUILDING CODE (CBC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA MECHANICAL CODE (CMC), CALIFORNIA ENERGY CODE (CENC), CALIFORNIA ELECTRICAL CODE (CEC).
   SOILS REPORT PREPARED FOR THE PROJECT BY HARO KASUNICH AND ASSOCIATES DATED OCTOBER 2017.
- 2. THE CONTRACTOR SHALL FAMILIARIZE THEMSELVES WITH THE PLANS, DETAILS, AND SPECIFICATIONS AND SITE CONDITIONS PRIOR TO THE START OF CONSTRUCTION. IN THE EVENT THAT THE CONTRACTOR FINDS ANY DISCREPANCIES, OMISSIONS, OR DEFICIENCIES IN THE PLANS, THE CONTRACTOR SHALL NOTIFY THE DESIGN ENGINEER AND THE OWNER'S REPRESENTATIVE
- 3. IT IS THE CONTRACTORS RESPONSIBILITY TO SECURE ALL REQUIRED PERMITS PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE COUNTY
- 4. THE TOPOGRAPHY, LOCATIONS AND SIZE OF UNDERGROUND UTILITIES AND OR OTHER STRUCTURES SHOWN HEREON WERE OBTAINED FROM A FIELD SURVEY (BY OTHERS) AND OR FROM RECORD INFORMATION. NEITHER THE ENGINEER NOR THE OWNER MAKES ANY REPRESENTATION TO THE ACCURACY OF TOPOGRAPHY. SIZE AND OR LOCATION OF ANY OF THE UTILITIES OR STRUCTURES SHOWN ON THESE PLANS NOR FOR THE EXISTENCE OF ANY OTHER BURIED OBJECTS OR UTILITIES WHICH MAY BE ENCOUNTERED THAT ARE NOT SHOWN ON THIS PLAN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY THE SIZE AND LOCATION OF EXISTING UNDERGROUND UTILITIES, SURFACE IMPROVEMENTS, AND OTHER STRUCTURES AND TAKE ALL NECESSARY PRECAUTIONS TO PROTECT THEM FROM DAMAGE DURING CONSTRUCTION.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING APPROPRIATE UTILITY COMPANIES AND REQUESTING VERIFICATION OF SERVICE POINTS, FIELD VERIFICATION OF LOCATION, SIZE, DEPTH, ETC. FOR ALL THEIR FACILITIES AND TO COORDINATE WORK SCHEDULES.
- 6. THE CONTRACTOR SHALL NOTIFY UNDERGROUND SERVICE ALERT AT (800) 227-2600 AT LEAST 48 HOURS PRIOR TO EXCAVATION TO VERIFY THE LOCATION OF EXISTING UNDERGROUND
- 7. CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH ANY CURRENTLY APPLICABLE SAFETY LAW OF ANY JURISDICTIONAL BODY. FOR INFORMATION REGARDING THIS PROVISION, THE CONTRACTOR IS DIRECTED TO CONTACT THE STATE OF CALIFORNIA, DIVISION OF OCCUPATIONAL SAFETY AND HEALTH. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL BARRICADES, SAFETY DEVICES, AND THE CONTROL OF TRAFFIC WITHIN THE CONSTRUCTION AREA. FOR ALL TRENCH EXCAVATION FIVE (5) FEET OR MORE IN DEPTH, THE CONTRACTOR SHALL OBTAIN A PERMIT FROM THE DIVISION OF OCCUPATIONAL SAFETY AND HEALTH PRIOR TO BEGINNING ANY EXCAVATION. A COPY OF THIS PERMIT SHALL BE AVAILABLE AT THE CONSTRUCTION SITE AT ALL TIMES.
- 8. EXISTING CURB, GUTTER, SIDEWALK, SURVEY MONUMENTS, AND OTHER IMPROVEMENTS WITHIN PROJECT SITE THAT ARE DAMAGED OR DISPLACED AS A RESULT OF THE CONTRACTOR'S ACTIVITIES SHALL BE REPLACED BY THE CONTRACTOR.
- 9. THE CONTRACTOR SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS AND SAFETY OF ALL PERSONS AND PROPERTY DURING THE COURSE OF CONSTRUCTION OF THE PROJECT. THE CONTRACTOR AGREES TO HOLD HARMLESS, INDEMNIFY AND DEFEND THE OWNER, THE ENGINEER, AND ALL DESIGN CONSULTANTS FROM ANY AND ALL LIABILITY, CLAIMS, LOSSES OR DAMAGES ARISING FROM THE PERFORMANCE OF THE WORK DESCRIBED HEREIN EXCEPT THOSE ARISING FROM THE SOLE NEGLIGENCE OF ANY OF THE PREVIOUSLY MENTIONED PEOPLE OR ENTITIES. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR SHALL LEAVE A 24-HOUR EMERGENCY TELEPHONE NUMBER WITH THE POLICE, FIRE DEPARTMENTS AND PRIVATE SECURITY COMPANY (IF APPLICABLE), AND KEEP THEM INFORMED DAILY REGARDING ANY CONSTRUCTION RELATED ACTIVITY IN THE PUBLIC RIGHT OF WAY.
- 10. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVAL, OFF-HAUL, AND PROPER DISPOSAL OF ALL ITEMS TO BE REMOVED INCLUDING BUT NOT LIMITED TO: CONCRETE, ASPHALT CONCRETE, STRIPING, ANY AND ALL OTHER DEBRIS FROM THE SITE, EXCESS MATERIAL FROM TRENCHING AND PAVEMENT CONSTRUCTION, TREES AND ROOT BALLS, FENCING AND SPOILS FROM EXCAVATION AT THE CONTRACTOR'S EXPENSE.
- 11. IF ARCHAEOLOGICAL RESOURCES OR HUMAN REMAINS ARE DISCOVERED DURING CONSTRUCTION, WORK SHALL BE HALTED WITHIN 150 FEET OF THE FIND UNTIL IT CAN BE EVALUATED BY A QUALIFIED PROFESSIONAL ARCHAEOLOGIST. IF THE FIND IS DETERMINED TO BE SIGNIFICANT, APPROPRIATE MITIGATION MEASURES SHALL BE FORMULATED AND IMPLEMENTED.
- 12. ALL REVISIONS TO THESE PLANS MUST BE APPROVED BY THE ENGINEER AS WELL AS THE OWNER PRIOR TO THEIR CONSTRUCTION AND SHALL BE ACCURATELY SHOWN ON RECORD DRAWINGS PRIOR TO THE ACCEPTANCE OF THE WORK AS COMPLETE. ANY CHANGES TO OR DEVIATIONS FROM THE PLANS MADE WITHOUT AUTHORIZATION SHALL BE AT THE CONTRACTOR'S SOLE RISK AND SHALL ABSOLVE THE ENGINEER OF ANY AND ALL RESPONSIBILITY ASSOCIATED WITH THE THE CHANGE OR DEVIATION.
- 13. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP THE SITE AND ADJACENT AREAS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY, THE CONTRACTOR SHALL REMOVE IT IMMEDIATELY.
- 14. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

  A) PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH
- B) COVER STOCKPILES OF DEBRIS, SOIL, OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST.
- C) KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST.

BUILDING DEPARTMENT AT LEAST 24 HOURS PRIOR TO THE START OF CONSTRUCTION.

- LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE.
- A COPY OF ALL FIELD REPORTS/COMPACTIONS TESTS AND FINAL GRADING REPORT SHALL BE SUBMITTED TO THE COUNTY AT SCHEDULED INSPECTIONS.
- 6. PAD ELEVATION/S SHALL BE CERTIFIED TO 0.1 FEET, PRIOR TO DIGGING ANY FOOTINGS OR SCHEDULING ANY INSPECTIONS.


#### GRADING AND DRAINAGE

- CONTRACTOR SHALL NOTIFY THE COUNTY 48 HOURS BEFORE STARTING ANY GRADING OPERATIONS.
- 2. ALL GRADING SHALL CONFORM TO THE COUNTY GRADING ORDINANCE AND THE EROSION CONTROL ORDINANCE.
- THE SOILS ENGINEER SHALL BE NOTIFIED AT LEAST TWO (2) DAYS IN ADVANCE OF COMMENCING WORK, INCLUDING SITE STRIPPING AND GRADING OPERATIONS. THIS WORK SHALL BE BSERVED AND TESTED BY THE SOILS ENGINEER.
- 4. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE REQUIRED PERMITS PRIOR TO THE COMMENCEMENT OF GRADING. RIGHT-OF-ENTRY, PERMISSION TO GRADE, AND ENCROACHMENT PERMIT(S) MAY BE REQUIRED PRIOR TO GRADING.
- 5. IT IS THE CONTRACTORS RESPONSIBILITY TO PREPARE THE GROUND SURFACE TO RECEIVE THE FILLS AND TO PLACE, SPREAD, MIX, WATER, AND COMPACT THE FILL. THE CONTRACTOR SHALL ALSO REMOVE ALL MATERIAL CONSIDERED UNSATISFACTORY.
- 6. WHERE UNSTABLE OR UNSUITABLE MATERIALS ARE ENCOUNTERED DURING SUBGRADE PREPARATION, THE AREA IN QUESTION SHALL BE OVER EXCAVATED AND BACKFILLED WITH SELECT
- 7. MAXIMUM CUT AND FILL SLOPE SHALL BE 3 HORIZONTAL TO 1 VERTICAL.
- 8. ALL CUT SLOPES SHALL BE ROUNDED TO MEET EXISTING GRADES AND BLEND WITH SURROUNDING TOPOGRAPHY. ALL GRADED SLOPES SHALL BE PLANTED WITH SUITABLE GROUND COVER.


  9. ALL FILL SLOPES SHALL BE COMPACTED IN ACCORDANCE WITH THE SOILS REPORT. THE TOE OF ALL SLOPES SHOULD BE SUPPORTED BY A KEY CUT A MINIMUM OF 3 FEET INTO UNDISTURBED SOILS TO THE INSIDE OF THE FILL TOE. THIS KEY SHOULD BE A MINIMUM OF 8 FEET IN WIDTH AND SLOPE AT NO LESS THAN 10% INTO THE SLOPE. IN ADDITION AS THE FILL ADVANCES UP THE SLOPE
- BENCHES 3 FEET ACROSS SHOULD BE SCARIFIED INTO THE FILL/UNDISTURBED SOIL INTERFACE. (SEE SOILS REPORT)


  10. TREE REMOVAL SHALL INCLUDE REMOVAL OF TRUNKS, STUMPS, AND ROOTBALLS. THE REMAINING CAVITY SHALL BE CLEARED OF ALL ROOTS LARGER THAN 1/2" TO A DEPTH OF NOT LESS
- THAN 18" AND BACKFILLED WITH SUITABLE MATERIAL THEN COMPACTED TO CONFORM WITH THE EXISTING GROUND.
- CONTRACTOR SHALL USE CAUTION WHEN GRADING AROUND AND/OR OVER EXISTING UNDERGROUND UTILITIES.
   ALL SURFACE DRAINAGE SHALL MAINTAIN 2% SLOPE MINIMUM UNLESS NOTED OTHERWISE.
- 13. PERVIOUS SURFACES IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT A SLOPE OF NOT LESS THAN 5% FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FEET OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED A MINIMUM OF 2% WHERE LOCATED WITHIN 10 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.
- 14. NO LAND CLEARING OR GRADING SHALL OCCUR ON THE SUBJECT PARCEL BETWEEN OCTOBER 15 AND APRIL 15 UNLESS AUTHORIZED BY THE DIRECTOR OF RMA-BUILDING SERVICES. IF AUTHORIZED, DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15) THE FOLLOWING MEASURES MUST BE TAKEN:
- A. DISTURBED SURFACES NOT INVOLVED IN IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.
- B. ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON DOWNHILL PROPERTIES.
- C. RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS, AND OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE.
- D. DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY THROUGH THE LIFE OF THE PROJECT DURING WINTER OPERATIONS
- . VEGETATION REMOVAL. ACTUAL GRADING SHALL BEGIN WITHIN 30 DAYS OF VEGETATION REMOVAL OR THAT AREA SHALL BE PLANTED.
- 6. NO VEGETATION REMOVAL OR GRADING WILL BE ALLOWED WHICH WILL RESULT IN SILTATION OF WATER COURSES OR UNCONTROLLABLE EROSION.
- 17. STOCKPILE TOPSOIL WITHIN THE CONSTRUCTION SITE AND REUSE AS PART OF THE LANDSCAPE RESTORATION PLAN, ALL EFFORTS TO BE MADE TO RESTRICT GRADING AND CONSTRUCTION


Inspection:	When:	Who:	Inspection By:	Date of Inspection:
Inspect and test	1)Prior to backfilling	Soils Engineer		
Keyway/Subexcavation/overexcavation:	2)During backfill placement – ongoing	Soils Engineer		
Inspect and Test Building Pad Subgrade:	Prior to excavation footings or placement of slab-on-grade materials	Soils Engineer		
Inspect Slab-on-grade installation:	Prior to concrete placement	Soils Engineer		
Inspect Foundation and/or retaining wall footing excavations:	Prior to reinforcement placement	Soils Engineer		
Inspect and Test Retaining wall backfill:	During backfill placement – ongoing	Soils Engineer		
	1)During fill placement	Soils Engineer		
Inspect and Test Driveway Fill, Subgrade and Baserock Placement:	2)Subgrade, prior to baserock placement	Soils Engineer		
	3)Baserock prior to AC, Concrete or Pavement	Soils Engineer		
Inspect and Test Drainage Installation:	1)After pipe placement, prior to backfill placement	Soils Engineer		
Thispeer and lest brainage marailanon.	2)During backfill placement – ongoing	Soils Engineer		




PROJECT#








#### **GENERAL NOTES** . THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO PREVENT AIRBORNE DUST FROM BECOMING A NUISANCE TO NEIGHBORING PROPERTIES. THE CONTRACTOR SHALL CONFORM TO THE STANDARDS FOR DUST-CONTROL AS ESTABLISHED BY THE AIR QUALITY MAINTENANCE DISTRICT. DUST CONTROL MEASURES TO BE IMPLEMENTED INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: A) PROVIDE EQUIPMENT AND MANPOWER REQUIRED FOR WATERING ALL EXPOSED OR DISTURBED EARTH. SUFFICIENT WATERING TO CONTROL DUST IS REQUIRED AT ALL TIMES. B) COVER STOCKPILES OF DEBRIS, SOIL, OR OTHER MATERIALS WHICH MAY CONTRIBUTE TO AIRBORNE DUST. C) KEEP CONSTRUCTION AREAS AND ADJACENT STREET FREE OF MUD AND DUST. D) LANDSCAPE, SEED, OR COVER PORTIONS OF THE SITE AS SOON AS CONSTRUCTION IS COMPLETE. THE CONTRACTOR SHALL ASSUME LIABILITY FOR CLAIMS RELATED TO WIND BLOWN MATERIAL. IF THE DUST CONTROL IS INADEQUATE AS DETERMINED BY THE COUNTY, THE CONSTRUCTION WORK SHALL BE TERMINATED UNTIL CORRECTIVE MEASURES ARE TAKEN. 2. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO KEEP STREETS AND ROADS FREE FROM DIRT AND DEBRIS. SHOULD ANY DIRT OR DEBRIS BE DEPOSITED IN THE PUBLIC RIGHT-OF-WAY, THE CONTRACTOR SHALL REMOVE IT IMMEDIATELY. 3. ALL CUT AND FILL SLOPES EXPOSED DURING CONSTRUCTION SHALL BE COVERED, SEEDED OR OTHERWISE TREATED TO CONTROL EROSION WITHIN 48 HOURS AFTER GRADING. CONTRACTOR SHALL REVEGETATE SLOPES AND ALL DISTURBED AREAS THROUGH AN APPROVED PROCESS AS DETERMINED BY THE COUNTY. THIS MAY CONSIST OF EFFECTIVE PLANTING OF RYE GRASS, BARLEY OR SOME OTHER FAST GERMINATING SEED. 4. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15), THE FOLLOWING MEASURES MUST BE TAKEN: A) VEGETATION REMOVAL SHALL NOT PRECEDE SUBSEQUENT GRADING OR CONSTRUCTION ACTIVITIES BY MORE THAN 15 DAYS. DURING THIS PERIOD, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE. DISTURBED SURFACES NOT INVOLVED IN THE IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND/OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION. B) ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR THE DOWNHILL PROPERTIES. C) RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS AND/OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE DISTURBED AREA OR SITE, THESE DRAINAGE CONTROL MEASURES MUST BE MAINTAINED BY THE CONTRACTOR AS NECESSARY TO ACHIEVE THEIR PURPOSE THROUGHOUT THE LIFE OF THE PROJECT. D) EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY CHECKED THROUGHOUT THE LIFE OF THE PROJECT DURING WINTER OPERATIONS. MONTEREY COUNTY GRADING/EROSION ORD. 2806-16.12.090) E) THE GRADING INSPECTOR MAY STOP OPERATIONS DURING PERIODS OF INCLEMENT WEATHER IF EROSION PROBLEMS ARE NOT BEING CONTROLLED ADEQUATELY. 5. IF VEGETATION REMOVAL TAKES PLACE PRIOR TO A GRADING OPERATION AND THE ACTUAL GRADING DOES NOT BEGIN WITHIN 30 DAYS FROM THE DATE OF REMOVAL, THEN THAT AREA SHALL BE PLANTED UNDER THE PROVISION OF SECTION 16.08.340 TO CONTROL EROSION. NO vegetation removal or grading will be allowed which will result in siltation of water courses or uncontrollable erosion. 6. ALL POLLUTANTS AND THEIR SOURCES, INCLUDING SOURCES OF SEDIMENT ASSOCIATED WITH CONSTRUCTION, CONSTRUCTION SITE EROSION AND ALL OTHER ACTIVITIES ASSOCIATED WITH CONSTRUCTION ACTIVITY ARE CONTROLLED: 7. ALL NON-STORM WATER DISCHARGES ARE IDENTIFIED AND EITHER ELIMINATED, CONTROLLED, OR TREATED; 8. SITE BMPS ARE TO BE EFFECTIVE AND RESULT IN THE REDUCTION OR ELIMINATION OF POLLUTANTS IN STORM WATER DISCHARGES AND AUTHORIZED NON-STORM WATER DISCHARGES FROM CONSTRUCTION ACTIVITY 9. STABILIZATION BMPS INSTALLED TO REDUCE OR ELIMINATE POLLUTANTS AFTER CONSTRUCTION IS COMPLETED. 10. BEST MANAGEMENT PRACTICES (BMPS) TO BE IMPLEMENTED BY THE PROJECT ARE LISTED BY CATEGORY. FACT SHEETS, AND DETAILS FOR THE BMPS SELECTED FOR THIS PROJECT, CAN BE FOUND IN THE CASQA STORMWATER BEST MANAGEMENT PRACTICE HANDBOOK. 1.PRIOR TO COMMENCEMENT OF LAND DISTURBANCE, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIROMENTAL SERVICES TO ENSURE ALL NECESSARY SEDIUMENT CONTROLS ARE IN PLACE AND THE PROJECT IS COMPLIANT WITH MONTEREY COUNTY 2. During construction, the owner/applicant shall schedule an inspection with rma-environmental services to inspect drainage device installation, review the maintenance and effectivemness of BMPs installed, and to verify that pollutants of CONCERN ARE NOT DISCHARGED FROM THE SITE, AT THE TIME OF THE INSPECTION THE APPLICANT SHALL PROVIDE CERTIFICATION THAT ALL NECESSARY GEOTECHNICAL INSPECTIONS HAVE BEEN COMPLETED TO THAT POINT. 3. PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO ENSURE ALL DISTURBED AREAS HAVE BEEN STABILIZED AND ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THAT ARE NO LONGER 4. THE APPLICANT SHALL PROVIDE CERTIFICATION FROM A LICENSED PRACTITIONER THAT ALL DEVELOPMENT HAS BEEN CONSTRUCTION IN ACCRODANCE WITH THE RECOMEMENDATIONS IN THE PROJECT GEOTECHNICAL REPORT. GOOD SITE MANAGEMENT "HOUSEKEEPING" . POLLUTANTS IN STORM WATER DISCHARGES FROM THE PROJECT DURING CONSTRUCTION MAY ORIGINATE FROM THE DAILY OPERATION OF EQUIPMENT, GRADING OPERATIONS, AND STOCKPILING OF MATERIALS. -DISCHARGERS SHALL IMPLEMENT GOOD HOUSEKEEPING MEASURES ON THE CONSTRUCTION SITE TO CONTROL THE AIR DEPOSITION OF SITE MATERIALS AND FROM SITE OPERATIONS. SUCH PARTICULATES CAN INCLUDE, BUT ARE NOT LIMITED TO, SEDIMENT, NUTRIENTS, TRASH, METALS, BACTERIA, OIL AND GREASE AND ORGANICS. WASTE MANAGEMENT POLLUTION CONTROL 1. THE DISCHARGER SHALL PREVENT DISPOSAL OF ANY RINSE OR WASH WATERS OR MATERIALS ON IMPERVIOUS OR PERVIOUS SITE SURFACES OR INTO THE STORM DRAIN SYSTEM. 2. THE DISCHARGER SHALL ENSURE THE CONTAINMENT OF SANITATION FACILITIES (E.G., PORTABLE TOILETS) TO PREVENT DISCHARGES OF POLLUTANTS TO THE STORM WATER DRAINAGE SYSTEM OR RECEIVING WATER. THE SANITATION FACILITIES SHALL BE CLEANED, REPLACED, AND INSPECTED REGULARLY FOR LEAKS AND SPILLS. 3. WASTE DISPOSAL CONTAINERS SHALL BE COVERED AT THE END OF EVERY BUSINESS DAY AND DURING A RAIN EVENT. NO DISCHARGES FROM WASTE DISPOSAL CONTAINERS TO THE STORM WATER DRAINAGE SYSTEM OR RECEIVING WATER SHALL BE ALLOWED. 4. STOCKPILED MATERIAL SHALL BE CONTAINED AND SECURELY PROTECTED FROM WIND AND RAIN AT ALL TIMES UNLESS ACTIVELY BEING USED. 5. procedures shall be developed that effectively address hazardous and nonhazardous spills. Equipment and materials for cleanup of spills shall be available on site. Spills and leaks shall be cleaned up immediately and disposed of properly. 6. CONCRETE WASHOUT AREAS SHALL BE CONTAINED SO THERE IS NO DISCHARGE INTO THE UNDERLYING SOIL AND ONTO THE SURROUNDING AREAS. 7. DISCHARGER SHALL MAINTAIN VEHICLES TO PREVENT OIL, GREASE, OR FUEL TO LEAK IN TO THE GROUND, STORM DRAINS OR SURFACE WATERS. ALL EQUIPMENT OR VEHICLES SHALL BE FUELED, MAINTAINED AND STORED IN A DESIGNATED AREA FITTED WITH APPROPRIATE BMPS. LEAKS SHALL BE CLEANED IMMEDIATELY AND DISPOSED OF PROPERLY. 8. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE WASTE MANAGEMENT POLLUTION CONTROL WHERE APPLICABLE: WM-1, MATERIAL DELIVERY AND STORAGE WM-2. MATERIAL USE WM-3, STOCKPILE MANAGEMENT WM-4, SPILL PREVENTION AND CONTROL WM-5, SOLID WASTE MANAGEMENT WM-6, HAZARDOUS WASTE MANAGEMENT WM-7 CONTAMINATED SOIL MANAGEMENT WM-8, CONCRETE WASTE MANAGEMENT WM-9, SANITARY/SEPTIC WASTE MANAGEMENT WM-10. LIQUID WASTE MANAGEMENT (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) 9. THE CONTRACTOR SHALL REVIEW CONSTRUCTION ACTIVITIES TO IDENTIFY AND QUANTIFY LIKELY CONSTRUCTION MATERIALS AND WASTES. SPECIAL NOTICE SHALL BE MADE OF MATERIALS AND WASTES WITH SPECIAL HANDLING OR DISPOSAL REQUIREMENTS; SUCH AS LEAD CONTAMINATED SOILS, CONCRETE SAW-CUTTING LIQUIDS, WASTE CHEMICALS AND EMPTY CHEMICAL CONTAINERS. THE CONTRACTOR SHALL FOLLOW ALL MANUFACTURERS' STORAGE AND HANDLING RECOMMENDATIONS AND FOLLOW ALL FEDERAL, STATE, AND LOCAL REGULATIONS. WHERE POSSIBLE, CONTRACTOR SHALL USE SAFER AND LESS POLLUTING PRODUCTS. EROSION CONTROL (SOIL STABILIZATION) 1. SUFFICIENT EROSION CONTROL MATERIALS WILL BE MAINTAINED ON-SITE TO ALLOW FOR IMMEDIATE DEPLOYMENT BEFORE THE ONSET OF RAIN. 2. DISCHARGERS SHALL PROVIDE EFFECTIVE SOIL COVERS FOR INACTIVE AREAS (MORE THAN 14 DAYS UN-DISTURBED) AND ALL FINISHED SLOPES, OPEN SPACE, UTILITY BACKFILL, AND COMPLETED LOTS. 3. DISCHARGERS SHALL LIMIT THE USE OF PLASTIC MATERIALS WHEN MORE SUSTAINABLE, ENVIRONMENTALLY FRIENDLY ALTERNATIVES EXIST. WHERE PLASTIC MATERIALS ARE DEEMED NECESSARY, THE DISCHARGER SHALL CONSIDER THE USE OF PLASTIC MATERIALS RESISTANT TO SOLAR **DEGRADATION** 4. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TEMPORARY AND FINAL EROSION CONTROL DURING CONSTRUCTION WHERE APPLICABLE: EC-1, SCHEDULING EC-2, PRESERVATION OF EXISTING VEGETATION EC-3, HYDRAULIC MULCH EC-4, HYDROSEEDING EC-5, SOIL BINDERS EC-6, STRAW MULCH EC-8, WOOD MULCHING EC-9, EARTH DIKES AND DRAINAGE SWALES EC-10, VELOCITY DISSIPATION DEVICES EC-11, SLOPE DRAINS EC-12, STREAMBANK STABILIZATION EC-13, POLYACRYLAMIDE (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) 5. SPECIAL CARE SHALL BE TAKEN SO THAT NO FILL MATERIALS SHALL BE PLACED, SPREAD, OR ROLLED DURING UNFAVORABLE WEATHER CONDITIONS. SEDIMENT CONTROL 1. SUFFICIENT QUANTITIES OF TEMPORARY SEDIMENT CONTROL MATERIALS WILL BE MAINTAINED ON-SITE THROUGHOUT THE DURATION OF THE PROJECT, TO ALLOW IMPLEMENTATION OF TEMPORARY SEDIMENT CONTROLS IN THE EVENT OF PREDICTED RAIN AND FOR RAPID RESPONSE TO 2. DISCHARGERS SHALL ESTABLISH AND MAINTAIN EFFECTIVE PERIMETER CONTROLS AND STABILIZE ALL CONSTRUCTION ENTRANCES AND EXITS TO SUFFICIENTLY CONTROL EROSION AND SEDIMENT DISCHARGES FROM THE SITE. 3. DISCHARGERS SHALL EFFECTIVELY MANAGE ALL RUN-ON, ALL RUNOFF WITHIN THE SITE AND ALL RUNOFF THAT DISCHARGES OFF THE SITE. RUN-ON FROM OFF-SITE SHALL BE DIRECTED AWAY FROM ALL DISTURBED AREAS OR SHALL COLLECTIVELY BE IN COMPLIANCE WITH THE EFFLUENT 4. DISCHARGERS SHALL APPLY LINEAR SEDIMENT CONTROLS ALONG THE TOE OF THE SLOPE, FACE OF THE SLOPE, AND AT THE GRADE BREAKS OF EXPOSED SLOPES. 5. DISCHARGERS SHALL ENSURE THAT CONSTRUCTION ACTIVITY TRAFFIC TO AND FROM THE PROJECT IS LIMITED TO ENTRANCES AND EXITS THAT EMPLOY EFFECTIVE CONTROLS TO PREVENT OFFSITE TRACKING OF SEDIMENT. 6. DISCHARGERS SHALL ENSURE THAT ALL STORM DRAIN INLETS AND PERIMETER CONTROLS, RUNOFF CONTROL BMPS, AND POLLUTANT CONTROLS AT ENTRANCES AND EXITS (E.G. TIRE WASHOFF LOCATIONS) ARE MAINTAINED AND PROTECTED FROM ACTIVITIES THAT REDUCE THEIR 7. DISCHARGERS SHALL INSPECT ON A DAILY BASIS ALL IMMEDIATE ACCESS ROADS DAILY. 8. AT A MINIMUM DAILY (WHEN NECESSARY) AND PRIOR TO ANY RAIN EVENT, THE DISCHARGER SHALL REMOVE ANY SEDIMENT OR OTHER CONSTRUCTION ACTIVITY RELATED MATERIALS THAT ARE DEPOSITED ON THE ROADS (BY VACUUMING OR SWEEPING). 9. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TEMPORARY AND FINAL SEDIMENT CONTROL DURING CONSTRUCTION WHERE APPLICABLE: SE-2, SEDIMENT BASIN SE-3, SEDIMENT TRAP SE-4, CHECK DAMS SE-5, FIBER ROLLS SE-6, GRAVEL BAG BERM SE-7, STREET SWEEPING AND VACUUMING SE-8, SANDBAG BARRIER SE-9, STRAW BALE BARRIER SE-10, STORM DRAIN INLET PROTECTION SE-11, CHEMICAL TREATMENT (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) TRACKING CONTROL 1. TRACKING CONTROLS SHALL BE IMPLEMENTED AND MAINTAINED YEAR-ROUND AND THROUGHOUT THE DURATION OF THE PROJECT, AT ALL ACCESS (INGRESS/EGRESS) POINTS TO THE PROJECT SITE WHERE VEHICLES AND/OR EQUIPMENT MAY TRACK SEDIMENT FROM THE CONSTRUCTION SITE ONTO PUBLIC OR PRIVATE ROADWAYS. 2. IN GENERAL, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE TRACKING CONTROL DURING CONSTRUCTION WHERE APPLICABLE: TC-1, STABILIZED CONSTRUCTION ENTRANCE/EXIT TC-2, STABILIZED CONSTRUCTION ROADWAY TC-3, ENTRANCE/OUTLET TIRE WASH (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) WIND EROSION CONTROL 1. WIND EROSION CONTROL BMPS SHALL BE IMPLEMENTED AND MAINTAINED YEAR-ROUND AND THROUGHOUT THE DURATION OF THE PROJECT ON ALL DISTURBED SOILS ON THE PROJECT SITE THAT ARE SUBJECT TO WIND EROSION, AND WHEN SIGNIFICANT WIND AND DRY CONDITIONS ARE ANTICIPATED DURING PROJECT CONSTRUCTION. THE OBJECTIVE OF WIND CONTROLS IS TO PREVENT THE TRANSPORT OF SOIL FROM DISTURBED AREAS OF THE PROJECT SITE BY WIND. 2. IN GENERAL, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE WIND EROSION CONTROL DURING CONSTRUCTION WHERE APPLICABLE: WE-1, WIND EROSION CONTROL (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK) NON-STORMWATER MANAGEMENT POLLUTION CONTROL 1. NON-STORM WATER DISCHARGES CONSIST OF ALL DISCHARGES TO/FROM A MUNICIPAL STORM WATER CONVEYANCE, WHICH DO NOT ORIGINATE FROM PRECIPITATION EVENTS (I.E., ALL DISCHARGES FROM A CONVEYANCE SYSTEM OTHER THAN STORM WATER). 2. DISCHARGERS SHALL IMPLEMENT MEASURES TO CONTROL ALL NON-STORM WATER DISCHARGES DURING CONSTRUCTION. 3. DISCHARGERS SHALL WASH VEHICLES IN SUCH A MANNER AS TO PREVENT NON-STORM WATER DISCHARGES. 4. DISCHARGERS SHALL CLEAN STREETS IN SUCH A MANNER AS TO PREVENT UNAUTHORIZED NON-STORM WATER DISCHARGES. 5. IN ADDITION TO THE ABOVE, THE PROJECT WILL IMPLEMENT THE FOLLOWING PRACTICES FOR EFFECTIVE NON-STORMWATER MANAGEMENT POLLUTION CONTROL WHERE APPLICABLE: NS-1, WATER CONSERVATION PRACTICES MIN NS-2, DEWATERING OPERATIONS NS-3, PAVING AND GRINDING OPERATIONS NS-4, TEMPORARY STREAM CROSSING NS-5, CLEAR WATER DIVERSION NS-6, ILLICIT CONNECTION/ILLEGAL DISCHARGE DETECTION AND REPORTING NS-7, POTABLE WATER / IRRIGATION NS-8, VEHICLE AND EQUIPMENT CLEANING NS-9, VEHICLE AND EQUIPMENT FUELING NS-10, VEHICLE AND EQUIPMENT MAINTENANCE NS-11, PILE DRIVING OPERATIONS NS-12, CONCRETE CURING NS-13, MATERIALS AND EQUIPMENT USE OVER WATER NS-14, CONCRETE FINISHING NS-15. STRUCTURE DEMOLITION/REMOVAL NS-16, TEMPORARY BATCH PLANTS (SOURCE: STORMWATER BEST MANAGEMENT HANDBOOK)





LANDSCAPE ARCHITECTURE 1312 Patch Court Marina, CA 93933 www.blisslandscapearchitecture.com

Santa Lucia Preserve, Lot 195 Potrero Trail Carmel Valley, CA 93923

drawn by: sheet size: 24"x36"

Preliminary Design Review Submittal 11.30.2017 Final Design Review Submittal 03.08.2018



03.08.18 Final Design Review Submittal

# LANDSCAPE MATERIALS + FINISHES

### NOTES

1 ALL ITEMS BELOW CORRESPOND TO NUMBERED ITEMS ON L1.0 SITE PLAN

2 PROVIDE MOCK-UP SAMPLES FOR ITEMS REQUESTED, MOCK UPS TO BE REVIEWED BY BLA

3 FOR PHOTO REFERENCES, REFER TO THIS SHEET

## DESIGNER/CONTRACTOR LEGEND


Bliss Landscape Architecture Tom Meaney Architecture

LC Landscape Contractor


Civil Engineer Structural Engineer

LC	Landscape Contracti
PC	Pool Contractor


LAN	DSCAPE ITEM	SPECIFICATION	DESIGNER	CONTRACTOR	NOTEO	CD	MOCK UF
1	ASPHALT PAVING	See civil drawings	RESPONSIBLE CE	RESPONSIBLE GC	NOTES	DETAIL # L1.2	REQUIREI YES
2	GRAVEL PAVING- PEDESTRIAN	Gravel: 3/8" 'Sierra Tan' or equivalent over min. 6" compacted aggregate base per geotech report Install steell edge where needed	BLA	GC+LC	Base prep by GC, Gravel prep by LC Gravel 3/4", rolled in two even courses Steel edge flush with gravel finish	L1.2	YES
3A	FLAGSTONE PAVING W/ PLANTED GAP	Stone: 2" stone set on 2" mortar bed (min), 'Oklahoma Multi-Blend' natural flagstone Base: Mortar set on compacted aggregate base per geotech report	BLA	GC	Hold concrete 3/4" from all exposed edges  No mortar or concrete (gaps open to sub-grade) between pavers	L1.2	YES
3B	FLAGSTONE PAVING	Stone: 2" stone set on 2" mortar bed (min), 'Oklahoma Multi-Blend' natural flagstone with 1/2" - 1" grouted joints  Base: Mortar set on compacted aggregate base per geotech report	BLA	GC	Hold concrete 3/4" from all exposed edges	L1.2	YES
4	STONE PAVING	Stone: 1" stone set on 2" mortar bed (min), 'Oklahoma Multi-Blend' natural flagstone cut pieces with 1/2" - 1" grouted joints All exposed edges of paving to be 2" stone (min.) Base: Concrete sub-slab on compacted aggregate base per geotech report	BLA	GC		L1.2	YES
4C	CONCRETE PAVING	PIP Concrete Paving with integral color and light. Compacted aggregate base as per Geo-tech Report.	BLA	GC		L1.2	-
5	MONOLITHIC STONE TREADS	Stone: 2" Monolithic stone tread set on 1/2" mortar bed (min)  Base: 6" Reinforced concrete sub-slab on compacted aggregate base per geotech report	BLA	GC	Stone type and finish TBD	L1.2	YES
6	CONCRETE STEPS	PIP Concrete Steps with integral color and light, w/ 1/4" radius corners, typ.  Base: compaced aggregate base per geotech report	BLA	GC		L1.2	YES
7	TIMBER DECK	"2x6 Thermal treated Ash decking", top-screw with 305 stainless steel, square-drive decking screws	BLA	GC		L1.2	YES
8	STONE RETAINING WALL	"Santa Maria Random Ashlar" Stone Cladding with grouted joints.  Full stone (90 degree) corners - no cut joints or exposed edges at corners  Sub-wall to be reinforced concrete or CMU. All exposed faces to receive stone cladding	BLA	GC		L1.2	YES
9	CONCRETE RETAINING WALL	Vertical board-from retaining wall. 14" thick concrete walls with alternating board width (all exposed sides) and integral color.	BLA	GC		L1.2	YES
10	LOW TIMBER SEAT WALL	"2x6 Thermal treated Ash cladding", top-screw with 305 stainless steel, square-drive decking screws Sub-wall to be reinforced concrete or CMU. All exposed faces to receive timber siding	BLA	GC		L1.2	YES
11	LOW STONE SEAT WALL	'St Helena Cottage' Stone Cladding, with back mortar only ('dry joints') Full stone (90 degree) corners - no cut joints or exposed edges at corners Sub-wall to be reinforced concrete or CMU. All exposed faces to receive stone cladding	BLA	GC		L1.2	YES
12	WATER FEATURE	Cast-in-place concrete basin with with integral color and vertical board-form finish	BLA	GC + PC		L1.2	YES
13	MONOLITHIC LIMESTONE WATER BASIN W/ STONE SCUPPER	Feature to include remote equipment box with adjustable flow water pump and filter assembly	BLA	GC + PC		L1.2	YES
14	SPA	Above-ground, Pre-manufactured all tile spa by Bradford Products, or approved equal Spa to include concrete slab, safety rated cover and integral equipment	BLA + PC	PC	Concrete coping: integral color TBD, finish TBD 1/8" radius corners TYP.	L1.2	YES
15	COURTYARD GARDEN GATE	Material TBD	BLA	LC		L1.2	-
16	GRAPE STAKE FENCE	4' high welded wire 'Field Fencing' with 4x4 rough-sawn redwood posts	BLA	GC + LC		L1.2	YES
17	BARBEQUE ISLAND	Cast concrete with integral color	BLA	GC		L1.2	YES
18	PIZZA OVEN	Concrete structure with pre-manufactured concrete + ceramic wood oven insert. Oven and flu to be horizontal board-form concrete	BLA	GC		L1.2	YES
19	OUTDOOR FIREPLACE	Horizontal board-form concrete structure with stone hearth	BLA	GC		L1.2	YES
20	PRE-CAST CONCRETE FIRE FEATURE	42"x42" 'Bento' Fire pit by Palo Form, charcoal concrete finish, electronic ignition, dark grey river rock topping	BLA	GC		L1.2	YES
21	LANDSCAPE BOULDERS	Stone type to be decided  Key into grade where retaining	BLA	LC	Stone selection to be approved by Landscape Architect	L1.2	-












































1312 Patch Court Marina, CA 93933

www.blisslandscapearchitecture .com

А	apn:	239-111-009	
8	title:Final Design R	Review Submittal	
L			

Rev:	Date:	Description:		
	11.30.2017	Preliminary Design Review Submittal		
	03.08.2018	Final Design Review Submittal		




LANDSCAPE ARCHITECTURE 1312 Patch Court Marina, CA 93933

www.blisslandscapearchitecture.com

Santa Lucia Preserve, Lot 195 Potrero Trail Carmel Valley, CA 93923

drawn by: sheet size: 24"x36" 03.08.2018 Final Design Review Submittal Signature 03.08.18 Final Design Review Submittal



1312 Patch Court Marina, CA 93933 www.blisslandscapearchitecture.com

Santa Lucia Preserve, Lot 195 Potrero Trail Carmel Valley, CA 93923

drawn by: sheet size: 24"x36"

Final Design Review Submittal 03.08.2018

03.08.18 Final Design Review Submittal

#### IRRIGATION NOTES

- 1. THE CONTRACTOR SHALL REVIEW RELATED DRAWINGS AND SHALL ENSURE COORDINATION WITH ALL APPLICABLE TRADES PRIOR TO SUBMITTING BID.
- 2. THE IRRIGATION SYSTEM SHALL BE INSTALLED IN CONFORMANCE WITH ALL APPLICABLE STATE AND LOCAL CODES AND ORDINANCES BY LICENSED CONTRACTORS AND EXPERIENCED WORKERS. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL REQUIRED PERMITS AND FEES RELATING TO THEIR WORK.
- 3. THIS DESIGN IS DIAGRAMMATIC. ALL PIPING, VALVES, ETC. SHOWN WITHIN PAVED AREAS IS FOR DESIGN CLARIFICATION ONLY AND SHALL BE INSTALLED IN PLANTING AREAS WHERE POSSIBLE. AVOID ANY CONFLICTS BETWEEN THE SPRINKLER SYSTEM, PLANTING AND ARCHITECTURAL FEATURES.
- 4. PARALLEL PIPES MAY BE INSTALLED IN COMMON TRENCH. PIPES ARE NOT TO BE INSTALLED DIRECTLY ABOVE ONE ANOTHER. TRENCHES SHALL BE AMPLE SIZE TO PERMIT THE PIPES TO BE LAID AT THE ELEVATIONS INTENDED AND TO PERMIT SPACE FOR JOINING.
- 5. CONTRACTOR SHALL RESTORE SURFACES, EXISTING UNDERGROUND INSTALLATIONS, ETC., DAMAGED OR CUT AS A RESULT OF EXCAVATIONS, TO ORIGINAL CONDITIONS IN A MANNER APPROVED BY THE OWNER'S REPRESENTATIVE.

REPRESENTATIVE. IN THE EVENT THAT THIS NOTIFICATION IS NOT PERFORMED, THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.

- 6. DO NOT WILLFULLY INSTALL THE SPRINKLER SYSTEM AS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES OR DIFFERENCES IN THE AREA DIMENSIONS EXIST THAT MIGHT NOT HAVE BEEN CONSIDERED IN THE ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHOULD BE BROUGHT TO THE ATTENTION OF THE OWNER'S AUTHORIZED
- 7. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BECOME FAMILIAR WITH ALL GRADE DIFFERENCES, LOCATION OF WALLS, RETAINING WALLS, ETC. COORDINATE WORK WITH THE GENERAL CONTRACTOR AND OTHER SUBCONTRACTORS FOR THE LOCATION AND THE INSTALLATION OF PIPE SLEEVES THROUGH WALLS, UNDER ROADWAYS, PAVING, STRUCTURES, ETC. CONTRACTOR TO VERIFY THE LOCATION OF EXISTING UNDERGROUND UTILITIES AND STRUCTURES PRIOR TO THE EXCAVATION OF TRENCHES. CONTRACTOR IS TO REPAIR ANY DAMAGE CAUSED BY THEIR WORK AT NO ADDITIONAL COST TO THE OWNER.
- 8. DUE TO THE SCALE OF THE DRAWINGS, IT IS NOT POSSIBLE TO INDICATE ALL OFFSETS, FITTINGS, SLEEVES, ETC., WHICH MAY BE REQUIRED. CAREFULLY INVESTIGATE THE STRUCTURAL AND FINISHED CONDITIONS AFFECTING ALL WORK AND PLAN WORK ACCORDINGLY, FURNISHING SUCH FITTINGS, ETC., AS MAY BE REQUIRED TO MEET SUCH CONDITIONS. DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATIVE OF THE WORK TO BE INSTALLED. THE WORK SHALL BE INSTALLED IN SUCH A MANNER AS TO AVOID CONFLICTS BETWEEN IRRIGATION SYSTEMS, PLANTING, AND ARCHITECTURAL FEATURES.
- 9. ELECTRICAL CONTRACTOR TO SUPPLY 120 VAC (2.5 AMP) SERVICE TO CONTROLLER LOCATION. IRRIGATION CONTRACTOR TO MAKE FINAL CONNECTION FROM ELECTRICAL STUB-OUT TO CONTROLLER. IRRIGATION CONTROL WIRE SHALL BE #14, U.L. APPROVED FOR DIRECT BURIAL. COMMON WIRE SHALL BE #12 U.L. APPROVED AND SHALL BE WHITE IN COLOR. WIRING TO INDIVIDUAL REMOTE CONTROL VALVES SHALL BE COLOR OTHER THAN WHITE.
- 10. EACH CONTROLLER SHALL HAVE ITS OWN INDEPENDENT GROUND WIRE.
- 11. REMOTE CONTROL VALVES SHALL BE WIRED TO CONTROLLER IN SEQUENCE AS SHOWN ON PLANS. RUN WIRE FROM EACH RCV TO THE CONTROLLER. SPLICING WIRES TOGETHER OUTSIDE OF VALVE BOXES WILL NOT BE PERMITTED. ATTACH A LABEL TO CONTROL WIRE AT THE CONTROLLER AND ATTACH AN ID TAG AT EACH REMOTE CONTROL VALVE INDICATING CONTROLLER AND STATION
- 12. SPLICING OF 24-VOLT WIRES WILL NOT BE PERMITTED EXCEPT IN VALVE BOXES. LEAVE A 36" COIL OF EXCESS WIRE AT EACH SPLICE AND 100 FEET ON CENTER ALONG WIRE RUN. TAPE WIRE IN BUNDLES 10 FEET ON CENTER. NO TAPING PERMITTED INSIDE SLEEVES.
- 13. WIRE CONNECTORS SHALL BE 3M-DBR/Y-6 DIRECT BURY UNLESS OTHERWISE NOTED.
- 14. INSTALL ONE (1) SPARE CONTROL WIRE FOR EVERY 6 (SIX) STATIONS ON THE CONTROLLER ALONG THE ENTIRE MAIN LINE. SPARE WIRES SHALL BE THE SAME COLOR (ONE WITH A WHITE STRIPE) AND OF A DIFFERENT COLOR THAN OTHER CONTROL WIRES. LOOP 36" EXCESS WIRE INTO EACH SINGLE VALVE BOX AND INTO ONE VALVE BOX IN EACH GROUP OF VALVES.
- 15. INSTALL VALVE BOXES MINIMUM 12" FROM AND PERPENDICULAR TO WALK, CURB, BUILDING OR LANDSCAPE FEATURE. AT MULTIPLE VALVE BOX GROUPS, EACH BOX SHALL BE AN EQUAL DISTANCE FROM THE WALK, CURB, ETC. AND EACH BOX SHALL BE MINIMUM 12" APART. SHORT SIDE OF VALVE BOXES SHALL BE PARALLEL TO WALK, CURB, ETC.
- 16. PRESSURE REGULATING DEVICES ARE REQUIRED IF WATER PRESSURE IS BELOW OR EXCEEDS THE RECOMMENDED PRESSURE OF THE SPECIFIED IRRIGATION DEVICES.
- 17. LOCATE HOSE BIBS A MINIMUM OF 12" FROM HARDSCAPE AREA.
- 18. THOROUGHLY FLUSH MAIN LINE BEFORE INSTALLING VALVES.
- 19. ALL SPRINKLER HEADS SHALL BE SET PERPENDICULAR TO FINISH GRADE OF THE AREA TO BE IRRIGATED UNLESS OTHERWISE DESIGNATED ON THE PLANS.
- 20. CHECK VALVES OR ANTI-DRAIN VALVES ARE REQUIRED ON ALL SPRINKLER HEADS WHERE LOW POINT DRAINAGE COULD OCCUR. FOR DRIP OR BUBBLER CIRCUITS, INSTALL KING BROS. CV SERIES CHECK VALVES IN LATERAL LINES FOR EVERY 10' OF ELEVATION CHANGE.
- 21. FLUSH AND ADJUST ALL SPRINKLER HEADS FOR OPTIMUM PERFORMANCE AND TO PREVENT OVERSPRAY ONTO WALKS, ROADWAYS AND/OR BUILDINGS AS MUCH AS POSSIBLE. THIS SHALL INCLUDE SELECTING THE BEST DEGREE OF FIXED ARC (OR AN ADJUSTABLE ARC IF FIXED ARC DOES NOT MATCH THE ARC TO BE IRRIGATED) TO FIT THE SITE CONDITIONS AND TO THROTTLE THE FLOW CONTROL AT EACH VALVE TO OBTAIN THE OPTIMUM OPERATING PRESSURE FOR EACH SYSTEM. ALL MAIN LINES SHALL BE FLUSHED PRIOR TO THE INSTALLATION OF IRRIGATION HEADS, BUBBLERS AND DRIP TUBING. AT 30 DAYS AFTER INSTALLATION EACH SYSTEM SHALL BE FLUSHED TO ELIMINATE GLUE AND DIRT PARTICLES FROM THE LINES.
- 22. WHEN VERTICAL OBSTRUCTIONS (STREET LIGHTS, TREES, FIRE HYDRANTS, ETC.) INTERFERE WITH THE SPRAY PATTERN OF THE HEADS SO AS TO PREVENT PROPER COVERAGE, FIELD ADJUST THE SPRINKLER SYSTEM BY INSTALLING A QUARTER. THIRD OR HALF CIRCLE HEAD AT THE SIDES OF THE OBSTRUCTION SO AS TO PROVIDE PROPER COVERAGE. ALL ADJUSTMENTS SHALL BE MADE AT NO ADDITIONAL COST TO THE OWNER.
- 23. NOTIFY ARCHITECT OF ANY ASPECTS OF LAYOUT THAT WILL PROVIDE INCOMPLETE OR INSUFFICIENT WATER COVERAGE OF PLANT MATERIAL AND DO NOT PROCEED UNTIL HIS/HER INSTRUCTIONS ARE OBTAINED.
- 24. LOCATE BUBBLERS ON UPHILL SIDE OF TREES. TREE BUBBLERS ARE FOR ESTABLISHMENT AND DROUGHT CONDITIONS. THEY ARE TO BE TURNED OFF AFTER TREES ARE ESTABLISHED AND TURNED ON DURING DROUGHT CONDITIONS.
- 25. IN ADDITION TO THE SLEEVES AND CONDUITS SHOWN ON THE DRAWINGS, THE IRRIGATION CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE INSTALLATION OF SLEEVES AND CONDUITS OF SUFFICIENT SIZE UNDER ALL PAVED AREAS.
- 26. ALL EXCAVATIONS ARE TO BE FILLED WITH COMPACTED BACKFILL. BACKFILL MATERIAL SHALL BE THE EARTH EXCAVATED FROM THE TRENCH AND FREE OF ROCKS AND OTHER FOREIGN COURSE. MATERIAL. COMPACT BACKFULL TO A MINIMUM OF 90 PERCENT OF ORIGINAL SOIL DENSITY. REPAIR ALL SETTLED TRENCHES PROMPTLY, FOR A PERIOD OF 1 YEAR AFTER COMPLETION OF WORK.
- 27. CONTRACTOR SHALL WARRANT THAT THE IRRIGATION SYSTEM WILL BE FREE FROM DEFECTS IN MATERIALS AND WORKMANSHIP FOR A PERIOD OF 1 YEAR AFTER FINAL ACCEPTANCE OF WORK.
- 28. ALL CONSTANT PRESSURE PIPES SHALL BE TESTED AT A MINIMUM OF 125 PSI FOR TWO HOURS. CENTER LOAD PIPING WITH A SMALL AMOUNT OF BACKFILL TO PREVENT ARCHING OR SLIPPING UNDER PRESSURE. NO FITTINGS SHALL BE COVERED. REPAIR FAULTY JOINTS WITH NEW MATERIALS. DO NOT USE CEMENT OR CAULKING TO REPAIR LEAKS.
- 29. WHERE IT IS NECESSARY TO EXCAVATE ADJACENT TO EXISTING TREES, USE ALL POSSIBLE CARE TO AVOID INJURY TO TREES, AND TREE ROOTS. EXCAVATION IN AREAS WHERE 2 INCH AND LARGER ROOTS OCCUR SHALL BE DONE BY HAND. ROOTS 2 INCHES AND LARGER IN DIAMETER SHALL BE WRAPPED IN A PLASTIC BAG AND SECURED WITH A RUBBER BAND. TRENCHES ADJACENT TO TREE SHOULD BE CLOSED WITHIN 24 HOURS; WHERE THIS IS NOT POSSIBLE, THE SIDE OF THE TRENCH ADJACENT TO THE TREE SHALL BE KEPT SHADED WITH BURLAP OR CANVAS.
- 30. THE SPRINKLER SYSTEM DESIGN IS BASED ON THE MINIMUM OPERATING PRESSURE SHOWN ON THE IRRIGATION DRAWINGS. VERIFY WATER PRESSURE PRIOR TO CONSTRUCTION. REPORT ANY DIFFERENCE BETWEEN THE WATER PRESSURE INDICATED ON THE DRAWINGS AND THE ACTUAL PRESSURE READING AT THE IRRIGATION POINT OF CONNECTION TO THE OWNER'S AUTHORIZED
- 31. IRRIGATION DEMAND: REFER TO IRRIGATION POINTS OF CONNECTION.
- 32. CONTRACTOR SHALL VERIFY REMOTE AND WEATHER SENSOR RECEPTION TO THE RECEIVER PRIOR TO INSTALLING THE CONTROLLER. IF SIGNAL IS TOO WEAK, EXTEND THE RECEIVER OUT TO A MAXIMUM OF 10' FROM THE CONTROLLER USING A 6 PIN PHONE CABLE WITH FEMALE ADAPTER. IF RECEPTION IS STILL TOO WEAK, CONTACT THE LANDSCAPE ARCHITECT FOR FURTHER INSTRUCTION.
- 33. OPERATE IRRIGATION CONTROLLER(S) BETWEEN THE HOURS OF 10:00 PM AND 7:00 AM.
- 34. NOTIFY ALL LOCAL JURISDICTIONS FOR INSPECTION AND TESTING OF INSTALLED BACKFLOW PREVENTION DEVICE.
- 35. NOTIFY UNDERGROUND SERVICE ALERT AT 811 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION.
- 36. AT LEAST 10 DAYS PRIOR TO COMPLETION OF CONSTRUCTION, PROVIDE THE OWNER WITH A MAINTENANCE MANUAL. DATA SHALL BE ON 8 1/2" X 11" SHEETS, IN A 3-RING BINDER AND SHALL
- INDEX SHEET WITH CONTRACTOR'S CONTACT INFORMATION AND LIST OF EQUIPMENT WITH LOCAL MANUFACTURER'S REPRESENTATIVES.
- CATALOG AND PARTS SHEET OF ALL MATERIAL AND EQUIPMENT. COMPLETE OPERATING AND MAINTENANCE INSTRUCTIONS FOR ALL EQUIPMENT.
- COMPLETE AND DATED MANUFACTURER'S WARRANTIES.
- 37. AT COMPLETION OF MAINTENANCE PERIOD, PROVIDE OWNER WITH THREE (3) EACH OF ALL OPERATING AND SERVICING KEYS AND WRENCHES REQUIRED FOR COMPLETE MAINTENANCE AND OPERATION OF ALL HEADS AND VALVES. PROVIDE TWO (2) EACH OF KEYS TO CONTROLLER CABINETS.
- 38. A DIAGRAM OF THE IRRIGATION PLAN SHOWING HYDROZONES SHALL BE KEPT WITH THE IRRIGATION CONTROLLER FOR SUBSEQUENT MANAGEMENT PURPOSES.
- 39. A CERTIFICATE OF COMPLETION SHALL BE FILLED OUT AND CERTIFIED BY EITHER THE DESIGNER OF THE LANDSCAPE PLANS, IRRIGATION PLANS, OR THE LICENSED LANDSCAPE CONTRACTOR FOR THE PROJECT.
- 40. AN IRRIGATION AUDIT REPORT SHALL BE COMPLETED AT THE TIME OF FINAL INSPECTION.

#### **DRIPLINE NOTES:**

- 1. PLANS ARE DIAGRAMMATIC. INSTALL DRIPLINE AND COMPONENTS PER MANUFACTURERS INSTRUCTIONS AND INSTALLATION DETAILS.
- 2. INSTALL DRIPLINE A MAXIMUM OF 18" APART WITH EMITTERS TRIANGULARLY SPACED. INSTALL 2" FROM PERIMETER OF PLANTED AREA. THERE SHOULD BE A MINIMUM OF TWO DRIPLINE LATERALS IN EACH PLANTED AREA. DRIPLINE SHALL BE INSTALLED AT A CONSISTANT DEPTH THROUGHOUT THE CIRCUIT.
- 3. PLACE AIR/VACUUM RELIEF VALVES AT THE HIGHEST POINTS OF EACH ZONE AND JUST BELOW CHECK VALVES ON SLOPES. INSTALL ONE AIR/VACUUM RELIEF VALVE FOR EVERY 1125" OF TOTAL DRIPLINE PER ZONE.
- 4. PLACE FLUSH VALVES AT THE HYDRAULIC CENTER OF THE EXHAUST HEADER OR AT LOW POINT ON SLOPES. INSTALL MINIMUM OF ONE FOR EVERY 15 GPM.
- 5. INSTALL IN-LINE CHECK VALVES ON SLOPES GREATER THAN 3% AND WHERE LOW-LINE DRAINAGE COULD CAUSE WET AREAS IN THE LOWEST AREAS OF AN IRRIGATION ZONE. CHECK VALVES SHALL BE PLACED EVERY 4-5 FEET BETWEEN DRIPLINE LATERALS AND BEFORE THE FLUSH VALVE.
- 6. ON ALL SLOPES AND MOUNDS, PLACE THE DRIPLINE LATERALS PARALLEL TO THE SLOPE CONTOUR WHERE POSSIBLE. INCREASE THE LATERAL SPACING BY 25% ON THE LOWER ONE-THIRD OF THE SLOPE TO AVOID EXCESS DRAINAGE.
- 7. PVC SUPPLY AND FLUSH LINE SIZING GUIDE (ALL SUPPLY AND FLUSH LINES SHALL
- BE THE SAME SIZE FOR THE ENTIRE ZONE): 0-8 GPM – 3/4"
- 8.1-15 GPM 1"
- 15.1-25 GPM 1 1/4"
- 8. FITTINGS SHALL BE OF THE SAME MANUFACTURER AS DRIPLINE.
- 9. STAPLE DRIPLINE TO GROUND EVERY 3 FEET. USE ADDITIONAL STAPLES OVER EACH TEE, ELBOW OR CROSS. USE U-SHAPED STAPLES TO AVOID PINCHING THE
- 10. THOROUGHLY FLUSH EACH INSTALLATION SEGMENT TO ENSURE NO DEBRIS CONTAMINATION OCCURS.
- 11. RUN THE DRIPLINE SYSTEM EVERY DAY OR EVERY OTHER DAY TO ESTABLISH PLANT MATERIAL. MAINTAIN A CONSISTENT MOISTURE BALANCE IN THE SOIL. IT IS IMPORTANT TO KEEP THE SOIL MOIST WITHOUT SATURATION.

#### **DRIP IRRIGATION NOTES:**

- 1. THE CONTRACTOR SHALL PROVIDE A DRIP EMITTER SYSTEM FOR ALL TREES, SHRUBS, AND GROUNDCOVER AS INDICATED ON THE IRRIGATION PLAN AND DETAILS.
- 2. EMITTERS ARE NOT SHOWN ON THE IRRIGATION PLAN. ACTUAL LAYOUT OF EMITTER SYSTEM SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD USING THE IRRIGATION PLAN AND THE DRIP IRRIGATION DETAILS AS A GUIDE, WHILE USING THE PLANTING PLAN FOR THE LOCATION AND QUANTITIES OF EMITTERS.
- 3. EACH 15 GALLON SHRUB SHALL RECEIVE THREE 1 GPH EMITTERS DISTRIBUTED EVENLY AROUND SHRUB (TWO SHALL BE ON UPHILL SIDE OF SHRUB), VIA DISTRIBUTION TUBING. REFER TO THE PLANTING PLAN FOR THE LOCATION AND QUANTITY OF SHRUBS.
- 4. EACH 5 GALLON SHRUB SHALL RECEIVE TWO 1 GPH EMITTERS ON OPPOSITE SIDES AND UPHILL OF SHRUB, VIA DISTRIBUTION TUBING. REFER TO THE PLANTING PLAN FOR THE LOCATION AND QUANTITY OF SHRUBS.
- 5. EACH 1 GALLON SHRUB SHALL RECEIVE TWO 1/2 GPH EMITTERS ON OPPOSITE SIDES AND UPHILL OF SHRUB, VIA DISTRIBUTION TUBING. REFER TO THE PLANTING PLAN FOR THE LOCATION AND QUANTITY OF SHRUBS.
- 6. INSTALL THE EMITTERS ON TOP OF THE ROOT BALL AND AS FAR FROM THE TRUNK OF THE PLANT AS POSSIBLE.
- 7. DISTRIBUTION TUBING SHALL BE A MAXIMUM OF 5' IN LENGTH FROM 1/2" TUBING TO EMITTER. EACH LENGTH OF 1/2" DRIP TUBING SHALL BE A MAXIMUM OF 25'.
- 8. INSTALL FLUSH VALVES AT THE END OF THE RIGID PVC AS SHOWN ON PLANS.
- 9. ALL PVC LATERAL PIPE TO DRIP TUBING SHALL BE 3/4" UNLESS OTHERWISE NOTED.
- 10. THE DRIP EMITTER SYSTEM LAYOUT SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING CONSTRUCTION AND AFTER PLANTING HAS BEEN

#### IRRIGATION LEGEND

SYMBOL	MODEL NUMBER	DESCRIPTION	PS	FLOW RATE (GPM)	MAX. RADIU	MAX. SPACIN
$\bigcirc$	570Z-12P-PRX-COM-O-T-15H,Q	TORO 12" POP-UP SHRUB SPRAY	30	2.31,1.16,.58	S 15'	G 14'
<b>●</b> ∨ ▽	570Z-12P-PRX-COM-O-T-12F,H,Q	TORO 12" POP-UP SHRUB SPRAY	30	1.48,.74,.37	12'	11'
<b></b>	570Z-12P-PRX-COM-O-T-10F	TORO 12" POP-UP SHRUB SPRAY	30	1.03,.51,.23	10'	9'
	570Z-6PS-COM-PRN-TF	TORO 12" POP-UP SHRUB ROTATOR	40	2.56	20.9'	19'
$\bigvee$	570Z-6PS-COM-PRN-TA	TORO 12" POP-UP SHRUB ROTATOR	40	.5-1.62	20'	19'
	T-MCRG-206	TORO DL2000 MICROLINE INSTALL BETWEEN PAVING STONES	40	.53 GPH PE	R EMITTER	R
•	LF40-PC	TORO PRESSURE COMPENSATING DRIP BUBBLER INSTALL TWO BUBBLERS PER TREE	40	4 GPH	-	-
NOT SHOWN	T-DPC04-DC, T-DPC02-DC	TORO NGE SINGLE OUTLET EMITTER	40	1 GPH, 1/2	: GPH	
<b>A</b>	-	COMPRESSION FITTING STUB-OUT FROM PVC RIGID P	PE TO PO	DLY TUBING		
Δ	T-FCH-H-FIPT	TORO DL2000 FLUSH VALVE				
NOT SHOWN	T-YD-500-34	TORO DL2000 AIR VENT				
	T-DL-MP9	TORO DL2000 POP-UP OPERATION INDICATOR				
•	700-OMR-100 SERIES/LT-T SERIES	IRRITROL REMOTE CONTROL VALVE WITH PRESSURE	REGULA1	TON / KBI PVC BA	LL VALVE	
<b>&amp;</b>	DZK-700 / LT-1000-T	TORO DRIP ZONE VALVE KIT - INCL. REMOTE CONTROL AND PRESET PRESSURE REGULATOR / KBI SCH 80 PV			H 150 MESI	H SCREEN
•+	261LF	ARROWHEAD - CHAMPION HOSE BIB WITH INTEGRAL V	ACUUM E	BREAKER		
H	T-113-LF	NIBCO LEAD FREE GATE VALVE (LINE SIZE)				
	FSI-T10-000	CST 1" FLOW SENSOR				
	2160-H	GRISWOLD 1" MASTER CONTROL VALVE (NORMALLY C	PEN)			
X	975XL2-1"	WILKINS LEAD-FREE REDUCED PRESSURE BACKFLOW	PREVEN	TER		
	MODEL 55	BADGER 1" WATER METER (SUB-METER FOR IRRIGATION	ON)			
$\checkmark$	CL-100-WIRELESS	IRRITROL CLIMATE LOGIC WIRELESS WEATHER SENSO	)R			
C	MC-24E PROMAX-UA	IRRITROL 24 STATION MC-E CONTROLLER - WALL MOU PRO MAX UNIVERSAL MAINTENANCE REMOTE KIT	NT			
		CONTROLLER AND STATION NUMBER				
C-1 1.6	3	APPLICATION RATE (INCHES)				
1" 15 30		OPERATING PRESSURE (PSI) OR AIR RELIEF VALVE QU	JANTITY			
		APPROXIMATE GALLONS PER MINUTE				
		REMOTE CONTROL VALVE SIZE				
		MAIN LINE: 1120-SCHEDULE 40 PVC SOLVENT WELD PI SCHEDULE 40 PVC SOLVENT WELD FITTINGS. 18" COV		PE WITH SCHED	JLE 80 ANI	D
		LATERAL LINE: 1120-CLASS 200 PSI PVC SOLVENT WE SOLVENT WELD FITTINGS. 12" COVER.	LD PIPE V	VITH SCHEDULE 4	40 PVC	
		DRIP TUBING: TORO T-EHD1645 BLUE STRIPE HOSE W COVER. DISTRIBUTION TUBING: TORO EHW0437-010 1			GS. 4"	
		SUB-SURFACE DRIPLINE: TORO DL2000 RGP-218-10 D DL2000 DRIPLINE TRI-LOC FITTINGS. 2" COVER. (18" E				
		SLEEVE (SL): 1120-CLASS 200 PVC PLASTIC PIPE. 24" (				

BROOKWATER IRRIGATION CONSULTANTS 480 ST. JOHN STREET, SUITE 220 PLEASANTON, CA 94566 TEL 925.855.0417 FAX 925.855.0357 EMAIL JANET@BROOKWATER.COM

239-111-009 03.21.18 title: Final Design Review Submittal

NONE apn:


drawn by:


sheet size: 24"x36"

Date: Description: 11.30.2017 Preliminary Design Review Submittal 03.08.2018 Final Design Review Submittal




**BLISS** 








NOTE: EVENLY COAT METAL FITTINGS EXPOSED TO SOIL AND CONCRETE WITH 3M


SCOTCHRAP PIPE PRIMER AND THEN WRAP WITH 3M SCOTCHRAP NO. 51 BLACK

















PIPE AND WIRE TRENCHING

NOT TO SCALE



NOT TO SCALE








# Thomas Residence

Santa Lucia Preserve, Lot 195 Potrero Trail Carmel Valley, CA 93923


scale:	NONE	apn: 239-111-009	Rev:	Date:	Description:		LANDSCAPE
date:	03.21.18	title: Final Design Review Submittal		11.30.2017	Preliminary Design Review Submittal		Signature
drawn by	y: JL			03.08.2018	Final Design Review Submittal		Signature 04/30/19 Expiration
sheet siz	ze: 24"x36"						OF CALIFO





BLISS LANDSCAPE ARCHITECTURE 1312 Patch Court Marina, CA 93933

















1. CONNECT 5/8" TUBE TO PVC LATERAL LINE USING COMPRESSION FITTINGS. 2. 5/8" HOSE SHALL NOT RUN LONGER THAN 20' FROM PVC LATERAL LINE.

+ + + + + +



- ZONE FLUSH VALVE PLUMBED

MANIFOLD CONNECTION (PVC TO

TO PVC (TYP)

- PVC EXHAUST HEADER

— DRIPLINE LATERAL

— PVC SUPPLY HEADER

MANIFOLD CONNECTION

REGULATOR

MOUND OR BERM

HIGH POINT)

FROM EDGE

CENTER FEED INLINE DRIP LAYOUT

NOT TO SCALE

AIR/VACUUM RELIEF LATERAL BLANK TUBING CENTERED ON

AIR/VACUUM RELIEF VALVE

PERIMETER LATERAL 2"

- INLINE DRIP EMITTER

OPERATION INDICATOR


(O.C. SPACING TBD)

(PLUMBED TO TUBING AT EACH


REMOTE CONTROL VALVE

WITH FILTER AND PRESSURE


(12" DEPTH)


























6. AIR/VACUUM RELIEF LATERAL, BLANK POLY TUBING CENTERED ON MOUND OR

7. AIR/VACUUM RELIEF VALVE AT HIGH POINT. REFER TO AIR/VACUUM RELIEF VALVE DETAIL.

$\overbrace{23}$	
(23)	

AIR/VACUUM RELIEF LATERAL NOT TO SCALE







THOMAS NESIDENCE
Santa Lucia Preserve, Lot 195 Potrero Trail
Carmel Valley, CA 93923



**ISOMETRIC** 

FINISH GRADE.

DRIPLINE TEE FITTING.

DRIPLINE MPT ADAPTER.

DRIPLINE LATERAL.

DEPTH OF TUBING PER SPECIFICATIONS

PVC TEE (SxSxT) WITH 1/2" FPT OUTLET.

DEPTH OF PVC SUPPLY MANIFOLD PER SPECIFICATIONS.

PVC SUPPLY MANIFOLD FROM REMOTE CONTROL VALVE ASSEMBLY.


NOT TO SCALE

CENTER FEED MANIFOLD

BLANK POLY TUBING, LENGTH AS NECESSARY.

<u>LEGEND</u>

22





20

IRRIGATION DETAILS

BLISS LANDSCAPE ARCHITECTURE 1312 Patch Court Marina, CA 93933

BROOKWATER

IRRIGATION CONSULTANTS 480 ST. JOHN STREET, SUITE 220

PLEASANTON, CA 94566 TEL 925.855.0417 FAX 925.855.0357 EMAIL JANET@BROOKWATER.COM

03.08.18 Final Design Review Submittal

				THOMAS RESIDEN ICIENT LANDSCAF		т			
eference Evapotrans	oiration (Eto)	46.31							
ZONE PLAN' NO. TYPE	`	PLANT FACTOR (PF)	IRRIGATION METHOD**	IRRIGATION EFFICIENCY (IE)	ETAF (PF/IE)	HYDROZONE AREA (HA) (Sq Ft)	ETAF x HA	ESTIMATED TOTAL WATER USE (ETWU)	% LANDSCAPE AREA
EGULAR LANDSCAPE AF	EA								
C-1 SHRU	B LW	0.30	T D	0.81	0.37	303	112	3,222	2.7%
C-2 SHRUI		0.50	D	0.81	0.62	582	359	10,315	5.2%
C-3 THYME B		0.30	DL	0.81	0.37	170	63	1,808	1.5%
C-4 TREE		0.50	B	0.81	0.62	25	15	443	0.2%
C-5 SHRUI		0.30	DL	0.81	0.37	894	331	9,507	8.0%
C-6 SHRUI		0.30	DL	0.81	0.37	540	200	5,742	4.8%
C-7 SHRUI		0.30	DL	0.81	0.37	1,000	370	10,634	9.0%
C-8 SHRU		0.50	D	0.81	0.62	506	312	8,968	4.5%
C-9 NATIVE ME.		0.30	MR	0.75	0.40	1,450	580	16,653	13.0%
C-10 NATIVE ME.	ADOW LW	0.30	MR	0.75	0.40	1,126	450	12,932	10.1%
C-11 NATIVE ME.	ADOW LW	0.30	MR	0.75	0.40	770	308	8,843	6.9%
C-12 NATIVE ME.	ADOW LW	0.30	S	0.75	0.40	365	146	4,192	3.3%
C-13 NATIVE ME.	ADOW LW	0.30	S	0.75	0.40	505	202	5,800	4.5%
C-14 SHRU	3 VLW	0.20	D	0.81	0.25	213	53	1,510	1.9%
C-15 NATIVE ME.	ADOW LW	0.30	MR	0.75	0.40	800	320	9,188	7.2%
C-16 NATIVE ME.	ADOW LW	0.30	MR	0.75	0.40	1,262	505	14,494	11.3%
C-17 NATIVE ME.	ADOW LW	0.30	MR	0.75	0.40	525	210	6,030	4.7%
POOL / SPA COVERE	D WF	0.50		1.00	0.50	60	30	861	0.5%
FOUNTAIN	WF	0.80		1.00	0.80	63	51	1,464	0.6%
	SCAPE AREAS)					11,159	4,618	132,607	100.0%

*Hydrozone Description	Total Sq. Ft.	% of Landscape
Cool Season Turf (CST)	0	0.0%
Warm Season Turf (WST)	0	0.0%
High Water Use Plants (HW)	0	0.0%
Bioretention Plants (BR)	0	0.0%
Medium Water Use Plants (MW)	1,113	10.0%
Low Water Use Plants (LW)	9,710	87.0%
Very Low Water Use Plants (VLW)	213	1.9%
Water Feature	123	1.1%
Special Landscape Area (SLA)	0	0.0%
TOTAL	11,159	100.0%
**Irrigation Method	11,159 Total Sq. Ft.	
**Irrigation Method	,	
**Irrigation Method Rotor (FC-R, PC-R)	Total Sq. Ft.	% of Landscape
	Total Sq. Ft.	% of Landscape
**Irrigation Method  Rotor (FC-R, PC-R)  Multi-Stream Rotator (MR)  Spray (S)	Total Sq. Ft.  0 5,933	% of Landscape 0.0% 53.8%
**Irrigation Method  Rotor (FC-R, PC-R)  Multi-Stream Rotator (MR)  Spray (S)  Bubbler (B)  Drip (D)	Total Sq. Ft.  0 5,933 870 25 1,604	% of Landscape 0.0% 53.8% 7.9% 0.2% 14.5%
**Irrigation Method  Rotor (FC-R, PC-R)  Multi-Stream Rotator (MR)  Spray (S)  Bubbler (B)  Drip (D)  In-Line Drip (DL)	Total Sq. Ft.  0 5,933 870 25 1,604 2,604	% of Landscape 0.0% 53.8% 7.9% 0.2% 14.5% 23.6%
Rotor (FC-R, PC-R) Multi-Stream Rotator (MR) Spray (S) Bubbler (B)	Total Sq. Ft.  0 5,933 870 25 1,604	% of Landscape 0.0% 53.8% 7.9% 0.2% 14.5%



BLISS LANDSCAPE ARCHITECTURE 1312 Patch Court Marina, CA 93933 www.blisslandscapearchitecture.com

Thomas Residence Santa Lucia Preserve, Lot 195 Potrero Trail Carmel Valley, CA 93923

NONE apn: date: 03.21.18 title: Final Design Review Submittal drawn by: sheet size: 24"x36"

> 239-111-009 Rev: Date: Description: 11.30.2017 Preliminary Design Review Submittal 03.08.2018 Final Design Review Submittal

## MONTEREY LANDSCAPE WATER USE STATEMENT

COUNTY OF

PROJECT NAME: THOMAS RESIDENCE
PROJECT ADDRESS: LOT 195 POTRERO TRAIL, SANTA LUCIA PRESERVE

JANET LUEHRS (CID, CLIA #43274) BROOKWATER INC., IRRIGATION CONSULTANTS PREPARED BY:

480 SAINT JOHN STREET, SUITE 220 PLEASANTON, CA 94566 925-855-0417 925-855-0357 (FAX) Janet@Brookwater.com (e-mail)

"I have complied with the criteria of the ordinance and applied them accordingly for the efficient use of water in the irrigation design plan."

Signed: Janet Luchus

PART ONE	MAXIMUM APPLIED WATER ALLOWANCE (MAWA)	
		$MAWA = ETo \times .62 \times [(ETAFx HA) + ((1-ETAF) \times SLA)]$
	YEARLY ETo	46.3
	CONVERSION FACTOR	0.62
	ETAF	0.55
	TOTAL IRRIGATED LANDSCAPE AREA (HA)	11,159 SQUARE FEET
	SPECIAL LANDSCAPE AREA (SLA)	0 SQUARE FEET
	LANDSCAPE WATER ALLOWANCE	176,220 GALLONS PER YEAR
	TOTAL ACRE FEET	0.54 ACRE FEET

PART TWO	ESTIMATED TOTAL WATER USE (ETWU)		
	(AVERAGE <i>ETAF</i> AND <i>ETWU</i> FRO	(AVERAGE <i>ETAF</i> AND <i>ETWU</i> FROM WATER EFFICIENT LANDSCAPE WORKSHEET)	
	AVERAGE ETAF FOR REGULAR LANDSCAPE AREAS (TOTAL ETAF x AREA / TOTAL AREA)	0.41	
	ETWU FOR REGULAR LANDSCAPE AREAS	132,607 GALLONS PER YEAR	
	SITE WIDE ETAF	0.41	
	ETWU FOR ALL LANDSCAPE AREAS	132,607 GALLONS PER YEAR	
	TOTAL ACRE FEET	0.41 ACRE FEET	



