Before the Zoning Administrator in and for the County of Monterey, State of California

In the matter of the application of:

SANSAMAR LLC (PLN170005)

RESOLUTION NO. 19-002

Resolution by the Monterey County Zoning Administrator:

- 1. Find that the project involves the demolition and construction of a new single family dwelling, which qualifies as a Class 3 Categorical Exemption pursuant to Section 15303 (a) of the CEQA Guidelines, and there are no exceptions pursuant to Section 15300.2; and
- 2. Approve a Combined Development Permit consisting of:
 - a. Coastal Administrative Permit for the demolition of an existing one-story single family dwelling;
 - b. Coastal Administrative Permit and Design Approval for the construction of an approximately 3,460 square foot two-story single family dwelling with and approximately 645 square foot attached garage; and
 - c. Coastal Development Permit for the removal of three (3) Oak trees.

24330 San Pedro Lane, Carmel, Carmel Land Use Plan, Coastal Zone (APN: 009-032-005-000)

The SANSAMAR application (PLN170005) came on for a public hearing before the Monterey County Zoning Administrator on January 10, 2019. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Monterey County Zoning Administrator finds and decides as follows:

FINDINGS AND EVIDENCE

1. **FINDING: CONSISTENCY** – The project, as conditioned, is consistent with the

applicable plans and policies which designate this area as appropriate

for development.

EVIDENCE: a) The project has been reviewed for consistency with the text, policies, and regulations in:

- 1982 Monterey County General Plan (General Plan);
- Carmel Area Land Use Plan (CAR LUP);
- Monterey County Coastal Implementation Plan, Part 4 (CIP);
- Monterey County Zoning Ordinance (Title 20);

No conflicts were found to exist. The subject property is located within the Coastal Zone; therefore, the 2010 Monterey County General Plan does not apply.

- b) Allowed Use. The property is located at 24330 San Pedro Lane, Carmel [Assessor's Parcel Number (APN) 009-032-005-000], Carmel Area Land Use Plan (LUP), Coastal Zone. The parcel is zoned Medium Density Residential, with a maximum density of 2 units per acre and a Design Control Overlay (Coastal Zone) [MDR/2-D(CZ)]. The MDR zoning district allows single-family dwellings as a principally permitted use subject to a Coastal Administrative Permit in each case (20.12.040.A). The project includes development related to the residential use of the property and therefore, the proposed project is a use allowed on the site. Standards for granting a Coastal Administrative Permit have been met in this case.
- c) <u>Lot Legality</u>. The subject parcel (0.54 acres), APN 009-032-005-000, is located on a residential subdivision created through map of "Third addition to Carmel Woods" and recorded on October 3, 1927 in Volume 3 of Maps, Cities and Towns, Page 47. Therefore, the County recognizes the subject parcel as a legal lot of record.
- d) <u>Design</u>. Pursuant to Chapter 20.44 of Title 20, the project site and surrounding area are designated as a Design Control Zoning District ("D" zoning overlay), which regulates the location, size, configuration, materials, and colors of structures and fences to assure the protection of the public viewshed and neighborhood character. The Applicant proposes exterior colors and materials that are consistent with the residential setting. The existing single family dwelling is a Californian Ranch style home, originally constructed in 1985, that sits along the northwestern portion of the lot. The new single family dwelling will have a contemporary architectural style and constitute colors and materials such as: an earth tone grey with tan cedar siding and carmel stone veneer accents, non-reflective zinc standing seam metal roofing and dark brown wood trim.

The location of the new single family dwelling will continue to have a footprint that lies within the northwestern portion of the parcel, but also extend towards the southern end. The second story of the home will remain towards the northern half of the parcel creating a majority of the visibility from the east and west elevations. The east elevation of the home is visible from San Pedro Lane; however, the home is screened with existing vegetation such as Monterey Pine and Coast Live Oak Trees. Further, the neighborhood consists of both one-story and two-story single family dwellings that have colors and materials subordinate to the surrounding environment. The architectural style of the homes in the neighborhood ranged between contemporary, spanish and ranch style homes. The materials, location and nature of the project are consistent with the neighborhood character and will not detract the visual integrity of the site.

Although the project will create a new structure larger in mass and size than the existing, it will not impact any visual resources viewed from a public viewing area. Map A of the CAR LUP illustrates that the subject property is not located within a viewshed area, as the property is not visible from Highway 1 or any other major public use area such as 17-Mile Drive, views of Pescadero Canyon, Scenic

- Road, and Point Lobos Reserve. Therefore, the project would not create any substantial visual impacts.
- Review of Development Standards. The subject parcel is zoned Medium Density Residential, 2 units per acre with a Design Control overlay within the Coastal Zone or "MDR/2-D (CZ)." The minimum setback required in this zoning district is a front setback of 20 feet, side setback of 5 feet and rear setback of 10 feet. Consistent with these standards, the proposed development maintains a 95 foot front setback, 5 foot side setback and 10 foot rear setback. The maximum building site coverage allowed is 35% and the proposed coverage is 19.1%. The maximum Floor Area Ratio (FAR) of the property is 45% and the FAR for the proposed development is at 21.1%. The proposed height of 23.5 feet, meets the maximum 30 feet allowed by zoning. Therefore, pursuant to Title 20 and as proposed, the project conforms to applicable development standards.
- f) Parking. Pursuant to Chapter 20.58 (Regulations for Parking) under Title 20, all residential developments shall have at least 1 covered parking space; covered parking shall count toward the two (2) required parking spaces. The project includes the construction of an approximately 645 square foot attached two car garage. Therefore, this project meets the parking requirements listed under Residential Use.
- g) <u>Public Access.</u> As demonstrated in Finding 6, the development is consistent with public access policies of the CAR LUP.
- h) The project was referred to the Carmel/Carmel Highlands Land Use Advisory Committee (LUAC) for review. Based on the LUAC Procedure guidelines adopted by the Monterey County Board of Supervisors, this application warranted referral to the LUAC because the development required Design Approval and approval at a public hearing. A motion to support the project was made with the members voting 6-0-1.
- i) Staff conducted a site inspection on December 18, 2018 to verify that the project on the subject property conforms to the plans submitted.
- j) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in RMA-Planning File No. PLN170005.
- 2. **FINDING: SITE SUITABILITY -** The site is physically suitable for the proposed use.
 - **EVIDENCE:** a) The project includes minor improvements associated with an established residential use in a residential neighborhood.
 - b) The project was reviewed by RMA-Planning, Cypress CSD Fire Protection District, RMA-Public Works, RMA-Environmental Services and Environmental Health Bureau. There has been no indication from these departments/agencies that the site is not suitable for the proposed development. Conditions recommended have been incorporated.

The following reports have been prepared and submitted with the application:

- Historic Report (LIB180377) prepared by Seth A. Bergstein, Pacific Grove, CA on August 3, 2016

- Tree Assessment/Forest Management Plan (LIB180378) prepared by Frank Ono, Pacific Grove, CA on September 11, 2018
- Geotechnical Report (LIB180379) prepared by Grice Engineering, Inc., Salinas, CA on September 21, 2018 County staff independently reviewed these reports and concurs with their conclusions. There are no further physical or environmental

their conclusions. There are no further physical or environmental constraints that would indicate that the site is not suitable for the use proposed. All development shall be in accordance with these reports.

- c) Staff conducted a site inspection on December 18, 2018 to verify that the site is suitable for this use.
- d) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN170005.

3. **FINDING:**

TREE REMOVAL – The siting, location, size and design has been established to minimize tree removal and has been limited to that required for the overall health and long-term maintenance of the property.

EVIDENCE: a)

- The development includes removal of three (3) Oak trees. Pursuant to Section 20.146.060 of the CIP, a Coastal Development Permit must be obtained for the removal of trees. A Forest Management Plan (LIB180378) was prepared for the property, which identified the site as constrained by pre-existing conditions and lack of available space due to the property being forested with Monterey Pine and Coast Live Oak trees. The trees range in health condition from good, fair and poor. The three (3) Oak trees being removed are all in fair health condition with one having a diameter of 15" and the other two (2) having a diameter of 8". The Forest Management Plan recommended replanting at a 1:1 ratio with three (3) five-gallon Coast live oaks trees in locations with the greatest opening on the parcel. Further recommendations such as pre-construction meeting and tree protection have been incorporated as standard conditions.
- b) The 15" Oak tree is located at the east elevation of the existing home and is already near the front of the home. The remaining two (2) Oak trees are at the southern end of the parcel and will lie within the building footprint of the proposed home. The property was analyzed to determine the best siting and location that would minimize tree removal. However, any adjustments to the proposed development would possibly result in other trees, larger in size, being impacted. The reduction of the development was taken into consideration but due to the proximity of the trees to the structure, the roots of the trees could possibly be obstructed, or the trees could potentially be a hazard to the home. The siting, location, size and design of the proposed development best suits the parcel and minimizes tree removal.
- c) Staff conducted a site inspection on December 18, 2018 to verify that the site is suitable for this use.
- d) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in RMA-Planning File No. PLN170005.

4. **FINDING:**

HEALTH AND SAFETY – The establishment, maintenance, or operation of the project applied for will not under the circumstances of this particular case be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use, or be detrimental or injurious to property and improvements in the neighborhood or to the general welfare of the County.

EVIDENCE: a)

- The project was reviewed by RMA-Planning, Cypress CSD Fire Protection District, RMA-Public Works, RMA-Environmental Services, and Environmental Health Bureau, and conditions have been recommended, where appropriate, to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
- b) Necessary public facilities are existing on the subject property. California American Water Company is the domestic water purveyor and the Carmel Area Wastewater District provides wastewater services. The project would not require intensification of services already provided.
- c) The project includes minor improvements associated with an established residential use in a residential neighborhood.
- d) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in RMA-Planning File No. PLN170005.

5. **FINDING:**

NO VIOLATIONS - The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision, and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.

EVIDENCE: a)

- a) Staff reviewed Monterey County RMA-Planning and RMA-Building Services records and is not aware of any violations existing on subject property.
- b) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN170005.

6. **FINDING:**

CEQA (Exempt): - The project is categorically exempt from environmental review and no unusual circumstances were identified to exist for the proposed project.

EVIDENCE:

- a) California Environmental Quality Act (CEQA) Guidelines Section 15303 (a) categorically exempts construction of new accessory structures.
- b) The proposed project is to allow the demolition of an existing single family dwelling and construction of a two-story single family dwelling and attached garage (approximately 4,105 square feet). Therefore, the project qualifies for a Class 3 categorical exemption pursuant to Section 15303 (a) of the CEQA guidelines.
- c) No adverse environmental effects were identified during staff review of the development application.
- d) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. The project does not involve a designated historical resource (See evidence Finding 2), a hazardous waste site,

- development located near or within view of a scenic highway, unusual circumstances that would result in a significant effect or development that would result in a cumulative significant impact.
- e) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN170005.

7. **FINDING:**

PUBLIC ACCESS – The project is in conformance with the public access and recreation policies of the Coastal Act (specifically Chapter 3 of the Coastal Act of 1976, commencing with Section 30200 of the Public Resources Code) and applicable Local Coastal Program, and does not interfere with any form of historic public use or trust rights.

EVIDENCE: a)

- No access is required as part of the project as no substantial adverse impact on access, either individually or cumulatively, as described in Section 20.146.130 of the CIP can be demonstrated.
- b) No evidence or documentation has been submitted or found showing the existence of historic public use or trust rights over this property.
- c) The subject project site is not described as an area where the Local Coastal Program requires public access (Figure 3, Local Coastal Program Public Access, in the Carmel Area Land Use Plan.
- d) Staff conducted a site inspection on December 18, 2018.
- e) The application, plans and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN170005.

8. **FINDING:**

APPEALABILITY - The decision on this project may be appealed to the Board of Supervisors and the California Coastal Commission.

EVIDENCE: a)

- <u>Board of Supervisors</u>. Pursuant to Section 20.86.030 of Title 20, an appeal may be made to the Board of Supervisors by any public agency or person aggrieved by a decision of an Appropriate Authority other than the Board of Supervisors.
- b) <u>Coastal Commission</u>. Pursuant to Section 20.86.080.A of Title 20, the project is subject to appeal by/to the California Coastal Commission because it involves development that is permitted in the underlying zone as a conditional use.

DECISION

NOW, THEREFORE, based on the above findings and evidence, the Planning Commission does hereby:

- 1. Find that the project involves the construction of a new single family dwelling, which qualifies as a Class 3 Categorical Exemption pursuant to Section 15303 (a) of the CEQA Guidelines, and there are no exceptions pursuant to Section 15300.2; and
- 2. Approve a Combined Development Permit consisting of:
 - a. Coastal Administrative Permit for the demolition of an existing one-story single family dwelling;
 - b. Coastal Administrative Permit and Design Approval for the construction of an approximately 3,460 square foot two-story single family dwelling with and approximately 645 square foot attached garage; and
 - c. Coastal Development Permit for the removal of three (3) Oak trees, in general conformance with the attached sketch and subject to the attached conditions, all being attached hereto and incorporated herein by reference.

PASSED AND ADOPTED this 10th day of January, 2019.

Mike Novo, Zoning Administrator

COPY OF THIS DECISION MAILED TO APPLICANT ON JAN 11 2019

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE JAN 2 2 2019

THIS PROJECT IS LOCATED IN THE COASTAL ZONE AND IS APPEALABLE TO THE COASTAL COMMISSION. UPON RECEIPT OF NOTIFICATION OF THE FINAL LOCAL ACTION NOTICE (FLAN) STATING THE DECISION BY THE FINAL DECISION MAKING BODY, THE COMMISSION ESTABLISHES A 10 WORKING DAY APPEAL PERIOD. AN APPEAL FORM MUST BE FILED WITH THE COASTAL COMMISSION. FOR FURTHER INFORMATION, CONTACT THE COASTAL COMMISSION AT (831) 427-4863 OR AT 725 FRONT STREET, SUITE 300, SANTA CRUZ, CA.

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

NOTES

1. You will need a building permit and must comply with the Monterey County Building Ordinance in every respect.

Additionally, the Zoning Ordinance provides that no building permit shall be issued, nor any use conducted, otherwise than in accordance with the conditions and terms of the permit granted or until ten days after the mailing of notice of the granting of the permit by the appropriate authority, or after granting of the permit by the Board of Supervisors in the event of appeal.

Do not start any construction or occupy any building until you have obtained the necessary permits and use clearances from Monterey County RMA-Planning and RMA-Building Services offices in Salinas.

2. This permit expires 3 years after the above date of granting thereof unless construction or use is started within this period.

Monterey County RMA Planning

Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN170005

1. PD001 - SPECIFIC USES ONLY

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Combined Development Permit consisting of: 1) Coastal Administrative Permit for the demolition of an existing one-story single family dwelling; 2) Coastal Administrative Permit and Design Approval for the construction of an approximately 3,460 square foot two-story single family dwelling with and approximately 645 square foot attached garage; and 3) Coastal Development Permit for the removal of three (3) Oak trees. The property is located at 24330 San Pedro Lane, Carmel (Assessor's Parcel Number 009-032-005-000), Carmel Land Use Plan, Coastal Zone. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the Director of RMA - Planning. Any use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

Compliance or Monitoring Action to be Performed: The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

Print Date: 1/10/2019 1:03:58PM Page 1 of 8

2. PD002 - NOTICE PERMIT APPROVAL

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

The applicant shall record a Permit Approval Notice. This notice shall state:

"A Combined Development Permit (Resolution Number 19-002) was approved by the Zoning Administrator for Assessor's Parcel Number 009-032-005-000 on January 10, 2019. The permit was granted subject to 16 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the Director of RMA - Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

Responsible Department:

RMA-Planning

Condition/Mitigation Monitoring Measure:

during course of construction, cultural, archaeological, historical paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified Monterey County RMA - Planning and a professional archaeologist can evaluate it. qualified archaeologist (i.e., an archaeologist registered with the immediately contacted Professional Archaeologists) shall be by the When contacted, the project planner and the archaeologist individual present on-site. shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.

(RMA - Planning)

Compliance or Monitoring Action to be Performed: The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

Print Date: 1/10/2019 1:03:58PM Page 2 of 8

4. PD006(A) - CONDITION COMPLIANCE FEE

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

The Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors, for the staff time required to satisfy conditions of approval. The fee in effect at the time of payment shall be paid prior to clearing any conditions of approval.

Compliance or Monitoring Action to be Performed:

Prior to clearance of conditions, the Owner/Applicant shall pay the Condition Compliance fee, as set forth in the fee schedule adopted by the Board of Supervisors.

5. PD047 - DEMOLITION/DECONSTRUCTION (MBUAPCD RULE 439)

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

In accordance with Monterey Bay Unified Air Pollution Control District Rule 439, construction plans shall include "Demolition and Deconstruction" notes that incorporate the following work practice standards:

- 1. Sufficiently wet the structure prior to deconstruction or demolition. Continue wetting as necessary during active deconstruction or demolition and the debris reduction process;
- 2. Demolish the structure inward toward the building pad. Lay down roof and walls so that they fall inward and not away from the building;
- 3. Commencement of deconstruction or demolition activities shall be prohibited when the peak wind speed exceeds 15 miles per hour.

All Air District standards shall be enforced by the Air District.

(RMA - Planning)

Compliance or Monitoring Action to be Performed:

Prior to the issuance of а demolition permit. applicable. the Owner/Applicant/Contractor "Demolition/Deconstruction" shall incorporate а the demolition site plan that includes, but is not limited to, the standards set forth in this condition.

During demolition, the Owner/Applicant/Contractor shall obtain any required Air District permits and the Air District shall conduct all deconstruction or demolition inspection activities as required by the Air District.

Print Date: 1/10/2019 1:03:58PM Page 3 of 8

6. PD016 - NOTICE OF REPORT

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Prior to issuance of building or grading permits, a notice shall be recorded with the Monterey County Recorder which states:

"A Forest Management Plan (LIB180378) has been prepared for this parcel by Frank Ono, Urban Forester, on September 11, 2018, and is on file in Monterey County RMA - Planning. All tree removal on the parcel must be in accordance with this Forest Management Plan."

(RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of grading and building permits, the Owner/Applicant shall submit proof of recordation of this notice to RMA - Planning.

Prior to occupancy, the Owner/Applicant shall submit proof, for review and approval, that all development has been implemented in accordance with the report to the RMA - Planning.

7. PD052 - PRE-CONSTRUCTION MEETING

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure:

Prior to the commencement grading construction activities. of any pre-construction meeting shall be held on the site. The meeting shall include representatives of each of the selected contractors, any consultant who will conduct required monitoring, the Owner/Applicant, the RMA-Planning Department and other appropriate County Departments. The purpose of the meeting is to review the conditions of approval that are applicable to the grading and construction of the approved development. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

Prior to commencement of any grading or construction activities, the Owner/Applicant shall contact RMA-Planning to schedule a pre-construction meeting prior to commencement of any grading or construction activities. The Owner/Applicant shall be responsible for ensuring that all appropriate contractors and technical consultants are in attendance. RMA-Planning staff shall be responsible for identifying and notifying other County Departments that should attend the meeting (if applicable).

Print Date: 1/10/2019 1:03:58PM Page 4 of 8

8. PD011 - TREE AND ROOT PROTECTION

Responsible Department: RMA-Planning

Condition/Mitigation **Monitoring Measure:**

Trees which are located close to construction site(s) shall be protected from inadvertent damage from construction equipment by fencing off the canopy driplines and/or critical root zones (whichever is greater) with protective materials, wrapping trunks with protective materials, avoiding fill of any type against the base of the trunks and avoiding an increase in soil depth at the feeding zone or drip-line of the retained Said protection, approved by certified arborist, shall be demonstrated prior to issuance of building permits subject to the approval of RMA - Director of Planning. there is any potential for damage, all work must stop in the area and a report, with mitigation measures, shall be submitted by certified arborist. Should any additional trees not included in this permit be harmed, during grading or construction activities, in such a way where removal is required, the owner/applicant shall obtain required permits. (RMA - Planning)

Compliance or Monitoring Action to be Performed:

Prior to issuance of grading and/or building permits, the Owner/Applicant shall submit evidence of tree protection to RMA - Planning for review and approval.

During construction, the Owner/Applicant/Arborist shall submit on-going evidence that tree protection measures are in place through out grading and construction phases. damage is possible, submit an interim report prepared by a certified arborist.

Prior to final inspection, the Owner/Applicant shall submit photos of the trees on the property to RMA-Planning after construction to document that tree protection has been successful or if follow-up remediation or additional permits are required.

PLN170005

Print Date: 1/10/2019 1:03:58PM Page 5 of 8

9. PD048 - TREE REPLACEMENT/RELOCATION

Responsible Department: RMA-Planning

Condition/Mitigation **Monitoring Measure:**

Prior to final inspection of the building permit, the applicant shall replace each tree approved for removal as follows:

- Replacement ratio: 1:1 for a total of three (3) five (5) gallon Coast live oak trees in locations with the greatest opening in the stand to allow for a minimum of competition and maximum sunlight. (If five (5) gallons are unavailable, smaller sizes may be substituted). Spacing between trees should be at least 8 feet. Occasional deep watering (more than two weeks apart) during the late spring, summer and fall is recommended for the first two years after establishment.
- Replacement ratio recommended by arborist: 1:1 for a total of three (3) five (5) gallon Coast live oak trees in locations with the greatest opening in the stand to allow for a minimum of competition and maximum sunlight. (If five (5) gallons are unavailable, smaller sizes may be substituted). Spacing between trees should be at least 8 feet. Occasional deep watering (more than two weeks apart) during the late spring, summer and fall is recommended for the first two years after establishment.

Replacement tree(s) shall be located within the same general location as the tree being removed. (RMA - Planning)

Compliance or Monitoring **Action to be Performed:**

The Owner/Applicant shall submit evidence of tree replacement to RMA-Planning for review and approval. Evidence shall be a receipt for the purchase of the replacement tree(s) and photos of the replacement tree(s) being planted.

Six months after the planting of the replacement tree(s), the Owner/Applicant shall submit evidence demonstrating that the replacement tree(s) are in a healthy, growing condition.

One year after the planting of the replacement tree(s), the Owner/Applicant shall submit a letter prepared by a County-approved tree consultant reporting on the health of the replacement tree(s) and whether or not the tree replacement was successful or if follow-up remediation measures or additional permits are required.

Page 6 of 8

Print Date: 1/10/2019 1:03:58PM

10. PW0044 - CONSTRUCTION MANAGEMENT PLAN

Responsible Department: RMA-Public Works

Condition/Mitigation Monitoring Measure:

The applicant shall submit a Construction Management Plan (CMP) to RMA-Planning and RMA - Public Works for review and approval. The CMP shall include measures to minimize traffic impacts during the construction/grading phase of the project.

CMP shall include, at a minimum, duration of the construction, hours of operation, truck routes, estimated number of truck trips that will be generated, number of construction workers, and on-site/off-site parking areas for equipment and workers and locations of truck staging areas. Approved measures included in the CMP shall be implemented by the applicant during the construction/grading phase of the project.

Compliance or Monitoring Action to be Performed: 1. Prior to issuance of the Grading Permit or Building Permit, Owner/Applicant/Contractor shall prepare a CMP and shall submit the CMP to the RMA-Planning Department and the

Department of Public Works for review and approval.

2. On-going through construction phases Owner/Applicant/Contractor shall implement the

approved measures during the construction/grading phase of the project.

11. STORMWATER CONTROL PLAN (PR1)

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall submit a stormwater control plan addressing the Post-Construction Requirements (PCRs) for Development Projects in the Central Coast Region. The stormwater control plan shall incorporate the measures identified on the completed the Site Design and Runoff Reduction Checklist. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or building permits, the applicant shall submit a stormwater control plan to RMA-Environmental Services for review and approval.

12. GRADING PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall submit a grading plan incorporating the recommendations in the project Geotechnical Report prepared by Grice Engineering, Inc., dated September 21, 2018. The grading plan shall include contour lines and cross-sections that identify the existing grade, proposed grade, and the extent of any proposed excavation and/or fill. The grading plan shall include the geotechnical inspection schedule that identifies when the inspections will be completed, who will conduct the inspection (i.e., PG, PE, and/or Special Inspector), a description of the required inspection, inspector name, and the completion date. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to issuance of any grading or building permits, the applicant shall submit a grading plan to RMA-Environmental Services for review and approval.

Print Date: 1/10/2019 1:03:58PM Page 7 of 8

13. EROSION CONTROL PLAN

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:

The applicant shall submit an erosion control plan in conformance with the requirements of Monterey County Code Chapter 16.12. The erosion control plan shall include a construction entrance, concrete washout, stockpile area(s), material storage area(s), portable sanitation facilities and waste collection area(s), as applicable. The plan shall also include RMA-Environmental Services standard inspection notes 1, 2, & 3. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed:

Prior to issuance of any grading or building permits, the applicant shall submit an erosion control plan to RMA-Environmental Services for review and approval. Standard inspection notes are available on the RMA-Environmental Services website.

14. GEOTECHNICAL PLAN REVIEW

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The applicant shall provide certification from the licensed practitioner that their geotechnical recommendations have been incorporated into the approved grading plan and stormwater control plan. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to issuance of any grading or construction permits, the applicant shall provide certification from the licensed practitioner(s).

15. WINTER INSPECTIONS - AREAS OF SPECIAL BIOLOGICAL SIGNIFICANCE (ASBS)

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure: The owner/applicant shall schedule weekly inspections with RMA-Environmental Services during the rainy season, October 15th to April 15th, to ensure contaminants are not discharged into the Carmel Bay Area of Special Biological Significance. This inspection requirement shall be noted on the Erosion Control Plan. (RMA-Environmental Services)

Compliance or Monitoring Action to be Performed: During construction, the owner/applicant shall schedule weekly inspections with RMA-Environmental Services in the rainy season (October 15th to April 15th).

16. AS-BUILT CERTIFICATION

Responsible Department: Environmental Services

Condition/Mitigation Monitoring Measure:


Prior to final inspection, the applicant shall provide a letter from a licensed engineer certifying that all development has been constructed in accordance with the recommendations in the Geotechnical Report and the approved grading plan and stormwater control plan. (RMA- Environmental Services)

Compliance or Monitoring Action to be Performed: Prior to final inspection, the owner/applicant shall provide RMA-Environmental Services a letter from a licensed practitioner.

Print Date: 1/10/2019 1:03:58PM Page 8 of 8

ADAMS RESIDENCE

carmel, california



jtp@justinpaulyarchitects.com LANDSCAPE LIGHTING PLAN CA LICENSE #C32962 LANDSCAPE IRRIGATION PLAN WATER USE SURVEYOR: WHITSON ENGINEERS LANDSCAPE PLANTING PLAN 9699 BLUE LARKSPUR LANE LANDSCAPE SITE SECTION / ELEVATION & MONTEREY, CA 93940 **GARDEN ELEMENT IDEAS** P. 831.649.5225 (2) COVERED SPACES PROVIDED. 2) COVERED REQ. P. 831.373.5065 30'-0" (MAIN STRUCTURE) SITE DEMOLITION PLAN MINIMAL. LESS THAN 100 CU.YD. **GRICE ENGINEERING AND GEOLOGY** PROPOSED ARCHITECTURAL SITE PLAN FOUNDATION SAM GRICE **EROSION CONTROL & CONSTRUCTION EXCAVATION SPOILS** 561 BRUNKEN AVE. MANAGEMENT PLAN SALINAS, CA 93901 TREE REMOVAL: SEE TABLE BELOW FIRST FLOOR PLAN ALLOWABLE LOT COVERAGE SECOND FLOOR PLAN FLOOR AREA RATIO SEE TABLE BELOW HALL LANDSCAPE DEISGN **ROOF PLAN** SCOTT HALL **BUILDING CODE DATA** NORTH & WEST ELEVATIONS 582 LIGHTHOUSE AVE. SUITES 3&4 R-3 (RESIDENCE) U (GARAGE) OCCUPANCY: PACIFIC GROVE, CA 93950 **SOUTH & EAST ELEVATIONS CONSTRUCTION TYPE** C: 831:901:0150 **BUILDING SECTIONS** DOOR SCHEDULES FRANK ONO WINDOW SCHEDULES 1213 MILES AVENUE ELECTRICITY PROVIDER: PACIFIC GROVE, CA 93950 ISA CERTIFIED ARBORIST #536 SOCIETY OF AMERICAN FORESTERS# 48004 P. 831.373.7086 FLOOR AREAS C. 831.594.2291 STRUCTURAL ENGINEER FIRST FLOOR TOTAL 4,101 21.1% GENERAL CONTRACTOR **LOT COVERAGE** 17.5% RESIDENCE FOOTPRIN COVERED AREA / OVERHEAD DECK 3,708 IMPERVIOUS SURFACES 2,744 4,482 23.1% **TOTAL REMOVED** TREE REMOVAL NON-SIGNIFICANT mmmm the GENERAL CONDITIONS SCOPE OF WORK

PROJECT TEAM

ARCHITECT:

IUSTIN PAULY

P. 831.920.1045

MONTEREY CA 93940


- SPRINKLER HEADS W/ARCHITECT.
- 2. FIRE ALARM SYSTEM SHALL CONFORM WITH THE 2013 CBC. COORDINATE LOCATION OF **VISIBLE COMPONENTS WITH ARCHITECT.**
- . DEFERRED TRUSS DRAWINGS: SUBMIT 2-SETS OF TRUSS DRAWINGS AND CALCULATIONS TO THE COUNTY/CITY FOR REVIEW AND APPROVAL.THE STRUCTURAL ENGINEER IS TO PROVIDE A SHOP DRAWINGS REVIEW STAMP ON THE TRUSS DRAWINGS, SIGNED AND DATED. THE TRUSSES ARE TO BE APPROVED BY THE COUNTY/CITY PRIOR TO REQUESTING THE ROOF SHEATHING INSPECTION AND WILL BE ASSESSED ADDITIONAL PLAN CHECKING FEES. (CBC 107.3.4.1)
- 4. PHOTOVOLTAIC PANEL SYSTEM. CONTRACTOR SHALL SECURE CONSTRUCTION **DOCUMENTS & BUILDING DEPARTMENT APPROVAL FOR ALL SYSTEMS AND REQUIREMENTS** RELATED TO THE PV ARRAY

APPLICABLE CODES

THIS PROJECT SHALL COMPLY WITH ALL CURRENT CODES AS FOLLOWS:

- 2016 CALIFORNIA BUILDING CODE 2016 CALIFORNIA PLUMBING CODE
- 2016 CALIFORNIA MECHANICAL CODE
- 2016 CALIFORNIA ENERGY CODE
- 2016 CALIFORNIA ELECTRICAL CODE
- 2016 CALIFORNIA FIRE CODE 2016 CALIFORNIA GREEN BUILDING CODE

2016 CALIFORNIA RESIDENTIAL CODE EROSION CONTROL & CONSTRUCTION MANAGEMNET PLAN



1018 × 10 13 kg w 202

TYPICAL CONSTRUCTION REQUIREMENTS OF THE 2016 CALIFORNIA STANDARDS CODE SHALL APPLY WHERE APPLICABLE AND WHEN NOT SPECIFICALLY NOTED OTHERWISE ON

PROJECT DATA

- SITE FAMILIARIZATION: CONTRACTOR IS RESPONSIBLE TO ACQUAINT HIMSELF WITH THE SITE PRIOR TO SUBMITTING A PROPOSAL. IF THE CONTRACTOR DISCOVERS ANY CONDITIONS DURING HIS SITE FAMILIARIZATION WHICH HE FEELS WILL ADVERSELY AFFECT THE WORK, OR WHICH HE FEELS HAVE NOT BEEN ADEQUATELY ADDRESSED BY THE CONTRACTOR DOCUMENTS, HE IS TO NOTIFY THE ARCHITECT IN WRITING. CONTRACTOR IS ALSO RESPONSIBLE FOR FAMILIARIZING HIM OR HERSELF WITH THE GEOTECHNICAL REPORT FROM GRICE ENGINEERING DATED 9/21/2018 AND ALL RECOMMENDATION MADE THEREIN.
- UNSATISFACTORY CONDITIONS: THE CONTRACTOR AND ALL SUBCONTRACTORS ARE RESPONSIBLE TO NOTIFY THE ARCHITECT IN WRITING OF ANY UNSAFE OR UNSATISFACTORY CONDITIONS IN THE EXISTING OR PROPOSED CONSTRUCTION WHICH ARE DISCOVERED DURING THE COURSE OF THE WORK.
- CONSTRUCTION DETAILS NOT SPECIFICALLY SHOWN ON THE DRAWINGS SHALL BE CARRIED OUT BY RESPECTIVE CONTRACTORS IN ACCORDANCE WITH THE BEST COMMON PRACTICE AND/OR WITH MANUFACTURER'S SPECIFICATIONS FOR INSTALLATION FOR THEIR MATERIALS OR ITEMS.
- DEMOLITION: COORDINATE ALL DEMOLITION REQUIREMENTS WITH THE OWNER. VERIFY WITH OWNER WHICH ITEMS, IF ANY, HE WISHES TO RETAIN FOR HIS USAGE. ALL OTHER ITEMS BECOME THE PROPERTY OF THE CONTRACTOR AND ARE TO BE PROPERLY REMOVED FROM THE PREMISES. UTILIZE DUST CONTROL MEASURES DURING DEMOLITION.
- 6. NO PERSON MAY TAP INTO ANY FIRE HYDRANT FOR ANY PURPOSE OTHER THAN FIRE SUPPRESSION OR EMERGENCY AID. WITHOUT FIRST OBTAINING WRITTEN APPROVAL FROM THE WATER PURVEYOR SUPPLYING WATER TO THE HYDRANT AND FROM THE MONTEREY COUNTY HEALTH DEPARTMENT.
- . MECHANICAL AND PLUMBING: IT IS THE ESSENCE OF THE CONTRACTOR THAT ALL SYSTEMS SHALL FUNCTION WELL INDIVIDUALLY AND IN COMBINATION WITH OTHER SYSTEMS.
- 8. ALL HOSES USED IN CONNECTION WITH ANY CONSTRUCTION ACTIVITIES SHALL BE EQUIPPED WITH A SHUT OFF NOZZLE. WHEN AN AUTOMATIC SHUT OFF NOZZLE CAN BE PURCHASED OR OTHERWISE OBTAINED FOR THE SIZE OR TYPE OF HOSE IN USE, THE NOZZLE SHALL BE AN AUTOMATIC SHUT OFF NOZZLE.

DEMO EXISTING RESIDENCE AND ALL EXISTING IMPERVIOUS SURFACES. CONSTRUCT NEW 2 STORY SINGLE FAMILY RESIDENCE WITH ATTACHED DECKS AND PATIOS: SEE AREAS FROM PROJECT DATA TABLE ON THIS SHEET.

- COVERED AND UNCOVERED WALKWAYS, PATIOS & DECKS SITE WALLS AND PEDESTRIAN PAVING
- LANDSCAPE REHABILITATION & TREE REMOVAL (SEE PROJECT DATA)
- NEW GAS FIRE PIT W/ NEW GAS LINE
- (N) ATTACHED 2 CAR GARAGE

(N) FIRE SPRINKLER SYSTEM

VICINITY MAP / TRUCK HAUL ROUTE



10/18/18 issued: revised: <u>11/20/18</u>

drawn by: DJA


SHEET INDEX


COVER SHEET

TITLE SHEET

FIRE SAFETY ZONE

LANDSCAPE LAYOUT PLAN






CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

COVER SHEET

sheet 14

sheets

NOT TO SCALE



Alvan & Sara Adams Landscape

PLANS / SECTION / ELEVATION FOR MONTEREY COUNTY RMA PLANNING REVIEW

GENERAL NOTES:

- THESE DRAWINGS SHALL BE CONSIDERED SUBSTANTIALLY COMPLETE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE ALL LABOR AND MATERIALS NECESSARY TO RENDER THE WORK COMPLETE, AS IS THE INTENT OF THESE DRAWINGS, EITHER SHOWN OR INFERRED HEREIN, THROUGH PROPER AND ESTABLISHED CONSTRUCTION PRACTICES. THE BUILDING CONTRACTOR, MASONRY / CONTRACTOR & GRADING CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFIED-ACTION OF ALL DIMENSIONS, GRADES AND OTHER SITE CONDITIONS WITHIN HIS SCOPE OF WORK. COORDINATION AND VERIFICATION DISCREPANCIES SHALL BE REPORTED TO THE LANDSCAPE ARCHITECT FOR CLARIFICATION AND CORRECTION PRIOR TO BEGINNING ANY WORK. CONCERNS WITH THE SITE DURING CONSTRUCTION WHICH MAY DIFFER GREATLY FORM THE DESIGN GOALS OR CREATE NEW OPPORTUNITIES SHALL BE REPORTED TO THE LANDSCAPE ARCHITECT IMMEDIATELY DURING THE WORK PHASE.
- 2. THE LANDSCAPE ARCHITECT SHALL ASSIST IN ANSWERING PLAN QUESTIONS OF ALL LANDSCAPE RELATED WORK AS CONSTRUCTED FROM THIS DESIGN.
- 3. IT SHALL BE THE CONTRACTORS RESPONSIBILITY FOR THE SUPERVISION OF THE WORK. ALL CONTRACTORS INVOLVED IN THE LANDSCAPE WORK SHALL HOLD CURRENT CALIFORNIA STATE LICENSES FOR THEIR TRADES. CERTIFICATES OF LIABILITY INSURANCE FOR AND NAMING THE PROJECT AND SHALL BE MADE OUT TO THE OWNER, ALVAN ADAMS.
- 4. LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ALL COORDINATION WITH OTHER CONTRACTORS ON SITE AS REQUIRED TO ACCOMPLISH ALL PLANTING OPERATIONS.
- LANDSCAPE CONTRACTOR IS RESPONSIBLE TO REVIEW SITE ENVIRONMENTAL CONDITIONS PRIOR TO AND DURING INSTALLATION OF PLANT MATERIAL. ANY DISCREPANCIES OR CONCERNS BETWEEN THE ENVIRONMENTAL SITE CONDITIONS (I.E. SOIL TYPE, WATER, CLIMATE, WIND SUN EXPOSURE AND ETC) WHICH MAY EFFECT THE PROJECT SUCCESS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT & THE PROJECT MANAGER.
- 6. THIS PROJECT SHALL COMPLY WITH TITLE 24 & 2016 CALIFORNIA COMMERCIAL CODE), CALIFORNIA BUILDING CODE (CBC), CALIFORNIA MECHANICAL CODE (CMC), CALIFORNIA PLUMBING CODE (CPC), CALIFORNIA ELECTRICAL CODE (CEC), AND CALIFORNIA ENERGY CODE (CEnc).
- 7. ANY PROPOSED SHUT DOWN OF UTILITIES SHALL ALERT THE OWNER. UNDERGROUND MARKINGS SHALL BE PREFORMED PRIOR TO ANY DIGGING TO OBTAIN AN 811 TICKET PRIOR TO FINALIZING PLANS AND CONSTRUCTION. call usa underground alert prior to any digging. usa (800) 642-244
- CONSTRUCTION DOCUMENTS WILL COMPLETE ALL LANDSCAPE SPECIFICATIONS & DETAILS TO COMPLETE THE BUILDING PERMIT APPLICATION.

LANDSCAPE DESIGN SCOPE:

THE LANDSCAPE PLAN POINTS TO THE A SUCCESSFUL ADAPTIVE RESOURCE MANAGEMENT WITH THE PLANT SELECTIONS; NATIVE CALIFORNIA AND MEDITERRANEAN IN LIMITED PLANTERS AND PERIMETER PLANTING AREAS AROUND THE PROPERTY WHICH IS RESPECTFUL FOR A SUCCESSFUL STEWARDSHIP FOR THIS COASTAL AREA AND THE PLANTED REPLANTING OF NATIVE TREES FOR THE APPROVED TREE REMOVALS IN CONCERT WITH THE FOREST MANAGEMENT REPORT - FRANK ONO, ARBORIST (SEPTEMBER 2018)

ZONE PLANTING: ALSO REFEREED TO AS HYDRO-ZONE IS A CORRELATION TO THE AMOUNT OF POTENTIAL WATER USED. THREE ARE A MIX OF PLANTS CONSIDERED DROUGHT TOLERANT OR WATER SAVING. ASSOCIATE PERIMETER PLANTINGS ALSO INCLUDE WATER SAVING PLANTS. THE OBVIOUS INCREASE IN WATER ALLOCATION IS PROXIMATE TO THE NEW BUILDING.

PLANTING IN THESE AREA ARE CLIMATE SENSITIVE TO A MEDITERRANEAN LATITUDES AND INCORPORATES MANY NATIVE PLANTS DRAWN FROM A CALIFORNIA FLORA. THERE ARE NO EXOTIC SPECIES CAPABLE OF NATURALIZING INTO THE SURROUNDING AREA ARE ON THIS PLANTING PALETTE.

Landscape Design Statement:

I Scott Hall, a registered California Landscape Architect (#3405), certify that these landscape Planting and Irrigation Plans comply with all County of Monterey and conditions for approval and intent thereof.

The Planting Plans include the use of Native California Water Saving ("drought tolerant") plant species and Mediterranean plant species and do not include invasive plant species.

The responsible and appropriate Water Saving plant species selected here is reflected in the Irrigation use of a LOW FLOW water saving Irrigation delivery system. The water conserving system is primarily Drip type irrigation which follows State and Local County requirements. The oversight in this local under the Monterey Peninsula Water Management District Lay and Ordinance No. 172 is Compliant here.

No Irrigation is designed around the existing *Quercus agrifolia* (Coast Live Oaks) and *Pinus radiata* (Monterey Pines) has been designed.



Digitally signed by Scott Hall Date: 2018.10.17 23:47:18

Scott Hall, registered California Landscape Architect #3404

SHEET INDEX:

- 1 TITLE SHEET / OVERALL SITE PLAN
- 2 FIRE SAFETY ZONE
- LANDSCAPE LAYOUT PLAN
- 4 LANDSCAPE LIGHTING PLAN
- LANDSCAPE IRRIGATION PLAN & WATER USE ESTIMATES
- LANDSCAPE PLANTING PLAN
- LANDSCAPE SITE SECTION / ELEVATION & GARDEN ELEMENT IDEAS


_____ of: 7 Sheets

TITLE SHEET & INDEX LANDSCAPE PLANS FOR INITIAL RMA PLANNING DEPARTMENT REVIEW

SCALE AS SHOWN

Revisions

Date Printed: 10-17-2018




Revisions


c5 #3405


dams


Job # 10-17-2018


Date Printed: 10-17-2018













BLT-IN BENCH & FIRE PIT IDEA SCALE: 1/2" = 1' - 0"

MATER URN IDEA

SCALE : 1/2" = 1' - 0"



SECTION THRU DECK & SPA



SCALE : 1/4" = 1' - 0"

L-7 of: 7 Sheets


Elements

Revisions

Job # 10-17-2018

Date Printed: 10-17-2018

MASH



10/18/18 issued: revised: 11/20/18

drawn by: DJA






CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED

WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

SURVEY

sheet 25 sheets




PERFORMED BY FRANK ONO, UBAN FORESTER DATED 9/11/2018 AND MONTEREY COUNTRY

issued: 10/18/18 11/20/18

drawn by: DJA





CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

SITE DEMOLITION PLAN

sheet 26



GENERAL NOTES

- I. THE SOILS ENGINEER SHALL BE NOTIFIED AT LEAST TWO (2) DAYS IN ADVANCE OF COMMENCING WORK, INCLUDING SITE STRIPPING AND GRADING OPERATIONS. THIS WORK SHALL BE OBSERVED AND TESTED BY THE SOILS ENGINEER.
- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE REQUIRED PERMITS PRIOR TO THE COMMENCEMENT OF GRADING. RIGHT-OF-ENTRY, PERMISSION TO GRADE, AND ENCROACHMENT PERMIT(S) MAY BE REQUIRED PRIOR TO GRADING.
- 3. IT IS THE CONTRACTORS RESPONSIBILITY TO PREPARE THE GROUND SURFACE TO RECEIVE THE FILLS AND TO PLACE, SPREAD, MIX, WATER, AND COMPACT THE FILL. THE CONTRACTOR SHALL ALSO REMOVE ALL MATERIAL CONSIDERED UNSATISFACTORY.
- 4. WHERE UNSTABLE OR UNSUITABLE MATERIALS ARE ENCOUNTERED DURING SUBGRADE PREPARATION, THE AREA IN QUESTION SHALL BE OVER EXCAVATED AND BACKFILLED WITH SELECT MATERIAL PER GEOTECHNICAL RECOMENDATIONS.
- 5. MAXIMUM CUT AND FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL PROVIDED THEY ARE LANDSCAPED WITH SOIL RETAINING GROUND COVERS AND ARE PROTECTED AGGAINST CONCENTRATED OVER SLOPE DRAINAGE.
- 6. ALL CUT SLOPES SHALL BE ROUNDED TO MEET EXISTING GRADES AND BLEND WITH SURROUNDING TOPOGRAPHY.ALL GRADED SLOPES SHALL BE PLANTED WITH SUITABLE GROUND COVER.
- 7. ALL FILL SLOPES SHALL BE COMPACTED IN ACCORDANCE WITH GEOTECHNICAL INVESTIGATION RECOMMENDATIONS. THE TOE OF ALL SLOPES SHOULD BE SUPPORTED BY A KEY CUT A MINIMUM OF 3 FEET INTO UNDISTURBED SOILS TO THE INSIDE OF THE FILL TOE.THIS KEY SHOULD BE A MINIMUM OF 8 FEET IN WIDTH AND SLOPE AT NO LESS THAN 10% INTO THE SLOPE. IN ADDITION AS THE FILL ADVANCES UP THE SLOPE BENCHES 3 FEET ACROSS SHOULD BE SCARIFIED INTO THE FILL/UNDISTURBED SOIL INTERFACE. (SEE SOILS
- 8. TREE REMOVAL SHALL INCLUDE REMOVAL OF TRUNKS, STUMPS, AND ROOT BALLS. THE REMAINING CAVITY SHALL BE CLEARED OF ALL ROOTS LARGER THAN 1/2" TO A DEPTH OFNOT LESS THAN 18" AND BACKFILLED WITH SUITABLE MATERIAL THEN COMPACTED TO CONFORM WITH THE EXISTING GROUND.
- 9. CONTRACTOR SHALL USE CAUTION WHEN GRADING AROUND AND/OR OVER EXISTING UNDERGROUND UTILITIES.

10. ALL SURFACE DRAINAGE SHALL MAINTAIN 2% SLOPE MINIMUM UNLESS NOTED OTHERWISE.

11. PERVIOUS SURFACES IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT A SLOPE OF NOT LESS THAN 5% FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FEET OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED A MINIMUM OF 2% WHERE LOCATED WITHIN 10 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.

reference notes

1 NOT USED

PROJECT AREAS

SEE TITLE SHEET

MATERIAL LEGEND


PROPOSED BUILDING FOOTPRINT



PAVED AC DRIVEWAY




STOWAR PAYING TONE PAYING



DECOMPOSEONGRAINETE PERMEABLE SURFACE (PERVIOUS)

10/18/18 issued:

revised: /\ 11/20/18 drawn by: DJA





CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED. USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

PROPOSED ARCHITECTURAL SITE PLAN

sheet 27

3. ACTUAL GRADING SHALL BEGIN WITHIN 30 DAYS OF VEGETATION REMOVAL OR THE AREA SHALL BE PLANTED TO CONTROL EROSION. VEGETATION REMOVAL BETWEEN OCTOBER 15 AND APRIL 15 SHALL NOT PRECEED SUBSEQUENT GRADING OR CONSTRUCTION ACTIVITIES BY MORE THAN 15 DAYS. DURING WINTER OPERATIONS (BETWEEN OCTOBER 15 AND APRIL 15) THE FOLLOWING MEASURES MUST BE TAKEN:

GENERAL NOTES (cont.)

DISTURBED SURFACES NOT INVOLVED IN IMMEDIATE OPERATIONS MUST BE PROTECTED BY MULCHING AND OR OTHER EFFECTIVE MEANS OF SOIL PROTECTION.

ALL ROADS AND DRIVEWAYS SHALL HAVE DRAINAGE FACILITIES SUFFICIENT TO PREVENT EROSION ON OR ADJACENT TO THE ROADWAY OR ON DOWNHILL

RUN-OFF FROM THE SITE SHALL BE DETAINED OR FILTERED BY BERMS, VEGETATED FILTER STRIPS, AND OR CATCH BASINS TO PREVENT THE ESCAPE OF SEDIMENT FROM THE SITE. D. DRAINAGE CONTROL MEASURES SHALL BE MAINTAINED AND IN PLACE AT THE END OF EACH DAY AND CONTINUOUSLY THROUGH THE LIFE OF THE PROJECT DURING WINTER OPERATIONS

DURING CONSTRUCTION, THE OWNER / APPLICANT SHALL SCHEDULE WEEKLY INSPECTIONS WITH RMA - ENVIRONMENTAL SERVICES IN THE RAINEY SEASON (OCTOBER 15TH TO APRIL 15TH)

IFGFND

	L	LGLND				
SYMBOL	CAL-TRANS BMP #	DESCRIPTION				
(DS)===		INDICATES DOWNSPOUT LOCATION W/SPLASH BLOCK. SEE ROOF PLAN AND ELEVATIONS.				
AD		INDICATES AREA DRAIN LOCATION.				
OOOOOOOO SC-1, SC-5 & SC-6		EARTHEN BURN, FIBER ROLL OR SILT FENCE (CONTRACTOR'S OPTION), INDICATES FIBERROLL, SEE DETAIL 20 ON THIS SHEET				
\$\ldots\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	SC-7	STREET SWEEPING				
	SC-10	INLET PROTECTION				
	TC-I &TC-3	STABALIZED CONSTRUCTION ENTERANCE/EXIT & TIRE WASH AREA				
CMM	WM-8	CONCRETE WASTE MANAGEMENT				
[]	SS-3, SS-4, SS-5 SS-6, SS-7, SS-8	TEMPORARY SOIL STABIZATION, PROVIDE ON ALL DISTURBED AREAS				
MSMM	WM-I	MATERIAL STORAGE AND WASTE MANAGEMENT AREA				
MM-3	WM-3	TEMPORARY STOCKPILES				
55	WM-9	SANITARY FACILITIES				
		NATURAL DRAINAGE COURSE				
		DIRECTION OF DRAINAGE				

WATER POLLUTION CONTROL NOTES

- I. ESTIMATED TOTAL ARE OF DISTURBANCE X ACRES.
- 2. BEST MANAGEMENT PRACTICES (BMPs) (MATERIAL AND THEIR CONSTRUCTION) SHALL CONFORM TO 2017 CALTRANS CONSTRUCTION SITE BEST MANAGEMENT PRACTICES (BMP) MANUAL.
- 3. THE BMPs SHOW ON THIS EROSION CONTROL PLAN SHALL BE ADJUSTED OR SUPPLEMENTED AS REQUIRED TO PROTECT WATER QUALITY AND/OR AS DIRECTED BY THE ARCHITECT OR JURISDICTION HAVING AUTHORITY.
- 4. THIS PLAN IS INTENDED TO BE USED FOR INTERIM WATER POLLUTION CONTROL ONLY AND IS NOT TO BE USED FOR FINAL ELEVATIONS OR PERMANENT IMPROVEMENTS.
- 5. CONTRACTOR SHALL BE RESPONSIBLE FOR MONITORING BMPs PRIOR TO, DURING, AND AFTER STORM EVENTS AND SHALL PROMPTLY CORRECT ANY DEFICIENCIES NOTED.
- 6. ALL PAVED AREAS SHALL BE KEPT CLEAN OF SOIL AND DEBRIS. REGULAR STREET SWEEPING IS REQUIRED. ADDITIONAL STREET SWEEPING MAY BE REQUIRED BY ARCHITECT OR JURISDICTION HAVING AUTHORITY.
- 7. REASONABLE CARE SHOULD BE TAKEN WHEN HAULING ANY EARTH, SAND, GRAVEL, STONE, DEBRIS, PAPER, OR ANY OTHER SUBSTANCE OVER ANY PUBLIC STREET, ALLEY, OR OTHER PUBLIC PLACE. ANY MATERIAL THAT IS TO BE HAULED OFF-SITE SHALL BE COVERED. SHOULD ANY BLOW, SPILL OR TRACK OVER AND UPON SAID PUBLIC OR ADJACENT PRIVATE PROPERTY, IMMEDIATE REMEDY SHALL OCCUR.
- 8. KEEP ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES ON SITE IN CASE IMMEDIATE REPAIRS OR MODIFICATIONS ARE REQUIRED. THESE SUPPLIES MAY INCLUDE ADDITIONAL SILF FENCING, FILTER FABRIC, HAY BALES, JUTE NETTING, BAGS AND TARPS.
- 9. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION WILL BE MINIMIZED, STATE AND LOCAL LAWS CONCERNING POLLUTION ABATEMENT SHALL BE COMPLIED WITH.
- 10. CONTRACTOR SHALL SUPPLY DUST CONTROL AS REQUIRED BY FEDERAL, STATE, AND LOCAL AGENCY REQUIREMENTS.
- II. PROVIDE TEMPORARY 'EFFECTIVE SOIL COVER' ON ALL INACTIVE DISTURBED AREAS (AREAS THAT HAVE NOT BEEN DISTURBED FOR AT LEAST 14 DAYS) PRIOR TO INSTALLATION OF FINAL LANDSCAPING, IF REQUIRED DUE TO PROJECT SCHEDULING.
- 12. PROVIDE WIND EROSION CONTROL AT ALL TIMES IN ACCORDANCE WITH BEST MANAGEMENT PRACTICE WE-I.
- 13. ESTABLISH AND MAINTAIN EFFECTIVE PERIMETER CONTROLS AND STABALIZE ALL CONSTRUCTION ENTERANCES AND EXITS TO SUFFICIENTLY CONTROL EROSION AND SEDIMENT DISCHARGES FROM THE SITE.
- PROVIDE SILT FENCE/FIBER ROLL AT CONSTRUCTION SITE PERIMETER WHERE RUN-OFF LEAVE THE CONSTRUCTION SITE
- PROVIDE INLET PROTECTION AT ALL DRAIN INLETS.
- 14. ALL GRADING SHALL CONFORM TO THE MONTEREY COUNTY GRADING ORDINANCE #2535, EROSION CONTROL ORDINANCE #2806 AND CALIFORNIA BUILDING CODE.
- 15. PRIOR TO THE COMMENCEMENT OF ANY LAND DISTURBANCE, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICE TO ENSURE ALL NECESSARY SEDIMENT CONTROLS ARE IN PLACE AND THE PROJECT IS COMPLIANT WITH MONTEREY COUNTY GRADING AND EROSION CONTROL REGULATIONS.
- 16. DURING CONSTRUCTION THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO UPDATE COMPACTION TEST RECORDS, INSPECT DRAINAGE DEVICE INSTALLATION, REVIEW THE MAINTENANCE AND EFFECTIVENESS OF BMPs INSTALLED AS WELL AS, TO ENSURE THAT POLLUTANTS OF CONCERN ARE NOT DISCHARGED FROM THE SITE.
- 17. PRIOR TO FINAL INSPECTION, THE OWNER/APPLICANT SHALL SCHEDULE AN INSPECTION WITH RMA-ENVIRONMENTAL SERVICES TO CONDUCT A FINAL GRADING INSPECTION, COLECT FINAL LETTER OF GEOTECHNICAL CONFORMANCE, ENSURE THAT ALL DISTURBED AREAS HAVE BEEN STABILIZED, AND THAT ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES THAT ARE NO LONGER NEEDED HAVE BEEN REMOVED.
- 18. ALL OR PART OF THE CONSTRUCTION PROJECT IS EXPECTED TO OCCUR DURING THE WINTER SEASON (OCTOBER 15th THROUGH APRIL 15th)
- 19. IT SHALL BE THE RESPONSIBILITY OF THE OWNER AND THE PERMITTEE TO ENSURE THAT EROSION DOES NOT OCCUR FROM AN ACTIVITY DURING OR AFTER PROJECT CONSTRUCTION. ADDITIONAL MEASURE, BEYOND THOSE SPECIFIED, MAY BE REQUIRED AS DEEMED NECESSARY TO CONTROL ACCELERATED EROSION (MCC 16.12.100)

GRADING NOTES

- THE SOILS ENGINEER SHALL BE NOTIFIED AT LEAST TWO (2) DAYS IN ADVANCE OF COMMENCING WORK, INCLUDING SITE STRIPPING AND GRADING OPERATIONS. THIS WORK SHALL BE OBSERVED AND TESTED BY THE SOILS ENGINEER.
- 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE THE REQUIRED PERMITS PRIOR TO THE COMMENCEMENT OF GRADING. RIGHT-OF-ENTRY, PERMISSION TO GRADE, AND ENCROACHMENT PERMIT(S) MAY BE REQUIRED PRIOR TO GRADING.
- 3. IT IS THE CONTRACTORS RESPONSIBILITY TO PREPARE THE GROUND SURFACE TO RECEIVE THE FILLS AND TO PLACE, SPREAD, MIX, WATER, AND COMPACT THE FILL. THECONTRACTOR SHALL ALSO REMOVE ALL MATERIAL CONSIDERED UNSATISFACTORY.
- . WHERE UNSTABLE OR UNSUITABLE MATERIALS ARE ENCOUNTERED DURING SUBGRADE PREPARATION, THE AREA IN QUESTION SHALL BE OVER EXCAVATED AND BACKFILLED WITH
- 5. MAXIMUM CUT AND FILL SLOPE SHALL BE 2 HORIZONTAL TO 1 VERTICAL.
- 6. ALL CUT SLOPES SHALL BE ROUNDED TO MEET EXISTING GRADES AND BLEND WITH SURROUNDING TOPOGRAPHY.ALL GRADED SLOPES SHALL BE PLANTED WITH SUITABLE GROUND COVER.
- 7. ALL FILL SLOPES SHALL BE COMPACTED IN ACCORDANCE WITH THE SOILS REPORT. THE TOE OF ALL SLOPES SHOULD BE SUPPORTED BY A KEY CUT A MINIMUM OF 3 FEET INTO UNDISTURBED SOILS TO THE INSIDE OF THE FILL TOE. THIS KEY SHOULD BE A MINIMUM OF 8 FEET IN WIDTH AND SLOPE AT NO LESS THAN 10% INTO THE SLOPE. IN ADDITION AS THE FILL ADVANCES UP THE SLOPE BENCHES 3 FEET ACROSS SHOULD BE SCARIFIED INTO THE FILL/UNDISTURBED SOIL INTERFACE. (SEE SOILS REPORT)
- 8. TREE REMOVAL SHALL INCLUDE REMOVAL OF TRUNKS, STUMPS, AND ROOT BALLS. THE REMAINING CAVITY SHALL BE CLEARED OF ALL ROOTS LARGER THAN 1/2" TO A DEPTH OFNOT LESS THAN 18" AND BACKFILLED WITH SUITABLE MATERIAL THEN COMPACTED TO
- CONFORM WITH THE EXISTING GROUND. 9. CONTRACTOR SHALL USE CAUTION WHEN GRADING AROUND AND/OR OVER EXISTING
- UNDERGROUND UTILITIES.
- 10. ALL SURFACE DRAINAGE SHALL MAINTAIN 2% SLOPE MINIMUM UNLESS NOTED OTHERWISE.
- 11. PERVIOUS SURFACES IMMEDIATELY ADJACENT TO THE FOUNDATION SHALL BE SLOPED AWAY FROM THE BUILDING AT A SLOPE OF NOT LESS THAN 5% FOR A MINIMUM DISTANCE OF 10 FEET MEASURED PERPENDICULAR TO THE FACE OF THE WALL. IF PHYSICAL OBSTRUCTIONS OR LOT LINES PROHIBIT 10 FEET OF HORIZONTAL DISTANCE, A 5% SLOPE SHALL BE PROVIDED TO AN APPROVED ALTERNATIVE METHOD OF DIVERTING WATER AWAY FROM THE FOUNDATION. SWALES USED FOR THIS PURPOSE SHALL BE SLOPED A MINIMUM OF 2% WHERE LOCATED WITHIN 10 FEET OF THE BUILDING FOUNDATION. IMPERVIOUS SURFACES WITHIN 10 FEET OF THE BUILDING FOUNDATION SHALL BE SLOPED A MINIMUM OF 2% AWAY FROM THE BUILDING.

GENERAL NOTES


- I. CONTRACTOR SHALL READ AND FAMILIARIZE THEMSELVES WITH THE GEOTECHNICAL REPORT PREPARED BY GRICE ENGINEERING DATED JULY 10, 2016. CONTRACTOR SHALL CONFORM TO GEOTECHNICAL RECOMMENDATIONS.
- 2. DRAINAGE PLAN SHOWN IS CONCEPTUAL, ACTUAL FIELD CONDITIONS MAY REQUIRE MODIFICATION TO PROVIDE EFFECTIVE DRAINAGE. MOST LIKELY SOME POST CONSTRUCTION MONITORING AND IMPROVEMENTS WILL BE REQUIRED.

revised:

drawn by:

issued:

11/21/18





ALL DRAWINGS AND WRITTEN MATERIALS CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED. USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

EROSION CONTROL & CONSTRUCTION MANAGEMENT

PLAN

sheet 28

sheets

FIBER ROLL NOT TO SCALE

MIN

I. USE 1"X1"X2" OR 1"X1"X3" WOOD STAKES, DEPENDING ON THE SOIL AND SLOPE

CONDITIONS. USE LONGER STAKES IN LOOSE SOIL, SHORTER STAKES IN DENSER

ROLLS SHOULD BE OVERLAPPED, NOT ABUTTED. IF CONTRACTOR DESIRES TO

3. PLACE FIBER ROLLS SECURELY IN THE TRENCH SO THAT SILT LADEN RUN-OFF

WITH STRONG TWINE TO ENSURE A GOOD CONNECTION.

PASSES OVER OR THROUGH, NOT UNDER THE FIBER ROLL.

PREVENT RUNOFF FROM GOING AROUND THE ROLL.

1"X1"X24"(OR) 1"X1"X36" WOOD

POSITION FIBER ROLLS END-TO-END, THEY SHALL TIE THE BUTTED ENDS TOGETHER

4. CONSTRACTOR SHALL REVIEW CASQA MANUAL FOR INSTALLATION GUIDANCE.

5. CASQA RECOMENDS THE ENDS OF THE FIBER ROLL BE TURNED UP-SLOPE TO

2. CASQA RECOMMENDS IF MORE THAN ONE FIBER ROLL IS PLACED IN A ROW, THE

INLET PROTECTION

PLAN VIEW

SECTION A-A

~ CATCH BASIN



issued: 10/18/18

revised: 11/20/18 drawn by: DJA

550 hartnell st, suite H nonterey, california 93940 p. 831.920.1045 f. 831.886.3660

STIN PAULY ARCHI



COASTAL DEVELOPMENT

n: 009-032-005-000

el, california

carmel, californic

DAMS


ALL DRAWINGS AND WRITTEN MATERIALS CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

FIRST FLOOR PLAN

sheet 30

sheets


A2.2





CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)

SECOND FLOOR PLAN



revised: 11/20/18





ALL DRAWINGS AND WRITTEN MATERIALS CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)



10/18/18

11/20/18


drawn by: DJA



CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)


NORTH & WEST ELEVATIONS

sheet 33



10/18/18

11/20/18



revised: 11/20/18

drawn by: DJA

JUSTIN T. PAULY

No. C-32692

REN. 01/31/2019



ALL DRAWINGS AND WRITTEN MATERIALS CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)


BUILDING SECTIONS

sheet 35 sheets

WIDTH HEIGHT	TEMP'D	TYPE		SIDELIGHT H WIDTH	HARDWARE GROUP	NOTES	~	1ARK WIDTH	HEIGHT	TEMP'D TYPE	DETAILS HEAD JAMB SILL	HARDWARE GROUP	NOTES	revised
8'-0"		A	HEAD JAMB SILL			NK SEGMENTED GARAGE DOOR		D10 3'-0"	8'-0"	E	HEAD JAMB SILL	20 MIN. RATED W/SELF CLOSING	HARDWARE	
-6" 7'-9 ^{1/2} "	YES	В		2'-10"	STEEL FRAME	DOOR w/ SIDELITES (SEE LEGEND FOR WIDTH)		DII 6'-0"	4'-6"	К				
-0" 8'-0"	YES	D		0"				D13 3'-0"	8'-0"	I				4
-0" 7'-0" -0" 7'-0"	YES YES	D 		2'-3"				D14 2'-0" D15 2'-6"	8'-0"	E				\
-0" 8'-0"	123	E		0"	MATCH SIDIN	G ON WALL		D16 2'-8"	8'-0"	E				
10" 8'-0"		FO		0"	MATCH SIDIN	G ON WALL; PROVIDE MAKE-UP AIR VENTILATION LOUVER	RS AS REQ'D FOR MECH. EQUIPMENT	D17 5'-0"	8'-0"	Н				
6" 6'-11"		E-I		0"	DUTCH DOC	R		D18 2'-6"	8'-0"	E				
								D19 2'-6" D20 2'-6"	8'-0"	E				
								D22 2'-6"	8'-0"	E				
								D24 2'-8"	8'-0"	I				
								D25 2'-6"	8'-0"	E				
								D28 2'-6" D29 3'-4"	7'-0"	E		LITH IZE OWNED PROVIDED RECI	CLAIMED WOOD FROM PHOENIX SUNS BASKETBALL COURT	
								D30 2'-6"	7'-0"	E		OTILIZE OVVINER TROVIDED RECE	LANTED WOOD TROTTT TOLINIX SONS BASIC PALLE COOK!	
								D31 2'-6"	7'-0"	E				
							_	D32 2'-6"	7'-0"	E				
								D33 2'-6" D34 2'-6"	7'-0"	E				
								D34 2'-6"	8'-0"	H				
		Α			В	D	E	E-1		÷O	Н	1	J	
													SURFACE SLIDER	e for:
K			Ĺ											new residence

20/18

, california 93940 p. 831.920.1045 f. 831.886.3660 aulyarchitects.com





EN MATERIALS
STITUTE THE
ED WORK OF
ME MAY NOT
EDISCLOSED
SENT OF THE
ARCHITECTS)

DULES

A5.1
of sheets

							WINDO	W SCHEDULE
MARK -	SIZE						HEAD	
	WIDTH	HEIGHT	TYPE	TEMPERED	SCREEN	SHADE	HEIGHT	NOTES
W02	5'-4"	7'-6"	В	YES			8'-0"	
W03	2'-6"	7'-6"	L				8'-0"	
W05	2'-0"	3'-0"	D	YES			8'-0"	
W06	2'-0"	3'-0"	D				8'-0"	
W07	6'-0"	9'-0"	Е	YES			9'-1"	
W08	6'-3 ^{1/2} "	8'-6"	F	YES			8'-6"	
W09	5'-0"	5'-4"	G				8'-6"	
WI0	3'-0"	3'-0"	Н				8'-6"	
WII	2'-6"	3'-6"	Н				8'-0"	
WI2	2'-6"	3'-6"	Н				8'-0"	
WI3	3'-0"	2'-0"	Н	YES			8'-0"	
WI6	6'-0"	8'-7"	Е	YES			8'-7"	
WI8	3'-0"	8'-7"	I	YES			8'-7"	
WI9	7'-9 ^{1/2} "	8'-6"	J	YES			8'-6"	
W20	6'-0"	9'-0"	Е	YES			9'-1"	
W2I	5'-0"	5'-4"	С				8'-10"	
W22	4'-0"	4'-4"	С				8'-0"	
W23	2'-0"	2'-6"	Н				6'-4"	
W24	2'-0"	2'-6"	Н				6'-4"	
W25	2'-0"	2'-6"	Н				6'-4"	
W26	4'-0"	4'-4"	G				7'-0"	
W27	4'-0"	4'-4"	G				7'-0"	
W28	4'-0"	4'-4"	G	YES			7'-0"	
W29	4'-0"	4'-4"	G				7'-0"	
W30	4'-0"	4'-4"	G				7'-0"	
W31	2'-6"	2'-8"	D				7'-0"	
W32	4'-4 ^{1/2} "	8'-0"	K	YES			8'-0"	

WINDOW NOTES:

I. ALL WINDOWS SHALL BE ALUMINUM CLAD WITH PRIMED WOOD INTERIOR, KOLBE VISTA LUXE OR APPROVED EQUAL UNLESS OTHERWISE NOTED

2.ALL WINDOW SCREENS SHALL BE STANDARD INSERTS, TYP.


3. SHADES: TBD

4. HARDWARE MOUNTING HEIGHT SHALL BE BETWEEN 34" AND 44" ABOVE THE FLOOR PER CBC 11B-404.2.7.

5. GLAZING TO BE LOW E^{2.}, CONTRACTOR TO PROVIDE GLAZING SAMPLES PROIR TO ORDERING FENESTRATION

6. SEE GENERAL NOTE #16 ON SHEET A0.1 FOR EGRESS WINDOW REQUIREMENTS


7. SEE EXTERIOR ELEVATIONS FOR HANDING





WINDOW ELEVATION

WINDOW LEGEND

TYPE







drawn by: DJA






ALL DRAWINGS AND WRITTEN MATERIALS CONTAINED HEREIN CONSTITUTE THE ORIGINAL AND UNPUBLISHED WORK OF THE ARCHITECT AND THE SAME MAY NOT BE DUPLICATED, USED OR DISCLOSED WITHOUT THE WRITTEN CONSENT OF THE ARCHITECT (© JUSTIN PAULY ARCHITECTS)


WINDOW SCHEDULES

sheet 37





SOUTH ELEVATION WEST ELEVATION





EAST ELEVATION NORTH ELEVATION



CEMENT PLASTER W/SEMI-SMOOTH FINISH BENJAMIN MOORE:



STONE VENEER: CARMEL STONE BROKEN COURSE/RANDOM PATTERN



VERTICAL CEDAR SIDING W/ CLEAR SEALER



METALSALES 24 GAUGE 18" WIDE I" MINI-BATTON STANDING SEAM ROOF, FINISH: MYSTIC PLUS



WOOD TRIM: PAINTED BENJAMIN MOORE: NORTH CREEK BROWN OR SIMILAR