Exhibit A

This page intentionally left blank.

DRAFT RESOLUTION

Before the RMA Zoning Administrator in and for the County of Monterey, State of California

In the matter of the application of: KHALSA DEVELOPMENT (PLN190428) RESOLUTION NO.

Resolution by the Monterey Zoning Administrator:

- Finding the project involves the construction of a single family dwelling in a residential area, which qualifies as a Class 3 Categorical Exemption pursuant to Section 15303(a) of the CEQA Guidelines; and there are no exceptions pursuant to Section 15300.2; and
- 2) Approving a Design Approval for the construction of a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot two-car garage.

[PLN190428 Khalsa Development, 11434 Del Monte Ave., Castroville, North County Area Plan, Castroville Community Plan (APN: 030-321-030-000)]

The Khalsa Development application (PLN190428) came for a public hearing before the Zoning Administrator on June 25, 2020. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Zoning Administrator finds and decides as follows: FINDINGS AND EVIDENCE

- FINDING: CONSISTENCY/DESIGN The Project is consistent with the applicable plans and policies which designate this area as appropriate for development, and is consistent with design standards for the area.
 EVIDENCE: a) During the course of review of this application, the project has been reviewed for consistency with the text, policies, and regulations in:
 - the 2010 Monterey County General Plan;
 - Castroville Community Plan;
 - Monterey County Zoning Ordinance (Title 21);

Communications were received from the public during the course of review of the project indicating concerns and potential inconsistency with the Planned Unit Development of which this project is part, but research and communication with the agent relieved those concerns. *See Evidence h below.* No conflicts were found to exist.

- <u>Allowed Use</u>. The property is located at 11434 Del Monte Avenue, Castroville (Assessor's Parcel Number 030-321-030-000), Castroville Community Plan. The proposed project is located on a 0.08 acre (3,438 square feet) vacant lot that is zoned residential.
- c) <u>Lot Legality.</u> The subject parcel is located in a residential subdivision created through the Sat Kirtan Singh/Kaur Khalsa Villa de Castro

Planned Unit Development (Resolution PC-00012). It is identified as Lot 9 on the Final Map, recorded December 19, 2001. Therefore, the subject parcel is a legal lot of record.

- d) <u>Design.</u> Pursuant to the Castroville Community Plan, the Project site and surrounding area are designated as a Design Control District (D District), which regulates the location, size, configuration, materials, and colors of structures and fences to assure the protection of the public viewshed and neighborhood character. Therefore, a Design Approval is required for the proposed development and the criteria to grant a Design Approval are met in this case. See Evidences e, f, g, and h below.
- e) The applicant proposes a two-story single family dwelling with a small porch and an attached two-car garage that incorporates architectural aesthetics in the Monterey style. The proposed architectural style is one of the preferred styles of the Castroville Community Plan Design Guidelines and is consistent with the surrounding residential neighborhood character.
- f) <u>Material and Color Finishes</u>. The applicant proposes exterior colors and materials that are consistent with the residential setting. The primary colors and materials include tan stucco body, light beige fascia and gutter trim, and brown asphalt shingles. The proposed exterior finishes are consistent with the surrounding residential neighborhood character.
- g) <u>Visual Resources.</u> Based on the evidence described above, the proposed structures and uses are consistent with the surrounding residential neighborhood character (i.e., structural design features, colors, and material finishes). As proposed, the project is consistent with neighborhood character, and assures visual integrity.
- Review of Development Standards. The project meets applicable (h) development standards in the Castroville Community Plan. The parcel is currently a vacant lot, zoned Medium Density Residential-Castroville (MDR-C) and is considered an "infill site." The Castroville Community Plan requires a minimum lot size of 2,500 square feet for small lot single family; the subject parcel is 3,438 square feet in size. Setbacks for small lots are 15 feet front, as low as zero, provided that the standards for minimum distance between buildings on adjacent properties are maintained on the sides, and 10 feet rear. The proposed project is planned to have 22 feet front, 5 feet and 7 feet, 9 inches sides, and 10 feet 4 inches rear setbacks. The minimum distance between buildings on adjacent properties is met. The height limit is 30 feet, and the proposed development is 25 feet in height. The allowable lot coverage for small lots is 35%, and the project is 32%. The project meets Title 21 parking standards by planning two covered parking spaces. The plans include placement and type of lighting that meets the Castroville Community Plan's requirements.

The project was referred to the Castroville Land Use Advisory Committee (LUAC) for review on May 4, 2020. The members present voted to support design approval (3-0), 2 absent. A member of the public who wished to attend the LUAC meeting wrote a letter of concern about its day-of cancellation (due to County Administrator instructions in response to novel coronavirus concerns) and their difficulty in finding subsequent online LUAC meeting posting. The letter of concern also highlighted two issues that they were going to speak to the LUAC about: the internal road in the PUD is unpaved, and a house on the opposite side of the PUD from the proposed project is perceived to be overcrowded and the occupants parking illegally. RMA-Planning staff and the project agent addressed these concerns with the member of the public.

The application, project plans, letter of concern and follow up email, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN190428.

2. **FINDING: SITE SUITABILITY** – The site is physically suitable for the use proposed.

- **EVIDENCE:** a) In March, 2000, the Planning Commission recommended Board of Supervisors approval on the re-subdivision of five parcels bounded on the west by Geil Street, the south by Koester Street, and the east side by Del Monte Street, resulting in fourteen detached, singlefamily lots. The project was processed for environmental assessment under CEQA with an Initial Study and Negative Declaration. RMA Planning identified potential impacts to archaeological resources. "Preliminary Cultural Resources Reconnaissance of Assessors Parcel Number 030-227004, 05, 06, 07 and 08, in Castroville, Monterey County, California," November 12, 1986 (LIB040418) by R. Paul Hampson and Gary S. Breschini Registered Professional Archaeologists with SOPA, concluded that there were no archaeological or cultural constraints that would indicate the site was not suitable for development. The subdivision was consistent with the 1982 Monterey County General Plan, which identified Castroville as a priority area for growth (1982 GP Appendix A, No. 4).
 - b) Specific to the 11434 Del Monte Avenue lot, which is the subject site for this proposed development, a Geotechnical Report was prepared November 12, 2019 by Grice Engineering, Inc., Salinas CA. The report recommended loose near surface soils be taken into account druing design and construction of the proposed residence. It concluded that there were no physical or environmental constraints that would indicate the site was not suitable for development. The report is attached to this resolution.
 - c) The project planner conducted a virtual site inspection on January 28, 2020 to verify that the project on the subject parcel conforms to the plans listed above and to verify that the site is suitable for this use.
 - d) The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN190428.
- 3. **FINDING: HEALTH AND SAFETY** Construction of this single family dwelling and garage will not, under the circumstances of this particular case, be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use, or be detrimental or injurious to

property and improvements in the neighborhood or to the general welfare of the County.

- **EVIDENCE:** a) The project was reviewed by the RMA-Planning. The project planner has recommended four conditions to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons
 - b) either residing or working in the neighborhood.
 The project has sewer and water lines onsite, with service provided by Castroville Community Service District.
 The application, project plans, and related support materials
 - c) submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN190428.
- 4. **FINDING: NO VIOLATIONS -** The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision, and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.
 - **EVIDENCE:** a) Staff reviewed Monterey County RMA-Planning and RMA-Building Services records and is not aware of any violations existing on subject property.
 - b) See preceding and following findings and evidence.
- 5. **FINDING CEQA (Exempt):** The project is a single family dwelling, which is categorically exempt from environmental review, and no unusual circumstances were identified to exist for the proposed project.
 - **EVIDENCE:** a) California Environmental Quality Act (CEQA) Guidelines Section 15303(a), categorically exempts the construction of one single family dwelling and accessory structures in a residential area.
 - b) The proposed project is to construct a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot two-car garage. Therefore, the project qualifies for a Class 3 categorical exemption pursuant to Sections 15303(a) of the CEQA guidelines.
 - c) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. The project does not involve a designated historical resource, a hazardous waste site, development located near or within view of a scenic highway, unusual circumstances that would result in a significant effect or development that would result in a cumulative significant impact. No adverse environmental effects were identified during staff review of the development application.
 - d) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN190428.
- FINDING: APPEALABILITY The decision on this project may be appealed to the Planning Commission.
 EVIDENCE: Section 21.80.040.A of the Monterey County Zoning Ordinance

(Planning Commission).

DECISION

NOW, THEREFORE, based on the above findings and evidence, the Zoning Administrator does hereby:

- 1) Find the project includes construction of a single family dwelling in a residential area that qualifies for a Class 3 Categorical Exemption pursuant to Section 15303(a) of the CEQA Guidelines; and there are no exceptions pursuant to Section 15300.2; and
- 2) Approve a Design Approval for the construction of a construction of a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot two-car garage, in general conformance with the attached plans and subject to the attached conditions which are both attached hereto and incorporated herein by reference.

PASSED AND ADOPTED this 25th day of June, 2020.

Mike Novo, Zoning Administrator

COPY OF THIS DECISION MAILED TO APPLICANT ON _____.

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE _____.

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

This permit expires 3 year after the above date of granting thereof unless construction or use is started within this period.

Monterey County RMA Planning

DRAFT Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN190428

1. PD001 - SPECIFIC USES ONLY

Responsible Department: RMA-Planning

Condition/Mitigation This Design Approval permit (PLN190428) allows the construction of a two-story **Monitoring Measure:** single family dwelling with a small porch and an attached two-car garage. The property is located at 11434 Del Monte Avenue, Castroville (Assessor's Parcel Number 030-321-030-000), Castroville Community Plan, North County Area Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the RMA Chief of Planning. Anv use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Compliance or Monitoring Action to be Performed:

2. PD002 - NOTICE PERMIT APPROVAL

Responsible Department: RMA-Planning

Condition/Mitigation The applicant shall record a Permit Approval Notice. This notice shall state:

"A Design Approval (Resolution Number _____) was approved by the Monterey County Zoning Administrator for Assessor's Parcel Number 030-321-030-000 on June 25, 2020. The permit was granted subject to 4 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the RMA Chief of Planning prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

Compliance or Monitoring Action to be Performed: Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

Responsible Department: **RMA-Planning**

Condition/Mitigation cultural, lf, during the course of construction, archaeological, historical or Monitoring Measure: paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a gualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a qualified archaeologist (i.e., an archaeologist registered with the Reaister of Professional Archaeologists) shall be immediately contacted by the responsible individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery. (RMA - Planning)

Compliance or Monitorina Action to be Performed:

The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

4. PD012(G) - LANDSCAPE PLAN & MAINTENANCE (OTHER)

Responsible Department: RMA-Planning

Condition/Mitigation Monitoring Measure: The site shall be landscaped. Prior to the issuance of building permits, three (3) copies of a landscaping plan shall be submitted to the RMA Chief of Planning. A landscape plan review fee is required for this project. Fees shall be paid at the time of landscape plan submittal. The landscaping plan shall be in sufficient detail to identify the location, species, and size of the proposed landscaping and shall include an irrigation plan. The landscaping shall be installed and inspected prior to occupancy. All landscaped areas and/or fences shall be continuously maintained by the applicant and all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition. (RMA - Planning)

Compliance or Prior to issuance of building permits, Owner/Applicant/Licensed Landscape the Monitoring Contractor/Licensed Landscape Architect shall submit landscape plans and Action to be Performed: contractor's estimate to RMA - Planning for review and approval. Landscaping plans shall include the recommendations from the Forest Management Plan or Biological All landscape plans shall be signed and stamped by licensed Survey as applicable. professional under the following statement, "I certify that this landscaping and irrigation plan complies with all Monterey County landscaping requirements including use of native, drought-tolerant, non-invasive species; limited turf; and low-flow, water conserving irrigation fixtures."

Prior to occupancy, the Owner/Applicant/Licensed Landscape Contractor/Licensed Landscape Architect shall ensure that the landscaping shall be installed and inspected.

On an on-going basis, all landscaped areas and fences shall be continuously maintained by the Owner/Applicant; all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition.

ABBREVIATIONS

GI GLB

GL GR GRD

GYP

HDR

HTR

HVAC

HORIZ

INCL

ID

JNT

JST

JB

KD

LAV

LIN

MH

MAX

MECH

MBR MTL

M.L.

MIN

MISC

MTG

NEC

NAT

NEC

(N) NOM

N

NTS

N/A

OC OPG

OD OA

OH

d

P.S.L.

PERF

PERP

PH

PL

PLY

PVC

PORC

PREFAB

PROP

PL

PA

PB

QTY

REC

R

REF

REG

R&R

REQD

ROW

RM

RGH

RND

SH

SVC

SIM SGL 1PH STC

SPKR SPEC

SQ SS

STD

STL

STR

STRUCT

SURF

S4S

S1S

S1S1E

S2S

SYS

TV

TELE

TEMP

TEMP

3PH

TP T&G T&B

TC

TB

TPL

2PH

TYP

ULT

24 X 36

CLEARPRINTO

T-STAT

SHTG

SCHED

REINF

PWR

PT

OBSC

LL

HD

GLUE LAMINATED BEAM GLASS GRADE GROUND GYPSUM HEADER HEATER HEATING, VENTILATING AND AIR CONDITIONING HOLDOWN HORIZONTAL INCLUDE(D), INCLUSIVE INSIDE DIAMETER. INTERNAL DIAMETER JOINT JOIST JUNCTION BOX **KILN-DRIED** LAVATORY LINEAR, LINEAL LIVE LOAD MANHOLE MAXIMUM MECHANICAL MEMBER METAL MICRO LAM BEAM MINIMUM MISCELLANEOUS MOUNTING NATIONAL ELECTRICAL CODE NATURAL NECESSARY NEW NOMINAL NORTH NOT TO SCALE NOT APPLICABLE OBSCURE **ON CENTER** OPENING OUTSIDE DIAMETER OVERALL OVERHEAD PARALAM PENNY (NAILS, ETC) PERFORATE(D) PERPENDICULAR PHASE PLAŤE PLYWOOD POINT POLYVINYL CHLORIDE PORCELAIN POWER PREFABRICATED PROPERTY PROPERTY LINE PUBLIC ADDRESS PUSH BUTTON QUANTITY RECESSED RADIUS **REFRIGERATE, REFRIGERATOR** REGISTER REINFORCE REMOVE AND REPLACE REQUIRED **RIGHT-OF-WAY** ROOM ROUGH ROUND SCHEDULE SINGLE HUNG (WINDOW) SERVICE SHEATHING SIMILAR SINGLE SINGLE-PHASE SOUND-TRANSMISSION CLASS SPEAKER SPECIFICATION SQUARE STAINLESS STEEL STANDARD STEEL STRUCTURAL STRUCTURE SURFACE SURFACED OR DRESSED FOUR SIDES SURFACES OR DRESSED ONE SIDE SURFACED OR DRESSED ONE SIDE AND ONE EDGE SURFACED OR DRESSED TWO SIDES SYSTEM TELEPHONE TELEVISION TEMPORARY TEMPERED GLASS THERMOSTAT THREE-PHASE **TOILET PAPER HOLDER TONGUE AND GROOVE** TOP AND BOTTOM TOP CHORD TOTAL LOAD TOWEL BAR TRIPLE TWO PHASE TYPICAL ULTIMATE UNDERGROUND UNIFORM BUILDING CODE UPPER UPPER AND LOWER VACUUM VENT THROUGH ROOF VENTILATE, VENTILATOR VERTICAL VOLTAGE VOLUME WASTE PIPE WATER CLOSET WATER HEATER WATERPROOF WEIGHT WELDED WEST WET BULB WITHOUT WOOD

GALVANIZED IRON

ACOUSTIC	ACST
ADAPTER	ADPTR
ADDENDUM, ADDITION (AL)	ADD
ADJACENT	ADJ
AGGREGATE	AGG
AIR CONDITION(ED)	A/C •
ALARM	ALM
ALIGNMENT	ALIGN
ALTERNATE	ALT
ALUMINUM	ALUM
AMERICAN WIRE GAGE	AWG
AMPERAGE (CURRENT)	Α
ANGLE (STRUCTURAL)	L
APARTMENT	APT
APPENDIX	APPX
APPROXIMATE	APPROX
ARCHITECTURE, ARCHITECTURAL	
ASPHALT	ASPH
ASSEMBLY	ASSY
ASSISTANT	ASST
AVENUE	AVE
AVERAGE	AVG
BALCONY	BALC
BASE PLATE	BP
BEAM	BM
BEARING	BRG
BELOW	BLW
BENCHMARK	BM
BETWEEN BIRMINGHAM WIRE GAGE	BETW
	BWG
BOARD BOTTOM	BD BOT
BOTTOM CHORD	BC
BUILDING	BLDG
CABINET	CAB
CALIFORNIA MECHANICAL CODE	CMC CEC
CALIFORNIA BUILDING CODE CALIFORNIA PLUMBING CODE	CBC CPC
CANTILEVER	CANTIL
CAPACITY	CAP
CAST IRON PIPE	CIP
CATALOG	CAT
CAULKING	CLKG
CEILING	CLG
CEMENT	CEM
CENTER	CTR
CENTERLINE	CL
CHECK VALVE	ČV
CIRCLE	CIR
CIRCUIT	CKT
CIRCULAR	CIRC
CLEANOUT	CO
CLEAR	CLR
	CLR
COATED	CTD
	CTD CW
COATED COLD WATER	CTD
COATED COLD WATER COLUMN	CTD CW COL
COATED COLD WATER COLUMN COMPOSITION	CTD CW COL COMP
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION	CTD CW COL COMP CONC
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS	CTD CW COL COMP CONC CONN CONST CONT
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR	CTD CW COL COMP CONC CONN CONST CONT CONTR
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD	CTD CW COL COMP CONC CONN CONST CONTR CONTR CSK CU DL
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE	CTD CW COL COMP CONC CONN CONST CONTR CONTR CSK CU DL DL DEG
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED)	CTD CW COL COMP CONC CONST CONST CONTR CSK CU DL DEG DSGN
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL	CTD CW COL COMP CONC CONN CONST CONTR CONTR CONTR CSK CU DL DEG DSGN DET
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER	CTD CW COL COMP CONC CONN CONST CONTR CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DIM
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR	CTD CW COL COMP CONC CONN CONST CONTR CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE	CTD CW COL COMP CONC CONN CONST CONTR CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW)	CTD CW COL COMP CONC CONST CONTR CONTR CONTR CONTR CONTR CONTR CONTR CONTR DE DE DE DE DE DE DE DE DIAG DIA DIM DW DR DBL DH
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN	CTD CW COL COMP CONC CONST CONTR CONTR CONTR CONTR CONTR CONTR CONTR CONTR DEL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL DH DN
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWN	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL DH DN DS
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL	CTD CW COL COMP CONC CONN CONST CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR	CTD CW COL COMP CONC CONN CONST CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTINGUISHER EXTINGUISHER EXTINGUISHER EXTINGUISHER EXTINGUISHER	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA HEAVY EXTRA STRONG	CTD CW COL COMP CONC CONST CONTR CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR
COATED COLD WATER COLUMN COMPOSITION CONRECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA HEAVY EXTRA STRONG EXTRUDE(D)	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD
COATED COLD WATER COLUMN COMPOSITION CONRECT, CONNECTOR CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA STRONG EXTRUDE(D) EXHAUST FAN	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT EXT EXT EXT
COATED COLD WATER COLUMN COMPOSITION CONRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIA DIA DIA DIA DIA DIA DIA DIA
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS	CTD CW COL COMP CONC CONN CONST CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD EF FAB
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD EF FAB FRP FIG
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL	CTD CW COL COMP CONC CONN CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD EF FAB FRP FIG FF
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXTRA STRONG EXTRUDE(D) EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EF FAB FRP FIG FF
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA STRONG EXTRUDE(D) EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR	CTD CW COL COMP CONC CONST CONT CONT CONT CONT CONT CONT CONT CON
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EL ENGR EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT STD EF FAB FF FP FL FD
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRIDE (D) EXTRA STRONG EXTRUDE (D) EXTRA STRONG EXTRUDE (D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOOR ING	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT XHVY XSTR EXT EF FAB FLG (FLRG)
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXTRING EXPANSION JOINT EXPOSED EXTERIOR EXTRING EXTRICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOORING FLUORESCENT	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT XHVY XSTR EF FAB FF FP FL FD FLG (FLRG) FLUOR
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXTANSION JOINT EXPOSED EXTERIOR EXTANSION JOINT EXPOSED EXTERIOR EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOOR ING	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT XHVY XSTR EXT EF FAB FF FP FIG FF FD FLG (FLRG) FLUOR FTG
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA STRONG EXTRUDE(D) EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOORING FLUORESCENT FOOUNDATION	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD EF FAB FL FD FLG (FLRG) FLUOR FTG FD
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOORING FLUORESCENT FOOTING FOUNDATION FORCED AIR FURNACE	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT XHVY XSTR ET FAB FF FF FL FD FLG (FLRG) FLUOR FTG FDN FAU
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWN DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTINGUISHER EXTRA STRONG EXTRUDE(D) EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOORING FLUORESCENT FOOUNDATION	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXH (E) EXP JT (EJ) EXP EXT EXT XHVY XSTR EXTD EF FAB FL FD FLG (FLRG) FLUOR FTG FD
COATED COLD WATER COLUMN COMPOSITION CONCRETE CONNECT, CONNECTOR CONSTRUCTION CONTINUE, CONTINUOUS CONTRACT, CONTRACTOR COUNTERSINK CUBIC DEAD LOAD DEGREE DESIGN(ED) DETAIL DIAGONAL DIAMETER DIMENSION DISHWASHER DOOR DOUBLE DOUBLE-HUNG (WINDOW) DOWNSPOUT EACH ELECTRIC, ELECTRICAL ELEVATION ENGINEER EQUAL EQUIPMENT EXCAVATE EXHAUST EXISTING EXPANSION JOINT EXPOSED EXTERIOR EXTRA HEAVY EXTRA STRONG EXTRUDE(D) EXHAUST FAN FABRICATE FIBERGLASS REINFORCED PLASTICS FIGURE FINISHED FLOOR LEVEL FIREPROOF FLOOR DRAIN FLOORING FLUORESCENT FOOTING FOUNDATION FORCED AIR FURNACE	CTD CW COL COMP CONC CONST CONT CONTR CSK CU DL DEG DSGN DET DIAG DIA DIM DW DR DBL DH DN DS EA ELEC EL ENGR EQ EQUIP EXC EXP JT (EJ) EXP EXT EXT XHVY XSTR EXT EXT XHVY XSTR ET FAB FF FF FL FD FLG (FLRG) FLUOR FTG FDN FAU

PLAN NOTATIONS UGND

BC PR &L	SYMBOL	DESCRIPTION
/AC /TR /ENT		SHEAR WALL TYPE
ERT	253	- DETAIL NUMBER - SHEET NUMBER
P C H		- REVISION NUMBER W CLOUD AROUND REVISED ITEMS
P T LD		-HORIZONTAL STRAP AT WALL
'B '/O 'D		VERTICAL STRAP AT WALL
	Φ	DIAMETER
	$\hat{\boldsymbol{\mu}}_{1}^{(1)}$, $\hat{\boldsymbol{\mu}}_{2}^{(1)}$,	SQUARE
		POST BELOW
		POST ABOVE

FIREBLOCKING REQUIRED

Fireblocking shall be provided to cut off all concealed draft openings (vertical and horizontal) and shall form an effective barrier between stories, between a top story and the roof space. Fireblocking shall be installed in wood framed construction in the following locations: 1. In concealed spaces of stud walls and partitions, including furred spaces and parallels rows of studs or staggered studs, as follows: 1.1 Vertically at the ceiling and floor levels. 1.2 Horizontally at intervals not exceeding 10 feet. At all interconnections between concealed vertical and horizontal spaces such as occur at soffits, drop ceilings and cove ceilings. In concealed spaces between stair stringers at the top and bottom of the run. Enclosed spaces under stairs shall comply with R302.7 At openings around vents, pipes, ducts, cables and wires at ceiling and floor level, with an approved material to resist the free passage of flame and products of combustion. The material filling this annular space shall not be required to meet ASTM E 136 requirements. For the fireblocking of chimneys and fireplaces, see R1003.19 N/A Contractor shall refer to CRC R302.11 for additional information not specified

above, and R302.11.1 for fireblocking materials.

GENERAL NOTES

- This project shall comply with the **2016 CBC, CRC, CMC, CPC, CFC**, 1. CEC, CAL-Green (mandatory section), California Energy Code based on the 2016 CA Energy Standards & Regulations, and all other governing codes and ordinances. The California Building Standards Code is based on the IBC & IFC, UMC & UPC and the NEC.
- **Copyrighted plans and documents:** The use of these plans and 2. specifications is restricted to the original site for which they were prepared. Publication of these documents is expressly limited to such use and reuse, and reproduction or publication by any method, in whole or part, is prohibited. Ownership of these documents remains with the designer, and visual contact with them constitutes prima facie evidence of the acceptance of these restrictions.
- Plans shall be scaled only where figures or other means of ascertaining 3. measurements are not given thereon, and then only where the scale of the drawings in question is plainly marked. Discrepancies shall be called to the attention of the designer for written interpretation before the work affected is executed.
- All wood framing members that rest on concrete or masonry exterior 4. foundation walls and are less than 8 inches from exposed ground shall be of redwood or preservative treated wood U.O.N. (CRC R317.1.2). **Contractor** shall field verify with owner all finishes including, finish
- carpentry, casework, and flooring.
- All roofing, siding, windows, sheetmetal and flashing shall be neatly done, 6. weathertight and substantial.
- All roof glass and glass in hazardous locations shall be of safety glazing 7. materials as per CRC R308. A permanent label per CRC R308.6.1 or R308.6.9 shall identify each light of safety glazing.
- Escape & Rescue Window: Bedrooms, and basements (unless noted in 8. CRC R310) shall have at least one exterior emergency escape and rescue opening in accordance with this section. Emergency escape and rescue openings shall open directly into a public way, or to a yard or court that opens to a public way.
 - **Note:** Escape and rescue openings shall have a minimum net clear opening of 5.7 s.f. U.O.N.. The minimum net clear opening height shall be 24". The minimum net clear opening width shall be 20". The opening shall have a sill height of not more than 44" above the floor. Exterior door may subsititute for excape and rescue window. See plans for natural light and ventilation compliance.
- **Roofing:** All roofing shall be installed in accordance with manufacturer's 9. specification and CRC R905. Builder to provide installation guide for inspection. Roofing manufacturer and approval are as follows: Comp. Shingles: GAF Timberline – Class "A", ICC #ESR-1475 or Certainteed – Class "A", ICC #ESR-3537
- 10. All metal connectors, to be Simpson Strong-tie. All connectors to be installed in accordance with manufacturer's specifications.
- 11. **Central Heating Furnace** shall be installed in accordance with
- manufacturer's specifications, and CMC 904. 12.
- Stucco Specifications: Exterior stucco (plaster) shall be a minimum of 7/8" thick, have 3-coats when applied over metal lath or wire fabric lath and not less than 2-coats when applied over masonry, concrete, pressurepreservative treated wood, decay resistant wood, or gypsum. Weather resistive barriers shall include 2 layers of grade 'D' paper over wood base sheathing. Install a 3 ½ ", 26 G. galvanized corrosion-resistant weep screed shall be installed at or below the foundation plate line on exterior stud walls. The screed shall be placed a minimum of 4" above earth or 2" above paved areas (CRC 703.6) See CBC 2512 for plaster applied over masonry.
- 13. Siding Specifications: Wood, hardboard, wood structural panel siding, wood shake or shingle siding, shall be installed over No. 15 asphalt felt, or ther approved water-resistive barrier such as Tyvek building wrap in accordance with CRC R703.
- **Fiber Cement** siding and other materials shall be installed in accordance with manufacturer's specifications, and CRC R703.
- 14. **Existing Utilities call 811:** Existing underground utilities and improvements are shown in their approximate locations and may not have been verified in the field and no guarantee is made as to the accuracy or completeness of the information shown. The contractor shall notify utility companies at least 2 working days in advance of construction to field locate utilities.

Call Underground Service Alert (U.S.A.) at 1-800-227-2600 or 811.

SPECIAL INSPECTIONS REQUIRED:

STRUCTURAL – Special Inspection See Structural Drawings

- 1. All Shear Wall nailing 4 inches o.c. or less including: P/2 Shear Wall E.N. 4" o.c.
 - P/3 Shear Wall E.N. 3" o.c.
 - P/4 Shear Wall E.N. 2" o.c.

DEFERRED SUBMITTAL ITEMS:

FIRE SPRINKLERS REQUIRED BY FIRE DEPARTMENT The building(s) and attached garage(s) shall be fully protected with automatic fire sprinkler system(s) installation shall be in accordance with the applicable NFPA standard. A minimum of (4) sets of plans for fire sprinkler systems must be submitted by a California licensed C-16 Contractor and approved prior to installation. This requirement is not intended to delay issuance of a building permit. A rough sprinkler inspection must be scheduled by the installing contractor and completed prior to requesting a framing inspection.

PLAN INDEX

SHEET	DESCRIPTION
T0 T1 T2	TITLE SHEET ENERGY COMPLIANCE ENERGY COMPLIANCE
C1	EROSION CONTROL & BMP'S
A1 A2 A3 A4 A5	SITE PLAN, ROOF PLAN FLOOR PLANS EXTERIOR ELEVATIONS CROSS SECTIONS DETAILS AND FINISH SCHEDULE
E1 E2	PLUMBING, MECHANICAL, AND ELECTRICAL NOTES ELECTRICAL PLANS
G1 G2	CAL-GREEN SH. 1 CAL-GREEN SH. 2
F1	FIRE DEPARTMENT NOTES
ร1 ร2 ร3 ร4 ร5 ร6 รา	STRUCTURAL NOTES STANDARD STRUCTURAL DETAILS ROOF FRAMING, FLOOR FRAMING, AND FOUNDATION PLANS DETAILS DETAILS DETAILS

BUILDING CLASSIFICATION

OCCUPANCY GROUP: R-3/U CONSTRUCTION TYPE: V-B SPRINKLERED STORIES: 2 HEIGHT: 25' **CODES: 2016 CALIFORNIA CODES** SCOPE OF WORK: NEW 1529 S.F. TWO STORY HOUSE W/ 432 S.F. TWO CAR GARAGE, AND 44 S.F. COVERED PORCH. GROUND DISTURBANCE: 1700 S.F. FLOOR AREA: HOUSE FIRST STORY 618 SF. SECOND STORY 911 S.F. GARAGE 432 S.F.

ENERGY COMPLIANCE METHOD: ENERGY PRO 7.2, 2016 ENERGY EFFICIENCY STANDARDS

CONSULTANTS

ENGINEER:	ALEXANDER OTT 603 PALM AVENUE SEASIDE, CA 93955 831 394-5936
ENERGY CONSULTANT:	MONTEREY ENERGY GROUP 26465 CARMEL RANCHO BLVD. CARMEL, CA 93923 831 250-0314
SOILS	

GRICE ENGINEERING, INC

561-A BRUNKEN AVENUE

SALINAS, CA 93901


831 375-1198

ENGINEER:


ADDRESS IDENTIFICATION


Prior to construction, a legible address identification shall be placed in a position that is visible from the street or road fronting the property. Address identification characters shall contrast with their background. Address numbers shall be all Arabic numbers or alphabetic letters. Numbers shall be spelled out. Each character shall not be less than 4 inches in height with a stroke width of not less than 0.5 inch. Where required by the fire code official, address identification shall be provided in additional approved locations to facilitate emergency response. Where access is by means of a private road and the building address cannot be viewed from the public way, a monument, pole or other sign or means shall be used to identify the structure. Address shall be maintained during construction.


A permanent address shall be posted on final project in accordance with the above specifications.




REVISIONS	BY
	-
EY, CA S	
IGN G CC RD., SUITE B3 / MONTEREY, CA. 93940 EAX AAK-5008	
sign 6 AG	
A CONSULTING DES A CONSULTING A CONSULTING	
364	4
HARI & YOKO KHALSA 4606 CERRILLOS DRIVE WOODLAND HILLS, CA 91364 (310) 292-8994 (310) 955-6342	
OWNERS: HARI & YOKO KHALSA 4606 CERRILLOS DRIVE WOODLAND HILLS, CA (310) 292-8994 (310) 955-6342	
KO KI ILLO D HIL 394	
& YOI CERR DLAN 292-8(
HARI & YOKO 4606 CERRILL WOODLAND H (310) 292-8994 (310) 955-6342	
ERS: I	
OWNE	
v	
AIA NIA	
SIDE ONT E, C	
ALSA RESIDENCE 134 DEL MONTE AVENUE STROVILLE, CALIFORNIA	000-00-170-000 .M
LSA 4 DE 1 RO	000
KHAL 11434 CAST	
x - 0 <	
Date 12-13-14	7
Drawn drafte	ct
Job 46.20	19
Sheet	· .
Of 21 Sheets	









It is unlawful to alter the substance of any official form or document of Monterey County. DA Request Form Inst

DA Request Form Instructions with Photo Guidelines Rev. 07/17/17

REPORT to MR. DARREN A. DAVIS DRAFTECT 2150 GARDEN ROAD, SUITE B-3 MONTEREY, CALIFORNIA 93940

GEOTECHNICAL REPORT for the proposed HARI KHALSA RESIDENCE 11434 DEL MONTE AVENUE CASTROVILLE, CALIFORNIA A. P. N. 030-321-030-000

by

GRICE ENGINEERING, INC. 561-A BRUNKEN AVENUE SALINAS, CALIFORNIA NOVEMBER 2019





ENGINEERING FOUNDATIONS

HYDROLOGY SEPTIC GEOTECHNICS EARTH STRUCTURES

> Salinas: (831) 422-9619 Monterey: (831) 375-1198 FAX: (831) 422-1896

561A Brunken Avenue Salinas, California 93901 griceengineering@sbcglobal.net

> File No. 7151-19.11 November 12, 2019

Mr. Darren A. Davis 2150 Garden Road, Suite B-3 Monterey, California 93940

Hari Khalsa Residence Project: 11434 Del Monte Avenue Castroville, California A. P. N. 030-321-030

Geotechnical Report Subject:

Dear Mr. Davis;

Pursuant to your request, we have completed our geotechnical investigation and evaluation of the above named site. It is our opinion that this site is suitable for the proposed development, provided the recommendations made herein are followed.

SOILS

In general, the near surface soils are loose and will need to be taken into account during design and construction of the proposed residence. Recommendations are given relative to this and other characteristics within the report and especially under Special Recommendations.

The report contained herein is made with our best efforts to evaluate the site, determine the site's geotechnical conditions and provide recommendations for these conditions. We submit this report with the understanding that it is the responsibility of the owner, or his representative, to ensure incorporation of these recommendations into the final plans, and their subsequent implementation in the field.

Page i

File No. 7151-19.11 November 12, 2019

Page ii

In addition, we recommend that GRICE ENGINEERING, INC., be retained to review the project plans and provide the construction supervision and testing required to document compliance with these recommendations. Should any site condition not mentioned in this report be observed, this office should be notified so that additional recommendations can be made, if necessary.

This report and the recommendations herein are made expressly for the above referenced project and may not be utilized for any other site without written permission of GRICE ENGINEERING, INC.

Please feel free to call this office should you have any questions regarding this report.



Very truly yours, GRICE ENGINEERING, INC.

Lawrence E. Grice, P.E. R.C.E. 66857

NOTICE TO OWNER

Any earthwork and grading performed without direct engineering supervision and materials testing by Grice Engineering Inc., will not be certified as complete and in accordance with the requirements set forth herein.

Foundations placed without observation of bearing conditions will not be certified as being in accordance with the requirements set forth herein.

Inspection of Work

It is recommended that all site work be inspected and tested during performance by this firm to establish compliance with these recommendations.

NOTIFY:	GRICE ENGINEERING INC.	SALINAS	(831) 422-9619
	561-A Brunken Avenue	MONTEREY	(831) 375-1198
	Salinas, California 93901	FAX	(831) 422-1896

A minimum of 48 hours (2 working days) notification is required prior to commencement of work so that scheduling for testing and inspections can be made.

Please be advised that costs incurred during inspection and testing of all site work is separate and not considered part of the fees as charged by Grice Engineering, Inc. for the report contained herein.

TABLE OF CONTENTS

LETTER OF TRANSMITTAL

Page No.

GEOTECHNICAL REPORT 1 Introduction, Method and Scope of Investigation 1 Site Description 1 Field Investigation 2 Site Soil Profile 3 Groundwater 3 Laboratory Testing 4 Seismic History 5 Regional Faults 5 Differential-Total Settlement - Static and Dynamic 6 Hydro-Collapse and Subsidence 6 Slope Stability 6 Seismic Strength Loss 6 Chemical Reactivity 7 Expansive Soils 7 Surface Rupture and Lateral Spreading 7 Seismicity 8 2016 California Building Code Geoseismic Classifications 8 CONCLUSIONS OF INVESTIGATION 9 Special Recommendations 9 Foundations and Footings 10
Slabs-on-Grade 11 Specifications for Rock Under Floor Slabs 12 Slope Ratio and Drainage 12 Surface Drainage and Erosion Control 13 Expansive Soils 14 Subsurface Drains 15 General Grading Recommendations 16
LIMITATIONS AND UNIFORMITY OF CONDITIONS
APPENDIX A.21Vicinity and Location Map22Site Map23Subdivision Map with Boring Locations24
APPENDIX B. 25 Boring Logs 26 Unified Soil Classification Chart 31
REFERENCES

GEOTECHNICAL REPORT for the proposed HARI KHALSA RESIDENCE 11434 DEL MONTE AVENUE CASTROVILLE, CALIFORNIA A. P. N. 030-321-030-000

Introduction, Method and Scope of Investigation

The purpose of this report is to evaluate the geotechnical properties of the site relative to the construction of a single family residence. From these findings recommendations are given for the design of the development and subsequent construction.

For this purpose, the site was investigated, and prior information concerning construction and subsurface exploration in this area was examined for soils and materials data. The investigation consisted of a detailed site evaluation, which included: a site inspection; a review of literature made available to GRICE ENGINEERING, INC., including Site Plans from Draftect; geotechnical drilling and soil sampling; materials evaluation; and analysis of the geotechnical properties of the site soils. This report concludes the results of the investigation and provides recommendations based on that work.

The findings and recommendations contained in this report are applicable only to the above named site and its proposed development, and may not be utilized for any other site or purpose without written permission of GRICE ENGINEERING, INC.

Site Description

The project site, 11434 Del Monte Avenue, is located to the southwest of Del Monte Avenue, approximately 92 feet northwest of its intersection with Koester Street, in the City of Castroville, an un-incorporated area of westernmost Monterey County, California. Please refer to the Vicinity and Location Maps and the Site Map in Appendix A for details.

The topography of the 3,462 square foot site encompasses a level area at an elevation of approximately 21 feet above mean sea level (msl). The majority of the undeveloped site is covered with grass.

Currently plans are for a two story, single family residence to be placed centrally on the lot. An attached two car garage is to be located on the residence's front facing the street with a short concrete driveway providing access. A concrete pathway will provide access to the front door while a small patio is to be located on the residence's rear.

Due to prior site activity, loose and disturbed soils and foreign objects may be encountered during construction and will have to be taken into account.

The approximately 1,529 square foot residence is to be of conventional wood construction with isolated and/or continuous spread footings. The approximately 432 square foot garage is to have a slab-on-grade floor.

Field Investigation

Our field investigation consisted of a site inspection, along with review of the drilling and sampling performed by Soils Surveys, Inc., Job #3784, February 21, 2003, in preparation of a Geotechnical Report for the overlaying subdivision. That investigation consisted of advancement of 3 exploratory bores to establish the subsurface soil profile, and obtain sufficient soil specimens to determine the soil characteristics. The report discusses exploratory drilling completed by M. Jacobs and Associates in 1987 for a similar purpose.

Drilling was accomplished by continuous flight auger, with the spoil constantly examined, classified, and logged by field method in accordance with the Unified Soil Classification Chart¹ which is the basis of ASTM D2487-10.

Relatively undisturbed soil samples were obtained by the penetration resistance method, (ASTM Method D1586-08), by which a split barrel sampler was driven a minimum of 18 inches into the sampled materials by free dropping a 140 pound weight 30 inches. The number of blows required to drive the sampler were recorded in 6 inch increments after conversion to Standard Penetration Resistance values (presumably). The number of blows required to drive the sampler the last two increments taken as the Standard Penetration Resistance. The split barrel sampler (ASTM D-1586-08), with dimensions of 1.375" I.D. x 2.0" O.D., is provided with 1 inch tall brass ring liners for the purpose of returning the samples to the laboratory in as near *in-situ** condition as possible.

* *In-situ* refers to the in place state of soil. *In-situ* native soils are those which are in-place as deposited by nature and have not been disturbed by man's actions in the historic past.

¹ Adopted 1952 by Corps of Engineers and Bureau of Reclamation. ASTM D2487 was developed as based on the Uniform Soils Classification Chart and System. The methods are equivalent.

Site Soil Profile

As found in the exploratory drilling, the site soils are generally consistent between each of the bores and is typical to the area.

The native topsoil was observed to be a black silty clay of medium plasticity. As encountered it was stiff and moist.

The native subsoils are a finely mottled olive-tan (yellowish brown) blend of silts and clay generally observed in lensatic deposition and of friable nature due to low moisture contents. As encountered they were moist and stiff.

The second bore was advanced to an approximate depth. In that bore at a depth of approximately 19 feet medium grained sands were encountered. These materials were observed medium dense to dense and dry to moist.

Complete soil characteristics and comments are reported on the boring logs at the depths observed. The logs completed by Soils Surveys, Inc. are included in Appendix B. Those by M. Jacobs were not available.

Groundwater

Free groundwater was encountered at this site at a depth of 26.0 feet below grade in the bores advanced by M. Jacobs as discussed in their report.

Laboratory Testing

Laboratory testing consisted of establishing the *in-situ* ** moisture content and dry density (ASTM D 2487-10) and unconfined penetration, direct shear testing (ASTM D 3080-04) and expansion index (ASTM D4829-08a). Standard Penetration Resistance values gained during the exploratory drilling are also included.

TABLE 1				
SUMMARY OF SOIL PROPERTIES				
TEST	MAXIMUM	MINIMUM		
Standard Penetration Resistance	62 blows/foot	9 blows/foot		
Unconfined Compression*	8 kips/ft ²	3 kips/ft ²		
In-Situ Density	112.7 lbs/ft ³	80.5 lbs/ft ³		
In-Situ Moisture	37.7 %	3.0 %		
Atterberg Limits	LL 44; PL 16; PI 28	LL 41; PL 15; PI 26		
Passing No. 200	65	47		
Compaction Curve	Compaction Curve 113.0 lbs/ft ³ @ 13.5 % water			

The following is a tabulation of the field and laboratory test result extremes:

All data obtained is reported in Appendix B including the boring logs, with soil classified described at depth observed.

* Pocket Penetrometer

** In-situ refers to the in-place state.

Seismic History

Although no fault traces are thought to directly cross the building site, Monterey County is traversed by a number of faults most of which are relatively minor hazards for the purposes of the site development. As such, this site will experience seismic activity of various magnitudes emanating from one or more of the numerous faults in the region.

Various maps presently exist, allowing observation on the site of distinctive geologic features. Some maps, such as that by Burkland and Associates (Reference No. 10) developed for Monterey County, are compilations from various sources detailing the locations of studied faults. Faults have inherit variances within their zones, and discoveries of new fault segments or entire faults is ongoing. There is also some difference in exact fault line location from source map to map, making precise location of said faults difficult. Therefore, relative to the information contained within this report, the following is considered to be as accurate as is currently possible from information made available to Grice Engineering Inc..

Regional Faults

Of most concern are active faults which have tectonic movement in the last 11,000 years and as such are called Holocene Faults and potentially active faults. The following are those nearest listed (Reference No. 12).

The most active is the San Andreas Rift System (Pajaro), located approximately 11.7 miles to the northeast. It has the greatest potential for seismic activity with estimated intensities of VIII-IX Mercalli in this location.

Other fault zones are the Zayante-Vergeles Fault Zone, the center of which is located approximately 7.8 miles to the northeast, the Rinconada Fault Zone, approximately 6.3 miles to the southwest, the Monterey Bay-Tularcitos Fault Zone, approximately 11.4 miles to the southwest, and the San Gregorio-Palo Colorado (Sur) Fault Zone, approximately 19.4 miles to the southwest. These zones are not as liable to rupture as the San Andreas and a seismic event at any of the above fault zones would likely produce earth movements of a lesser intensity at the site.

Liquefaction

The site soils are considered not susceptible to liquefaction as those portions which are cohesive clays and silts and medium dense to dense sands.

Differential-Total Settlement - Static and Dynamic

The recommendations given in the Geotechnical Report are such that concerns of settlement are negligible. The total settlement is expected to be less than 1/4 inch and the expected differential settlement less than one half that.

Hydro-Collapse and Subsidence

As observed the loose or disturbed soils near surface possess some capacity to settle under hydraulic loading or compress when saturated depending on the overburden pressure. Hydro-collapse in the native soils column is not common in the area. The recommendations given in this report were established to reduce the potential of this occurring.

The area is not within a known Subsidence Zone.

Slope Stability

Inspection of the site indicates that no landslides are located above or below the building area and the area is generally not susceptible to slope failure as it is near level.

Seismic Strength Loss

The site soils are considered resistant to seismic strength loss and the resulting momentary liquefaction. The relatively short duration of earthquake loading will not provide a significant number of high amplitude stress cycles to alter the strain characteristics. Additionally the clay-silt fraction is not considered quick nor sensitive, as such it will not have the associated loss of strength.

Chemical Reactivity

The area is well developed with structures, generally found on Portland Cement products. Additionally these structures date back to the 1940's or earlier. Much of the concrete used in these structures has remained as cast. The area soils are not known for sulfate reaction with Portland cement products and as such chemical reactivity is not considered a problem in this area.

Expansive Soils

In general the site soils are or contain clayey silts and clays of low to moderate plasticity. These soils are typical to the area. Expansivity has not been influential to the local structures and on grade pavements as no significant deformations attributable to expansive soils were observed. As any clay soil has some potential for expansivity, recommendations are given to minimize this potential.

Surface Rupture and Lateral Spreading

The project site is located 6.3 miles to the northeast of the Rinconada Fault (Quaternary). The site inspection did not reveal any surface features indicating a fault rupture has occurred at the site. The existing structure, driveways and roads do not reveal any strains which would be attributable to subsurface lateral or vertical displacements resulting from fault slip. Therefore surface rupture from fault activity across the site is considered improbable.

The project site is underlain by relatively strong soils. These materials are considered resistant to lateral spreading. As such surface rupture from lateral spreading is considered improbable.

Seismicity

It is recommended that all structures be designed and built in accordance with the requirements of the California Building Code's current edition. All buildings should be founded on undisturbed native soils and/or tested and accepted engineering fill to prevent resonance amplification between soils and the structure.

2016 California Building Code Geoseismic Classifications

The California Building Code, 2016 edition (Reference No. 13), provides for seismic design values. These values are to be utilized when evaluating structural elements. The soils profile determination is based on the penetration resistance data developed from advancement of exploratory bores. Using averaged penetration values per depth of soils type gives an overall site value of 26 blows/foot penetration resistance as per Equation 20.4-3, ASCE 7-10. The geoseismic character is as listed in the following table.

LATITUDE	ITUDE 36.763334 SOIL Stiff Soils PROFILE:			
LONGITUDE -121.747012 SITE CLASS D				
PERIOD	S	F	Sm	Sd
0.2 sec	Ss = 1.500	Fa = 1.000	Sms = 1.500	Sds = 1.000
1.0 sec	S1 = 0.598	Fv = 1.500	Sm1 = 0.897	Sd1 = 0.598

CONCLUSIONS OF INVESTIGATION

In general, the suitable, *in-situ**, native soils and certified engineered fill are acceptable for foundation purposes and display engineering properties adequate for the anticipated soil pressures, providing the recommendations in this report are followed.

Special Recommendations

As observed the surficial soils are imported fill or disturbed native soils to depths ranging from one to three feet. These soils are not considered suitable for support of on grade structures (engineered structures, eg. interior floor slabs, pavement, etc.) and foundations. Therefore it is recommended that such soils and any other unsuitable soils be processed as engineered fill within the building envelopes and extent of on grade structures. The minimum depth of processing is to include all such soils and the native topsoil were encountered. The depth is to be increased, as necessary, to include all unsuitable soils. Actual depth of processing is to be determined by the soils engineer or his representative during grading operations.

The site soils are clay of medium plasticity. Although expansivity is not a great concern in the area, some caution is warranted. As such recommendations are given on page 14 to minimize such expansivity.

The area has been developed and as such underground utilities may be located within the area of proposed construction. In addition, buried objects or deeply disturbed soils may also be encountered. As such all care and practice is to be exercised to observe for and locate any such objects. Where these objects are to be removed or use discontinued, they are to be removed in their entirety and all disturbed soils are to be processed as engineered fill.

The base of all excavations and over-excavations are to be inspected by the Soils Engineer prior to further processing, steel or form placement.

Any further site activity, especially grading and foundation excavations, should be under the direction of a qualified Soils Engineer or their Representative.

Should the spectrum of development change, this office should be notified so that additional recommendations can be made, if necessary.

^{*} Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics adequate for support of the intended load or application.

Foundations and Footings

Geotechnical evaluation indicates that square, round, and continuous spread footings are satisfactory types of support. The minimum embedment for shallow, spread foundations is 12 inches for single stories and 18 inches for two stories into suitable, *in-situ**, native soils or certified engineered fill. Embedment depths do not take into account the loose upper top soils, disturbed soils or any other unacceptable soils which exist at the site, e.g., any un-engineered fill, landscaping soils, etc.

VERTICAL SOIL PRESSURES ¹			
FOOTING TYPE	DEAD LOAD, kips/ft ²	DEAD + LL, kips/ft ²	
Spread & Isolated	2.5	3.3	
LATERAL SOIL PRESSURES ¹			
TYPE	VALUE, lbs/ft ²		
Active Earth Pressure	30 lbs/ft ³ (Equivalent Fluid Pressure)		
Restrained Earth Pressure	50 lbs/ft ³ (Equivalent Fluid Pressure)		
Seismic	2 lbs/ft ³ xH ² applied at 0.6H		
Friction at Base	0.30 × Dead Load		
Passive Earth Pressure	300 lbs/ft ³ × H ^{2 NOTE2}		
Uplift Friction	140 lbs/ft ² × H		

Notes: LL = Live Load; DL = Dead Load; H = Vertical height of material retained. One-third increase to be allowed for wind and seismic forces.

¹ For depths into acceptable native materials or engineered fill.

² Excludes near surface 0.5 feet of *in-situ* soils.

Pile and Pier foundation information is not provided as none are required or proposed. All foundation excavations are to be cleaned of debris and loose or otherwise unsuitable soils prior to placement of concrete.

* Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics adequate for support of the intended load or application.

Slabs-on-Grade

All slabs should be constructed over a prepared sub-grade placed on suitable *insitu** native material or certified engineered fill. The site exploration observed that the existing surficial soils are loose to depths of approximately 1 foot. These soils should not be relied upon for support of slabs on grade or other surficial structures.

As such where any unsuitable soils remain after excavation to subgrade they are to be processed as engineered fill prior to further fill placement or construction of the on grade structure. At a minimum the upper 6 inches of subgrade below all surficial structures should be processed as engineered fill in areas of on grade structures.

The native topsoil is a silty clay of low-medium to medium plasticity. This soil may change volume from variation in water content. Where new slabs are to be supported by these soils special consideration should be given to providing a properly prepared subgrade and pavement section. Further recommendations are given under Expansive Soils below.

The sub-grade materials should be observed and accepted by a qualified Soils Engineer or their representative prior to placement of forms, reinforcing or concrete.

On-grade slabs should be placed over a moisture vapor barrier consisting of a waterproof membrane (Moist Stop, 10 mil Visqueen, or equal) with a 2 inch protective sand cover. The waterproof membrane should be placed over a capillarity break consisting of 4 inches of open graded rock; round and sub-round rock is recommended to prevent puncture of the membrane. Open graded crushed aggregate may be utilized, provided the vapor barrier is protected from puncture by a cushion of filter fabric (Mirafi 140N or equal) laid over the aggregate prior to placement of the membrane. Where such concerns are not warranted, alternative underlayment may be utilized at the owners discretion.

All care and practice required to prevent puncture of the membrane during placement and pouring of covering slabs should be utilized during construction. Unless otherwise required for structural purposes, all slabs should be reinforced with a minimum of No.4, Grade 40, deformed steel reinforcing bar, 24 inches o.c., each way, to prevent separation and displacement in cases of cracking.

* Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics acceptable for support of the intended load or application.

Specifications for Rock Under Floor Slabs

Definition: Graded gravel of crushed rock for use under floor slabs shall consist of a minimum thickness of mineral aggregate placed in accordance with these specifications and in conformance with the dimensions shown on the project plans. The minimum thickness is specified under the section Slabs-on-Grade above.

Material: The mineral aggregate for use under floor slabs shall consist of broken stone, crushed or uncrushed gravel, quarry waste, or a combination thereof. The aggregate shall be free from adobe, vegetable matter, loam, volcanic tuff, and other deleterious substances. It shall be of such quality that the absorption of water in a saturated dry condition does not exceed 3 percent of the oven dry weight of the sample.

Grading: The mineral aggregate shall be of such size that the percentage composition by dry weight as determined by the use of laboratory sieves, U.S. Standard, in compliance with ASTM C 136-06, Standard Method for Sieve Analysis of Fine and Coarse Aggregates, will conform to the following grading specification:

SIEVE SIZE	PERCENTAGE PASSING SIEVE	
3/4 inch	100 %	
No. 4	0 - 10 %	
No. 200	0 - 2 %	

Placing: Sub-grade upon which gravel or crushed rock is to be placed shall be prepared as outlined in the Recommended Grading Specifications. In addition, the Sub-grade shall be kept moist so that no drying cracks appear prior to pouring slabs. If cracks appear, Sub-grade shall be moistened until cracks close.

Slope Ratio and Drainage

Analysis of site soils indicate that cut and fill slope ratios of 2 horizontal to 1 vertical will be satisfactory provided they are landscaped with soil retaining ground covers and are protected against concentrated over slope drainage.

Surface Drainage and Erosion Control

Design and construction of the project should fit the topographic and hydrologic features of the site. It is important to minimize unnecessary grading of or near steep slopes. Disturbing native vegetation and natural soil structure allows runoff velocity and transport of sediments to increase.

General surface drainage should be retained at low velocity by slope, sod or other energy reducing features sufficient to prevent erosion, with concentrated over-slope drainage carried in lined channels, flumes, pipe or other erosionpreventing installations.

Runoff flows should be directed into pipes or lined ditches and then onto an energy dissipater before discharging into streams or drainage ways. De-silting should be provided as necessary and may take form of stilling basins, gravel berms, forested/vegetated screens, etc.

All concentrated roof and area drainage should be conveyed and released to grade as divided as possible away from structures. If available runoff should be released to existing storm drain structure or patterns.

A sub-surface dispersal system may not be used as the site subsoils are not sufficiently permeable to infiltrate storm runoff.

Recent changes to the drainage requirements has the potential to alter drainage patterns. This has been observed to effect structures which have otherwise not been affected or to alter the way they are affected. As such new drainage modifications on this and adjacent parcels may negatively affect drainage patterns.

During construction, never store cut and fill material where it may wash into streams or drainage ways. Keep all culverts and drainage facilities free of silt and debris. Keep emergency erosion control materials such as straw mulch, plastic sheeting, and sandbags on-site and install these at the end of each day as necessary.

Re-vegetate and protect exposed soils by October 15. Use appropriate grass/legume seed mixes and/or straw mulch for temporary cover. Plan permanent vegetation to include native and drought tolerant plants. Seeding and re-vegetation may require special soil preparation, fertilizing, irrigation, and mulching.

Expansive Soils

As observed, the site soils are clay of moderate plasticity. In general these clays do not act expansively and the local structures are typically not subject to the affects of expansive clays. However improper treatment of these clays will result in unacceptable behavior and some precaution is economically warranted.

A potential for expansivity is in allowing those clayey soils, exposed by excavation and which are to be covered by foundations, slabs or engineered fill, to dry and not be re-saturated prior to placement of overlaying structure. Therefore it is recommended that all exposed clayey soils which are to be covered by engineered fill, foundations or slabs be kept at or above natural moisture or placed moisture content and above 3 percent over optimum moisture content. All native soils used as fill are to be placed at greater than 3 percent optimum moisture and compacted to a Relative Compaction between 88 and 91 percent.

Subsurface Drains

Use of spun filter fabric is not recommended for use in construction subsurface drains as this type of fabric typically becomes clogged. Should filter fabric be necessary it is recommended that a woven fabric be used such as Mirafi Filterweave 300. Otherwise we would recommend omission of the fabric and placement of Caltrans Class 1, Type 'A" or "B" drain rock, and that any fabric only be placed near the top of the trench between the gravel and earth backfill or where the gravel extends to grade, 1 foot below finish grade.

CLASS 1		
SIEVE SIZES	PERCENTAGE PASSING	
	TYPE A	TYPE B
50.0-mm/2 inches		100
37.5-mm/1.5 inches		95-100
19.0-mm/0.75 inches	100	50-100
12.5-mm/0.5 inches	95-100	
9.5-mm/0.415 inches	70-100	15-55
4.75-mm/No. 4	0-55	0-25
2.36-mm/No. 8	0-10	0-5
75.0-µm/No.200	0-3	0-3

General Grading Recommendations

For those items not directly addressed, it is recommended that all earthwork be performed in accordance with the following.

<u>General:</u> This item shall consist of all clearing and grubbing; preparation of land to be filled; excavation and fill of the land; spreading, compaction and control of the fill; and all subsidiary work necessary to complete the graded area to conform with the lines, grades and slopes as shown on the approved plans.

The Contractor shall provide all equipment and labor necessary to complete the work as specified herein, as shown on the approved plans as stated in the project specifications.

<u>Preparation:</u> Site preparation will consist of clearing and grubbing any existing structures and deleterious materials from the site, and the earthwork required to shape the site to receive the intended improvements, in accordance with the recommended grading specifications and the recommendations as provided above.

All vegetable matter, irreducible material greater than 4 inches and other deleterious materials shall be removed from the areas in which grading is to be done. Such materials not suitable for reuse shall be disposed of as directed.

After the foundation for fill has been cleared, it shall be brought to the proper moisture content by adding water or aerating and compacting to a Relative Compaction of not less than 90% or as specified. The soils shall be tested to a depth sufficient to determine quality and shall be approved by the Soils Engineer for foundation purposes prior to placing engineered fill.

<u>General Fill:</u> General fill shall be placed only on approved surfaces, as engineered fill, and shall be compacted to 90% Relative Compaction. Native soils accepted for fill or existing aggregate fill may be used for fill purposes provided all aggregate larger than 6 inches are removed. The material for engineered fill shall be approved by the Soils Engineer before commencement of grading operations.

Each layer shall be compacted to a Relative Compaction of not less than 90% or as specified in the soils report and on the accepted plans. Compaction shall be continuous over the entire area of each layer.

The selected fill material shall be placed in layers which, when compacted, shall not exceed 6 inches in thickness. Each layer shall be spread evenly and shall

be thoroughly mixed during the spreading to ensure uniformity of material in each layer. Fill shall be placed such that cross fall does not exceed 1 foot in 20 unless otherwise directed.

When fill material includes rock or concrete rubble, no irreducible material larger than 4 inches in greatest dimension will be allowed except under the direction of the Soils Engineer.

Imported Materials: Materials imported for fill purposes shall be classified as: SAND, group symbol SW, SP, SC or SM, as given in ASTM 2487-10, "The Classification of Soils For Engineering Purposes." In all cases the portion finer than the No. 200 sieve shall not contain any greatly expansive clays and shall be free from vegetable matter and other deleterious materials. The material for engineered fill shall be approved by the Soils Engineer before commencement of grading operations.

<u>Structural Backfill:</u> Trench, wall and structural backfill shall be placed only on approved surfaces, as engineered fill, and shall be compacted to 95% Relative Compaction. Materials imported for backfill purposes shall have a Sand Equivalent of no less than 30 and shall be classified as Clean Sands as designated in "The Classification of Soils For Engineering Purposes" (ASTM 2487-10).

<u>Pavement Grades:</u> All pavement grades shall be of uniform thickness, density and moisture prior to placement of the next grade. Flexure of each or all grades shall not exceed 0.25 inches in 5 feet under an axial load of 18.5 kip.

Aggregate Base Course: All aggregates used for specified base courses, shall be handled in a manner which prevents segregation and non-uniformity of gradation.

<u>Compaction:</u> All re-compacted soils and/or engineered fill should be placed at a minimum 90% Relative Compaction or at the value required for that portion of the work. All pavement sections should be compacted to a minimum of 95% Relative Compaction.

Field density testing shall be completed by the Soils Engineer on each compacted layer or as determined by the Soils Engineer. At least one test shall be made for each 500 cubic yards or fraction thereof, placed with a minimum of two tests per layer in isolated areas. Where a sheeps'-foot roller is used, the soil may be disturbed to a depth of several inches. Density tests shall be taken in compacted materials below the disturbed surface. When these tests indicate that the density of any layer of fill or portion thereof, is below the required density,

that particular layer or portion shall be reworked until the required density has been obtained.

<u>Moisture:</u> During compaction moisture content of native soils should be that consistent with the moisture relative to 95% Relative Compaction and in no case should these materials be placed at less than 3 percent above the specific optimum moisture content for the soil in question. The engineer may elect to accept high moisture compacted soils provided the materials are at 95% Relative Wet Density at that moisture content.

The moisture content of the fill material shall be maintained in a suitable range to permit efficient compaction. The Soils Engineer may require adding moisture, aerating, or blending of wet and dry soils.

All earth moving and work operations shall be controlled to prevent water from running into and pooling in excavated areas. All such water shall be promptly removed and the site kept drained.

<u>Tests:</u> All materials placed should be tested in accordance with the Compaction Control Tests: "Density of Soil In-Place by Sand Cone Method" (ASTM D-1556-07), "Moisture-Density Relationship of Soils" (ASTM D-1557-09), and "Density of Soils In-Place by Nuclear Method" (ASTM D-6938-10).

The standard test used to define maximum densities of all compaction work shall be the A.S.T.M. D-1557-09, Moisture Density of Soils, using a 10-pound ram and 18-inch drop. All densities shall be expressed as a relative density in terms of the maximum density obtained in the laboratory by the foregoing standard procedure.

<u>Deleterious Materials:</u> Materials containing an excess of 5% (by weight) of vegetative or other deleterious matter may be utilized in areas of landscaping or other non-structural fills. Deleterious material includes all vegetative and non-mineral material, and all non-reducible stone, rubble and/or mineral matter of greater than 6 inches.

<u>Over-Excavations:</u> Over-excavations, when required, should include the foundation and pavement envelopes. Such excavations should extend beyond edge of development a minimum of 5 feet and to an imaginary line extending away and downward at a slope of 45 degrees from the edge of development. The process shall include the complete removal of the required soils and subsequent placement of engineered fill. After removal of the soils to the required depth, the base of the excavation shall be inspected and approved by the Soils Engineer or his representative prior to further soils processing or

placement. Based on this inspection other recommendations may be made.

Existing Conditions: In developed areas underground utilities may be located within the area of proposed construction. In addition, buried objects or deeply disturbed soils may also be encountered. As such all care and practice is to be exercised to observe for and locate any such objects. Where these objects are to be removed or use discontinued, they are to be removed in their entirety and all disturbed soils are to be processed as engineered fill.

Key: All fills on slopes greater than 1 vertical to 6 horizontal shall be keyed into the adjacent soil. The toe of all slopes should be supported by a key cut a minimum of 3 feet into undisturbed soils to the inside of the fills toe. This key should be a minimum of 6 feet in width and slope at no less than 10% into the slope. In addition, as the fill advances up slope benches, 3 feet across, should be scarified into the fill/undisturbed soil interface.

<u>Seasonal Limits:</u> When the work is interrupted by rain, fill operations shall not be resumed until field tests by the Soils Engineer indicate that the moisture content and density of the fill is as previously specified and soils to be placed are in suitable condition

<u>Unusual Conditions:</u> In the event that any unusual conditions are encountered during grading operations which are not covered by the soil investigation or the specifications, the Soils Engineer shall be immediately notified such that additional recommendations may be made.

LIMITATIONS AND UNIFORMITY OF CONDITIONS

The recommendations of this report are based on our understanding of the project as represented by the plans, and the assumption that the soil conditions do not deviate from those represented in this site soils investigation. Therefore, should any variations or undesirable conditions be encountered during construction, or if the actual project will differ from that planned at this time, GRICE ENGINEERING INC. should be notified and provided the opportunity to make addendum recommendations if required.


NOTIFY:	GRICE ENGINEERING INC.	SALINAS	(831) 422-9619
	561-A Brunken Avenue	MONTEREY	(831) 375-1198
	Salinas, California 93901	FAX	(831) 422-1896


This report is issued with admonishment to the Owner and to his representative(s), that the information contained herein should be made available to the responsible project personnel including the architects, engineers, and contractors for the project. The recommendations contained herein should be incorporated into the plans, the specifications, and the final work.


It is requested that GRICE ENGINEERING INC. be retained to review the project grading and foundation plans to ensure compliance with these recommendations. Further, it is the position of GRICE ENGINEERING INC. that work performed without our knowledge and supervision, or the direction and supervision of a project responsible professional soils engineer renders this report invalid.

It is our opinion the findings of this report are **valid** as of the **present date**, <u>however</u>, changes in the **Codes and Requirements** can occur and change the recommendations given within this report concerning the property. In addition changes in the conditions of a property can occur with the passage of time, due either to natural processes or to the works of man and may affect this property. In addition, changes in **standards** may occur as a result of legislation, or the broadening of knowledge, and these changes may require re-evaluation of the conditions stated herein. Accordingly, the findings of this report may be invalidated wholly, or partially, by changes beyond our control. Therefore, this report is subject to review and should not be relied upon after a period of **three years**.

APPENDIX A







APPENDIX B

EXPLORATIO	N DR	ILL	LOG	ì		HOLE	NO. 1							
PROJECT Khalsa-Villa De Castro Subdivision	-Castrovill	e Job#	3784	DATE 1/16/03 LOGGED BY MAR										
DRILL RIG Cenozoic B-24 Mobile	HOLE	DIA. 4"		SAMPL	ER Terz	zaghi Split Spoon (SPT)								
GROUNDWATER DEPTH:	INITIAL			FINAL		HOLE E	ELEV. 18	•						
DESCRIPTION	SOIL TYPE	DEPTH	SAMPLE	BLOWS PER	DRY DENSITY	WATER	ΓΙΦΛΙΡ ΓΙΜΙΤ	PLASTIC LIMIT	DOCKET DEN					
Black silty clay; stiff, moist	CL/CH	1												
		2	SPT						-					
Same	CL/CH	3	XXX	10	85.5	24.7	44	15	2.					
Black silty clay; stiff, moist	CL/CH	4							-					
Olive-tan clayey silt/silty clay; slightly mottled, very stiff, moist	CL	5	SPT											
Bottom of hole @ 6.5'	CL	6 7	xxx	26	86.1	17.0			2.					
		8												
		9 10												
		11												
		12												
		13												
		14												
		15												
		17												
		18												
		19												
		20							-					

EXPLORATION	N DR	ILL	LOC	3		HOLE NO. 2							
PROJECT Khalsa-Villa De Castro Subdivision	-Castrovil	le Job	# 3784	DATE	1/16/03	LOGGE	ED BY M	AR					
DRILL RIG Cenozoic B-24 Mobile	HOLE	DIA. 4"		SAMP	LER Terz	aghi Spli	t Spoon	(SPT)					
GROUNDWATER DEPTH:	INITIAL	-		FINAL		HOLE	ELEV. 21	.5'					
DESCRIPTION	SOIL TYPE	DEPTH	SAMPLE	BLOWS PER	DRY DENSITY	WATER	LIQUID LIMIT	PLASTIC LIMIT	POCKET PEN.				
Black silty clay; stiff, moist	CL/CH	1											
		2	SPT										
Same	CL/CH		XXX	9	86.7	24.1			1.5				
		3		+	+								
	CL/CH	4											
Olive-tan clayey silty/silty clay: very stiff, moist	CL	5											
		-	SPT										
		6	XXX	28	85.7	24.5			2.0				
		7											
		8											
		9											
				<u></u>									
Olive-brown silty lean clay: stiff	CL	10											
		11											
		12											
Olive-brown silty clay; very stiff, moist	CL	10	SPT										
		13	XXX	17	85.2	37.7			3.0				
		14											
		15											
		16											
Dive-brown silty clay; very stiff	CL	17											
		18											
Grey-brown medium grained sand:	SP	19	SPT										
ery dense, dry			XXX	58	106.3	3.6							
DEPTH 24.5'	SOIL S	20 SUR	VEYS	INC.	1	l	1						

EXPLORATION	I DR	ILL I	LOG			HOLE	NO. 20	CONTIN	UED
DESCRIPTION	SOIL TYPE	DEPTH	SAMPLE	BLOWS PER	DRY DENSITY	WATER	LIQUID LIMIT	PLASTIC LIMIT	POCKET PEN.
Grey-brown medium grained sand: very dense	SP	21							
Gravelly @ 22'	SP SP/SW	22							
Grey-tan brown medium sand	SP	23	SPT						
Bottom of hole @ 24.5'	SP	25	XXX	62	112.7	3.0			
		26							
		28							
		29							
		30							
		32							
		33							
		35							
		36 37							
		38							
		39							
		40							
		42							
DEPTH 24.5' Job #3784	SOIL	SUR	/EYS	NC.	l	I			

EXPLORATIO	N DR	ILL	LOG	; 		HOLE	NO. 3		
PROJECT Khalsa-Villa De Castro Subdivisio	on-Castrovil	le Job‡	# 3784	DATE '	1/16/03	LOGGE	D BY M	AR	
DRILL RIG Cenozoic B-24 Mobile	HOLE	DIA. 4"		SAMPL	ER Terz	aghi Split	Spoon	(SPT)	
GROUNDWATER DEPTH:	INITIAL			FINAL		HOLE E	LEV. 21	1	
DESCRIPTION	SOIL TYPE	DEPTH	SAMPLE	BLOWS PER	DRY DENSITY	WATER	LIQUID LIMIT	PLASTIC LIMIT	POCKET PEN.
Grey-brown silty clay; dry	CL/CH	1							
Black silty lean clay; moist, stiff	CL	2	SPT						
	CL	3	XXX	10	89.9	23.8	41	15	2.0
		4	1000						
Olive-tan silty lean clay; stiff	CL								<u> </u>
		5	<u> </u>						
		6							
		7							
		8							
		9							
		10							
Olive-tan silty lean clay; moist, stiff, slightly mottled	CL	11	SPT						
Bottom of hole @ 11.5'	CL	12	XXX	12	80.5	35.3			4.0
19 - 19 - 19 - 19 - 19 - 19 - 19 - 19 -		13							
		14							
		15							
		16							
		17							
		18]				
		19							
		20							

		MOISTURE DE	ENSITY TESTS		
Test Hole No.	Depth Ft.	Moisture Content %	Dry Density p.c.f,	Standard Penetration Blows/Foot	Pocket Penetrometer Tons/Sq.Ft.
1	2-2.5	24.7	85.5	10	2.0
1	6-6.5	17.0	86.1	26	2.5
2	2-2.5	24.1	86.7	9	1.5
2	6-6.5	24.5	85.7	28	2.0
2	13-13.5	37.7	85.2	17	3.0
2	19-19.5	3.6	106.3	58	
2	24-24.5	3.0	112.7	62	
3	2.5-3	23.8	89.9	10	2.0
3	11-11.5	35.3	80.5	12	4.0

Two Plasticity Index (Atterberg Limits) tests were made from the driven core samples; results of these tests are tabulated as follows:

	water and the second	PLAST	ICITY INDEX	TESTS		
Test Hole No.	. Depth Feet	% Passing Sieve No, 4	% Passing Sieve No. 40	Liquid Limit	Plastic Limit	Plasticity Index
1	2-2.5	100	47	44	16	28
3	2-2.5	100	65	41	15	26

One Compaction Curve was made based on A.S.T.M. D1557-91. Results of that test are as follows:

Compaction Curve A.S.T.M. D 1557-91

	and the second se	Maximum	Optimum
Curve		Density	Moisture
No.	Material Description	p.c.f.	%
1	Black silty clay (Native)	113.0	13.5

The test hole logs and these tests indicate that the surface and near surface native soil consists of moderately expansive, stiff silty clay to depths ranging from 13 to 18.5 feet below surface; dense sand and gravelly sand was found below the clayey soil to a depth of 46 feet, and stiff silty clay was found from 46 to 50 feet. No free ground water was found in any of our recent test holes to a depth of 24.5 feet on the day of drilling; however free ground water was observed at 26 feet below surface in a Jacobs test hole on January 6, 1987.

2

TION	LABORATORY CLASSIFICATION CRITERIA	$C_{u} = \frac{D_{ED}}{D_{10}}$ Greater than 4 $C_{a} = \frac{D_{20}}{(D_{20})}$ Between one and 3	Not meeting all gradation re-	Atterberg limits below "A" line or PI less than 4	ettine casa symbols. GC, SW, S	Bord GM, (Not meeting all grad	Solution Attraction of the second state of the	More		OMPARING SOILS AT EQUAL LIQUID LIMIT Toundness and dry sterothth increases with	increasing plasticity index.					30 40 30 50 70 30 70 30 70 80 70 80 70 80 70 80 70 90 70 90 70 90 70 90 70 90 70 90 70 90 70 70 70 70 70 70 70 70 70 70 70 70 70			TOUGHNESS (Consistency near plastic limit)	After removing particles larger that the No. d0 size size, a spectiment of sell about one-half inch cube in size is midded to the consistency of publy. If no do six, water must be added and if sixs, the specimen should be specied on it in a thin typer and allowed to be sume noiskue by experigion. Then the	I on a smooth surface or between the parts more autread about one-eggit between the standard recipient preparatedly. Durning this manpulated the educed and the specimen stiffens, finally loses its plasticity, and crumbles	After the structure of the structure structure structure of the structure and a slight kneading action contanued until the lump crumples.	The tougher the thread near the plastic limit and the stiffer the lump when it finally cumbles, the more potent is the calloidal algri fraction in the soil. Wadness of the thread at the plastic limit and quick loss of contense of the lump behavior the plastic limit indicate there intergance to the voltasticity, or materials such as isalinitype thay and organic disks which occure below the Al-line.	Highly organic clays have a very weak and spongy feel at the plastic limit.
SIFICATION & ASTM D2487: INCLUDING IDENTIFICATION AND DESCRIPTION TYPICAL NAMES INFORMATION REQUIRED LABORATORY CLASSIFICATION CRITER		e. 9veia 0	size curv n No. 20	m grain : aller tha zwollo:	dentifica dentifican (fractin an aified as fo sp, SW, SF	are class of fines (are class	y to sege geineor	ateoreta ned no pr nising ean	Determin Dependii Soo (oos	i ərti br	iyîtnebi B	ni əviu B	100000	лівар өзі иі утізіта В с	าง	шŊ,	•	with clay bind		S (Consistency r	g particles large d to the consiste ead out in a thin	olled out by han ter. The thread tent is gradually stic limit is reach	d crumbles, the p crumbles.	the thread near 1 colloidal clay fra of the lump belo n-type clays and	c clays have a v
UDING IDENTIFICATION AND	INFORMATION REQUIRED FOR DESCRIBING SOILS	Give typical name, indicate approximate percentages of sand and gravel, max.	size; angularity, surface condition, and hardness of the coarse grains; local or geologic name and other pertinent	descriptive information, and symbol in parentheses.	For undisturbed soils add information on stratification, degree of compactness,	cementation, moisture conditions and drainage characteristics.	EXAMPLE: Silty Sand, gravelly; about 20% hard,	angular gravel particles + inch maximum size; rounded and subangular sand grains coarse to fine, about 15 %	non-plastic tines with low ory strength, well compacted and moist in place, alluvial sand; (SM).		Give typical name, indicate degree and character of plasticity, amount and movimum eiter of coarse arreine roller in	wet conditions, odor if any, local or geologic name, and other pertinent descriptive information and sumbal in	parentheses.	 For undisturbed soils add information or structure, stratification, consistency in undisturbed and remolded states, 	EXAMPLE:	Clayey silt, brown, slightly plastic, small percentage of fine sand, numerous	vertical root holes, firm and dry in place, loess; (ML).	amle GW-GC, well graded gravel-sand mixtur	R FRACTIONS inches. For field classification purposes, inchera with the tast	TOUGHNES					Highly organ
SIFICATION & ASTM D2487	TYPICAL NAMES	Well graded gravels, gravel-sand mixtures, little or no fines.	Poorly graded gravels, gravel-sand mixtures, little or no fines.	Silty gravels, poorly graded gravel-sand-silt mixtures.	Clayey gravels, poorly graded gravel-sand-clay mixtures.	Well graded sands, gravelly sands, little or no fines,	Poorly graded sands, gravelly sands, little or no fines.	Silty sands, poorly graded sand-silt mixtures.	Clayey sands, poorly graded sand-clay mixtures.		Inorganic silts and very vine sands, rock flour, silty or clayey fine sands withg slight plasticity.	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, sility clays, lean clays.	Organic sitts and organic sitt-clays of low plasticity.	Inorganic silts, micaceous or diatomaceous fine sandy or sitty soils, elastic silts.	Inorganic clays of high plasticity, fat clays.	Organic clays of medium to high plasticity.	Peat and other highly organic soils.	oups are designated by combinations of group symbols. For examle GW-GC, well graded gravel-sand mixture with clay binder	FIELD IDENTIFICATION PROCEDURES FOR FINE GRAINED SOILS OR FRACTIONS be performed on the minus No. Steve size particles, approximately thin interfaces. For field classification purposes, and a constantiant and and a constantiant and the montes the montes that interfaces with the test	Is not interluced, simply remove by names me coarse partones man in DRY STRENGTH (Crushing characteristics)	After removing particles larger than No. 40 sieve size, mold a par of soil to the consistency of putty, adding water if necessary. Allow the part to tyto requeterly by one, sun, or a participation and then test the stremotil to be breaking safet cumbling between the fingers. This strength is an messure of the	racter and dyality of the colloidal fraction contained in the soil. The dy easing plasticity.	High dry strength is chracterize for clayed the CH group. A pyrical horizent set presses only and a pyrical pyrical pyrical strength. Silv fine suid and silicit have about the same sight dry strength, but can be storgarguisted by the field with the powdering the dired speciment. Fine samd feels grith whereas a byderatigati has the smooth feel of flour.		
CH3	GROUP SYMBOLS N.	ВV	GР	Ø	g	s NS	SP	SM	sc		ML	Ъ	Р	MM	CH	HO	đ	of two gro	FIELD IDE	DRY :	After addir its st	chan	High very distir typic		
SUL	Ited weights	al amounts of all is.	zes with some g.	cedures see ML	dures see CL	ial amounts of all es.	zes with some g.	edures see ML	lures see CL	D SIEVE SIZE TOUGHNESS (CONDICTENCY NEAR PARTICE CANDIN	None	Medium	Slight	Slight to medium	High	Slight to medium	spongy feel and exture.	characteristics of two grou ard.	are to	2010	with a soil soft but	rously ance of water	issy. When the surface, f water character of	stic clay has ik reaction.	22
UNIFIE	CEDURES ctions on estima	Wide range in grain size and substantial amounts intermediate particle sizes.	Predominatly one size or a range of sizes intermediate sizes missing.	Non-plastic fines (for identification procedures below).	Plastic fires (for identification procedures below).	Vide range in grain sizes and substantial intermediate particle sizes.	Predominatly one size or a range of sizes intermediate sizes missing.	on-plastic fines (for idendification procedures below).	Plastic fines (for identification procedures see CL below).	SMALLER THAN No. 4 DILATANCY	Quick to slow	None to very slow	Slaw	Slow to none	None	None to very slow	Readily identified by color, odor, spon frequently by fibrous texture	s: Soils possessing ch nart are U.S. Standard	These procedures		ize, prepare a pot of moist soil with a water if necessary to make the soil soft but	contally, stricking vigi posists of the appear	ncy and becomes gli gloss disappear fror idity of appearance o ssist in identifying the	reactoin whereas a plastic clay has show a moderately quick reaction.	MATION-JANUARY 1962
	ATION PRO and basing fre	Vide range in grair interr	Predominatly one interm	Ion-plastic fines (f	Plastic fines (for	fide range in grain interr	Predominatly one interm	on-plastic fines (fo	Plastic fines (for	RES ON FRACTION	None to slight	Medium to high	Slight to medium	Slight to medium	High to very high	Medium to high	Readily identifie freque	undary classifications: Soils sieve sizes on this chart are			40 sieve size, prepi dd enough water if r	and and shake hori. A positive reaction c	s to a livery consists igers, the water and r crumbles. The rap during squeezing a	and most distinct re ypical rock flour, sh	BUREAU OF RECLA
	FIELD IDENTIFICATION PROCEDURES Excluding particles larger than 3 inches and basing fractions on estimated weights	action size ELS size si no si no si no si no	ELS GRAV GRAV Coarse fr GRAV GRAV GRAV	GRAVE (fines) isble isble isble isble isble isble isble isble isble isble isble	More thai is larger is vay be	raked eye faction fe 1/4" siz for 1/4" siz fron sr no sr s	le to the to CCEANS Castse f CLEANS (Little c (Little c	Hitcle visib AMI ATM ATM ATM ATM ATM ATM ATM ATM ATM ATM	isq teellsm srdt eroM ellisme ei	IDENTIFICATION PROCEDU	No. 200 a size is at CLAYS size than	ONA S	SILT:	sater	An her ner	STJIS	NIC SOILS	N. Boundary N. All sieve siz		DILATANCY (Reaction to shaking)	After removing portions larger than No. 40 sleve volume of about one-half cubic inch. Add enough not sticky	Place the pot in the open paim of one h against the other hand several times. A	on the startise of the point which includes to a hirty vortication; and headments globs; When on the sample is squared between the ingers; the water and globs disappear from the surface the post fifthers and finally at rackets are curvibles. The point of application presenter of variancer of during shaking and of its disappearance during squares and sasting assist. In dentifying the character of	the fines in a soll. Very fine clean sands give the quickes and n no reaction. Inorganic silts, such as a typical	ADOPTED BY: CORPS OF ENGINEERS AND BUREAU OF RECLAMATION-JANUARY
	Exclu	si 93			AINED							1105	ИИЕD	E GB/	EIN										
	CC en Aver liformia	93901		GIL Inas: (8		ER 2-9619 75-1198	NC 5 FAX:		1C 422-181	96	(nifi	ed	Soi	ils (Cla	assi		T atior		F

REFERENCES

- 1. American Society of Civil Engineers, Minimum Design Loads for Buildings and Other Structures, ASCE Standard ASCE/SEI 7-05 Including Supplement No. 1, 2006, 385 pp.
- Allen, C. R., 1975; Geological criteria for evaluating seismicity, GSA Bull. v. 86, p. 1041-1057.
- Bailey, E. H., Irwim, W. P. and Jones, D. L., 1964, Franciscan and Related Rocks, and their significance in the Geology of Western California, CDMG Bulletin 183, 177 pp.
- 4. Bailey, E.H., Ed., 1966, **Geology of Northern California**, CDMG Bulletin 190, 507 pp.
- 5. Blair, M.L. and Spangle, W. E., 1979, Seismic Safety and Land-Use Planning - Selected Examples from California, USGS Professional Paper 941-B.
- 6. Bolt, B. A., 1975; Geological Hazards, Springer-Verlag, 328 p.
- 7. Bryant, W. A., 1985; Faults in the Southern Monterey Bay area, CDMG Fault Evaluation Report FER-167, 13 pp.
- Bullis, K.C., 1980, Environmental Constraints Analysis of Monterey County, Part I: Seismic and Geologic Hazards, Monterey County Planning Department, General Update Program, Second printing June 1982, 54pp and appendices.
- 9. Bullis, K.C., 1981, Environmental Constraints Analysis of Monterey County, Part I: Flood, Fire and Miscellaneous Hazards; Emergency Preparedness, Monterey County Planning Department, General Update Program, pp 55-104 and appendices.
- 10. Burkland and Assoc., 1975, Seismic Safety Element of the Monterey County General Plan, 50 pp w/appendices.
- 11. Burkland and Associates, 1975; **Geotechnical study for the seismic safety** element, Monterey County, California, File No. K3-0113-M1, 125 pp.
- 12. California Department of Conservation, 1998, Maps of Known Active Fault Near-Source Zones in California and Adjacent Portions of Nevada, International Conference of Building Officials, Introduction & Maps.

- 2016 California Building Code, California Code of Regulations, Title 24, 2 Volumes, California Building Standards Commission, Based on the 2015 International Building Code.
- 14. Clark, J. C. and Reitman, J. D., 1973. Oligocene stratigraphy, tectonics, and paleogeography southwest of the San Andreas fault, Santa Cruz Mountains and Gabilan Range, California Coast Ranges: U.S. G. S. Professional Paper 783, 18 p.
- 15. Clark, J. C., Diblee, T. W. Jr., Greene, H. G., and Bowen, O. E., Jr., 1974, Preliminary geologic map of the Monterey and Seaside 7.5 minute quadrangles, Monterey County, California, with emphasis on active faults, USGS Miscellaneous Field Studies Map MF-577.
- Clark, Joseph C., Dupré, William R., & Rosenberg, Lewis I., Geological Map of the Monterey and Seaside 7.5 minute Quadrangles, Monterey County, California: A Digital Database, 1997, U. S. Department of the Interior, U. S. Geological Survey, Open-File Report 97-30, Map and Pamphlet, 26 pp.
- 17. Clark, Joseph C., Brabb, Earl E., & Rosenberg, Lewis I., 2000, Geologic Map of the Spreckels 7.5-Minute Quadrangle, Monterey County, California, USGS/Department of the Interior, Map MF-2349 & Pamphlet, 22 pp.
- Clark, Joseph C. & Rosenberg, Lewis I., March 1999, Southern San Gregorio Fault Displacement: Stepover Segmentation VS. Through-Going Tectonics, USGS /Department of the Interior-National Earthquake Hazards Reduction Program, Award number 1434-HQ-98-GR-00007, 22 pp without Appendices
- 19. Cleveland, G.B., 1975, Landsliding in Marine Terrace Terrain, California, CDMG Special Report 119, 24pp.
- 20. Compton, R. R., 1966; Granitic and metamorphic rocks of the Salinian Block, California Coast Ranges, CDMG Bulletin 190, p. 277-287.
- 21. Diblee, T. W. Jr., 1966; Evidence for cumulative offset on the San Andreas fault in central and northern California, CDMG Bulletin 190.
- 22. Diblee, T. W., Jr., 1999; Geologic Map of the Monterey Peninsula and Vicinity, Monterey, Salinas, Point Sur, and Jamesburg 15-Minute Quadrangles, Monterey County, California, Diblee Geological Foundation Map #DF-71.

- 23. Dickinson, William R., Duccea, Mihai, Rosenberg, Lewis I., Greene, H. Gary, Graham, Stephan A., Clark, Joseph C., Weber, Gerald E., Kidder, Steven, Ernst, W. Gary and Brabb, Earl E., 2005; Net dextral slip, Neogene San Gregorio-Hosgri fault zone, coastal California: Geologic evidence and tectonic implications, Geological Society of America, Special Paper 391, 43 pp.
- 24. Dittmer, E. and Stein, C., 1977, Salinas Seismic Hazards Technical Report, Department of Community Development, City of Salinas, 73 pp.
- 25. Dupre, W. R. and Tinsley, J. C. III, 1980, Geology and liquefaction potential of northern Monterey and southern Santa Cruz, California: USGS Miscellaneous Field Studies Map 1199, Scale 1:62,500, 2 sheets.
- 26. Dupre, W. R., 1990, Maps Showing Geology and Liquefaction Susceptibility of Quaternary Deposits in the Monterey, Seaside, Spreckels and Carmel Valley Quadrangles, Monterey County, CA, U. S. Geological Survey and University of Huston, Map #MF-2096, 2 Sheets
- 27. Durham, D.L., 1974; Geology of the Southern Salinas Valley Area, California, USGS Professional Paper 819, 111 pp.
- 28. Greene, H. G., Lee, W.H.K., McCulloch, D.S., and Brabb, E.E., 1973; Faults and Earthquakes in the Monterey Bay Region, California, USGS MF 518, maps and paper, 14pp.
- 29. Greene, H. G., 1977; Geology of the Monterey Bay region, USGS Open-File Report p. 77-718.
- 30. Hays, W.W., 1980, **Procedures for Estimating Earthquake Ground Motions**, USGS Professional Paper 1114, 77 pp.
- 31. Jennings, C. W., and Strand, R. G., 1958; Geologic Map of California, Olaf P. Jenkins edition, Santa Cruz sheet, Scale 1:250,000, third printing 1971.
- 32. Jennings, C. W., and Bryant, W. A., 2010 Fault Activity Map of California: California Geological Survey Geologic Data Map, No. 6, Map Scale 1:750,000, Includes "An Explanatory Text to Accompany the Fault Activity Map of California", 94 pp
- Lee, L. Don, Gudson, Seldon and Kauffman, Marvin E., 1978, Physical Geology, 5th Ed., Prentice Hall, Inc, Englewwod Cliffs, New Jersey 07632, 490 pp.

- 34. Lindh, A. G., 1983; Preliminary assessment of long-term probabilities for large earthquakes along selected fault segments of the San Andreas fault system in California, USGS Open File Report 83-63, 15 p.
- 35. Nason, R. D., and Rogers, T. H., 1967; Self-guiding map to active faulting in the San Juan Bautista quadrangle, conference on geologic problems of the San Andreas fault system, Stanford University, scale 1:24,000.
- 36. Nilsen, T.H., Diblee, T.W. Jr., and Blake, M.C. Jr., 1990, Geology of the Central Diablo Range, CA, Field Trip June 2-3.
- Oakeshott, G. B., 1966; San Andreas fault in the California Coast Range Province, in Bailey, E. H., ed., Geology of Northern California, CDMG Bulletin 190, p. 357-373.
- Plafker, G. and Galloway, J.P., eds., 1989 (approved for publication), Lessons Learned from the Loma Prieta, California, Earthquake of October 17, 1989, USGS Circular 1045, 48 pp.
- 39. Ray, R.G., 1960, Aerial Photographs in Geologic Interpretation and Mapping, USGS Professional Paper 373, seventh printing, 1984, 230 pp.
- 40. Real Estate Data Inc., 1980; Aerial/Map Volume of Monterey County, California, Photo 110, 2398 NW 119th St., Miami, FLA 33167, fifteenth edition.
- 41. Robbins, S.L., 1982, **Complete Bouguer Gravity, Aeromagnetic, and Generalized Geologic map of the Hollister 15-minute Quadrangle, CA**, Geophysical Investigations Map GP 945, 2 sheets, Scale 1:62,500.
- 42. Sarna-Wojcicki, A.M., Pampeyan, E.H. and Hall, N.T., 1975, Maps Showing Recently Active Breaks Along the San Andreas Fault Between the Central Santa Cruz Mountains and the Northern Gabilan Range, CA, 2 maps, text is on map 2, Scale 1:24,000.
- 43. Spangle, Wm. and Associates, Burkland and Associates, and Thorup, Richard R., July 1974; Faults, Seismicity and Tsunami Hazards: Monterey County, California: Part of Geological Report, County Map 3, File No. K4-0113-M1.
- Tinsley, J. C. III, 1975, Quaternary geology of northern Salinas Valley, Monterey County, California: Stanford University PhD. thesis, 194 p., map, scale 1:62,500.
- 45. US Department of Agriculture, Soil Conservation Service, 1978, **Soil Survey**, **Monterey County, CA**, 226 pages and maps.

- 46. US Geological Survey, California Geological Survey, 2006, Quaternary Fault and Fold Database for the United States, access date same as report, from URL: <u>http://earthquakes.usgs.gov/regional/qfaults/</u>
- 47. US Geological Survey / California Geological Survey, 2006, **The USGS Store**, **Map Locator**, access date same as report, from URL: <u>http://store.usgs.gov/</u> click on 'map locator'
- 48. USGS Earthquake Hazards Program, Seismic Design Values for Buildings-Earthquake Ground Motion Parameter, URL: <u>http://earthquake.usgs.gov/research/hazmaps/design/index.php</u>
- 49. USGS Open File Report 88-398, 1988, **Probabilities of Large Earthquakes Occurring in California on the San Andreas Fault**, by the Working Group on California Earthquake Probabilities, 62 pp.
- 50. Wallace, R. E., 1970; Earthquake recurrence intervals on the San Andreas fault, GSA Bulletin, v. 81.
- 51. Wagner, David L., Greene, H. Gary, Saucedo, George J. and Pridmore, Cynthia L. Compiled by., Watkins, Sarah E., Little, Jason D. and Bizzarro, Joseph J. Digitalized by. 2002, California Department of Conservation, Geologic Map of the Monterey 30' x 60' Quadrangle and Adjacent Areas, CA, 3 maps and CD-ROM
- 52. Ward, P.L. and Page, R.A., 1989, **The Loma Prieta Earthquake of Oct 17**, **1989**, USGS Pamphlet, Hdgen, L.D. and Troll, J.A., eds., second printing, revised, January 1990.
- 53. Wyss, M., 1979; Estimating maximum expectable magnitude of earthquakes from fault dimensions, Geology, v. 7, n. 7, p. 336-340.
- 54. Youd, T. L., and Hoose, S. N., 1978; Historic ground failures in northern California triggered by earthquakes, USGS Professional Paper P-993, p. 177