

# Exhibit B

This page intentionally left blank.

## **DRAFT RESOLUTION**

### **Before the RMA Zoning Administrator in and for the County of Monterey, State of California**

In the matter of the application of:

**KHALSA DEVELOPMENT (PLN190429)  
RESOLUTION NO.**

Resolution by the Monterey Zoning Administrator:

- 1) Finding the project involves the construction of a single family dwelling in a residential area, which qualifies as a Class 3 Categorical Exemption pursuant to Section 15303(a) of the CEQA Guidelines; and there are no exceptions pursuant to Section 15300.2; and
- 2) Approving a Design Approval for the construction of a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot two-car garage.

[PLN190429 Khalsa Development, 11430 Del Monte Ave., Castroville, North County Area Plan, Castroville Community Plan (APN: 030-321-031-000)]

**The Khalsa Development application (PLN190429) came for a public hearing before the Zoning Administrator on June 25, 2020. Having considered all the written and documentary evidence, the administrative record, the staff report, oral testimony, and other evidence presented, the Zoning Administrator finds and decides as follows:**

#### **FINDINGS AND EVIDENCE**

1. **FINDING:** **CONSISTENCY/DESIGN** – The Project is consistent with the applicable plans and policies which designate this area as appropriate for development, and is consistent with design standards for the area.  
**EVIDENCE:**
  - a) During the course of review of this application, the project has been reviewed for consistency with the text, policies, and regulations in:
    - the 2010 Monterey County General Plan;
    - Castroville Community Plan;
    - Monterey County Zoning Ordinance (Title 21);Communications were received from the public during the course of review of the project indicating concerns and potential inconsistency with the Planned Unit Development of which this project is part, but research and communication with the agent relieved those concerns. A letter and follow-up email were sent in reference to PLN190428. They are attached to that project's files, and discussed in the staff report. No conflicts were found to exist.
  - b) Allowed Use. The property is located at 11430 Del Monte Avenue, Castroville (Assessor's Parcel Number 030-321-031-000), Castroville Community Plan. The proposed project is located on a 0.096 acre (4,205 square feet) vacant lot that is zoned residential.

- c) Lot Legality. The subject parcel is located in a residential subdivision created through the Sat Kirtan Singh/Kaur Khalsa Villa de Castro Planned Unit Development (Resolution PC-00012). It is identified as Lot 10 on the Final Map, recorded December 19, 2001. Therefore, the subject parcel is a legal lot of record.
- d) Design. Pursuant to the Castroville Community Plan, the project site and surrounding area are designated as a Design Control District (D District), which regulates the location, size, configuration, materials, and colors of structures and fences to assure the protection of the public viewshed and neighborhood character. Therefore, a Design Approval is required for the proposed development and the criteria to grant a Design Approval are met in this case. See Evidences e, f, g, and h below.
- e) The applicant proposes a two-story single family dwelling with attached two-car garage and small porch that incorporates architectural aesthetics in the Monterey style. The proposed architectural style is one of the preferred styles of the Castroville Community Plan Design Guidelines and is consistent with the surrounding residential neighborhood character.
- f) Material and Color Finishes. The applicant proposes exterior colors and materials that are consistent with the residential setting. The colors and materials include light beige stucco body, off-white fascia and gutter trim, and brown asphalt shingles. The proposed exterior finishes are consistent with the surrounding residential neighborhood character.
- g) Visual Resources. Based on the evidence described above, the proposed structures and uses are consistent with the surrounding residential neighborhood character (i.e., structural design features, colors, and material finishes). As proposed, the project is consistent with neighborhood character, and assures visual integrity.
- h) Review of Development Standards. The project meets applicable development standards in the Castroville Community Plan. The parcel is currently a vacant lot, zoned Medium Density Residential-Castroville (MDR-C) and is considered an “infill site.” The Castroville Community Plan requires a minimum lot size of 2,500 square feet for small lot single family; the subject parcel is 4,205 square feet in size. Setbacks for small lots are 15 feet front, as low as zero, provided that the standards for minimum distance between buildings on adjacent properties are maintained on the sides, and 10 feet rear. The proposed project is planned to have 22 feet front, 5 feet and 7 feet, 9 inch sides, and 32 feet rear setbacks. The minimum distance between buildings on adjacent properties is met. The height limit for small lot single family is 30 feet, and the proposed development height is 25 feet, 6 inches. The allowable lot coverage for small lots is 35%, and the coverage of the proposed project is 26%. The project meets Title 21 parking standards by planning two covered parking spaces. The plans include placement and type of lighting that meets the Castroville Community Plan’s requirements. The project was referred to the Castroville Land Use Advisory Committee (LUAC) for review on May 4, 2020. The members present voted to support design approval (3-0), 2 absent.



The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN190429.

2.       **FINDING:**       **SITE SUITABILITY** – The site is physically suitable for the use proposed.
- EVIDENCE:**   a)   In March, 2000, the Planning Commission recommended Board of Supervisors approval on the re-subdivision of five parcels bounded on the west by Geil Street, the south by Koester Street, and the east side by Del Monte Street, resulting in fourteen detached, single-family lots. The project was processed for environmental assessment under CEQA with an Initial Study and Negative Declaration. RMA Planning identified potential impacts to archaeological resources. “Preliminary Cultural Resources Reconnaissance of Assessors Parcel Number 030-227004, 05, 06, 07 and 08, in Castroville, Monterey County, California,” November 12, 1986 (LIB040418) by R. Paul Hampson and Gary S. Breschini Registered Professional Archaeologists with SOPA, concluded that there were no archaeological or cultural constraints that would indicate the site was not suitable for development. The subdivision was consistent with the 1982 Monterey County General Plan, which identified Castroville as a priority area for growth (1982 GP Appendix A, No. 4).
- b)   Specific to the 11430 Del Monte Avenue lot, which is the subject site for this proposed development, a Geotechnical Report was prepared November 12, 2019 by Grice Engineering, Inc., Salinas CA. The report recommended loose near surface soils be taken into account during design and construction of the proposed residence. It concluded that there were no physical or environmental constraints that would indicate the site was not suitable for development. The document is attached to this resolution.
- c)   The project planner conducted a virtual site inspection on January 28, 2020 to verify that the project on the subject parcel conforms to the plans listed above and to verify that the site is suitable for this use.
- d)   The application, plans, and supporting materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN190429.
3.       **FINDING:**       **HEALTH AND SAFETY** – Construction of this single family dwelling and garage will not, under the circumstances of this particular case, be detrimental to the health, safety, peace, morals, comfort, and general welfare of persons residing or working in the neighborhood of such proposed use, or be detrimental or injurious to property and improvements in the neighborhood or to the general welfare of the County.
- EVIDENCE:**   a)   The project was reviewed by the RMA-Planning. The project planner has recommended four conditions to ensure that the project will not have an adverse effect on the health, safety, and welfare of persons either residing or working in the neighborhood.
- b)   The project has sewer and water lines onsite, with service provided by Castroville Community Service District.

- c) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development are found in Project File PLN190429.
4.       **FINDING:**       **NO VIOLATIONS** - The subject property is in compliance with all rules and regulations pertaining to zoning uses, subdivision, and any other applicable provisions of the County's zoning ordinance. No violations exist on the property.
- EVIDENCE:** a) Staff reviewed Monterey County RMA-Planning and RMA-Building Services records and is not aware of any violations existing on subject property.
- b) See preceding and following findings and evidence.
5.       **FINDING**       **CEQA (Exempt):** - The project is a single family dwelling, which is categorically exempt from environmental review, and no unusual circumstances were identified to exist for the proposed project.
- EVIDENCE:** a) California Environmental Quality Act (CEQA) Guidelines Section 15303(a), categorically exempts the construction of one single family dwelling and accessory structures in a residential area.
- b) The proposed project is to construct a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot attached two-car garage. Therefore, the project qualifies for a Class 3 categorical exemption pursuant to Sections 15303(a) of the CEQA guidelines.
- c) None of the exceptions under CEQA Guidelines Section 15300.2 apply to this project. The project does not involve a designated historical resource, a hazardous waste site, development located near or within view of a scenic highway, unusual circumstances that would result in a significant effect or development that would result in a cumulative significant impact. No adverse environmental effects were identified during staff review of the development application.
- d) The application, project plans, and related support materials submitted by the project applicant to Monterey County RMA-Planning for the proposed development found in Project File PLN190429.
6.       **FINDING:**       **APPEALABILITY** - The decision on this project may be appealed to the Planning Commission.
- EVIDENCE:**       Section 21.80.040.A of the Monterey County Zoning Ordinance (Planning Commission).

### **DECISION**

**NOW, THEREFORE,** based on the above findings and evidence, the Zoning Administrator does hereby:

- 1) Find the project includes construction of a single family dwelling in a residential area that qualifies for a Class 3 Categorical Exemption pursuant to Section 15303(a) of the CEQA Guidelines; and there are no exceptions pursuant to Section 15300.2; and
- 2) Approve a Design Approval for the construction of a 1,529 square foot two-story house with a 44 square foot porch and an attached 432 square foot two-car garage, in general

conformance with the attached plans and subject to the attached conditions which are both attached hereto and incorporated herein by reference.

**PASSED AND ADOPTED** this 25<sup>th</sup> day of June, 2020.

---

Mike Novo, Zoning Administrator

COPY OF THIS DECISION MAILED TO APPLICANT ON \_\_\_\_\_.

THIS APPLICATION IS APPEALABLE TO THE BOARD OF SUPERVISORS.

IF ANYONE WISHES TO APPEAL THIS DECISION, AN APPEAL FORM MUST BE COMPLETED AND SUBMITTED TO THE CLERK TO THE BOARD ALONG WITH THE APPROPRIATE FILING FEE ON OR BEFORE \_\_\_\_\_.

This decision, if this is the final administrative decision, is subject to judicial review pursuant to California Code of Civil Procedure Sections 1094.5 and 1094.6. Any Petition for Writ of Mandate must be filed with the Court no later than the 90th day following the date on which this decision becomes final.

This permit expires 3 year after the above date of granting thereof unless construction or use is started within this period.

# Monterey County RMA Planning

## DRAFT Conditions of Approval/Implementation Plan/Mitigation Monitoring and Reporting Plan

PLN190429

### 1. PD001 - SPECIFIC USES ONLY

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** This Design Approval permit (PLN190429) allows the construction of a two-story single family dwelling with a small porch and attached two-car garage. The property is located at 11430 Del Monte Avenue, Castroville (Assessor's Parcel Number 030-321-031-000), Castroville Community Plan, North County Area Plan. This permit was approved in accordance with County ordinances and land use regulations subject to the terms and conditions described in the project file. Neither the uses nor the construction allowed by this permit shall commence unless and until all of the conditions of this permit are met to the satisfaction of the RMA Chief of Planning. Any use or construction not in substantial conformance with the terms and conditions of this permit is a violation of County regulations and may result in modification or revocation of this permit and subsequent legal action. No use or construction other than that specified by this permit is allowed unless additional permits are approved by the appropriate authorities. To the extent that the County has delegated any condition compliance or mitigation monitoring to the Monterey County Water Resources Agency, the Water Resources Agency shall provide all information requested by the County and the County shall bear ultimate responsibility to ensure that conditions and mitigation measures are properly fulfilled. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to conditions and uses specified in the permit on an ongoing basis unless otherwise stated.

### 2. PD002 - NOTICE PERMIT APPROVAL

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The applicant shall record a Permit Approval Notice. This notice shall state:  
"A Design Approval (Resolution Number \_\_\_\_\_) was approved by the Monterey County Zoning Administrator for Assessor's Parcel Number 030-321-031-000 on June 25, 2020. The permit was granted subject to 4 conditions of approval which run with the land. A copy of the permit is on file with Monterey County RMA - Planning."

Proof of recordation of this notice shall be furnished to the RMA Planning Director prior to issuance of grading and building permits, Certificates of Compliance, or commencement of use, whichever occurs first and as applicable. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** Prior to the issuance of grading and building permits, certificates of compliance, or commencement of use, whichever occurs first and as applicable, the Owner/Applicant shall provide proof of recordation of this notice to the RMA - Planning.

### 3. PD003(A) - CULTURAL RESOURCES NEGATIVE ARCHAEOLOGICAL REPORT

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** If, during the course of construction, cultural, archaeological, historical or paleontological resources are uncovered at the site (surface or subsurface resources) work shall be halted immediately within 50 meters (165 feet) of the find until a qualified professional archaeologist can evaluate it. Monterey County RMA - Planning and a qualified archaeologist (i.e., an archaeologist registered with the Register of Professional Archaeologists) shall be immediately contacted by the responsible individual present on-site. When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for recovery.  
(RMA - Planning)

**Compliance or Monitoring Action to be Performed:** The Owner/Applicant shall adhere to this condition on an on-going basis.

Prior to the issuance of grading or building permits and/or prior to the recordation of the final/parcel map, whichever occurs first, the Owner/Applicant shall include requirements of this condition as a note on all grading and building plans. The note shall state "Stop work within 50 meters (165 feet) of uncovered resource and contact Monterey County RMA - Planning and a qualified archaeologist immediately if cultural, archaeological, historical or paleontological resources are uncovered."

When contacted, the project planner and the archaeologist shall immediately visit the site to determine the extent of the resources and to develop proper mitigation measures required for the discovery.

#### 4. PD012(G) - LANDSCAPE PLAN & MAINTENANCE (OTHER)

**Responsible Department:** RMA-Planning

**Condition/Mitigation Monitoring Measure:** The site shall be landscaped. Prior to the issuance of building permits, three (3) copies of a landscaping plan shall be submitted to the RMA Chief of Planning. A landscape plan review fee is required for this project. Fees shall be paid at the time of landscape plan submittal. The landscaping plan shall be in sufficient detail to identify the location, species, and size of the proposed landscaping and shall include an irrigation plan. The landscaping shall be installed and inspected prior to occupancy. All landscaped areas and/or fences shall be continuously maintained by the applicant and all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition. (RMA - Planning)

**Compliance or Monitoring Action to be Performed:** Prior to issuance of building permits, the Owner/Applicant/Licensed Landscape Contractor/Licensed Landscape Architect shall submit landscape plans and contractor's estimate to RMA - Planning for review and approval. Landscaping plans shall include the recommendations from the Forest Management Plan or Biological Survey as applicable. All landscape plans shall be signed and stamped by licensed professional under the following statement, "I certify that this landscaping and irrigation plan complies with all Monterey County landscaping requirements including use of native, drought-tolerant, non-invasive species; limited turf; and low-flow, water conserving irrigation fixtures."

Prior to occupancy, the Owner/Applicant/Licensed Landscape Contractor/Licensed Landscape Architect shall ensure that the landscaping shall be installed and inspected.

On an on-going basis, all landscaped areas and fences shall be continuously maintained by the Owner/Applicant; all plant material shall be continuously maintained in a litter-free, weed-free, healthy, growing condition.

GALVANIZED IRON  
GLUE LAMINATED BEAM  
GLASS  
GRADE  
GROUND  
GYPSUM  
HEADER  
HEATER  
HEATING, VENTILATING AND  
AIR CONDITIONING  
HOLDOWN  
HORIZONTAL  
INCLUDE(D), INCLUSIVE  
INSIDE DIAMETER,  
INTERNAL DIAMETER  
JOINT  
JOIST  
JUNCTION BOX  
KILN-DRIED  
LAVATORY  
LINEAR, LINEAL  
LIVE LOAD  
MANHOLE  
MAXIMUM  
MECHANICAL  
MEMBER  
METAL  
MICRO LAM BEAM  
MINIMUM  
MISCELLANEOUS  
MOUNTING  
NATIONAL ELECTRICAL CODE  
NATURAL  
NECESSARY  
NEW  
NOMINAL  
NORTH  
NOT TO SCALE  
NOT APPLICABLE  
OBSCURE  
ON CENTER  
OPENING  
OUTSIDE DIAMETER  
OVERALL  
OVERHEAD  
PARALAM  
PENNY (NAILS, ETC)  
PERFORATED(D)  
PERPENDICULAR  
PHASE  
PLATE  
PLYWOOD  
POINT  
POLYVINYL CHLORIDE  
PORCELAIN  
POWER  
REFABRICATED  
PROPERTY  
PROPERTY LINE  
PUBLIC ADDRESS  
PUSH BUTTON  
QUANTITY  
RECESSED  
RADIUS  
REFRIGERATE, REFRIGERATOR  
REGISTER  
REINFORCE  
REMOVE AND REPLACE  
REQUIRED  
RIGHT-OF-WAY  
ROOM  
ROUGH  
ROUND  
SCHEDULE  
SINGLE HUNG (WINDOW)  
SERVICE  
SHEATHING  
SIMILAR  
SINGLE  
SINGLE-PHASE  
SOUND-TRANSMISSION CLASS  
SPEAKER  
SPECIFICATION  
SQUARE  
STAINLESS STEEL  
STANDARD  
STEEL  
STRUCTURAL  
STRUCTURE  
SURFACE  
SURFACED OR DRESSED  
FOUR SIDES  
SURFACES OR DRESSED  
ONE SIDE  
SURFACED OR DRESSED ONE  
SIDE AND ONE EDGE  
SURFACED OR DRESSED  
TWO SIDES  
SYSTEM  
TELEPHONE  
TELEVISION  
TEMPORARY  
TEMPERED GLASS  
THERMOSTAT  
THREE-PHASE  
TOILET PAPER HOLDER  
TONGUE AND GROOVE  
TOP AND BOTTOM  
TOP CHORD  
TOTAL LOAD  
TOWEL BAR  
TRIPLE  
TWO PHASE  
TYPICAL  
ULTIMATE  
UNDERGROUND  
UNIFORM BUILDING CODE  
UPPER  
UPPER AND LOWER  
VACUUM  
VENT THROUGH ROOF  
VENTILATE, VENTILATOR  
VERTICAL  
VOLUME  
WASTE PIPE  
WATER CLOSET  
WATER HEATER  
WATERPROOF  
WEIGHT  
WELDED  
WEST  
WET BULB  
WITHOUT  
WOOD

GI  
GLB  
GL  
GR  
GRD  
GYP  
HDR  
HTR  
  
HVAC  
HD  
HORIZ  
INCL  
  
ID  
JST  
JB  
KD  
LAV  
LIN  
LL  
MH  
MAX  
MECH  
MBR  
MTL  
MLL  
MIN  
MISC  
MTG  
NEC  
NAT  
NEC  
(N)  
NOM  
N  
NTS  
N/A  
OBSC  
OC  
OPG  
OD  
OA  
OH  
P.S.L.  
d  
PERF  
PERP  
PH  
PL  
PLY  
PT  
PVC  
PORC  
PWR  
PREFAB  
PROP  
PL  
PA  
PB  
QTY  
REC  
R  
REF  
REIN  
R&R  
REQD  
ROW  
RM  
RGH  
RND  
SCHD  
SH  
SVC  
SHTG  
SIM  
SGL  
1PH  
STC  
SPKR  
SPEC  
SQ  
SS  
STD  
STL  
STR  
STRUCT  
SURF  
S4S  
S1S  
S1S1E  
S2S  
SYS  
TELE  
TV  
TEMP  
TEMP  
T-STAT  
3PH  
TP  
T&G  
T&B  
TC  
TL  
TB  
TRPL  
2PH  
TYP  
ULT  
UGND  
UBC  
UPR  
U&L  
VAC  
VTR  
VENT  
VERT  
VOL  
WP  
WC  
WH  
WP  
WT  
WLD  
W  
WB  
W/O  
WD

ABBREVIATIONS

ACOUSTIC  
ADAPTER  
ADDENDUM, ADDITION (AL)  
ADJACENT  
AGGREGATE  
AIR CONDITION(ED)  
ALARM  
ALIGNMENT  
ALTERNATE  
ALUMINUM  
AMERICAN WIRE GAGE  
AMPERAGE (CURRENT)  
ANGLE (STRUCTURAL)  
APARTMENT  
APPENDIX  
APPROXIMATE  
ARCHITECTURE, ARCHITECTURAL  
ASPHALT  
ASSEMBLY  
ASSISTANT  
AVENUE  
AVERAGE  
BALCONY  
BASE PLATE  
BEAM  
BEARING  
BELOW  
BENCHMARK  
BETWEEN  
BIRMINGHAM WIRE GAGE  
BOARD  
BOTTOM  
BOTTOM CHORD  
BUILDING  
CABINET  
CALIFORNIA MECHANICAL CODE  
CALIFORNIA ELECTRICAL CODE  
CALIFORNIA BUILDING CODE  
CALIFORNIA PLUMBING CODE  
CANTILEVER  
CAPACITY  
CAST IRON PIPE  
CATALOG  
CAULKING  
CEILING  
CEMENT  
CENTER  
CENTERLINE  
CHECK VALVE  
CIRCLE  
CIRCUIT  
CIRCULAR  
CLEANOUT

CLEAR  
COATED  
COLD WATER  
COLUMN  
COMPOSITION  
CONCRETE  
CONNECT, CONNECTOR  
CONSTRUCTION  
CONTINUE, CONTINUOUS  
CONTRACT, CONTRACTOR  
COUNTERSINK  
CUBIC  
DEAD LOAD  
DEGREE  
DESIGN(ED)  
DETAIL  
DIAGONAL  
DIAMETER  
DIMENSION  
DISHWASHER  
DOOR  
DOUBLE  
DOUBLE-HUNG (WINDOW)  
DOWN  
DOWNSPOUT  
EACH  
ELECTRIC, ELECTRICAL  
ELEVATION  
ENGINEER  
EQUAL  
EQUIPMENT  
EXCAVATE  
EXHAUST  
EXISTING  
EXPANSION JOINT  
EXPOSED  
EXTERIOR  
EXTINGUISHER  
EXTRA HEAVY  
EXTRA STRONG  
EXTRUDE(D)  
EXHAUST FAN  
FABRICATE  
FIBERGLASS REINFORCED  
PLASTICS  
FIGURE  
FINISHED FLOOR LEVEL  
FIREPROOF  
FLOOR  
FLOOR DRAIN  
FLOORING  
FLUORESCENT  
FOOTING  
FOUNDATION  
FORCED AIR FURNACE  
FURNACE

ACST  
ADPTR  
ADD  
ADJ  
ARG  
AVC  
ALM  
ALIGN  
ALT  
ALUM  
AWG  
A  
L  
APT  
APFX  
APPROX  
ARCH  
ASPH  
ASSY  
ASST  
AVE  
AVG  
BALC  
BP  
BM  
BRG  
BLW  
BM  
BETW  
BWG  
BD  
BOT  
BC  
BLDG  
CAB  
CMC  
CEC  
CBC  
CPC  
CANTIL  
CAP  
CIP  
CAT  
CLKG  
CLG  
CEM  
CTR  
CL  
CV  
CIR  
CKT  
CIRC  
CO  
  
CLR  
CTD  
CW  
COL  
COMP  
CONC  
CONN  
CONST  
COIN  
CONTR  
CSK  
CU  
DL  
DEG  
DSGN  
DET  
DIAG  
DIA  
DIM  
DW  
DR  
DBL  
DH  
DN  
DS  
EA  
ELEC  
EL  
ENGR  
EQ  
EQUIP  
EXC  
EXH  
(E)  
EXP JT (EJ)  
EXP  
EXT  
EXT  
XHVV  
XSTR  
EXTD  
EF  
FAB  
FRP  
FIG  
FF  
FP  
FL  
FD  
FLG (FLRG)  
FLUOR  
FTG  
FDN  
FAU  
FURN

FIREBLOCKING REQUIRED

Fireblocking shall be provided to cut off all concealed draft openings (vertical and horizontal) and shall form an effective barrier between stories, between a top story and the roof space. Fireblocking shall be installed in wood framed construction in the following locations:

- In concealed spaces of stud walls and partitions, including furred spaces and parallels rows of studs or staggered studs, as follows:  
1.1 Vertically at the ceiling and floor levels.  
1.2 Horizontally at intervals not exceeding 10 feet.
- At all interconnections between concealed vertical and horizontal spaces such as occur at soffits, drop ceilings and cove ceilings. In concealed spaces between stair stringers at the top and bottom of the run. Enclosed spaces under stairs shall comply with R302.7
- At openings around vents, pipes, ducts, cables and wires at ceiling and floor level, with an approved material to resist the free passage of flame and products of combustion. The material filling this annular space shall not be required to meet ASTM E 136 requirements.
- For the fireblocking of chimneys and fireplaces, see R1003.19
- N/A

Contractor shall refer to CRC R302.11 for additional information not specified above, and R302.11.1 for fireblocking materials.

GENERAL NOTES

- This project shall comply with the **2016 CBC, CRC, CMC, CPC, CFC, CEC, CAL-Green** (mandatory section), **California Energy Code** based on the 2016 CA Energy Standards & Regulations, and all other governing codes and ordinances. The California Building Standards Code is based on the IBC & IFC, UMC & UPC and the NEC.
- Copyrighted plans and documents:** The use of these plans and specifications is restricted to the original site for which they were prepared. Publication of these documents is expressly limited to such use and reuse, and reproduction or publication by any method, in whole or part, is prohibited. Ownership of these documents remains with the designer, and visual contact with them constitutes prima facie evidence of the acceptance of these restrictions.  
Plans shall be scaled only where figures or other means of ascertaining measurements are not given thereon, and then only where the scale of the drawings in question is plainly marked. Discrepancies shall be called to the attention of the designer for written interpretation before the work affected is executed.
- All wood framing members that rest on concrete or masonry exterior foundation walls and are less than 8 inches from exposed ground shall be of redwood or preservative treated wood U.O.N. (CRC R317.1.2).  
**Contractor** shall field verify with owner all finishes including, finish carpentry, casework, and flooring.
- All roofing, siding, windows, sheetmetal and flashing shall be neatly done, weathertight and substantial.
- All roof glass and glass** in hazardous locations shall be of safety glazing materials as per CRC R308. A permanent label per CRC R308.6.1 or R308.6.9 shall identify each light of safety glazing.
- Escape & Rescue Window:** Bedrooms, and basements (unless noted in CRC R310) shall have at least one exterior emergency escape and rescue opening in accordance with this section. Emergency escape and rescue openings shall open directly into a public way, or to a yard or court that opens to a public way.  
**Note:** Escape and rescue openings shall have a minimum net clear opening of 5.7 s.f. U.O.N.. The minimum net clear opening height shall be 24". The minimum net clear opening width shall be 20". The opening shall have a sill height of not more than 44" above the floor. Exterior door may substitute for escape and rescue window. See plans for natural light and ventilation compliance.
- Roofing:** All roofing shall be installed in accordance with manufacturer's specification and CRC R905. Builder to provide installation guide for inspection. Roofing manufacturer and approval are as follows:  
Comp. Shingles: GAF Timberline – Class "A", ICC #ESR-1475 or Certainteed – Class "A", ICC #ESR-3537
- All metal connectors,** to be Simpson Strong-tie. All connectors to be installed in accordance with manufacturer's specifications.
- Central Heating Furnace** shall be installed in accordance with manufacturer's specifications, and CMC 904.
- Stucco Specifications:** Exterior stucco (plaster) shall be a minimum of 7/8" thick, have 3-coats when applied over metal lath or wire fabric lath and not less than 2-coats when applied over masonry, concrete, pressure-preservative treated wood, decay resistant wood, or gypsum. Weather resistive barriers shall include 2 layers of grade 'D' paper over wood base sheathing. Install a 3 1/2", 26 G. galvanized corrosion-resistant weep screed shall be installed at or below the foundation plate line on exterior stud walls. The screed shall be placed a minimum of 4" above earth or 2" above paved areas (CRC 703.6)  
See CBC 2512 for plaster applied over masonry.
- Siding Specifications:** Wood, hardboard, wood structural panel siding, wood shake or shingle siding, shall be installed over No. 15 asphalt felt, or ther approved water-resistive barrier such as Tyvek building wrap in accordance with CRC R703.  
**Fiber Cement** siding and other materials shall be installed in accordance with manufacturer's specifications, and CRC R703.
- Existing Utilities call 811:** Existing underground utilities and improvements are shown in their approximate locations and may not have been verified in the field and no guarantee is made as to the accuracy or completeness of the information shown. The contractor shall notify utility companies at least 2 working days in advance of construction to field locate utilities.  
Call Underground Service Alert (U.S.A.) at 1-800-227-2600 or 811.

SPECIAL INSPECTIONS REQUIRED:

- STRUCTURAL – Special Inspection** See Structural Drawings
- All Shear Wall nailing 4 inches o.c. or less including:  
P/2 Shear Wall E.N. 4" o.c.  
P/3 Shear Wall E.N. 3" o.c.  
P/4 Shear Wall E.N. 2" o.c.

DEFERRED SUBMITTAL ITEMS:

- FIRE SPRINKLERS REQUIRED BY FIRE DEPARTMENT**  
The building(s) and attached garage(s) shall be fully protected with automatic fire sprinkler system(s) installation shall be in accordance with the applicable NFPA standard. A minimum of (4) sets of plans for fire sprinkler systems must be submitted by a California licensed C-16 Contractor and approved prior to installation. This requirement is not intended to delay issuance of a building permit. A rough sprinkler inspection must be scheduled by the installing contractor and completed prior to requesting a framing inspection.

PLAN INDEX

| SHEET | DESCRIPTION                                       |
|-------|---|
| T0    | TITLE SHEET                                       |
| T1    | ENERGY COMPLIANCE                                 |
| T2    | ENERGY COMPLIANCE                                 |
| C1    | EROSION CONTROL & BMP'S                           |
| A1    | SITE PLAN, ROOF PLAN                              |
| A2    | FLOOR PLANS                                       |
| A3    | EXTERIOR ELEVATIONS                               |
| A4    | CROSS SECTIONS                                    |
| A5    | DETAILS AND FINISH SCHEDULE                       |
| E1    | PLUMBING, MECHANICAL, AND ELECTRICAL NOTES        |
| E2    | ELECTRICAL PLANS                                  |
| G1    | CAL-GREEN SH. 1                                   |
| G2    | CAL-GREEN SH. 2                                   |
| F1    | FIRE DEPARTMENT NOTES                             |
| S1    | STRUCTURAL NOTES                                  |
| S2    | STANDARD STRUCTURAL DETAILS                       |
| S3    | ROOF FRAMING, FLOOR FRAMING, AND FOUNDATION PLANS |
| S4    | DETAILS   |
| S5    | DETAILS   |
| S6    | DETAILS   |
| S7    | DETAILS   |

BUILDING CLASSIFICATION

OCCUPANCY GROUP: R-3/U  
CONSTRUCTION TYPE: V-B SPRINKLERED  
STORIES: 2 HEIGHT: 25'  
CODES: 2016 CALIFORNIA CODES  
SCOPE OF WORK: NEW 1529 S.F. TWO STORY HOUSE W/ 432 S.F. TWO CAR GARAGE, AND 44 S.F. COVERED PORCH.  
GROUND DISTURBANCE: 1700 S.F.  
FLOOR AREA: HOUSE FIRST STORY 618 SF.  
SECOND STORY 911 S.F.  
GARAGE 432 S.F.

ENERGY COMPLIANCE METHOD: ENERGY PRO 7.2, 2016 ENERGY EFFICIENCY STANDARDS

CONSULTANTS

**ENGINEER:** ALEXANDER OTT  
603 PALM AVENUE  
SEASIDE, CA 93955  
831 394-5936


**ENERGY CONSULTANT:** MONTEREY ENERGY GROUP  
26465 CARMEL RANCHO BLVD.  
CARMEL, CA 93923  
831 250-0314

**SOILS ENGINEER:** GRICE ENGINEERING, INC  
561-A BRUNKEN AVENUE  
SALINAS, CA 93901  
831 375-1198

ADDRESS IDENTIFICATION

Prior to construction, a legible address identification shall be placed in a position that is visible from the street or road fronting the property. Address identification characters shall contrast with their background. Address numbers shall be all Arabic numbers or alphabetic letters. Numbers shall be spelled out. Each character shall not be less than 4 inches in height with a stroke width of not less than 0.5 inch. Where required by the fire code official, address identification shall be provided in additional approved locations to facilitate emergency response. Where access is by means of a private road and the building address cannot be viewed from the public way, a monument, pole or other sign or means shall be used to identify the structure. Address shall be maintained during construction.

A permanent address shall be posted on final project in accordance with the above specifications.



| REVISIONS | BY |
|-----------|----|
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |

BUILDING DESIGN & CONSULTING  
2150 GARDEN RD., SUITE B3 / MONTEREY, CA 93940  
(831) 946-5986

**OWNER:** DATTI KHALSA  
2567 MAIN STREET  
SOCQUEL, CA 95073  
PH: (831) 818-0181

**KHALSA RESIDENCE**  
11430 DEL MONTE AVENUE  
CASTROVILLE, CALIFORNIA  
APN: 030-321-031-000

|       |           |
|-------|-----------|
| Date  | 12.13.19  |
| Scale |           |
| Drawn | drafttect |
| Job   | 65-2019   |
| Sheet | T0        |
| Of 21 | Sheets    |



| REVISIONS | BY |
|-----------|----|
| 11-18-19  | D  |
| 12-13-19  | D  |
|           |    |
|           |    |
|           |    |
|           |    |


BUILDING DESIGN  
& CONSULTING  
draftact

2165 GARDEN RD., SUITE B5 / MONTEREY, CA 93940  
(831) 646-5888  
FAX: 646-5888

**KHALSA RESIDENCE**  
**11430 DEL MONTE AVENUE**  
**CASTROVILLE, CALIFORNIA**  
**APN: 030-321-031-000**


|       |          |
|-------|----------|
| Date  | 11-2-19  |
| Scale |          |
| Drawn |          |
| Job   | 652019   |
| Sheet | A1       |
| Of    | 5 Sheets |

| ATTIC VENTILATION   |                        |
|---|------------------------|
| AREA  | 1050 SF = 3.5 SF REQ'D |
| COR   | 300 SF = 3.5 SF REQ'D  |
| INSTALL (12) 22" X 3 1/2" FULL MESH SCREEN VENTS AS SHOWN |                        |
| A 20 LF OF COR-A-VENT                                     |                        |
| RIDGE VENT OF 12 SQ IN/LF                                 |                        |



ROOF PLAN

1/4"=1'-0"




| FLOOR AREA         |           |
|--------------------|-----------|
| MAIN FLOOR (1ST)   | 618 SF    |
| UPPER FLOOR (2ND)  | 911       |
| TOTAL HOUSE        | 1529      |
| GARAGE             | 432       |
| LOT COVERAGE       |           |
| BUILDING FOOTPRINT | 1050 SF   |
| PORCH              | 44        |
| TOTAL LOT AREA     | 1094      |
|                    | 432 = 26% |

- NOTES
- EXISTING CONTOURS
  - PROPOSED CONTOURS
  - DARK SKY LED LIGHTS
  - NO EXCAVATIONS, NO FILL
  - LAND DISTURBED 1700 SF

DRAINAGE NOTES

- Roof drain downspouts shall be installed on all roof overhangs, and shall discharge onto concrete splash blocks or pavement, and drain away from structure as noted below.
- All finish grades including patios, and driveways shall be contoured to slope away from proposed structures:  
**Site Grading (CRC 401.3):** Surface Drainage shall be diverted to a storm sewer conveyance or other approved point of collection that does not create a hazard. Lots shall be graded to drain surface water away from foundation walls. The grade shall fall a minimum of 6 inches within the first 10 feet. **Exception:** Where lot lines, walls, slopes, or other physical barriers prohibit 6 inches of fall within 10 feet, drains or swales shall be constructed to ensure drainage away from the structure. Impervious surface (pavers, etc.) within 10 feet of the building foundation shall slope a minimum of 2 percent away from the building. All drainage facilities should be checked and maintained periodically to remove obstructions and assure proper function.
- See sheet #C1 for erosion control and BMP's.




SITE PLAN

1"=10'





| REVISIONS | BY |
|-----------|----|
| 11-18-19  | D  |
| 12-13-19  | D  |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |



**KHALSA RESIDENCE**  
**11430 DEL MONTE AVENUE**  
**CASTROVILLE, CALIFORNIA**  
**APN: 030-321-031-000**

|       |          |
|-------|----------|
| Date  | 11-2-19  |
| Scale |          |
| Drawn |          |
| Job   | 652019   |
| Sheet | A/2      |
| Of    | 2 Sheets |




**WALL LEGEND**  
 2x4 STUDS  
 2x6 STUDS

| REVISIONS | BY |
|-----------|----|
| 11-18-19  | D  |
| 12-13-19  | D  |
|           |    |
|           |    |
|           |    |
|           |    |
|           |    |


BUILDING DESIGN  
 & CONSULTING  
**draft**  
 2150 GARDEN RD., SUITE B3 / MONTEREY, CA 95040  
 (831) 546-5986

KHALSA RESIDENCE  
 11430 DEL MONTE AVENUE  
 CASTROVILLE, CALIFORNIA  
 APN: 030-321-031-000


|              |
|--------------|
| Date 11-2-19 |
| Scale        |
| Drawn        |
| Job 652019   |
| Sheet        |
| Of 3 Sheets  |



SOUTH ELEVATION 1/4\"/>




EAST ELEVATION 1/4\"/>



FENCE ELEVATION 1/4\"/>



WEST ELEVATION 1/4\"/>




NORTH ELEVATION 1/4\"/>



COLOR SAMPLES FOR PROJECT FILE NO.

PUN190429


DATTA - 11430 DEL MONTE AVE.



Materials: STUCCO

Description: BODY

Colors: KELLY MOORE SPANISH SAND  
231



Materials: FASCIA & GUTTER

Description: \_\_\_\_\_

Colors: KELLY MOORE BONE  
27



Materials: ASPHALT COMP. SHINGLES

Description: ROOF

Colors: GAF: BARKWOOD

**REPORT  
to  
MR. DARREN A. DAVIS  
DRAFTECT  
2150 GARDEN ROAD, SUITE B-3  
MONTEREY, CALIFORNIA 93940**

**GEOTECHNICAL REPORT  
for the proposed  
DATTA KHALSA RESIDENCE  
11430 DEL MONTE AVENUE  
CASTROVILLE, CALIFORNIA  
A. P. N. 030-321-031-000**

**by**

**GRICE ENGINEERING, INC.  
561-A BRUNKEN AVENUE  
SALINAS, CALIFORNIA  
NOVEMBER 2019**

# GRICE ENGINEERING INC

ENGINEERING    GEOTECHNICS    SEPTIC    HYDROLOGY  
FOUNDATIONS    SOILS    EARTH STRUCTURES

561A Brunken Avenue  
Salinas, California 93901  
griceengineering@sbcglobal.net

Salinas: (831) 422-9619  
Monterey: (831) 375-1198  
FAX: (831) 422-1896

File No. 7152-19.11  
November 12, 2019

Page i

Mr. Darren A. Davis  
2150 Garden Road, Suite B-3  
Monterey, California 93940

Project:      Datta Khalsa Residence  
                 11430 Del Monte Avenue  
                 Castroville, California  
                 A. P. N. 030-321-031

Subject:      Geotechnical Report

Dear Mr. Davis;

Pursuant to your request, we have completed our geotechnical investigation and evaluation of the above named site. It is our opinion that this site is suitable for the proposed development, provided the recommendations made herein are followed.

In general, the near surface soils are loose and will need to be taken into account during design and construction of the proposed residence. Recommendations are given relative to this and other characteristics within the report and especially under Special Recommendations.

The report contained herein is made with our best efforts to evaluate the site, determine the site's geotechnical conditions and provide recommendations for these conditions. We submit this report with the understanding that it is the responsibility of the owner, or his representative, to ensure incorporation of these recommendations into the final plans, and their subsequent implementation in the field.

In addition, we recommend that GRICE ENGINEERING, INC., be retained to review the project plans and provide the construction supervision and testing required to document compliance with these recommendations. Should any site condition not mentioned in this report be observed, this office should be notified so that additional recommendations can be made, if necessary.

This report and the recommendations herein are made expressly for the above referenced project and may not be utilized for any other site without written permission of GRICE ENGINEERING, INC.

Please feel free to call this office should you have any questions regarding this report.

Very truly yours,  
GRICE ENGINEERING, INC.



Lawrence E. Grice, P.E.  
R.C.E. 66857

## NOTICE TO OWNER

Any earthwork and grading performed without direct engineering supervision and materials testing by Grice Engineering Inc., will not be certified as complete and in accordance with the requirements set forth herein.

Foundations placed without observation of bearing conditions will not be certified as being in accordance with the requirements set forth herein.

### **Inspection of Work**

It is recommended that all site work be inspected and tested during performance by this firm to establish compliance with these recommendations.

|         |                           |          |                |
|---------|---------------------------|----------|----------------|
| NOTIFY: | GRICE ENGINEERING INC.    | SALINAS  | (831) 422-9619 |
|         | 561-A Brunken Avenue      | MONTEREY | (831) 375-1198 |
|         | Salinas, California 93901 | FAX      | (831) 422-1896 |

A minimum of 48 hours (2 working days) notification is required prior to commencement of work so that scheduling for testing and inspections can be made.

**Please be advised that costs incurred during inspection and testing of all site work is separate and not considered part of the fees as charged by Grice Engineering, Inc. for the report contained herein.**



## TABLE OF CONTENTS

### Page No.

#### LETTER OF TRANSMITTAL

|  |    |
|--|----|
| <b>GEOTECHNICAL REPORT</b> .....                               | 1  |
| Introduction, Method and Scope of Investigation .....          | 1  |
| Site Description .....   | 1  |
| Field Investigation .....                                      | 2  |
| Site Soil Profile .....  | 3  |
| Groundwater .....  | 3  |
| Laboratory Testing .....                                       | 4  |
| Seismic History .....  | 5  |
| Regional Faults .....  | 5  |
| Differential-Total Settlement - Static and Dynamic .....       | 6  |
| Hydro-Collapse and Subsidence .....                            | 6  |
| Slope Stability .....  | 6  |
| Seismic Strength Loss .....                                    | 6  |
| Chemical Reactivity .....                                      | 7  |
| Expansive Soils .....  | 7  |
| Surface Rupture and Lateral Spreading .....                    | 7  |
| Seismicity .....   | 8  |
| 2016 California Building Code Geoseismic Classifications ..... | 8  |
| <b>CONCLUSIONS OF INVESTIGATION</b> .....                      | 9  |
| Special Recommendations .....                                  | 9  |
| Foundations and Footings .....                                 | 10 |
| Slabs-on-Grade .....   | 11 |
| Specifications for Rock Under Floor Slabs .....                | 12 |
| Slope Ratio and Drainage .....                                 | 12 |
| Surface Drainage and Erosion Control .....                     | 13 |
| Expansive Soils .....  | 14 |
| Subsurface Drains .....  | 15 |
| General Grading Recommendations .....                          | 16 |
| <b>LIMITATIONS AND UNIFORMITY OF CONDITIONS</b> .....          | 20 |
| <b>APPENDIX A</b> .....  | 21 |
| Vicinity and Location Map .....                                | 22 |
| Site Map .....   | 23 |
| Subdivision Map with Boring Locations .....                    | 24 |
| <b>APPENDIX B</b> .....  | 25 |
| Boring Logs .....  | 26 |
| Unified Soil Classification Chart .....                        | 31 |
| <b>REFERENCES</b> .....  | 32 |



**GEOTECHNICAL REPORT  
for the proposed  
DATTA KHALSA RESIDENCE  
11430 DEL MONTE AVENUE  
CASTROVILLE, CALIFORNIA  
A. P. N. 030-321-031-000**

**Introduction, Method and Scope of Investigation**

The purpose of this report is to evaluate the geotechnical properties of the site relative to the construction of a single family residence. From these findings recommendations are given for the design of the development and subsequent construction.

For this purpose, the site was investigated, and prior information concerning construction and subsurface exploration in this area was examined for soils and materials data. The investigation consisted of a detailed site evaluation, which included: a site inspection; a review of literature made available to GRICE ENGINEERING, INC., including Site Plans from Draftect; geotechnical drilling and soil sampling; materials evaluation; and analysis of the geotechnical properties of the site soils. This report concludes the results of the investigation and provides recommendations based on that work.

The findings and recommendations contained in this report are applicable only to the above named site and its proposed development, and may not be utilized for any other site or purpose without written permission of GRICE ENGINEERING, INC.

**Site Description**

The project site, 11430 Del Monte Avenue, is located to the southwest of Del Monte Avenue, approximately 129 feet northwest of its intersection with Koester Street, in the City of Castroville, an un-incorporated area of westernmost Monterey County, California. Please refer to the Vicinity and Location Maps and the Site Map in Appendix A for details.

The topography of the 4,205 square foot site encompasses a level area at an elevation of approximately 21 feet above mean sea level (msl). The majority of the undeveloped site is covered with grass.

Currently plans are for a two story, single family residence to be placed centrally on the lot. An attached two car garage is to be located on the residence's front facing the street with a short concrete driveway providing access. A concrete pathway will provide access to the front door while a small patio is to be located on the residence's rear.

Due to prior site activity, loose and disturbed soils and foreign objects may be encountered during construction and will have to be taken into account.

The approximately 1,529 square foot residence is to be of conventional wood construction with isolated and/or continuous spread footings. The approximately 432 square foot garage is to have a slab-on-grade floor.

### **Field Investigation**

Our field investigation consisted of a site inspection, along with review of the drilling and sampling performed by Soils Surveys, Inc., Job #3784, February 21, 2003, in preparation of a Geotechnical Report for the overlaying subdivision. That investigation consisted of advancement of 3 exploratory bores to establish the subsurface soil profile, and obtain sufficient soil specimens to determine the soil characteristics. The report discusses exploratory drilling completed by M. Jacobs and Associates in 1987 for a similar purpose.

Drilling was accomplished by continuous flight auger, with the spoil constantly examined, classified, and logged by field method in accordance with the Unified Soil Classification Chart<sup>1</sup> which is the basis of ASTM D2487-10.

Relatively undisturbed soil samples were obtained by the penetration resistance method, (ASTM Method D1586-08), by which a split barrel sampler was driven a minimum of 18 inches into the sampled materials by free dropping a 140 pound weight 30 inches. The number of blows required to drive the sampler were recorded in 6 inch increments after conversion to Standard Penetration Resistance values (presumably). The number of blows required to drive the sampler the last two increments taken as the Standard Penetration Resistance. The split barrel sampler (ASTM D-1586-08), with dimensions of 1.375" I.D. x 2.0" O.D., is provided with 1 inch tall brass ring liners for the purpose of returning the samples to the laboratory in as near *in-situ*\* condition as possible.

\* *In-situ* refers to the in place state of soil. *In-situ* native soils are those which are in-place as deposited by nature and have not been disturbed by man's actions in the historic past.

---

<sup>1</sup> Adopted 1952 by Corps of Engineers and Bureau of Reclamation. ASTM D2487 was developed as based on the Uniform Soils Classification Chart and System. The methods are equivalent.

### **Site Soil Profile**

As found in the exploratory drilling, the site soils are generally consistent between each of the bores and is typical to the area.

The native topsoil was observed to be a black silty clay of medium plasticity. As encountered it was stiff and moist.

The native subsoils are a finely mottled olive-tan (yellowish brown) blend of silts and clay generally observed in lensatic deposition and of friable nature due to low moisture contents. As encountered they were moist and stiff.

The second bore was advanced to an approximate depth of 24.5 feet. In that bore at a depth of approximately 19 feet medium grained sands were encountered. These materials were observed medium dense to dense and dry to moist.

Complete soil characteristics and comments are reported on the boring logs at the depths observed. The logs completed by Soils Surveys, Inc. are included in Appendix B. Those by M. Jacobs were not available.

### **Groundwater**

Free groundwater was encountered at this site at a depth of 26.0 feet below grade in the bores advanced by M. Jacobs as discussed in their report.



### Laboratory Testing

Laboratory testing consisted of establishing the *in-situ* \*\* moisture content and dry density (ASTM D 2487-10) and unconfined penetration, direct shear testing (ASTM D 3080-04) and expansion index (ASTM D4829-08a). Standard Penetration Resistance values gained during the exploratory drilling are also included.

The following is a tabulation of the field and laboratory test result extremes:

| TABLE 1                         |  |                          |
|---------------------------------|--|--------------------------|
| SUMMARY OF SOIL PROPERTIES      |  |                          |
| TEST                            | MAXIMUM                                  | MINIMUM                  |
| Standard Penetration Resistance | 62 blows/foot                            | 9 blows/foot             |
| Unconfined Compression*         | 8 kips/ft <sup>2</sup>                   | 3 kips/ft <sup>2</sup>   |
| <i>In-Situ</i> Density          | 112.7 lbs/ft <sup>3</sup>                | 80.5 lbs/ft <sup>3</sup> |
| <i>In-Situ</i> Moisture         | 37.7 %                                   | 3.0 %                    |
| Atterberg Limits                | LL 44; PL 16; PI 28                      | LL 41; PL 15; PI 26      |
| Passing No. 200                 | 65                                       | 47                       |
| Compaction Curve                | 113.0 lbs/ft <sup>3</sup> @ 13.5 % water |                          |

All data obtained is reported in Appendix B including the boring logs, with soil classified described at depth observed.

\* Pocket Penetrometer

\*\* *In-situ* refers to the in-place state.

## **Seismic History**

Although no fault traces are thought to directly cross the building site, Monterey County is traversed by a number of faults most of which are relatively minor hazards for the purposes of the site development. As such, this site will experience seismic activity of various magnitudes emanating from one or more of the numerous faults in the region.

Various maps presently exist, allowing observation on the site of distinctive geologic features. Some maps, such as that by Burkland and Associates (Reference No. 10) developed for Monterey County, are compilations from various sources detailing the locations of studied faults. Faults have inherent variances within their zones, and discoveries of new fault segments or entire faults is ongoing. There is also some difference in exact fault line location from source map to map, making precise location of said faults difficult. Therefore, relative to the information contained within this report, the following is considered to be as accurate as is currently possible from information made available to Grice Engineering Inc..

## **Regional Faults**

Of most concern are active faults which have tectonic movement in the last 11,000 years and as such are called Holocene Faults and potentially active faults. The following are those nearest listed (Reference No. 12).

The most active is the San Andreas Rift System (Pajaro), located approximately 11.7 miles to the northeast. It has the greatest potential for seismic activity with estimated intensities of VIII-IX Mercalli in this location.

Other fault zones are the Zayante-Vergeles Fault Zone, the center of which is located approximately 7.8 miles to the northeast, the Rinconada Fault Zone, approximately 6.3 miles to the southwest, the Monterey Bay-Tularcitos Fault Zone, approximately 11.4 miles to the southwest, and the San Gregorio-Palo Colorado (Sur) Fault Zone, approximately 19.4 miles to the southwest. These zones are not as liable to rupture as the San Andreas and a seismic event at any of the above fault zones would likely produce earth movements of a lesser intensity at the site.

### **Liquefaction**

The site soils are considered not susceptible to liquefaction as those portions which are cohesive clays and silts and medium dense to dense sands.

### **Differential-Total Settlement - Static and Dynamic**

The recommendations given in the Geotechnical Report are such that concerns of settlement are negligible. The total settlement is expected to be less than 1/4 inch and the expected differential settlement less than one half that.

### **Hydro-Collapse and Subsidence**

As observed the loose or disturbed soils near surface possess some capacity to settle under hydraulic loading or compress when saturated depending on the overburden pressure. Hydro-collapse in the native soils column is not common in the area. The recommendations given in this report were established to reduce the potential of this occurring.

The area is not within a known Subsidence Zone.

### **Slope Stability**

Inspection of the site indicates that no landslides are located above or below the building area and the area is generally not susceptible to slope failure as it is near level.

### **Seismic Strength Loss**

The site soils are considered resistant to seismic strength loss and the resulting momentary liquefaction. The relatively short duration of earthquake loading will not provide a significant number of high amplitude stress cycles to alter the strain characteristics. Additionally the clay-silt fraction is not considered quick nor sensitive, as such it will not have the associated loss of strength.



### **Chemical Reactivity**

The area is well developed with structures, generally found on Portland Cement products. Additionally these structures date back to the 1940's or earlier. Much of the concrete used in these structures has remained as cast. The area soils are not known for sulfate reaction with Portland cement products and as such chemical reactivity is not considered a problem in this area.

### **Expansive Soils**

In general the site soils are or contain clayey silts and clays of low to moderate plasticity. These soils are typical to the area. Expansivity has not been influential to the local structures and on grade pavements as no significant deformations attributable to expansive soils were observed. As any clay soil has some potential for expansivity, recommendations are given to minimize this potential.

### **Surface Rupture and Lateral Spreading**

The project site is located 6.3 miles to the northeast of the Rinconada Fault (Quaternary). The site inspection did not reveal any surface features indicating a fault rupture has occurred at the site. The existing structure, driveways and roads do not reveal any strains which would be attributable to subsurface lateral or vertical displacements resulting from fault slip. Therefore surface rupture from fault activity across the site is considered improbable.

The project site is underlain by relatively strong soils. These materials are considered resistant to lateral spreading. As such surface rupture from lateral spreading is considered improbable.

## Seismicity

It is recommended that all structures be designed and built in accordance with the requirements of the California Building Code's current edition. All buildings should be founded on undisturbed native soils and/or tested and accepted engineering fill to prevent resonance amplification between soils and the structure.

## 2016 California Building Code Geoseismic Classifications

The California Building Code, 2016 edition (Reference No. 13), provides for seismic design values. These values are to be utilized when evaluating structural elements. The soils profile determination is based on the penetration resistance data developed from advancement of exploratory bores. Using averaged penetration values per depth of soils type gives an overall site value of 26 blows/foot penetration resistance as per Equation 20.4-3, ASCE 7-10. The geoseismic character is as listed in the following table.

| 2015 I.B.C. - 2016 C.B.C. EARTHQUAKE LOADS: SECTION 1613                  |             |               |             |             |
|---|-------------|---------------|-------------|-------------|
| LATITUDE  | 36.763334   | SOIL PROFILE: | Stiff Soils |             |
| LONGITUDE   | -121.747012 | SITE CLASS    | D           |             |
| PERIOD  | S           | F             | Sm          | Sd          |
| 0.2 sec   | Ss = 1.500  | Fa = 1.000    | Sms = 1.500 | Sds = 1.000 |
| 1.0 sec   | S1 = 0.598  | Fv = 1.500    | Sm1 = 0.897 | Sd1 = 0.598 |
| Seismic Design Category to be assigned by structural engineer or designer |             |               |             |             |



## CONCLUSIONS OF INVESTIGATION

In general, the suitable, *in-situ*\*, native soils and certified engineered fill are acceptable for foundation purposes and display engineering properties adequate for the anticipated soil pressures, providing the recommendations in this report are followed.

### Special Recommendations

As observed the surficial soils are imported fill or disturbed native soils to depths ranging from one to three feet. These soils are not considered suitable for support of on grade structures (engineered structures, eg. interior floor slabs, pavement, etc.) and foundations. Therefore it is recommended that such soils and any other unsuitable soils be processed as engineered fill within the building envelopes and extent of on grade structures. The minimum depth of processing is to include all such soils and the native topsoil were encountered. The depth is to be increased, as necessary, to include all unsuitable soils. Actual depth of processing is to be determined by the soils engineer or his representative during grading operations.

The site soils are clay of medium plasticity. Although expansivity is not a great concern in the area, some caution is warranted. As such recommendations are given on page 14 to minimize such expansivity.

The area has been developed and as such underground utilities may be located within the area of proposed construction. In addition, buried objects or deeply disturbed soils may also be encountered. As such all care and practice is to be exercised to observe for and locate any such objects. Where these objects are to be removed or use discontinued, they are to be removed in their entirety and all disturbed soils are to be processed as engineered fill.

The base of all excavations and over-excavations are to be inspected by the Soils Engineer prior to further processing, steel or form placement.

Any further site activity, especially grading and foundation excavations, should be under the direction of a qualified Soils Engineer or their Representative.

Should the spectrum of development change, this office should be notified so that additional recommendations can be made, if necessary.

\* Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics adequate for support of the intended load or application.

## Foundations and Footings

Geotechnical evaluation indicates that square, round, and continuous spread footings are satisfactory types of support. The minimum embedment for shallow, spread foundations is 12 inches for single stories and 18 inches for two stories into suitable, *in-situ*\*, native soils or certified engineered fill. Embedment depths do not take into account the loose upper top soils, disturbed soils or any other unacceptable soils which exist at the site, e.g., any un-engineered fill, landscaping soils, etc.

| VERTICAL SOIL PRESSURES <sup>1</sup> |  |                                 |
|--------------------------------------|--|---------------------------------|
| FOOTING TYPE                         | DEAD LOAD, kips/ft <sup>2</sup>                            | DEAD + LL, kips/ft <sup>2</sup> |
| Spread & Isolated                    | 2.5  | 3.3                             |
| LATERAL SOIL PRESSURES <sup>1</sup>  |  |                                 |
| TYPE                                 | VALUE, lbs/ft <sup>2</sup>                                 |                                 |
| Active Earth Pressure                | 30 lbs/ft <sup>3</sup> (Equivalent Fluid Pressure)         |                                 |
| Restrained Earth Pressure            | 50 lbs/ft <sup>3</sup> (Equivalent Fluid Pressure)         |                                 |
| Seismic                              | 2 lbs/ft <sup>3</sup> × H <sup>2</sup> applied at 0.6H     |                                 |
| Friction at Base                     | 0.30 × Dead Load   |                                 |
| Passive Earth Pressure               | 300 lbs/ft <sup>3</sup> × H <sup>2</sup> NOTE <sup>2</sup> |                                 |
| Uplift Friction                      | 140 lbs/ft <sup>2</sup> × H                                |                                 |

Notes: LL = Live Load; DL = Dead Load; H = Vertical height of material retained.  
One-third increase to be allowed for wind and seismic forces.

<sup>1</sup> For depths into acceptable native materials or engineered fill.

<sup>2</sup> Excludes near surface 0.5 feet of *in-situ* soils.

Pile and Pier foundation information is not provided as none are required or proposed. All foundation excavations are to be cleaned of debris and loose or otherwise unsuitable soils prior to placement of concrete.

\* Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics adequate for support of the intended load or application.



## Slabs-on-Grade

All slabs should be constructed over a prepared sub-grade placed on suitable *in-situ*\* native material or certified engineered fill. The site exploration observed that the existing surficial soils are loose to depths of approximately 1 foot. These soils should not be relied upon for support of slabs on grade or other surficial structures.

As such where any unsuitable soils remain after excavation to subgrade they are to be processed as engineered fill prior to further fill placement or construction of the on grade structure. At a minimum the upper 6 inches of subgrade below all surficial structures should be processed as engineered fill in areas of on grade structures.

The native topsoil is a silty clay of low-medium to medium plasticity. This soil may change volume from variation in water content. Where new slabs are to be supported by these soils special consideration should be given to providing a properly prepared subgrade and pavement section. Further recommendations are given under Expansive Soils below.

The sub-grade materials should be observed and accepted by a qualified Soils Engineer or their representative prior to placement of forms, reinforcing or concrete.

On-grade slabs should be placed over a moisture vapor barrier consisting of a waterproof membrane (Moist Stop, 10 mil Visqueen, or equal) with a 2 inch protective sand cover. The waterproof membrane should be placed over a capillarity break consisting of 4 inches of open graded rock; round and sub-round rock is recommended to prevent puncture of the membrane. Open graded crushed aggregate may be utilized, provided the vapor barrier is protected from puncture by a cushion of filter fabric (Mirafi 140N or equal) laid over the aggregate prior to placement of the membrane. Where such concerns are not warranted, alternative underlayment may be utilized at the owners discretion.

All care and practice required to prevent puncture of the membrane during placement and pouring of covering slabs should be utilized during construction. Unless otherwise required for structural purposes, all slabs should be reinforced with a minimum of No.4, Grade 40, deformed steel reinforcing bar, 24 inches o.c., each way, to prevent separation and displacement in cases of cracking.

\* Suitable, *in-situ*, native soils are those soils which are in-place as deposited by nature and have characteristics acceptable for support of the intended load or application.

### **Specifications for Rock Under Floor Slabs**

**Definition:** Graded gravel of crushed rock for use under floor slabs shall consist of a minimum thickness of mineral aggregate placed in accordance with these specifications and in conformance with the dimensions shown on the project plans. The minimum thickness is specified under the section Slabs-on-Grade above.

**Material:** The mineral aggregate for use under floor slabs shall consist of broken stone, crushed or uncrushed gravel, quarry waste, or a combination thereof. The aggregate shall be free from adobe, vegetable matter, loam, volcanic tuff, and other deleterious substances. It shall be of such quality that the absorption of water in a saturated dry condition does not exceed 3 percent of the oven dry weight of the sample.

**Grading:** The mineral aggregate shall be of such size that the percentage composition by dry weight as determined by the use of laboratory sieves, U.S. Standard, in compliance with ASTM C 136-06, Standard Method for Sieve Analysis of Fine and Coarse Aggregates, will conform to the following grading specification:

| SIEVE SIZE | PERCENTAGE PASSING SIEVE |
|------------|--------------------------|
| 3/4 inch   | 100 %                    |
| No. 4      | 0 - 10 %                 |
| No. 200    | 0 - 2 %                  |

**Placing:** Sub-grade upon which gravel or crushed rock is to be placed shall be prepared as outlined in the Recommended Grading Specifications. In addition, the Sub-grade shall be kept moist so that no drying cracks appear prior to pouring slabs. If cracks appear, Sub-grade shall be moistened until cracks close.

### **Slope Ratio and Drainage**

Analysis of site soils indicate that cut and fill slope ratios of 2 horizontal to 1 vertical will be satisfactory provided they are landscaped with soil retaining ground covers and are protected against concentrated over slope drainage.



## **Surface Drainage and Erosion Control**

Design and construction of the project should fit the topographic and hydrologic features of the site. It is important to minimize unnecessary grading of or near steep slopes. Disturbing native vegetation and natural soil structure allows runoff velocity and transport of sediments to increase.

General surface drainage should be retained at low velocity by slope, sod or other energy reducing features sufficient to prevent erosion, with concentrated over-slope drainage carried in lined channels, flumes, pipe or other erosion-preventing installations.

Runoff flows should be directed into pipes or lined ditches and then onto an energy dissipater before discharging into streams or drainage ways. De-silting should be provided as necessary and may take form of stilling basins, gravel berms, forested/vegetated screens, etc.

All concentrated roof and area drainage should be conveyed and released to grade as divided as possible away from structures. If available runoff should be released to existing storm drain structure or patterns.

A sub-surface dispersal system may not be used as the site subsoils are not sufficiently permeable to infiltrate storm runoff.

Recent changes to the drainage requirements has the potential to alter drainage patterns. This has been observed to effect structures which have otherwise not been affected or to alter the way they are affected. As such new drainage modifications on this and adjacent parcels may negatively affect drainage patterns.

During construction, never store cut and fill material where it may wash into streams or drainage ways. Keep all culverts and drainage facilities free of silt and debris. Keep emergency erosion control materials such as straw mulch, plastic sheeting, and sandbags on-site and install these at the end of each day as necessary.

Re-vegetate and protect exposed soils by October 15. Use appropriate grass/legume seed mixes and/or straw mulch for temporary cover. Plan permanent vegetation to include native and drought tolerant plants. Seeding and re-vegetation may require special soil preparation, fertilizing, irrigation, and mulching.

### **Expansive Soils**

As observed, the site soils are clay of moderate plasticity. In general these clays do not act expansively and the local structures are typically not subject to the affects of expansive clays. However improper treatment of these clays will result in unacceptable behavior and some precaution is economically warranted.

A potential for expansivity is in allowing those clayey soils, exposed by excavation and which are to be covered by foundations, slabs or engineered fill, to dry and not be re-saturated prior to placement of overlaying structure. Therefore it is recommended that all exposed clayey soils which are to be covered by engineered fill, foundations or slabs be kept at or above natural moisture or placed moisture content and above 3 percent over optimum moisture content. All native soils used as fill are to be placed at greater than 3 percent optimum moisture and compacted to a Relative Compaction between 88 and 91 percent.

### Subsurface Drains

Use of spun filter fabric is not recommended for use in construction subsurface drains as this type of fabric typically becomes clogged. Should filter fabric be necessary it is recommended that a woven fabric be used such as Mirafi Filterweave 300. Otherwise we would recommend omission of the fabric and placement of Caltrans Class 1, Type 'A' or "B" drain rock, and that any fabric only be placed near the top of the trench between the gravel and earth backfill or where the gravel extends to grade, 1 foot below finish grade.

| CLASS 1             |                    |        |
|---------------------|--------------------|--------|
| SIEVE SIZES         | PERCENTAGE PASSING |        |
|                     | TYPE A             | TYPE B |
| 50.0-mm/2 inches    | ----               | 100    |
| 37.5-mm/1.5 inches  | ----               | 95-100 |
| 19.0-mm/0.75 inches | 100                | 50-100 |
| 12.5-mm/0.5 inches  | 95-100             | -----  |
| 9.5-mm/0.415 inches | 70-100             | 15-55  |
| 4.75-mm/No. 4       | 0-55               | 0-25   |
| 2.36-mm/No. 8       | 0-10               | 0-5    |
| 75.0-µm/No.200      | 0-3                | 0-3    |



### **General Grading Recommendations**

For those items not directly addressed, it is recommended that all earthwork be performed in accordance with the following.

General: This item shall consist of all clearing and grubbing; preparation of land to be filled; excavation and fill of the land; spreading, compaction and control of the fill; and all subsidiary work necessary to complete the graded area to conform with the lines, grades and slopes as shown on the approved plans.

The Contractor shall provide all equipment and labor necessary to complete the work as specified herein, as shown on the approved plans as stated in the project specifications.

Preparation: Site preparation will consist of clearing and grubbing any existing structures and deleterious materials from the site, and the earthwork required to shape the site to receive the intended improvements, in accordance with the recommended grading specifications and the recommendations as provided above.

All vegetable matter, irreducible material greater than 4 inches and other deleterious materials shall be removed from the areas in which grading is to be done. Such materials not suitable for reuse shall be disposed of as directed.

After the foundation for fill has been cleared, it shall be brought to the proper moisture content by adding water or aerating and compacting to a Relative Compaction of not less than 90% or as specified. The soils shall be tested to a depth sufficient to determine quality and shall be approved by the Soils Engineer for foundation purposes prior to placing engineered fill.

General Fill: General fill shall be placed only on approved surfaces, as engineered fill, and shall be compacted to 90% Relative Compaction. Native soils accepted for fill or existing aggregate fill may be used for fill purposes provided all aggregate larger than 6 inches are removed. The material for engineered fill shall be approved by the Soils Engineer before commencement of grading operations.

Each layer shall be compacted to a Relative Compaction of not less than 90% or as specified in the soils report and on the accepted plans. Compaction shall be continuous over the entire area of each layer.

The selected fill material shall be placed in layers which, when compacted, shall not exceed 6 inches in thickness. Each layer shall be spread evenly and shall



be thoroughly mixed during the spreading to ensure uniformity of material in each layer. Fill shall be placed such that cross fall does not exceed 1 foot in 20 unless otherwise directed.

When fill material includes rock or concrete rubble, no irreducible material larger than 4 inches in greatest dimension will be allowed except under the direction of the Soils Engineer.

Imported Materials: Materials imported for fill purposes shall be classified as: SAND, group symbol SW, SP, SC or SM, as given in ASTM 2487-10, "The Classification of Soils For Engineering Purposes." In all cases the portion finer than the No. 200 sieve shall not contain any greatly expansive clays and shall be free from vegetable matter and other deleterious materials. The material for engineered fill shall be approved by the Soils Engineer before commencement of grading operations.

Structural Backfill: Trench, wall and structural backfill shall be placed only on approved surfaces, as engineered fill, and shall be compacted to 95% Relative Compaction. Materials imported for backfill purposes shall have a Sand Equivalent of no less than 30 and shall be classified as Clean Sands as designated in "The Classification of Soils For Engineering Purposes" (ASTM 2487-10).

Pavement Grades: All pavement grades shall be of uniform thickness, density and moisture prior to placement of the next grade. Flexure of each or all grades shall not exceed 0.25 inches in 5 feet under an axial load of 18.5 kip.

Aggregate Base Course: All aggregates used for specified base courses, shall be handled in a manner which prevents segregation and non-uniformity of gradation.

Compaction: All re-compacted soils and/or engineered fill should be placed at a minimum 90% Relative Compaction or at the value required for that portion of the work. All pavement sections should be compacted to a minimum of 95% Relative Compaction.

Field density testing shall be completed by the Soils Engineer on each compacted layer or as determined by the Soils Engineer. At least one test shall be made for each 500 cubic yards or fraction thereof, placed with a minimum of two tests per layer in isolated areas. Where a sheeps'-foot roller is used, the soil may be disturbed to a depth of several inches. Density tests shall be taken in compacted materials below the disturbed surface. When these tests indicate that the density of any layer of fill or portion thereof, is below the required density,

that particular layer or portion shall be reworked until the required density has been obtained.

Moisture: During compaction moisture content of native soils should be that consistent with the moisture relative to 95% Relative Compaction and in no case should these materials be placed at less than 3 percent above the specific optimum moisture content for the soil in question. The engineer may elect to accept high moisture compacted soils provided the materials are at 95% Relative Wet Density at that moisture content.

The moisture content of the fill material shall be maintained in a suitable range to permit efficient compaction. The Soils Engineer may require adding moisture, aerating, or blending of wet and dry soils.

All earth moving and work operations shall be controlled to prevent water from running into and pooling in excavated areas. All such water shall be promptly removed and the site kept drained.

Tests: All materials placed should be tested in accordance with the Compaction Control Tests: "Density of Soil In-Place by Sand Cone Method" (ASTM D-1556-07), "Moisture-Density Relationship of Soils" (ASTM D-1557-09), and "Density of Soils In-Place by Nuclear Method" (ASTM D-6938-10).

The standard test used to define maximum densities of all compaction work shall be the A.S.T.M. D-1557-09, Moisture Density of Soils, using a 10-pound ram and 18-inch drop. All densities shall be expressed as a relative density in terms of the maximum density obtained in the laboratory by the foregoing standard procedure.

Deleterious Materials: Materials containing an excess of 5% (by weight) of vegetative or other deleterious matter may be utilized in areas of landscaping or other non-structural fills. Deleterious material includes all vegetative and non-mineral material, and all non-reducible stone, rubble and/or mineral matter of greater than 6 inches.

Over-Excavations: Over-excavations, when required, should include the foundation and pavement envelopes. Such excavations should extend beyond edge of development a minimum of 5 feet and to an imaginary line extending away and downward at a slope of 45 degrees from the edge of development. The process shall include the complete removal of the required soils and subsequent placement of engineered fill. After removal of the soils to the required depth, the base of the excavation shall be inspected and approved by the Soils Engineer or his representative prior to further soils processing or



placement. Based on this inspection other recommendations may be made.

Existing Conditions: In developed areas underground utilities may be located within the area of proposed construction. In addition, buried objects or deeply disturbed soils may also be encountered. As such all care and practice is to be exercised to observe for and locate any such objects. Where these objects are to be removed or use discontinued, they are to be removed in their entirety and all disturbed soils are to be processed as engineered fill.

Key: All fills on slopes greater than 1 vertical to 6 horizontal shall be keyed into the adjacent soil. The toe of all slopes should be supported by a key cut a minimum of 3 feet into undisturbed soils to the inside of the fills toe. This key should be a minimum of 6 feet in width and slope at no less than 10% into the slope. In addition, as the fill advances up slope benches, 3 feet across, should be scarified into the fill/undisturbed soil interface.

Seasonal Limits: When the work is interrupted by rain, fill operations shall not be resumed until field tests by the Soils Engineer indicate that the moisture content and density of the fill is as previously specified and soils to be placed are in suitable condition

Unusual Conditions: In the event that any unusual conditions are encountered during grading operations which are not covered by the soil investigation or the specifications, the Soils Engineer shall be immediately notified such that additional recommendations may be made.

### **LIMITATIONS AND UNIFORMITY OF CONDITIONS**

The recommendations of this report are based on our understanding of the project as represented by the plans, and the assumption that the soil conditions do not deviate from those represented in this site soils investigation. Therefore, should any variations or undesirable conditions be encountered during construction, or if the actual project will differ from that planned at this time, GRICE ENGINEERING INC. should be notified and provided the opportunity to make addendum recommendations if required.

|         |                           |          |                |
|---------|---------------------------|----------|----------------|
| NOTIFY: | GRICE ENGINEERING INC.    | SALINAS  | (831) 422-9619 |
|         | 561-A Brunken Avenue      | MONTEREY | (831) 375-1198 |
|         | Salinas, California 93901 | FAX      | (831) 422-1896 |

This report is issued with admonishment to the Owner and to his representative(s), that the information contained herein should be made available to the responsible project personnel including the architects, engineers, and contractors for the project. The recommendations contained herein should be incorporated into the plans, the specifications, and the final work.

It is requested that GRICE ENGINEERING INC. be retained to review the project grading and foundation plans to ensure compliance with these recommendations. Further, it is the position of GRICE ENGINEERING INC. that work performed without our knowledge and supervision, or the direction and supervision of a project responsible professional soils engineer renders this report invalid.


It is our opinion the findings of this report are **valid** as of the **present date**, **however**, changes in the **Codes and Requirements** can occur and change the recommendations given within this report concerning the property. In addition changes in the conditions of a property can occur with the passage of time, due either to natural processes or to the works of man and may affect this property. In addition, changes in **standards** may occur as a result of legislation, or the broadening of knowledge, and these changes may require re-evaluation of the conditions stated herein. Accordingly, the findings of this report may be invalidated wholly, or partially, by changes beyond our control. Therefore, this report is subject to review and should not be relied upon after a period of **three years**.

REVISED 01-07-2011



## **APPENDIX A**

Vicinity and Location Map



Vicinity Map



Location Map







## **APPENDIX B**

| EXPLORATION DRILL LOG   |           |              |        |                                    |             | HOLE NO. 1     |              |               |             |
|---|-----------|--------------|--------|------------------------------------|-------------|----------------|--------------|---------------|-------------|
| PROJECT Khalsa-Villa De Castro Subdivision-Castroville Job # 3784     |           |              |        |                                    |             | DATE 1/16/03   |              | LOGGED BY MAR |             |
| DRILL RIG Cenozoic B-24 Mobile  |           | HOLE DIA. 4" |        | SAMPLER Terzaghi Split Spoon (SPT) |             |                |              |               |             |
| GROUNDWATER DEPTH:  |           | INITIAL ---  |        | FINAL ---                          |             | HOLE ELEV. 18' |              |               |             |
| DESCRIPTION   | SOIL TYPE | DEPTH        | SAMPLE | BLOWS PER                          | DRY DENSITY | W A T E R      | LIQUID LIMIT | PLASTIC LIMIT | POCKET PEN. |
| Black silty clay; stiff, moist  | CL/CH     | 1            |        |                                    |             |                |              |               |             |
|   |           |              | SPT    |                                    |             |                |              |               |             |
|   |           | 2            |        |                                    |             |                |              |               |             |
| Same  | CL/CH     | 3            | XXX    | 10                                 | 85.5        | 24.7           | 44           | 15            | 2.0         |
|   |           | 4            |        |                                    |             |                |              |               |             |
| Black silty clay; stiff, moist  | CL/CH     | 5            |        |                                    |             |                |              |               |             |
| Olive-tan clayey silt/silty clay; slightly mottled, very stiff, moist | CL        | 6            | SPT    |                                    |             |                |              |               |             |
| Bottom of hole @ 6.5'   | CL        | 7            | XXX    | 26                                 | 86.1        | 17.0           |              |               | 2.5         |
|   |           | 8            |        |                                    |             |                |              |               |             |
|   |           | 9            |        |                                    |             |                |              |               |             |
|   |           | 10           |        |                                    |             |                |              |               |             |
|   |           | 11           |        |                                    |             |                |              |               |             |
|   |           | 12           |        |                                    |             |                |              |               |             |
|   |           | 13           |        |                                    |             |                |              |               |             |
|   |           | 14           |        |                                    |             |                |              |               |             |
|   |           | 15           |        |                                    |             |                |              |               |             |
|   |           | 16           |        |                                    |             |                |              |               |             |
|   |           | 17           |        |                                    |             |                |              |               |             |
|   |           | 18           |        |                                    |             |                |              |               |             |
|   |           | 19           |        |                                    |             |                |              |               |             |
|   |           | 20           |        |                                    |             |                |              |               |             |

DEPTH 6.5' SOIL SURVEYS INC.



| EXPLORATION DRILL LOG   |             |              |        |                                    |             | HOLE NO. 2                 |              |               |             |
|---|-------------|--------------|--------|------------------------------------|-------------|----------------------------|--------------|---------------|-------------|
| PROJECT Khalsa-Villa De Castro Subdivision-Castroville Job # 3784 |             |              |        |                                    |             | DATE 1/16/03 LOGGED BY MAR |              |               |             |
| DRILL RIG Cenozoic B-24 Mobile                                    |             | HOLE DIA. 4" |        | SAMPLER Terzaghi Split Spoon (SPT) |             |                            |              |               |             |
| GROUNDWATER DEPTH:  |             | INITIAL --   |        | FINAL ---                          |             | HOLE ELEV. 21.5'           |              |               |             |
| DESCRIPTION   | SOIL TYPE   | DEPTH        | SAMPLE | BLOWS PER                          | DRY DENSITY | W A T E R                  | LIQUID LIMIT | PLASTIC LIMIT | POCKET PEN. |
| Black silty clay; stiff, moist                                    | CL/CH       | 1            |        |                                    |             |                            |              |               |             |
|   |             |              | SPT    |                                    |             |                            |              |               |             |
|   |             | 2            |        |                                    |             |                            |              |               |             |
| Same  | CL/CH       | 3            | XXX    | 9                                  | 86.7        | 24.1                       |              |               | 1.5         |
|   |             | 4            |        |                                    |             |                            |              |               |             |
| Olive-tan clayey silty/silty clay; very stiff, moist              | CL/CH<br>CL | 5            |        |                                    |             |                            |              |               |             |
|   |             |              | SPT    |                                    |             |                            |              |               |             |
|   |             | 6            |        |                                    |             |                            |              |               |             |
|   |             |              | XXX    | 28                                 | 85.7        | 24.5                       |              |               | 2.0         |
|   |             | 7            |        |                                    |             |                            |              |               |             |
|   |             | 8            |        |                                    |             |                            |              |               |             |
|   |             | 9            |        |                                    |             |                            |              |               |             |
| Olive-brown silty lean clay; stiff                                | CL          | 10           |        |                                    |             |                            |              |               |             |
|   |             | 11           |        |                                    |             |                            |              |               |             |
|   |             | 12           |        |                                    |             |                            |              |               |             |
| Olive-brown silty clay; very stiff, moist                         | CL          |              | SPT    |                                    |             |                            |              |               |             |
|   |             | 13           |        |                                    |             |                            |              |               |             |
|   |             |              | XXX    | 17                                 | 85.2        | 37.7                       |              |               | 3.0         |
|   |             | 14           |        |                                    |             |                            |              |               |             |
|   |             | 15           |        |                                    |             |                            |              |               |             |
|   |             | 16           |        |                                    |             |                            |              |               |             |
| Olive-brown silty clay; very stiff                                | CL          | 17           |        |                                    |             |                            |              |               |             |
|   |             | 18           |        |                                    |             |                            |              |               |             |
|   |             |              | SPT    |                                    |             |                            |              |               |             |
| Grey-brown medium grained sand;<br>very dense, dry                | SP          | 19           |        |                                    |             |                            |              |               |             |
|   |             |              | XXX    | 58                                 | 106.3       | 3.6                        |              |               | -           |
|   |             | 20           |        |                                    |             |                            |              |               |             |

DEPTH 24.5'

SOIL SURVEYS INC.

| EXPLORATION DRILL LOG                      |           |       |        |           |             | HOLE NO. 2 CONTINUED |              |               |             |
|--|-----------|-------|--------|-----------|-------------|----------------------|--------------|---------------|-------------|
| DESCRIPTION                                | SOIL TYPE | DEPTH | SAMPLE | BLOWS PER | DRY DENSITY | W A T E R            | LIQUID LIMIT | PLASTIC LIMIT | POCKET PEN. |
| Grey-brown medium grained sand: very dense | SP        | 21    |        |           |             |                      |              |               |             |
|  | SP        |       |        |           |             |                      |              |               |             |
| Gravelly @ 22'                             | SP/SW     | 22    |        |           |             |                      |              |               |             |
|  |           | 23    |        |           |             |                      |              |               |             |
| Grey-tan brown medium sand                 | SP        |       | SPT    |           |             |                      |              |               |             |
|  |           | 24    |        |           |             |                      |              |               |             |
| Bottom of hole @ 24.5'                     | SP        |       | XXX    | 62        | 112.7       | 3.0                  |              |               | ---         |
|  |           | 25    |        |           |             |                      |              |               |             |
|  |           | 26    |        |           |             |                      |              |               |             |
|  |           | 27    |        |           |             |                      |              |               |             |
|  |           | 28    |        |           |             |                      |              |               |             |
|  |           | 29    |        |           |             |                      |              |               |             |
|  |           | 30    |        |           |             |                      |              |               |             |
|  |           | 31    |        |           |             |                      |              |               |             |
|  |           | 32    |        |           |             |                      |              |               |             |
|  |           | 33    |        |           |             |                      |              |               |             |
|  |           | 34    |        |           |             |                      |              |               |             |
|  |           | 35    |        |           |             |                      |              |               |             |
|  |           | 36    |        |           |             |                      |              |               |             |
|  |           | 37    |        |           |             |                      |              |               |             |
|  |           | 38    |        |           |             |                      |              |               |             |
|  |           | 39    |        |           |             |                      |              |               |             |
|  |           | 40    |        |           |             |                      |              |               |             |
|  |           | 41    |        |           |             |                      |              |               |             |
|  |           | 42    |        |           |             |                      |              |               |             |
| DEPTH 24.5' Job #3784                      |           |       |        |           |             | SOIL SURVEYS INC.    |              |               |             |

| EXPLORATION DRILL LOG   |           |              |        |                                    |             | HOLE NO. 3                 |              |               |             |
|---|-----------|--------------|--------|------------------------------------|-------------|----------------------------|--------------|---------------|-------------|
| PROJECT Khalsa-Villa De Castro Subdivision-Castroville Job # 3784 |           |              |        |                                    |             | DATE 1/16/03 LOGGED BY MAR |              |               |             |
| DRILL RIG Cenozoic B-24 Mobile                                    |           | HOLE DIA. 4" |        | SAMPLER Terzaghi Split Spoon (SPT) |             |                            |              |               |             |
| GROUNDWATER DEPTH:  |           | INITIAL ---  |        | FINAL ---                          |             | HOLE ELEV. 21'             |              |               |             |
| DESCRIPTION   | SOIL TYPE | DEPTH        | SAMPLE | BLOWS PER                          | DRY DENSITY | W A T E R                  | LIQUID LIMIT | PLASTIC LIMIT | POCKET PEN. |
| Grey-brown silty clay; dry  | CL/CH     | 1            |        |                                    |             |                            |              |               |             |
| Black silty lean clay; moist, stiff                               | CL        | 2            | SPT    |                                    |             |                            |              |               |             |
|   | CL        | 3            | XXX    | 10                                 | 89.9        | 23.8                       | 41           | 15            | 2.0         |
|   | CL        | 4            |        |                                    |             |                            |              |               |             |
| Olive-tan silty lean clay; stiff                                  | CL        | 5            |        |                                    |             |                            |              |               |             |
|   |           | 6            |        |                                    |             |                            |              |               |             |
|   |           | 7            |        |                                    |             |                            |              |               |             |
|   |           | 8            |        |                                    |             |                            |              |               |             |
|   |           | 9            |        |                                    |             |                            |              |               |             |
|   |           | 10           |        |                                    |             |                            |              |               |             |
| Olive-tan silty lean clay; moist, stiff, slightly mottled         | CL        | 11           | SPT    |                                    |             |                            |              |               |             |
| Bottom of hole @ 11.5'  | CL        | 12           | XXX    | 12                                 | 80.5        | 35.3                       |              |               | 4.0         |
|   |           | 13           |        |                                    |             |                            |              |               |             |
|   |           | 14           |        |                                    |             |                            |              |               |             |
|   |           | 15           |        |                                    |             |                            |              |               |             |
|   |           | 16           |        |                                    |             |                            |              |               |             |
|   |           | 17           |        |                                    |             |                            |              |               |             |
|   |           | 18           |        |                                    |             |                            |              |               |             |
|   |           | 19           |        |                                    |             |                            |              |               |             |
|   |           | 20           |        |                                    |             |                            |              |               |             |

DEPTH 11.5' SOIL SURVEYS INC.



| <b>MOISTURE DENSITY TESTS</b> |           |                    |                    |                                 |                                 |
|-------------------------------|-----------|--------------------|--------------------|---------------------------------|---------------------------------|
| Test Hole No.                 | Depth Ft. | Moisture Content % | Dry Density p.c.f. | Standard Penetration Blows/Foot | Pocket Penetrometer Tons/Sq.Ft. |
| 1                             | 2-2.5     | 24.7               | 85.5               | 10                              | 2.0                             |
| 1                             | 6-6.5     | 17.0               | 86.1               | 26                              | 2.5                             |
| 2                             | 2-2.5     | 24.1               | 86.7               | 9                               | 1.5                             |
| 2                             | 6-6.5     | 24.5               | 85.7               | 28                              | 2.0                             |
| 2                             | 13-13.5   | 37.7               | 85.2               | 17                              | 3.0                             |
| 2                             | 19-19.5   | 3.6                | 106.3              | 58                              | --                              |
| 2                             | 24-24.5   | 3.0                | 112.7              | 62                              | --                              |
| 3                             | 2.5-3     | 23.8               | 89.9               | 10                              | 2.0                             |
| 3                             | 11-11.5   | 35.3               | 80.5               | 12                              | 4.0                             |

Two Plasticity Index (Atterberg Limits) tests were made from the driven core samples; results of these tests are tabulated as follows:

| <b>PLASTICITY INDEX TESTS</b> |            |                       |                        |              |               |                  |
|-------------------------------|------------|-----------------------|------------------------|--------------|---------------|------------------|
| Test Hole No.                 | Depth Feet | % Passing Sieve No. 4 | % Passing Sieve No. 40 | Liquid Limit | Plastic Limit | Plasticity Index |
| 1                             | 2-2.5      | 100                   | 47                     | 44           | 16            | 28               |
| 3                             | 2-2.5      | 100                   | 65                     | 41           | 15            | 26               |

One Compaction Curve was made based on A.S.T.M. D1557-91. Results of that test are as follows:

**Compaction Curve A.S.T.M. D 1557-91**

| Curve No. | Material Description      | Maximum Density p.c.f. | Optimum Moisture % |
|-----------|---------------------------|------------------------|--------------------|
| 1         | Black silty clay (Native) | 113.0                  | 13.5               |

The test hole logs and these tests indicate that the surface and near surface native soil consists of moderately expansive, stiff silty clay to depths ranging from 13 to 18.5 feet below surface; dense sand and gravelly sand was found below the clayey soil to a depth of 46 feet, and stiff silty clay was found from 46 to 50 feet. No free ground water was found in any of our recent test holes to a depth of 24.5 feet on the day of drilling; however free ground water was observed at 26 feet below surface in a Jacobs test hole on January 6, 1987.



# UNIFIED SOIL CLASSIFICATION & ASTM D2487: INCLUDING IDENTIFICATION AND DESCRIPTION

| UNIFIED SOIL CLASSIFICATION & ASTM D2487: INCLUDING IDENTIFICATION AND DESCRIPTION |                              |  |   |                   |  |   |   |   |  |
|--|------------------------------|--|---|-------------------|--|---|---|---|--|
| FIELD IDENTIFICATION PROCEDURES  |                              |  |   | TYPICAL NAMES     |  | INFORMATION REQUIRED FOR DESCRIBING SOILS   |   | LABORATORY CLASSIFICATION CRITERIA  |  |
| Excluding particles larger than 3 inches and basing fractions on estimated weights |                              |  |   | GROUP SYMBOL, No. |  |   |   |   |  |
| COARSE GRAINED SOILS   | GRAVELS                      | More than half of coarse fraction is larger than No. 4 sieve size  | CLEAN GRAVELS (little or no fines)  | GW                | Well graded gravels, gravel-sand mixtures, little or no fines. | Give typical name, indicate approximate percentages of sand and gravel, max. size, angularity, surface condition, and hardness of the coarse grains; local or geologic name and other pertinent descriptive information, and symbol in parentheses.             | $C_u = \frac{D_{60}}{D_{10}}$<br>$C_c = \frac{(D_{30})^2}{(D_{10} \times D_{60})}$  | Greater than 4<br>Between one and 3   |  |
|  |                              |  | Non-plastic fines (for identification procedures see ML below).                           | GM                | Silty gravels, poorly graded gravel-sand-silt mixtures.        |   | Not meeting all gradation requirements for GW   |   |  |
|  |                              |  | Plastic fines (for identification procedures see CL below).                               | GC                | Clayey gravels, poorly graded gravel-sand-clay mixtures.       | For undisturbed soils add information on stratification, degree of compaction, cementation, moisture conditions and drainage characteristics.   | Atterberg limits below "A" line or PI less than 4<br>Atterberg limits above "A" line or PI greater than 7   | Above "A" line with PI between 4 and 7 are <b>borderline</b> cases requiring use of dual symbols          |  |
| FINE GRAINED SOILS   | SANDS                        | More than half of coarse fraction is smaller than No. 4 sieve size | CLEAN SANDS (little or no fines)  | SW                | Well graded sands, gravelly sands, little or no fines.         |   | $C_u = \frac{D_{60}}{D_{10}}$<br>$C_c = \frac{(D_{30})^2}{(D_{10} \times D_{60})}$  | Greater than 6<br>Between one and 3   |  |
|  |                              |  | Predominantly one size or a range of sizes with some intermediate particle sizes missing. | SP                | Poorly graded sands, gravelly sands, little or no fines.       | EXAMPLE:<br>Silty Sand, gravelly, about 20% hard, angular gravel particles 1/2 inch maximum size; rounded and subangular sand grains coarse to fine, about 15% non-plastic fines with low dry strength, well compacted and moist in place, alluvial sand, (SM). | Less than 5%<br>More than 5% to 12%<br>More than 12%  | Not meeting all gradation requirements for SW   |  |
|  |                              | More than half of coarse fraction is smaller than No. 4 sieve size | Non-plastic fines (for identification procedures see ML below).                           | SM                | Silty sands, poorly graded sand-silt mixtures.                 |   | Atterberg limits below "A" line or PI less than 4<br>Atterberg limits above "A" line or PI greater than 7   | Above "A" line with PI between 4 and 7 are <b>borderline</b> cases requiring use of dual symbols          |  |
|  | SILTS AND CLAYS              | Liquid limit less than 50  | Plastic fines (for identification procedures see CL below).                               | SC                | Clayey sands, poorly graded sand-clay mixtures.                |   | Determine percentages of gravel and sand from grain size curve. Depending on percentage of fines (fraction smaller than No. 200 sieve size) coarse grained soils are classified as follows:<br>GM, GP, SW, SC | Atterberg limits below "A" line or PI less than 4<br>Atterberg limits above "A" line or PI greater than 7 |  |
|  |                              |  |   |                   |  |   |   |   |  |
|  |                              |  |   |                   |  |   |   |   |  |
| HIGHLY ORGANIC SOILS   | Liquid limit greater than 50 |  |   |                   |  |   |   |   |  |
|  |                              |  |   |                   |  |   |   |   |  |
|  |                              |  |   |                   |  |   |   |   |  |

Use grain size curve in identifying the fractions as given under field identification.

Give typical name, indicate degree and character of plasticity, amount and maximum size of coarse grains, color in wet conditions, odor if any, local or geologic name, and other pertinent descriptive information, and symbol in parentheses.

For undisturbed soils add information or structure, stratification, consistency in undisturbed and remolded states, moisture and drainage conditions.

EXAMPLE:  
Clayey silt, brown, slightly plastic, small percentage of fine sand, numerous vertical root holes, firm and dry in place, loess, (ML).

COMPARING SOILS AT EQUAL LIQUID LIMIT

Toughness and dry strength increases with increasing plasticity index.

TOUGHNESS (Consistency near plastic limit)

After removing particles larger than No. 40 sieve size, a specimen of soil about one-half inch cube in size is molded to the consistency of putty. If too dry, water must be added and if sticky, the specimen should be spread out in a thin layer and allowed to lose some moisture by evaporation. Then the specimen is rolled out by hand on a smooth surface of between the palms into a thread about one-eighth inch in diameter. The thread is then folded and rerolled repeatedly. During this manipulation the soil is kneaded and the specimen softens. Finally loess is plasticity, and crumbles when the plastic limit is reached.

After the thread crumbles, the pieces should be lumped together and a slight kneading action continued until the lump crumbles.

The tougher the thread near the plastic limit and the stiffer the lump when it finally crumbles, the more potent the colloidal clay from the soil. Values of toughness are used to distinguish soils of different types such as kaolin-type clays and organic clays which occur below the A-line.

Highly organic clays have a very weak and spongy feel at the plastic limit.

FIELD IDENTIFICATION PROCEDURES FOR FINE GRAINED SOILS OR FRACTIONS

These procedures are to be performed on the minus No. 40 sieve size particles, approximately 1/4 inches. For field classification purposes, screening is not intended; simply remove by hands the coarse particles that interfere with the test.

DRY STRENGTH (Crushing characteristics)

After removing particles larger than No. 40 sieve size, mold a part of soil to the consistency of putty, adding enough water to make it moldable. Then press the soil between the fingers. This strength is a measure of the character and quality of the colloidal fraction contained in the soil. The dry strength increases with increasing plasticity.

High dry strength is characteristic for clays of the CH group. A typical inorganic silt possesses only moderate dry strength. Organic silts and clays of the MH and OH groups, however, can be distinguished by the test when powdering the dried specimen. Fine sand feels gritty whereas a typical silt has the smooth feel of flour.

N. Boundary classifications: Soils possessing characteristics of two groups are designated by combinations of group symbols. For example GW-SC, well graded gravel-sand mixture with clay binder.

N. All sieve sizes on this chart are U.S. Standard.

These procedures are to be performed on the minus No. 40 sieve size particles, approximately 1/4 inches. For field classification purposes, screening is not intended; simply remove by hands the coarse particles that interfere with the test.

DRY STRENGTH (Crushing characteristics)

After removing particles larger than No. 40 sieve size, mold a part of soil to the consistency of putty, adding enough water to make it moldable. Then press the soil between the fingers. This strength is a measure of the character and quality of the colloidal fraction contained in the soil. The dry strength increases with increasing plasticity.

High dry strength is characteristic for clays of the CH group. A typical inorganic silt possesses only moderate dry strength. Organic silts and clays of the MH and OH groups, however, can be distinguished by the test when powdering the dried specimen. Fine sand feels gritty whereas a typical silt has the smooth feel of flour.

DIATANCY (Reaction to shaking)


After removing portions larger than No. 40 sieve size, prepare a part of moist soil with a volume of about one-half cubic inch. Add enough water if necessary to make the soil soft but not sticky.

Place the pot in the open palm of one hand and shake horizontally, striking vigorously against the other hand several times. A positive reaction consists of the appearance of water in the pot, the soil becoming very soft, and the soil becoming very sticky. If the soil is very stiff, the sample is squeezed between the fingers, the water and gloss disappear from the surface, the pot stiffens and finally it cracks or crumbles. The rapidity of appearance of water during shaking and of its disappearance during squeezing assist in identifying the character of the fines in a soil.

Very fine clean sands give the quickest and most distinct reaction whereas a plastic clay has no reaction. Inorganic silts, such as a typical rock flour, show a moderately quick reaction.

ADOPTED BY: CORPS OF ENGINEERS AND BUREAU OF RECLAMATION-JANUARY 1962

103-D-347



FOR LABORATORY CLASSIFICATION OF FINE GRAINED SOILS

PLASTICITY CHART

TOUGHNESS (Consistency near plastic limit)

After removing particles larger than the No. 40 sieve size, a specimen of soil about one-half inch cube in size is molded to the consistency of putty. If too dry, water must be added and if sticky, the specimen should be spread out in a thin layer and allowed to lose some moisture by evaporation. Then the specimen is rolled into a thread of uniform diameter. The thread is then folded and re-rolled repeatedly. During this manipulation the moisture content is gradually reduced and the specimen stiffens, finally losing its plasticity, and crumbles when the plastic limit is reached.

After the thread crumbles, the pieces should be lumped together and a slight kneading action continued until the lump crumbles.

The tougher the thread near the plastic limit and the stiffer the lump when it finally crumbles, the more potent is the colloidal clay fraction in the soil. Weakness of the thread at the plastic limit and quick loss of coherence of the lump below the plastic limit indicate either inorganic clay of low plasticity, or materials such as kaolin-type clays and organic clays which occur below the A-line.

Highly organic clays have a very weak and spongy feel at the plastic limit.

FIELD IDENTIFICATION PROCEDURES FOR FINE GRAINED SOILS OR FRACTIONS

These procedures are to be performed on the minus No. 40 sieve size particles, approximately 1/25 inches. For field classification purposes, screening is not intended; simply remove by hands the coarse particles that interfere with the test.

DRY STRENGTH (Crushing characteristics)

After removing particles larger than No. 40 sieve size, mold a part of soil to the consistency of putty, adding water if necessary. Allow the part to dry completely by oven, sun, or air drying, and then test its strength by breaking and crumbling between the fingers. This strength is a measure of the character and quality of the colloidal fraction contained in the soil. The dry strength increases with increasing plasticity.

High dry strength is characteristic for clays of the CH group. A typical inorganic silt possesses only very slight dry strength. Silty fine sand and silts have about the same slight dry strength, but can be distinguished by the feel when powdering the dried specimen. Fine sand feels gritty whereas a typical silt has the smooth feel of flour.

N. Boundary classifications. Soils possessing characteristics of two groups are designated by combinations of group symbols. For example GW-GC, well graded gravel-sand mixture with clay binder.

N. All sieve sizes on this chart are U.S. Standard.

DILATANCY (Reaction to shaking)

After removing portions larger than No. 40 sieve size, prepare a pot of moist soil with a volume of about one-half cubic inch. Add enough water if necessary to make the soil soft but not sticky.

Place the pot in the open palm of one hand and shake horizontally, striking vigorously against the other hand several times. A positive reaction consists of the appearance of water on the surface of the pot which changes to a livery consistency and becomes glossy. When the sample is squeezed between the fingers, the water and gloss disappear from the surface, the pot stiffens and finally it cracks or crumbles. The rapidity of appearance of water during shaking and of its disappearance during squeezing assist in identifying the character of the fine sand in a soil.

Very fine clean sands give the quicks and most distinct reaction whereas a plastic clay has no reaction. Inorganic silts, such as a typical rock flour, show a moderately quick reaction.

ADOPTED BY: CORPS OF ENGINEERS AND BUREAU OF RECLAMATION-JANUARY 1952

103-D-347

## REFERENCES

1. American Society of Civil Engineers, **Minimum Design Loads for Buildings and Other Structures, ASCE Standard ASCE/SEI 7-05 Including Supplement No. 1**, 2006, 385 pp.
2. Allen, C. R., 1975; **Geological criteria for evaluating seismicity**, GSA Bull. v. 86, p. 1041-1057.
3. Bailey, E. H., Irwin, W. P. and Jones, D. L., 1964, **Franciscan and Related Rocks, and their significance in the Geology of Western California**, CDMG Bulletin 183, 177 pp.
4. Bailey, E.H., Ed., 1966, **Geology of Northern California**, CDMG Bulletin 190, 507 pp.
5. Blair, M.L. and Spangle, W. E., 1979, **Seismic Safety and Land-Use Planning - Selected Examples from California**, USGS Professional Paper 941-B.
6. Bolt, B. A., 1975; **Geological Hazards**, Springer-Verlag, 328 p.
7. Bryant, W. A., 1985; **Faults in the Southern Monterey Bay area**, CDMG Fault Evaluation Report FER-167, 13 pp.
8. Bullis, K.C., 1980, **Environmental Constraints Analysis of Monterey County, Part I: Seismic and Geologic Hazards**, Monterey County Planning Department, General Update Program, Second printing June 1982, 54pp and appendices.
9. Bullis, K.C., 1981, **Environmental Constraints Analysis of Monterey County, Part I: Flood, Fire and Miscellaneous Hazards; Emergency Preparedness**, Monterey County Planning Department, General Update Program, pp 55-104 and appendices.
10. Burkland and Assoc., 1975, **Seismic Safety Element of the Monterey County General Plan**, 50 pp w/appendices.
11. Burkland and Associates, 1975; **Geotechnical study for the seismic safety element**, Monterey County, California, File No. K3-0113-M1, 125 pp.
12. California Department of Conservation, 1998, **Maps of Known Active Fault Near-Source Zones in California and Adjacent Portions of Nevada**, International Conference of Building Officials, Introduction & Maps.



13. 2016 California Building Code, **California Code of Regulations, Title 24, 2 Volumes, California Building Standards Commission**, Based on the 2015 International Building Code.
14. Clark, J. C. and Reitman, J. D., 1973. **Oligocene stratigraphy, tectonics, and paleogeography southwest of the San Andreas fault, Santa Cruz Mountains and Gabilan Range, California Coast Ranges**: U.S. G. S. Professional Paper 783, 18 p.
15. Clark, J. C., Diblee, T. W. Jr., Greene, H. G., and Bowen, O. E., Jr., 1974, **Preliminary geologic map of the Monterey and Seaside 7.5 minute quadrangles, Monterey County, California, with emphasis on active faults**, USGS Miscellaneous Field Studies Map MF-577.
16. Clark, Joseph C., Dupré, William R., & Rosenberg, Lewis I., **Geological Map of the Monterey and Seaside 7.5 minute Quadrangles, Monterey County, California: A Digital Database**, 1997, U. S. Department of the Interior, U. S. Geological Survey, Open-File Report 97-30, Map and Pamphlet, 26 pp.
17. Clark, Joseph C., Brabb, Earl E., & Rosenberg, Lewis I., 2000, **Geologic Map of the Spreckels 7.5-Minute Quadrangle, Monterey County, California**, USGS/Department of the Interior, Map MF-2349 & Pamphlet, 22 pp.
18. Clark, Joseph C. & Rosenberg, Lewis I., March 1999, **Southern San Gregorio Fault Displacement: Stepover Segmentation VS. Through-Going Tectonics**, USGS /Department of the Interior-National Earthquake Hazards Reduction Program, Award number 1434-HQ-98-GR-00007, 22 pp without Appendices
19. Cleveland, G.B., 1975, **Landsliding in Marine Terrace Terrain, California**, CDMG Special Report 119, 24pp.
20. Compton, R. R., 1966; **Granitic and metamorphic rocks of the Salinian Block, California Coast Ranges**, CDMG Bulletin 190, p. 277-287.
21. Diblee, T. W. Jr., 1966; **Evidence for cumulative offset on the San Andreas fault in central and northern California**, CDMG Bulletin 190.
22. Diblee, T. W., Jr., 1999; **Geologic Map of the Monterey Peninsula and Vicinity, Monterey, Salinas, Point Sur, and Jamesburg 15-Minute Quadrangles, Monterey County, California**, Diblee Geological Foundation Map #DF-71.

23. Dickinson, William R., Ducea, Mihai, Rosenberg, Lewis I., Greene, H. Gary, Graham, Stephan A., Clark, Joseph C., Weber, Gerald E., Kidder, Steven, Ernst, W. Gary and Brabb, Earl E., 2005; **Net dextral slip, Neogene San Gregorio-Hosgri fault zone, coastal California: Geologic evidence and tectonic implications**, Geological Society of America, Special Paper 391, 43 pp.
24. Dittmer, E. and Stein, C., 1977, **Salinas Seismic Hazards Technical Report**, Department of Community Development, City of Salinas, 73 pp.
25. Dupre, W. R. and Tinsley, J. C. III, 1980, **Geology and liquefaction potential of northern Monterey and southern Santa Cruz, California**: USGS Miscellaneous Field Studies Map 1199, Scale 1:62,500, 2 sheets.
26. Dupre, W. R., 1990, **Maps Showing Geology and Liquefaction Susceptibility of Quaternary Deposits in the Monterey, Seaside, Spreckels and Carmel Valley Quadrangles, Monterey County, CA**, U. S. Geological Survey and University of Houston, Map #MF-2096, 2 Sheets
27. Durham, D.L., 1974; **Geology of the Southern Salinas Valley Area, California**, USGS Professional Paper 819, 111 pp.
28. Greene, H. G., Lee, W.H.K., McCulloch, D.S., and Brabb, E.E., 1973; **Faults and Earthquakes in the Monterey Bay Region, California**, USGS MF 518, maps and paper, 14pp.
29. Greene, H. G., 1977; **Geology of the Monterey Bay region**, USGS Open-File Report p. 77-718.
30. Hays, W.W., 1980, **Procedures for Estimating Earthquake Ground Motions**, USGS Professional Paper 1114, 77 pp.
31. Jennings, C. W., and Strand, R. G., 1958; **Geologic Map of California, Olaf P. Jenkins edition, Santa Cruz sheet**, Scale 1:250,000, third printing 1971.
32. Jennings, C. W., and Bryant, W. A., 2010 **Fault Activity Map of California: California Geological Survey Geologic Data Map**, No. 6, Map Scale 1:750,000, Includes "An Explanatory Text to Accompany the Fault Activity Map of California", 94 pp
33. Lee, L. Don, Gudson, Seldon and Kauffman, Marvin E., 1978, **Physical Geology**, 5<sup>th</sup> Ed., Prentice Hall, Inc, Englewood Cliffs, New Jersey 07632, 490 pp.



34. Lindh, A. G., 1983; **Preliminary assessment of long-term probabilities for large earthquakes along selected fault segments of the San Andreas fault system in California**, USGS Open File Report 83-63, 15 p.
35. Nason, R. D., and Rogers, T. H., 1967; **Self-guiding map to active faulting in the San Juan Bautista quadrangle, conference on geologic problems of the San Andreas fault system**, Stanford University, scale 1:24,000.
36. Nilsen, T.H., Diblee, T.W. Jr., and Blake, M.C. Jr., 1990, **Geology of the Central Diablo Range, CA**, Field Trip June 2-3.
37. Oakeshott, G. B., 1966; **San Andreas fault in the California Coast Range Province**, in Bailey, E. H., ed., **Geology of Northern California**, CDMG Bulletin 190, p. 357-373.
38. Plafker, G. and Galloway, J.P., eds., 1989 (approved for publication), **Lessons Learned from the Loma Prieta, California, Earthquake of October 17, 1989**, USGS Circular 1045, 48 pp.
39. Ray, R.G., 1960, **Aerial Photographs in Geologic Interpretation and Mapping**, USGS Professional Paper 373, seventh printing, 1984, 230 pp.
40. Real Estate Data Inc., 1980; **Aerial/Map Volume of Monterey County, California**, Photo 110, 2398 NW 119th St., Miami, FLA 33167, fifteenth edition.
41. Robbins, S.L., 1982, **Complete Bouguer Gravity, Aeromagnetic, and Generalized Geologic map of the Hollister 15-minute Quadrangle, CA**, Geophysical Investigations Map GP 945, 2 sheets, Scale 1:62,500.
42. Sarna-Wojcicki, A.M., Pampeyan, E.H. and Hall, N.T., 1975, **Maps Showing Recently Active Breaks Along the San Andreas Fault Between the Central Santa Cruz Mountains and the Northern Gabilan Range, CA**, 2 maps, text is on map 2, Scale 1:24,000.
43. Spangle, Wm. and Associates, Burkland and Associates, and Thorup, Richard R., July 1974; **Faults, Seismicity and Tsunami Hazards: Monterey County, California**: Part of Geological Report, County Map 3, File No. K4-0113-M1.
44. Tinsley, J. C. III, 1975, **Quaternary geology of northern Salinas Valley, Monterey County, California**: Stanford University PhD. thesis, 194 p., map, scale 1:62,500.
45. US Department of Agriculture, Soil Conservation Service, 1978, **Soil Survey, Monterey County, CA**, 226 pages and maps.

46. US Geological Survey, California Geological Survey, 2006, **Quaternary Fault and Fold Database for the United States**, access date same as report, from URL: <http://earthquakes.usgs.gov/regional/qfaults/>
47. US Geological Survey / California Geological Survey, 2006, **The USGS Store, Map Locator**, access date same as report, from URL: <http://store.usgs.gov/> click on 'map locator'
48. USGS Earthquake Hazards Program, **Seismic Design Values for Buildings-Earthquake Ground Motion Parameter**, URL: <http://earthquake.usgs.gov/research/hazmaps/design/index.php>
49. USGS Open File Report 88-398, 1988, **Probabilities of Large Earthquakes Occurring in California on the San Andreas Fault**, by the Working Group on California Earthquake Probabilities, 62 pp.
50. Wallace, R. E., 1970; **Earthquake recurrence intervals on the San Andreas fault**, GSA Bulletin, v. 81.
51. Wagner, David L., Greene, H. Gary, Saucedo, George J. and Pridmore, Cynthia L. Compiled by., Watkins, Sarah E., Little, Jason D. and Bizzarro, Joseph J. Digitalized by. 2002, California Department of Conservation, **Geologic Map of the Monterey 30' x 60' Quadrangle and Adjacent Areas, CA**, 3 maps and CD-ROM
52. Ward, P.L. and Page, R.A., 1989, **The Loma Prieta Earthquake of Oct 17, 1989**, USGS Pamphlet, Hdgen, L.D. and Troll, J.A., eds., second printing, revised, January 1990.
53. Wyss, M., 1979; **Estimating maximum expectable magnitude of earthquakes from fault dimensions**, Geology, v. 7, n. 7, p. 336-340.
54. Youd, T. L., and Hoose, S. N., 1978; **Historic ground failures in northern California triggered by earthquakes**, USGS Professional Paper P-993, p. 177

This page intentionally left blank.