



Proposed Aesthetic Treatments

05-1K010 | Big Creek Retaining Wall

January 2025

Prepared by District 5 Landscape Architecture

Stain Galvanized Surfaces



Stained Posts and Guardrail



Stained Cable Railing

Stain shall be applied to exposed galvanized surfaces to reduce reflectivity and provide a natural brown color. This includes, but is not limited to, cable railing, gabion baskets, galvanized drainage components, posts, and guardrail.

Gabion Wall



Stained Gabion Baskets with Dark Stone




Native Stone Barrier Overlooking China Basin Beach at PM 26.72

Stain shall be applied to gabion baskets. Stone color shall complement the local geology and should be dark in color.

Integral Concrete Coloring



Soldier Pile Wall with Integrally Colored Coping and Walers



Fed. Std. 595C 30372

Exposed concrete shall receive integral color to match Federal Standards 595C 30372. This includes, but is not limited to, concrete coping, gutter, walers, and concrete drainage components.

Soldier Pile Wall



Soldier Pile Wall with Colored Piles and Untreated Timber Lagging



Fed. Std. 595C 30108

Vertical steel piles shall be painted to match Federal Standard 595C 30108. Horizontal timber lagging shall not receive aesthetic treatment.